

SECTION 110000 - EQUIPMENT

PART 1 - GENERAL

1.1 SUMMARY

- A. Refer to Medical Equipment List for all Medical Equipment, Appliances, Equipment, Toilet, Bathing & Laundry Accessories, AV and IT equipment. Coordinate with Owner's AV, IT & Security team for additional equipment. Coordinate install with Owner.
- B. Section includes equipment standards.

1.2 ACTION SUBMITTALS

- A. Product Data: Submit product data for each type of equipment required. Include complete operating characteristics, dimensions, and finishes for each type of equipment.

1.3 INFORMATIONAL SUBMITTALS

- A. UL and NEMA Compliance: Provide electrical equipment that are listed and labeled by UL and that comply with applicable NEMA standards.
- B. Warranties: Submit manufacturer's standard written warranty, for each type of equipment required, in which manufacturer agrees to repair or replace equipment or components that fail in materials or workmanship within two years from date of Substantial Completion.

1.4 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For each type of equipment.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- A. Equipment: Provide residential/pantry appliances, and audio/visual equipment listed in the Medical Equipment List and Specifications listed in the Appendix.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install equipment according to manufacturer's written instructions.
- B. Securely anchor built-in equipment to supporting cabinets or countertops with concealed fasteners. Verify that clearances are adequate for proper functioning and that rough openings are completely concealed.
- C. Place freestanding equipment in final locations after finishes have been completed in each area. Verify that clearances are adequate to properly operate equipment.
- D. Mount audio/visual equipment according to manufacturer's instructions for vibration isolation of equipment.
- E. Test each item of equipment to verify proper operation. Make necessary adjustments.
- F. Verify that accessories required have been furnished and installed.
- G. Remove packing material from equipment and leave units in clean condition, ready for operation.

END OF SECTION