

Bidding RFI Responses and additional information

CPL Project #15068.00 – March 29, 2021 - **UPDATED**

RFI	Subject	Request	Response
1	Deliveries	Please confirm pathway for deliveries	Plan showing pathway for deliveries is included in Bid Addendum #1 on Sheet A101
2	CT Physicist Report	Please provide Physicist's Report for CT.	Physicist Report for CT shielding was distributed to all bidders at PreBid Meeting at GSH on 03.17.2021; also included in Bid Addendum #1 03.29.2021 – an updated Physicist Report for the new CT has been issued by the owner...attached.
3	RF Shielding	Bidding documents contain "performance criteria" for RF Shielding for MRI. GC is responsible for contracting RF Shielding vendor for project specific requirements. Philips to provide list of "approved vendors".	Mike DiNapoli from Philips stated the (2) approved vendors are Lindgren & Universal. 03.29.2021- NELCO has been added by Philips as an approved RF Shielding Vendor.
4	HVAC Equipment	Please provide schedule/spec on HVAC equipment tagged: AC-1, AC-2, AC-3, AC-4.	"Equipment Room AC Schedule" provided in Bidding Addendum 1; Sheet H900.
5	Dewatering	Please clarify extent of dewatering. Would it be prudent to carry an allowance at this time?	GC should include budget to provide a "temporary sump" during duration of slab construction in MRI area. Please see notes on S201 & S800 for waterstop and waterproofing admixture requirements.
6	Temporary partitions	Will stark wall be sufficient for temp partitions / temp enclosures?	Properly installed (meeting ICRA requirements) Starc Systems walls are acceptable.
7	Door Hardware Schedule	Will/Can a specification be issued for the Hollow Metal and Door Hardware?	Final hardware being coordinated with GSH vendor. It will be distributed in or before final Bid addendum.
8	Steam Generator	Schedule Sheet drawing H900 shows a new steam generator tagged H-1. MER drawing H700 talks about an existing clean steam skid.	H-1 is a new clean steam generator that will be serving AHU-19. It shows up on 2/H201.2 and is in the AC-1 mechanical room.

Bidding RFI Responses and additional information

CPL Project #15068.00 – March 29,2021 - **UPDATED**

		<p>a. Is the H-1 steam generator new or existing?</p> <p>b. If it is new, H-1 does not appear on any of the floor plans.</p>	
9	BMS Contractor	Is there a BMS Contractor for this project?	Siemens Charlie Smigen 1-973-583-6483
10	Fire Alarm Contractor	Is there a fire alarm vendor for this project?	Simplex/Johnson Controls; contact name pending from GSH.
11	Allowances	B of subsection 1.06, Section 012100 Allowances states that the 'Contractors overhead, profit, for work under the contingency allowance is included in the Contract sum and is not part of the allowance'. Please clarify.	Response pending...
12	ACT-3	ACT-3 according to the Finish Schedule is size 2x2. Some corridors on plan A103 show 2x4 ACT tiles as ACT-3. Please clarify.	Room Finish Schedule will be updated as part of final Bid Addendum; an appropriate 2'x4' tile will be added.