



ADDENDUM NO. 1

PROJECT: Ossining Union Free School District - HVAC Improvements

CPL PROJECT NO. 14428.16/17

SED PROJECT NO. 66-14-01-03-0-004-023/042

DATE: March 19, 2021

Include this Addendum as part of the Contract Documents. It supplements portions of the original specifications and drawings, the extent of which shall remain, except as revised herein:

CLARIFICATIONS:

- 1.1 See attached Sign in sheet from the Pre-bid walkthrough on March 11rd 2021 at 4pm.**
- 1.2 Roofing work shall be done by a Carlisle authorized contractor to maintain buildings existing roof warranty.**
- 1.3 Case work modifications at the Park Elementary school shall be coordinated with the district. The District is responsible for reworking casework as needed for the replacement of the unit ventilators.**
- 1.4 The Park elementary school building is eligible for listing in the state and national registers of historic places. The proposed replacement of the exterior louvers can be wider than those currently extant however, the number of louvers, their locations on the façade and height shall remain the same. See schedule on PES/H900 for new louver sizes.**

CHANGES TO THE PROJECT MANUAL:

- 1.5 Specification section 01 1000**
 - a) Remove 1.7.A. and replace with the following:**
 - A. On-Site Work Hours: Work shall be between the hours of 7:00 a.m. to 4:00 p.m., Monday through Friday, except otherwise indicated.**
 - 1. Weekend Hours: Coordinate work during weekend hours with the Owner.**
 - 2. Early Morning and Evening Hours: Coordinate work hours with the Owner.**
 - 3. Hours for Utility Shutdowns: Coordinate hours for utility shutdowns with the Owner.**



CHANGES TO THE PROJECT DRAWINGS:

- 1.6 Refer to drawing PES-E203, Electrical Equipment Wiring Schedule, Item Number 1.
Replace wiring size shown with “(3) #10, (1) #10G in 3/4” conduit.**
- 1.7 Refer to drawing PES-E203, Electrical Equipment Wiring Schedule, Item Number 1.
Replace panel/circuit shown with “2N-50,52,54”.**

END OF ADDENDUM NO. 1



OSSINING

UNION FREE SCHOOL DISTRICT



ARCHITECTURE
ENGINEERING
PLANNING
CPLteam.com

Ossining UFSD-
HVAC Improvements

Project: 14428.16, 14428.17

Pre-Bid meeting 4:00 PM Thursday, March 11, 2021

7

	NAME	COMPANY	PHONE NUMBER	EMAIL ADDRESS
1)	MARK MATSZEWSKI	DELTA ELECTRIC	914-376-5911	mma@pscdeltaelectricinc.nc
2)	ZACH MULKERN	MENGLER	(845) 279 7029	ZMULKERN@MENGLERMEDIA
3)	Nicholas Lopinto	CAQS	914 355 1384	nlopinto@caqs.com
4)				
5)				
6)				
7)				
8)				