

**BID ADDENDUM NO. 1**

OWNER: PORT CHESTER – RYE UNION FREE SCHOOL DISTRICT  
113 BOWMAN AVE.  
RYE BROOK, NY 10573

PROJECT NAME: PORT CHESTER FLOOD REPAIRS AND RELATED WORK  
JOHN F. KENNEDY ELEMENTARY SCHOOL

F&D PROJECT #: 21444.01

The items set forth herein, whether of omission, addition, substitution, or clarification are to be included in and form a part of the proposal submitted. This Addendum is hereby included in and made a part of the Contract Documents, dated 10/18/2021 whether or not attached thereto. All requirements of the original project specifications and drawings shall remain in force except as amended by this addendum.

DATE: October 21, 2021

This addendum consists of one (1) page.

**THE FOLLOWING ARE MODIFICATIONS, CLARIFICATIONS, DELETIONS OR ADDITIONS TO THE SPECIFICATIONS:**

**SECTION 01 1000 SUMMARY OF CONTRACT**

Paragraph 1.11 A. 2. a.

Delete in its entirety and substitute the following:

Start of Construction thru Substantial Completion:

- a. 7:30 AM thru 10:30 PM. Monday thru Friday.
- b. Exception: All work in Stairs A & B shall be performed between 3:30 PM and 10:30 PM when school is not in session.

**SECTION 01 1500 TEMPORARY FACILITIES AND CONTROL**

Delete all references to Temporary Heat and Lighting.

**SECTION 08 1113 HOLLOW METAL DOORS AND FRAMES**

Add the following new section:

“1.8 Temporary Doors: In the event that project doors will not be installed by the date of Substantial Completion, the Contractor shall provide temporary doors and hardware.

1. Type of door shall be Contractor's option wood or metal.
2. Door fire ratings and hardware shall be as indicate on the Door Schedule.

Schedule installation with Owner's Representative.

**SECTION 09 3000 TILING**

Paragraph 2.3. SETTING MATERIALS

2.3.A.3 Applications: Delete “for all walls and floors” and substitute “for all floors”.

Add new paragraph “2.3.A.4: Mapei Corporation: Product Keraflex Plus use for all walls”.

Paragraph 3.2.A: Add the following: “and completely scarified off the concrete block”.

Paragraph 3.5.A: Delete in its entirety and substitute “Over cementitious backer units and masonry install in accordance with TCNA (HB) Method W223, with specified adhesive and grout.”

**END OF BID ADDENDUM NO. 1**