

Principals:

Mark D. Fellenzer, P.E., LEED AP  
John D. Fellenzer, P.E., MBA, LEED Green Associate

Founder:

Archie D. Fellenzer, Jr., P.E.  
(1924 - 2014)

## ADDENDUM NO. # 1

The information contained herein, revises, supplements, and/or supersedes the specific parts of the documents referred to and shall be attached to and become part of such documents as if originally forming a part thereof. Except as herein modified, all other provisions of the documents shall remain in full force as originally set forth.

**ISSUED TO:** FILBEN GROUP

**PROJECT:** Braemar at Montebello Assisted Living  
F.E. Project No. 15-345

**DATE:** February 28, 2020

**ISSUED BY:** Erik Raessler

**PAGES :** 1 Page plus attachment.

**ATTACHMENT:** Sketches showing specification and location of water storage tank ST-1.

---

### **REQUESTS FOR INFORMATION (Questions with Responses in Italics):**

1. RE: Specifications 23 3113, Page 7 Item C.9 & Page 14 Item G.1:  
Specifications above indicate liner is to be double wall ductwork with 2" thick insulation.  
Item G.1 indicates Supply Air Ducts to be lined. Is it the intention that all supply ductwork on the project is to be lined up to air outlets?  
*There is no intention to use duct liner in any ductwork. Disregard any specification section that requires duct liner. All insulation requirements shall be found in Specification 23 0713.*
2. No spec for F.S. supplied.  
*Floor sinks in the kitchen shall be Zurn model Z1750-SCD 12"x12"x6" type 304 stainless steel.*
3. There is a toilet labeled WC-4 and no spec supplied.  
*All toilets labeled WC-4 shall be labeled WC-3.*

-----END OF ADDENDUM-----