



15 14 13 12 11 10 9 8 7 6 5 4 3 2 1

L  
K  
J  
H  
G  
F  
E  
D  
C  
B  
A

GENERAL NOTES	
1	THE CONTRACTOR SHALL PROTECT EXISTING SERVICES AND EQUIPMENT DURING THE WORK.

REMOVAL KEYED NOTES:	
R1	REMOVE EXISTING AIR HANDLER AND ALL ASSOCIATED DUCTWORK BACK TO EXTENT OF THE ROOM. REMOVE EXISTING CEILING SUPPORTS. REMOVE PIPING BACK TO MAIN AND CAP. REMOVE EXISTING CONTROL WIRING. PREPARE PIPING FOR NEW INSTALLATION.
R2	REMOVE EXISTING EXHAUST FAN. MC TO PROVIDE AND INSTALL CAP AND INSULATION ON EXISTING ROOF CURB. EXISTING FLASHING ON FAN CURB IS HOT WITH ASBESTOS, AVOID CONTACT. REFER TO DETAIL 8/MS-H501
R3	DISCONNECT AND REMOVE EXISTING FIN TUBE HEATERS AND ASSOCIATED HOT WATER SUPPLY/RETURN PIPING
R4	EXISTING O.A. LOUVERS TO BE REMOVED BY M.C. G.C. TO PROVIDE NEW WINDOWS TO MATCH EXISTING

VEST. B-17

ENTRY #15

GYMNASIUM B-18

14

1

GYMNASIUM HVAC REMOVAL PLAN

MS-H101

SCALE: 1/8" = 1'-0"

0

4'

8'

16'

SCALE: 1/8" = 1'-0"

STATE OF NEW YORK

SEAL

REIS SANDOZ

2024.10.25

ARCHITECT



NEW YORK OKLAHOMA NORTH CAROLINA  
TEXAS COLORADO

**KSQ Design**  
215 West 40th Street | 15th Floor  
New York, NY 10018  
914.682.3700 office  
[www.ksq.design](http://www.ksq.design)

Owner

**Yorktown Central School District**  
2725 Crompond Road  
Yorktown Heights, NY 10598  
914 243 8000 office

### Construction Manager

Arris Contracting Co.  
189 Smith Street  
Poughkeepsie, NY 12601  
845 473 6300 office  
845 473 1453 fax

**MEP Engineer**

DELTA Engineers, Architects, & Land  
Surveyors, DPC  
220 Harborside Dr, Suite #202  
Schenectady, NY 12305  
518.690.0046 office

**Structural Engineer**

Clapper Structural Engineering, PLLC  
160 Partition Street  
Saugerties, New York 12477  
845.943.9601 office  
[www.clapperstructural.com](http://www.clapperstructural.com)

**Civil Engineer**

The Chazen Companies  
547 River Street  
Troy, New York 12180  
518.266.7323 office  
[www.chazencompanies.com](http://www.chazencompanies.com)

SED CONTROL NUMBERS	
1	2
3	4
5	6
7	8
9	10
11	12
13	14
15	16
17	18
19	20
21	22
23	24
25	26
27	28
29	30
31	32
33	34
35	36
37	38
39	40
41	42
43	44
45	46
47	48
49	50
51	52
53	54
55	56
57	58
59	60
61	62
63	64
65	66
67	68
69	70
71	72
73	74
75	76
77	78
79	80
81	82
83	84
85	86
87	88
89	90
91	92
93	94
95	96
97	98
99	100

YHS - #66-24-02-06-0-005-028  
MS - #66-24-02-06-0-007-027  
CES - #66-24-02-06-0-003-022  
MES - #66-24-02-06-0-004-025  
BES - #66-24-02-06-0-002-020



DISTRICT WIDE  
IMPROVEMENTS 2020  
PHASE II

MILDRED E. STRANG  
MIDDLE SCHOOL  
2701 CROMPOND RD.  
YORKTOWN HEIGHTS, NY 10598

## REVISIONS

[illegible]

ISSUED: BID ISSUE

DATE: 10/25/2021


**SCALE:** AS NOTED

**SHEET NAME:**  
GYMNASIUM REMOVAL  
PLAN


SHEET NUMBER:

MS-H101






### 3 ROOF PIPING PENETRATION DETAIL



**SEQUENCE OF OPERATION**

1. PUMP STARTS ON CALL FOR HEAT AND 3-WAY VALVE SHALL MODULATE TO MAINTAIN SPACE TEMPERATURE WITHOUT CYCLING.
2. FREEZE PROTECTION OVERRIDE, OF OA. TEMPERATURE <35° PUMP IS ON 3-WAY OPENS TO BYPASS IF NOT HEATING.

NOTE
1. SET BALANCING VALVES TO EQUAL THE PRESSURE DROP ACROSS THE HYDRONIC COIL




NOTE: SEE SPECIFICATION 23 05 40 "HANGER & SUPPORTS"

NOTE: ADD WIND RESTRAINTS AS NEEDED.


NOTE: SUPPORT DUCTWORK EVERY 10 FT. EVERY OTHER DUCT SUPPORT MAY BE MOUNTED ON FEET DIRECTLY ON ROOF MEMBRANE INSTEAD OF BEING ANCHORED TO THE ROOF DECK.

NOTE: REFER TO 6/MS-H501


1 DUCTWORK ROOF SUPPORT DETAIL 1 (ANCHORED)  
MS-H501 SCALE: NOT TO SCALE



6 DUCTWORK ROOF SUPPORT DETAIL 2 (UN-ANCHORED)  
MS-H501 SCALE: NOT TO SCALE




5 RTU ROOF CURB DETAIL  
MS-H501 SCALE: NOT TO SCALE




NOTE: MC TO REMOVE ROOFING AND INSULATION AS REQUIRED AND ROOFING CONTRACTOR TO REPAIR ROOFING AND INSULATION PER ROOFING MANUFACTURERS REQUIREMENTS.


4 DUCTWORK ROOF PENETRATION AND SUPPORT DETAIL  
MS-H501 SCALE: NOT TO SCALE



8 ROOF CURB CAP DETAIL  
MS-H501 SCALE: NOT TO SCALE



7 DUCTSOX SUSPENSION DETAIL  
MS-H501 SCALE: NOT TO SCALE



VENTILATION REQUIREMENTS								
Space Designation	Area SF	Occupants /1000 SF	Total	Ventilation Required Per Occup.	Per SF	Uncorrected Ventilation	Efficiency Factor	Corrected CFM
MS Gym	6,100	7	43	20.00	0.18	1,950	80%	2,440
Total	6,100		43			1,950	80%	2,440

PUMP SCHEDULE											
TAG	SERVICE	TYPE	FLUID	GPM	HEAD	RPM	ELECTRICAL		DISCONNECT		
							HP	VOLTS/PH/HZ	TYPE	FURNISHED BY	INSTALLED BY
P-4	RTU-4	IN-LINE CIRC.	HW	15	23	1725	3/4	120/1/60	SWITCH	EC	EC
P-5	RTU-5	IN-LINE CIRC.	HW	15	23	1725	3/4	120/1/60	SWITCH	EC	EC

TAG	SERVICE	TYPE	AIRFLOW (CFM)	OUTSIDE AIR (CFM)	SUPPLY FAN				EXHAUST FAN				DX COOLING										HEATING								NOTES	BASIS OF DESIGN
					ESP (IN. WG)	TOTAL SP (IN. WG)	FAN TYPE	HP	ESP (IN. WG)	TOTAL SP (IN. WG)	FAN TYPE	HP	CAPACITY					ENTERING AIR (MIXED)		LEAVING AIR		ENTERING WATER (°F)	LEAVING WATER (°F)	ENTERING AIR DRY BULB (°F)	LEAVING AIR DRY BULB (°F)	GPM	WATER PD (FT)	AIR PD (IN)	OUTPUT MBH	MEDIUM		
													IEER	NOMINAL TONAGE	TOTAL (MBH)	SENS. (MBH)	LATENT (MBH)	DRY BULB (°F)	WET BULB (°F)	DRY BULB (°F)	WET BULB (°F)											
RTU-4	GYMNASIUM	RTU	6250	1300	1.5	3	PLENUM	7.5	.75		PLENUM	5	14.2	16	200.18	166.83	33	79	64.76	53.8	53.64	180	150	59.4	99	15	1.1	0.5	276	HW	1,2,3,4,5,6	AAON
RTU-5	GYMNASIUM	RTU	6250	1300	1.5	3	PLENUM	7.5	.75		PLENUM	5	14.2	16	200.18	166.83	33	79	64.76	53.8	53.64	180	150	59.4	99	15	1.1	0.5	276	HW	1,2,3,4,5,6	AAON

1. COORDINATE SIZE AND LOCATION OF UNIT WITH EXISTING FRAMING, MOUNT/SECURE/ANCHOR UNIT ON DUNNAGE PROVIDED BY GC.

2. COORDINATE SIZE AND LOCATION OF ROOF PENETRATIONS WITH GC FOR SUPPLY AND RETURN DUCT.

3. ALL WORK IS R.Y.M.C. (ABAJTMENT, STEEL, CURBS, ROOF FLASHING, ETC.). ONLY ITEM EXCLUDED IS ELECTRICAL BY EC.

4. PROVIDE SMOKE DETECTOR IN RETURN AIR STREAM.

5. PROVIDE 2 STAGE FILTER; 2" MERV-8 & 4" MERV-14.

6. RTU SHALL HAVE A FRONT, HORIZONTAL DISCHARGE AND BOTTOM, VERTICAL RETURN

1. COORDINATE SIZE AND LOCATION OF UNIT WITH EXISTING FRAMING. MOUNT/SECURE/ANCHOR UNIT ON DUNNAGE PROVIDED BY GC.
2. COORDINATE SIZE AND LOCATION OF ROOF PENETRATIONS WITH GC FOR SUPPLY AND RETURN DUCT.
3. ALL WORK IS BY MC (ABATEMENT, STEEL, CURBS, ROOF FLASHING, ETC.). ONLY ITEM EXCLUDED IS ELECTRICAL BY EC.

4. PROVIDE SMOKE DETECTOR IN RETURN AIR STREAM
5. PROVIDE 2 STAGE FILTER; 2" MERV-8 & 4" MERV-14
6. RTU SHALL HAVE A FRONT, HORIZONTAL DISCHARGE AND BOTTOM, VERTICAL RETURN



## CAFETERIA RTU CONTROL DIAGRAM

### GYM RTU SEQUENCE OF OPERATION

## UNOCCUPIED MODE:

1. WITHOUT A CALL FOR HEAT THE RTU SHALL SHUT DOWN.
  - A. THE FAN CONTROLLER SHALL BE IN THE OFF POSITION.
  - B. THE OUTSIDE AIR AND RETURN AIR DAMPERS SHALL BE CLOSED.
2. UPON A CALL FOR HEAT THE RTU SHALL OPERATE AS FOLLOWS:
  - A. THE NIGHT SETBACK TEMPERATURE SHALL BE:
    - I. HEATING: 62 DEGREES (ADJUSTABLE)
    - II. COOLING: NO OPERATION
  - B. THE RETURN AIR DAMPER SHALL OPEN TO 100%
  - C. THE SUPPLY FAN SHALL RAMP TO FULL SPEED
  - D. THE 3-WAY HOT WATER CONTROL VALVE SHALL MODULATE FULLY OPEN AND THE CIRCULATING PUMP SHALL START.
  - E. WHEN THE SPACE TEMPERATURE REACHES THE SETPOINT THE UNIT SHALL SHUT DOWN IN REVERSE ORDER OF THE STARTUP.

## FREEZE PROTECTION

1. IF THE OAT < 40° F THE COIL CIRCULATING PUMP SHALL START
2. THE 3-WAY VALVE SHALL OPEN TO THE COIL A MINIMUM OF 10% FLOW.
3. THE 3-WAY VALVE SHALL FURTHER MODULATE AS REQUIRED TO MAINTAIN SPACE TEMPERATURE.

### PRE-OCCUPIED START-UP.

3. THE PRE-OCCUPIED START TIME SHALL BE ONE HOUR BEFORE THE START OF SCHOOL (ADJUSTABLE). AT THIS TIME:
  - A. THE RETURN AIR DAMPER SHALL OPEN
  - B. THE OUTSIDE AIR DAMPER SHALL REMAIN CLOSED UNLESS THERE IS A CALL FOR "FREE COOLING"
  - C. THE SUPPLY FAN SHALL START
  - D. THE SYSTEM SHALL BRING THE SPACE TO NORMAL OCCUPIED TEMPERATURES.
  - E. 30 MINUTES BEFORE NORMAL OCCUPANCY THE OA DAMPER SHALL OPEN TO 50% AND THE RELIEF AND RETURN AIR DAMPERS ADJUSTING TO MAINTAIN THE DESIGN AIR FLOW
4. SETPOINT TEMPERATURES ARE THE NORMAL OCCUPIED VALUES
5. ON A CALL FOR HEAT: THE 3-WAY CONTROL VALVE SHALL OPEN AND STARTING THE CIRCULATING PUMP SHALL START.
6. ON A CALL FOR COOLING THE VRF COMPRESSOR SHALL START IF FREE COOLING IS NOT AVAILABLE.

1. SETPOINT TEMPERATURES:
  - A. HEATING: 68 ° F (ADJUSTABLE)
  - B. COOLING: 72 ° F (ADJUSTABLE)
  - C. FREE COOLING SETPOINT OAT 5° F < RAT (ADJUSTABLE)
2. OCCUPIED SCHEDULE OPERATION:
  - A. THE OCCUPIED SCHEDULE SHALL BE UNIQUELY PROGRAMMABLE FROM THE BUILDING CONTROL HEAD END. INITIAL SETTINGS:
    - I. FROM 30 MINUTES PRIOR TO THE FIRST LUNCH PERIOD UNTIL 30 MINUTES AFTER THE LAST LUNCH PERIOD.
    - II. AFTER THE FINAL LUNCH PERIOD THE CAFETERIA RTU SHALL RETURN TO THE PRE-OCCUPIED MODE UNTIL THE END OF THE SCHOOL DAY.
  - B. THE SUPPLY FAN SHALL CONTINUE TO OPERATE NORMALLY.
  - C. THE OUTSIDE AIR DAMPER SHALL OPEN TO THE MINIMUM POSITION.
    - I. MINIMUM OUTSIDE AIR/UNIT: 2800 CFM (ADJUSTABLE)
    - II. IF IN COOLING MODE THE CONTROLLER SHALL EVALUATE THE POTENTIAL FOR FREE COOLING AND ADJUST THE OUTSIDE AIR, RETURN AIR, RELIEF DAMPERS AND POWERED EXHAUST ACCORDINGLY.
  - D. THE CONTROLLER SHALL CONTINUE TO MONITOR THE SPACE TEMPERATURE AND MODULATE THE HOT WATER CONTROL VALVE OR THE VRF SYSTEM ACCORDINGLY.
3. SPECIAL EVENT OVERRIDE:
  - A. THE SYSTEM SHALL HAVE AN OVERRIDE FUNCTION THAT MAY BE INITIATED BY THE HEAD END COMPUTER. THE OVERRIDE SHALL BE ABLE SPECIFY THE DATE, START AND FINISH TIMES OF THE EVENT.
  - B. THE OVERRIDE COMMAND WILL HAVE A BUILT IN ONE-HOUR PRE-OCCUPIED CYCLE.

## STATUS ALARMS AND SETPOINTS

1. THE CONTROLLER SHALL INTERFACE EITHER DIRECTLY OR VIA A BACNET CONNECTION WITH BUILDING AUTOMATION SYSTEM'S HEAD END.
2. THE HEAD SHALL AT A MINIMUM BE ABLE TO READ THE STATUS OF THE FOLLOWING:
  - A. SPACE TEMPERATURE AND SETPOINT
  - B. FAN STATUS
  - C. CIRCULATING PUMP STATUS
  - D. HOT WATER CONTROL VALVE POSITION
  - E. DX COOLING STATUS.
    - I. SUPPLY AIR TEMPERATURE
3. ADJUSTABLE SETPOINTS SHALL INCLUDE:
  - A. SPACE TEMPERATURE
  - B. OCCUPANCY SCHEDULE
  - C. SPECIAL EVENT OVERRIDE
  - D. MINIMUM SUPPLY AIR TEMPERATURE.
4. THE FOLLOWING ALARMS SHALL BE REPORTED:
  - A. SPACE TEMPERATURE 3 DEGREES ABOVE OR BELOW THE SETPOINT (ADJUSTABLE)
  - B. DIRTY FILTER AS MEASURED BY DIFFERENTIAL PRESSURE
  - C. FAN FAILURE
  - D. DX COMPRESSOR FAILURE
  - E. HIGH FAN STATIC PRESSURE
5. SMOKE ALARM:
  - A. THE SMOKE DETECTOR SHALL REPORT TO THE FIRE ALARM SYSTEM WHICH WILL SHUT THE RTU DOWN IN THE EVENT OF FIRE/SMOKE

1  
MS-H701

### CAFE ROOFTOP UNIT SEQUENCE OF OPERATIONS

SCALE: NTS



ARCHITECT

ksqdesign

NEW YORK OKLAHOMA NORTH CAROLINA  
TEXAS COLORADO

**KSQ Design**  
215 West 40th Street | 15th Floor  
New York, NY 10018  
914.682.3700 office  
[www.ksq.design](http://www.ksq.design)

## Owner

**Yorktown Central School District**  
2725 Crompond Road  
Yorktown Heights, NY 10598  
914 243 8000 office

### Construction Manager

Arris Contracting Co.  
189 Smith Street  
Poughkeepsie, NY 12601  
845 473 6300 office  
845 473 1453 fax

**MEP Engineer**

DELTA Engineers, Architects, & Land  
Surveyors, DPC  
220 Harborside Dr, Suite #202  
Schenectady, NY 12305  
518.690.0046 office

## Structural Engineer


Clapper Structural Engineering, PLLC  
160 Partition Street  
Saugerties, New York 12477  
845.943.9601 office  
[www.clapperstructural.com](http://www.clapperstructural.com)

## Civil Engineer

The Chazen Companies  
547 River Street  
Troy, New York 12180  
518.266.7323 office  
[www.chazencompanies.com](http://www.chazencompanies.com)

**SED CONTROL NUMBERS**

YHS - #66-24-02-06-0-005-028  
MS - #66-24-02-06-0-007-027  
CES - #66-24-02-06-0-003-022  
MES - #66-24-02-06-0-004-025  
BES - #66-24-02-06-0-002-020



## DISTRICT WIDE IMPROVEMENTS 2020 PHASE II

MILDRED E. STRANG  
MIDDLE SCHOOL  
2701 CROMPOND RD.  
YORKTOWN HEIGHTS, NY 10598

## REVISIONS

[illegible]

**ISSUED:** BID ISSUE

DATE: 10/25/2021

**SCALE:** AS NOTED

**SHEET NAME:**  
CONTROL DIAGRAMS

SHEET NUMBER:

MS-H701