



**C1 SIGN POST BOLLARD DETAIL**  
NOT TO SCALE



C4 2' CONCRETE "TIP-OUT" CURB  
NOT TO SCALE



**C7 TREE PROTECTION DETAIL**  
NOT TO SCALE

A 6" LAYER OF COARSE MULCH OR WOODCHIPS IS TO BE PLACED BENEATH THE DRILLPILE OF THE PROTECTED TREE TO BE KEPT 12" FROM THE TRUNK.

2. A PROTECTIVE BARRIER OF 6" CHAIN LINK FENCING SHALL BE INSTALLED AROUND THE DRILLPILE OF PROTECTED TREES (S). THE FENCING CAN BE MOVED WITHIN THE DRILLPILE IF AUTHORIZED BY THE PROJECT ARBORIST OR C.O.R. BUT NOT CLOSER THAN 2' FROM THE TRUNK OF ANY TREE. FENCE POSTS SHALL BE 1.5" IN DIAMETER AND ARE TO BE DRIVEN 2' INTO THE GROUND. THE DISTANCE BETWEEN TREES SHALL NOT BE MORE THAN 12'. THIS ENCLOSED AREA IS THE TREE PROTECTION ZONE (TPZ).

3. MOVABLE BARRIERS OF CHAIN LINK FENCING SECURED TO CENTRAL BLOCKS CAN BE SUBSTITUTED FOR "FIXED" FENCING IF THE PROJECT ARBORIST AND C.O.R. AGREE THAT THE FENCING WILL HAVE TO BE MOVED TO ACCOMMODATE CERTAIN PHASES OF CONSTRUCTION. THE BUILDER MAY NOT MOVE THE FENCE WITHOUT AUTHORIZATION FROM THE PROJECT ARBORIST OR C.O.R.

4. WHERE THE C.O.R. OR PROJECT ARBORIST HAS DETERMINED THAT TREE PROTECTION FENCING WILL INTERFERE WITH THE USE OF THE SITE FOR CRANES, TREE WRAPS MAY BE USED AS AN ALTERNATIVE FORM OF TREE PROTECTION. WOODEN SLATS AT LEAST ONE INCH THICK ARE TO BE BOUND SECURELY, EDGE TO EDGE, AROUND THE TRUNK. A SINGLE LAYER OF MORE OR ORANGE PLASTIC CONSTRUCTION FENCING IS TO BE WRAPPED AND SECURED AROUND THE OUTSIDE OF THE WOODEN SLATS. THE FENCING SHALL BE SECURED TO THE TRUNK OF THE TREE BY THE PROJECT ARBORIST. STRAW WADDOLE OR MORE PLASTIC CAN ALSO BE USED AS A TRUNK WRAP BY COILING THE WADDOLE AROUND THE TRUNK UP TO A MINIMUM HEIGHT OF SIX FEET FROM GRADE. A SINGLE LAYER OF MORE OR ORANGE PLASTIC CONSTRUCTION FENCING IS TO BE WRAPPED AND SECURED AROUND THE STRAW WADDOLE.

5. ALLOW THE FOLLOWING CONDITIONS TO DO NOT:

a. ALLOW RUN OFF OF SPILLAGE OF DAMAGING MATERIALS INTO THE AREA BELOW ANY TREE CANOPY.

b. STORE OR MATERIALS, STOCKPILE SOIL, OR PARK OR DRIVE VEHICLES WITHIN THE TPZ.

c. CUT, BREAK, SNIP, OR BRUISE ROOTS, BRANCHES, OR TRUNKS WITHOUT FIRST OBTAINING AUTHORIZATION FROM THE C.O.R.

6. ALLOW FIRES UNDER AND ADJACENT TO TREES.

d. DISCHARGE EXHAUST INTO FOLIAGE.

e. SECURE CHAIN, CHAIN, OR ROPE TO TREES OR SHRUBS.

7. TRENCH, DIG OR OTHERWISE EXCAVATE WITHIN THE DRILLPILE OR TPZ OF THE TREE(S) WITHOUT FIRST OBTAINING AUTHORIZATION FROM THE C.O.R.

h. APPLY SOIL STERILANTS UNDER PAVEMENT NEAR EXISTING TREES.

8. ONLY EXCAVATION BY HAND OR COMPRESSED AIR SHALL BE ALLOWED WITHIN THE DRILLPILE OF TREES. MACHINE TRENCHING SHALL NOT BE ALLOWED.

9. AVOID INJURY TO TREE ROOTS. WHEN A DITCHING MACHINE, WHICH IS BEING USED OUTSIDE OF THE DRILLPILE OF TREES, ENCOUNTERS ROOTS SMALLER THAN 2" THE WALL OF THE TRENCH ADJACENT TO THE TREES SHALL BE HAND TRIMMED, MAKING CLEAR, CLEAN CUTS THROUGH THE ROOTS. ALL DAMAGED, TORN OR CUT TREES SHALL BE GIVEN A CHANCE TO RECOVER AND SHOULD BE PROMPTLY DECAY. TRENCHES SHALL BE FILLED WITHIN 24 HOURS, BUT WHERE THIS IS NOT POSSIBLE, THE SIDE OF THE TRENCH ADJACENT TO THE TREES SHALL BE KEPT SHAD WITH FOUR LAYERS OF DAMPENED, UNTREATED BURLAP WETTED AS FREQUENTLY AS NECESSARY TO KEEP THE BURLAP WET. ROOTS DAMAGED BY TRENCHING SHALL BE REPORTED TO THE PROJECT ARBORIST, WHO WILL DECIDE WHETHER THE CONTRACTOR MAY CUT THE ROOT AS MENTIONED ABOVE OR SHALL EXCAVATE AND REMOVE THE DAMAGED, COMPRESSED AIR FROM THE ROOT. ROOT IS TO BE PROTECTED WITH DAMPENED BURLAP.

10. ROUTE PIPES OUTSIDE OF THE AREA THAT IS 10 TIMES THE DIAMETER OF A PROTECTED TREE TO AVOID CONFLICT WITH TREES.


9. WHERE IT IS NOT POSSIBLE TO REROUTE PIPES OR TRENCHES, THE CONTRACTOR SHALL BORE BENEATH THE DRILLPILE OF THE TREE. THE BORING SHALL TAKE PLACE NOT LESS THAN 3' BELOW THE SURFACE OF THE SOIL IN ORDER TO AVOID ENCOUNTERING 'FEEDER' ROOTS.

10. ANY DAMAGE DUE TO CONSTRUCTION ACTIVITIES SHALL BE REPORTED TO THE PROJECT ARBORIST OR C.O.R. WITHIN SIX HOURS SO THAT REMEDIAL ACTION CAN BE TAKEN.

11. AN ISA CERTIFIED ARBORIST OR ASCA REGISTERED CONSULTING ARBORIST SHALL BE RETAINED AS THE PROJECT ARBORIST TO MONITOR THE TREE PROTECTION SPECIFICATIONS. THE PROJECT ARBORIST SHALL BE RESPONSIBLE FOR THE TREE PROTECTION AND TREES. SHOULD THE BUILDER FAIL TO FOLLOW THE TREE PROTECTION SPECIFICATION IT SHALL BE THE RESPONSIBILITY OF THE PROJECT ARBORIST TO REPORT THE MATTER TO THE C.O.R. AS AN ISSUE OF NON-COMPLIANCE.

12. VIOLATION OF ANY OF THE ABOVE PROVISIONS MAY RESULT IN SANCTIONS OR OTHER DISCIPLINARY ACTION.

IT IS REQUIRED THAT THE SITE ARBORIST PROVIDE PERIODIC INSPECTIONS DURING CONSTRUCTION. FOUR-WEEK INTERVALS WOULD BE SUFFICIENT TO ACCESS AND MONITOR THE EFFECTIVENESS OF THE TREE PROTECTION PLAN AND TO PROVIDE RECOMMENDATIONS FOR ANY ADDITIONAL CARE OR TREATMENT.



REDUCER THRUST BLOCK DIMENSIONING					
SIZE	WIDTH (FT-IN)	HEIGHT (FT-IN)	SIZE	WIDTH (FT-IN)	HEIGHT (FT-IN)
6x4 NPS	1'-6"	1'-6"	16x8 NPS	4'-6"	4'-6"
8x4 NPS	2'-3"	2'-3"	16x10 NPS	4'-0"	4'-0"
8x6 NPS	1'-9"	1'-9"	16x12 NPS	3'-6"	3'-6"
10x4 NPS	2'-6"	2'-6"	20x12 NPS	5'-0"	5'-0"
10x6 NPS	2'-0"	2'-0"	20x16 NPS	4'-0"	4'-0"
12x4 NPS	3'-3"	3'-3"	24x12 NPS	6'-6"	6'-6"
12x6 NPS	3'-0"	3'-0"	24x16 NPS	5'-9"	5'-9"
12x10 NPS	2'-3"	2'-3"	24x20 NPS	6'-6"	4'-6"


PIPE SIZE	WIDTH (FT-IN)	HEIGHT (FT-IN)	PIPE SIZE	WIDTH (FT-IN)	HEIGHT (FT-IN)
4 NPS	1'-0"	0'-6"	14 NPS	3'-0"	1'-3"
6 NPS	1'-3"	0'-9"	16 NPS	3'-3"	1'-9"
8 NPS	1'-9"	0'-9"	18 NPS	3'-6"	1'-9"
10 NPS	2'-0"	1'-0"	20 NPS	3'-6"	2'-0"
12 NPS	2'-3"	1'-3"	24 NPS	4'-6"	2'-3"

TEE/DEAD END THRUST BLOCK DIMENSIONING					
PIPE SIZE	WIDTH (FT-IN)	HEIGHT (FT-IN)	PIPE SIZE	WIDTH (FT-IN)	HEIGHT (FT-IN)
4 NPS	2'-0"	1'-0"	14 NPS	5'-6"	3'-3"
6 NPS	3'-0"	1'-3"	16 NPS	6'-6"	3'-6"
8 NPS	3'-3"	2'-0"	18 NPS	7'-6"	4'-0"
10 NPS	4'-3"	2'-3"	20 NPS	8'-6"	4'-3"
12 NDC	5'-3"	2'-6"	24 NDC	10'-3"	5'-3"

MINIMUM RESTRAINED LENGTH OF PIPE $\phi T=I_{D_0} L_0$										
FITTING	4 NPS	6 NPS	8 NPS	10 NPS	12 NPS	14 NPS	16 NPS	18 NPS	20 NPS	24 NPS
11 1/2" BEND	1'-3"	2'-0"	2'-6"	3'-0"	3'-6"	4'-0"	4'-6"	5'-0"	5'-6"	6'-3"
22 1/2" BEND	1'-3"	2'-0"	2'-6"	3'-0"	3'-6"	4'-0"	4'-6"	5'-0"	5'-6"	6'-6"
45° BEND	3'-0"	4'-0"	5'-3"	6'-3"	7'-6"	8'-6"	9'-6"	10'-6"	11'-6"	13'-6"
90° BEND	7'-0"	9'-9"	12'-6"	15'-6"	18'-0"	20'-0"	23'-0"	25'-6"	28'-0"	32'-6"
DEAD END	8'-6"	12'-6"	16'-0"	19'-3"	23'-0"	26'-0"	29'-6"	33'-0"	36'-0"	42'-0"

NOTES: PVC PIPE WILL TYPICALLY HAVE SLIGHTLY GREATER RESTRAINED LENGTH  
 NOTES FOR POLYETHYLENE WRAPPED PIPE, MULTIPLY VALUES IN TABLE BY 1.45

**F1 WATER THRUST RESTRAINT DETAILS**  
NOT TO SCALE



PANEL HEIGHT	NUMBER OF BRACKET KITS PER POST
77"H	3

Gate Post Dimensions		
Panel	Opening	Post
77"	3' to 5'	3" x 3" 11GA

HORIZONTAL LOUVERS	0.08" THICK
VERTICAL FLAT	2" x 11GA
VERTICAL WIRES	8GA

**F6 FENCE AND GATES AT GENERATOR PAD**  
NOT TO SCALE


VA FORM 08-6231

**MEP**  
550 North Reo Street, Suite 203  
Tampa, FL 33609  
(813) 289-4700  
Nicholas Stephenson, PE



**TRIPLE C - THE A&E GROUP**

**A MULTI-DISCIPLINE COMP.**



**VA** | U.S. Department  
of Veterans Affairs

Approved

CG505