



FIRE ALARM PLAN - DEMOLITION WORK

SCALE: 1/8" = 1'-0"

FIRE ALARM DEMOLITION KEYED NOTES (DENOTED AS ⚙)	
1.	THE EXISTING STAND ALONE OCCUPANT NOTIFICATION APPLIANCE AND THE ASSOCIATED CABLING/CONDUIT SHALL BE DEMOLISHED AND BE COMPLETELY REMOVED FROM THE FUTURE DOLLAR TREE SPACE. PROPERLY DISPOSE OF THE OCCUPANT NOTIFICATION APPLIANCE. EXISTING OCCUPANT NOTIFICATION APPLIANCE IS NOT CONNECTED TO THE FIRE ALARM SYSTEM.
2.	THE EXISTING STAND ALONE COMBINATION SMOKE / OCCUPANT NOTIFICATION APPLIANCE AND THE ASSOCIATED CABLING/CONDUIT SHALL BE DEMOLISHED AND BE COMPLETELY REMOVED FROM THE FUTURE DOLLAR TREE SPACE. PROPERLY DISPOSE OF THE SMOKE / OCCUPANT NOTIFICATION APPLIANCE. EXISTING COMBINATION SMOKE / OCCUPANT NOTIFICATION APPLIANCE IS NOT CONNECTED TO THE FIRE ALARM SYSTEM.

FIRE ALARM EXISTING TO REMAIN KEYED NOTES (DENOTED AS ◇)	
1.	THE EXISTING FIRE ALARM CONTROL PANEL AND ASSOCIATED EQUIPMENT LOCATED OUTSIDE THE DOLLAR TREE SPACE SHALL REMAIN AS CURRENTLY CONFIGURED. THE FIRE ALARM CONTROL PANEL SHALL TRANSMIT FIRE ALARM, SUPERVISORY, AND TROUBLE SIGNALS OFF-SITE AS CURRENTLY CONFIGURED.
2.	THE EXISTING FIRE SPRINKLER RISER SERVING THE DOLLAR TREE SPACE IS CURRENTLY LOCATED OUTSIDE OF THE PROPOSED DOLLAR TREE SPACE. ELECTRONICALLY MONITORED BY THE LANDLORDS FIRE ALARM CONTROL PANEL AND SHALL REMAIN AS CURRENTLY CONFIGURED.
3.	THE EXISTING DUCT SMOKE DETECTORS ARE ELECTRONICALLY SUPERVISED BY THE FIRE ALARM SYSTEM. THE ADDRESSABLE INPUT MODULES AND ASSOCIATED CABLING/CONDUIT SHALL REMAIN AS CURRENTLY CONFIGURED.

FIRE ALARM SYMBOL KEY	
	EXISTING STAND ALONE CEILING MOUNTED VISUAL APPLIANCE TO BE DISCONNECTED AND REMOVED (NOT CONNECTED TO FACP)
	EXISTING STAND ALONE COMBINATION CEILING MOUNTED AUDIBLE/VISUAL APPLIANCE & SMOKE ALARM - TO BE DISCONNECTED AND REMOVED (NOT CONNECTED TO FACP)
	EXISTING DUCT TYPE SMOKE DETECTOR TO REMAIN (R = RETURN SIDE)
	DUCT-TYPE PHOTOELECTRIC SMOKE DETECTOR (CONVENTIONAL) (POWERED BY RTU) (R = RETURN SIDE)
	STAND ALONE CARBON MONOXIDE ALARM (10 YEAR BATTERY OPERATED)
	NEW ADDRESSABLE INPUT MODULE (COMPATIBLE WITH EXISTING FACP)
	REMOTE TEST STATION / ANNUNCIATOR (SYSTEM SENSOR RTS1515KEY)
	FIRE ALARM PLENUM RATED CONDUCTORS (RED IN COLOR)
	JUNCTION BOX
	END OF LINE RESISTOR

370 WEST 40TH STREET 10TH FLOOR
NEW YORK, NY 10018
212 216 8866
www.ccdesignbuild.com

mark	date	by	description

06/15/2022	2022/7/10/2026	VA	ACD
date	project	designed	checked

Dean Associates
Architects Incorporated
Architecture & Interior Design
7 Kimball Lane Suite E6
Ipswich MA 01940
p: 781.397.8092 f: 781.397.8094
www.deanassoc.com

ENGINEER OF RECORD:
JACOB P. HEMKE, P.E.
LICENSE NO. 086219
FOUR CONVEYANCES:
PROFESSIONAL ENGINEER, P.E.
210 WEST 40TH ST., 10TH FLOOR
NEW YORK, NY 10018
PHONE: 212 216 8866
CORPORATE CERTIFICATE OF AUTHORITY
NO. 41885
WARNING: IT IS A VIOLATION OF THE NEW YORK STATE EDUCATION LAW, ARTICLE 145, SECTION 2109 FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT IN ANY WAY.

06/15/22

166 S. LIBERTY DRIVE - DEAL #13216 / STORE #2573
STONY POINT, NY 10980
FIRE ALARM PLAN - DEMOLITION WORK

project sheet

FAD1