

# DOOR SCHEDULE




DOOR											LABEL	HARDWARE	REMARKS			
NO.	DESCRIPTION	TYPE	WIDTH	HEIGHT	THICK	MATERIAL	FINISH	TYPE	MATERIAL	FINISH						
<b>LOWER LEVEL</b>																
102A	ELEVATOR EQUIP	DI	3'-0"	7'-0"	1-3/4"	H.M.	FNT	F2	H.M.	FNT	H-2	J-2	---	1 HR	H-1, L-4, C-2, D8-1, U8-2	
103A	STAIR 1	DI	3'-0"	7'-0"	1-3/4"	H.M.	FNT	F2	H.M.	FNT	H-2	J-2	---	1 HR	H-1, L-1, C-1, D8-1, U8-2	SIGN (S)
104A	STAIR 2	DI	3'-0"	7'-0"	1-3/4"	H.M.	FNT	F2	H.M.	FNT	H-2	J-2	---	1 HR	H-1, L-1, C-1, D8-1, U8-2	SIGN (S)

<b>1ST FLOOR</b>																	
201A	LOADING (EXT)	WI	5'-0"	7'-10"	1-3/4"	ALUM	PREFIN	WI	ALUM	PREFIN	3/ASJ	---	3/ASJ	---		HARDWARE BY DOOR MFR	AUTO SLIDING DOOR-COORD W/ ELEC
202A	STAIR 1	DI	3'-0"	7'-0"	1-3/4"	H.M.	FNT	F2	H.M.	FNT	H-2	J-2	---	1 HR	H-1, L-1, C-1, D8-1, U8-2	SIGN (S)	
202B	STAIR 1 (EXT)	DI	3'-0"	7'-0"	1-3/4"	INSUL H.M.	FNT	F2	H.M.	FNT	H-1	J-1	8-1	---	H-2, L-4, C-3, T-1, U8-1	SIGN (S)	
203A	STAIR 2	DI	3'-0"	7'-0"	1-3/4"	H.M.	FNT	F2	H.M.	FNT	H-2	J-2	---	1 HR	H-1, L-1, C-1, D8-1, U8-2	SIGN (S)	
203B	STAIR 2 (EXT)	DI	3'-0"	7'-0"	1-3/4"	INSUL H.M.	FNT	F2	H.M.	FNT	H-1	J-1	8-1	---	H-2, L-4, C-3, T-1, U8-1	SIGN (S)	
204A	SPRINK / PUMP (EXT)	DI	3'-0"	7'-0"	1-3/4"	INSUL H.M.	FNT	F2	H.M.	FNT	H-3	J-3	8-1	---	H-2, L-4, C-3, T-1, U8-1		
205A	ELECTRICAL	DI	3'-0"	7'-0"	1-3/4"	H.M.	FNT	F1	H.M.	FNT	H-4	J-4	---	---	H-1, L-4, C-2, D8-1, 8-1		

<b>2ND FLOOR</b>																
302A	STAIR 1	DI	3'-0"	7'-0"	1-3/4"	H.M.	FNT	F2	H.M.	FNT	H-2	J-2	---	1 HR	H-1, L-1, C-1, D8-1, U8-2	SIGN (S)
303A	STAIR 2	DI	3'-0"	7'-0"	1-3/4"	H.M.	FNT	F2	H.M.	FNT	H-2	J-2	---	1 HR	H-1, L-1, C-1, D8-1, U8-2	SIGN (S)

**HARDWARE LEGEND - INDICATED MANUFACTURERS ARE BASIS OF DESIGN**


H-1	HAGER BB127S HINGES 1-1/2" FR 4-1/2x4-1/2	652 (26D)	C-1	LCN 4030 HINGE SIDE MTD, 8NB	ALUM	T-1	NGP BUMPER SEAL THRESHOLD 0965	ALUM
H-2	HAGER BB181NRP HINGES 1-1/2" FR 4-1/2x4-1/2	630 (32D)	C-2	LCN 4030 EDA, PARALLEL ARM, 8NB	ALUM	U8-1	NGP WEATHERSTRIPPING 7006A, SWEEP 200NA ANOD	BLACK
			C-3	LCN 4040XP SCUSH, PARALLEL ARM, 8NB	ALUM	U8-2	NGP 5050C HEAD AND JAMB SMOKE SEAL	BLACK
L-1	SCHLAGE PASSAGE LATCH AL409-SAT	626				8-1	SILENCERS, HAGER 30TD	GRAY
L-2	SCHLAGE PRIVACY LOCK AL409-SAT	626						
L-3	SCHLAGE CLASSROOM LOCK AL10PD-SAT	626	D8-1	HAGER 234W WALL MTD DOOR STOP	652 (26D)			
L-4	SCHLAGE STOREROOM LOCK AL80PD-SAT	626						



### STORAGE UNIT DOORS

TYPE	DIMENSION	DESCRIPTION
A	8'-0" W x 7'-0" H	ROLL-UP
B	3'-0" W x 7'-0" H	ROLL-UP
C	8'-0" W x 7'-0" H	ROLL-UP
D	3'-0" W x 7'-0" H	ROLL-UP
E	6'-0" W x 7'-0" H	ROLL-UP
F	3'-0" W x 7'-0" H	SWING
G	3'-0" W x 7'-0" H	SWING ACCESSIBLE
H	8'-0" W x 7'-0" H	ROLL-UP AUTOMATIC OPERATOR

NOTE: STORAGE UNIT DOORS PROVIDE BY STORAGE UNIT SYSTEM MANUFACTURER



**DOOR AND WINDOW NOTES:**

- FIELD VERIFY ALL ROUGH OPENING DIMENSIONS.
- ON WINDOW AND DOOR TYPES INDICATES SAFETY GLASS LOCATIONS. PROVIDE SAFETY GLASS COMPLYING WITH CPSC 16 CFR 1201.

# FINISH SCHEDULE

NO.	ROOM	FLOOR	BASE	WALLS	CLG	REMARKS
<b>LOWER LEVEL</b>						
101	LOBBY	CONC-S	---	EXP/FI	EXP	FI AT CMU WALLS, U8-1
102	ELEVATOR EQUIP	CONC-S	---	CMU	GB-FI	
103	STAIR 1	CONC-S	---	CMU-FI	EXP	
104	STAIR 2	CONC-S	---	CMU-FI	EXP	
105	UNITS	CONC-S	---	EXP/FI	EXP	FI AT CMU WALLS
106	HALLWAY	CONC-S	HB-1	EXP/FI	EXP	FI AT CMU WALLS

<b>1ST FLOOR</b>						
201	LOADING	CONC-S	---	EXP/FI	EXP	FI AT CMU WALLS, U8-1
202	STAIR 1	CONC-S	---	CMU-FI	EXP	
203	STAIR 2	CONC-S	---	CMU-FI	EXP	
204	SPRINK / PUMP	CONC-S	---	EXP/FI	EXP	FI AT GB WALLS
205	ELECTRICAL	CONC-S	---	EXP/FI	EXP	FI AT GB WALLS
206	UNITS	CONC-S	---	EXP/FI	EXP	FI AT CMU WALLS
207	HALLWAY	CONC-S	HB-1	EXP/FI	EXP	FI AT CMU WALLS

<b>2ND FLOOR</b>						
301	LOBBY	CONC-S	---	EXP/FI	EXP	FI AT CMU WALLS, U8-1
302	STAIR 1	CONC-S	---	CMU-FI	EXP	
303	STAIR 2	CONC-S	---	CMU-FI	EXP	
304	UNITS	CONC-S	---	EXP/FI	EXP	FI AT CMU WALLS
305	HALLWAY	CONC-S	HB-1	EXP/FI	EXP	FI AT CMU WALLS

- ### FINISH SCHEDULE NOTES
- FINISH UNSCHEDULED CLOSETS AND SPACES TO MATCH ADJOINING ROOMS.
  - PAINT HOLLOW METAL DOORS AND FRAMES PB UNO.
  - PAINT LADDERS, STAIR RAILS, STAIR STRUCTURE, AND STAIR FLOOR PLATE P4, SEMI GLOSS.
  - PROVIDE 0.080"x4"x4" HIGH ALUM DIAMOND PLATE CORNER GUARDS AT ALL CORRIDOR/LOBBY OUTSIDE CORNERS.
  - PROVIDE HALLWAY SYSTEM WITH PIERS, HEADERS AND PANELS PAINTED SEMI GLOSS "GLOSSY WHITE", AND CEILING DOORS AND FRAMES PAINTED SEMI GLOSS "GLOSSY WHITE" UNO.
  - COVER EXPOSED GYP BD IN LOBBIES AND STORAGE CORRIDORS WITH HALLWAY PANELS TO THE HEIGHT OF THE HALLWAY SYSTEM. PAINT EXPOSED GYP BD ABOVE HALLWAY PANELS P1.
  - COVER EXPOSED GYP BD IN STORAGE UNITS WITH UNIT PARTITION PANELS TO THE HEIGHT OF THE UNIT PARTITIONS. PAINT EXPOSED GYP BD ABOVE PARTITION PANELS P1.
  - PROVIDE RT-1 FLOORING IN ELEVATOR CABS.
  - COVER EXPOSED ELEVATOR CMU IN LOBBIES AND STORAGE CORRIDORS WITH HALLWAY PANELS TO THE HEIGHT OF THE HALLWAY SYSTEM. PAINT EXPOSED ELEVATOR CMU ABOVE HALLWAY PANELS IN LOBBIES AND STORAGE CORRIDORS P1. PAINT EXPOSED ELEVATOR CMU IN STORAGE UNITS FROM FLOOR TO CEILING P1.
  - PAINT EXPOSED STAIR CMU IN STORAGE CORRIDORS AND STORAGE UNITS FROM FLOOR TO CEILING P1.

# FINISH SCHEDULE LEGEND

CMU	CONCRETE MASONRY UNITS - NO FINISH
CMU-Fx	CONCRETE MASONRY UNITS - PAINT IN COLOR/GLOSS INDICATED
CONC-S	CONCRETE SLAB - SEAL WITH CLEAR EPOXY COATINGS - 2 COATS IN ALL SPACES EXCEPT 1 COAT INSIDE STORAGE UNITS
EXP	EXPOSED STRUCTURE - NO FINISH
EXP-Fx	EXPOSED STRUCTURE - PAINT IN COLOR/GLOSS INDICATED
GB	GYPBUM BOARD - NO FINISH
GB-Fx	GYPBUM BOARD - PAINT IN COLOR/GLOSS INDICATED
HB-1	HALLWAY BASE - 0.080" x 12" HIGH ALUM DIAMOND PLATE
P1	SHERWIN-WILLIAMS SW7028 "INCREDIBLE WHITE", EGG SHELL
P2	SHERWIN-WILLIAMS SW1028 "INCREDIBLE WHITE", SEMI-GLOSS
P3	SHERWIN-WILLIAMS SW1064 "PASSIVE", EGG SHELL
P4	SHERWIN WILLIAMS SW6811 "HONORABLE BLUE", MATTE
P5	SHERWIN WILLIAMS SW1061 "CITYSCAPE", SEMI-GLOSS
RT-1	RUBBER TILE - ROFFPE 3% VANTAGE PROFILE, "DARK GRAY" 150.
U8-1	WAINSCOT - 0.080"x48" HIGH ALUM DIAMOND PLATE



THESE DRAWINGS AND DESIGN ARE THE PROPERTY OF STANARD ARCHITECTURE, INC. AND SHALL NOT BE REPRODUCED WITHOUT THE ARCHITECT'S PERMISSION. THEY WERE PREPARED FOR THE PROJECT SITE IN CONJUNCTION WITH THE ISSUE DATE AND REVISED DATE INDICATED HEREON. ALL DIMENSIONS MUST BE VERIFIED BY THE ARCHITECT BEFORE PROCEEDING WITH CONSTRUCTION. DO NOT SCALE DRAWINGS.

Life Storage #230  
Self Storage Phase II  
1639 Route 22  
Brewster, NY 10509



ISSUE FOR CONSTRUCTION REVISIONS:

PROJECT NUMBER	201941
DATE	6-5-20

SHEET NUMBER  
**A7.1**

1  
A11 DOOR DETAILS  
SCALE: 1-1/2"=1'-0"

