

SECTION 312323

EXCAVATION AND FILL FOR UTILITIES

PART 1 - GENERAL

1.01 SUMMARY

A. Section Includes:

1. Excavating, backfilling, and compacting utility trenches such as water, gas, irrigation, storm drain, sewer lines, concrete-encased conduits, and manholes, vaults, valve boxes, catch basins, underground tanks, thrust blocks, yard boxes, pull boxes and other utility appurtenances.

B. Related Requirements:

1. Section 02 4113 - Site Demolition.
2. Section 33 4000 - Storm Sewer Utilities.
3. Section 33 4600 - Subdrainage.

1.02 PROJECT REQUIREMENTS

A. Import and Export of Earth Materials:

1. Fees: Pay as required by authorities having jurisdiction over the area.
2. Bonds: Post as required by authorities having jurisdiction over the area.
3. Haul Routes and Restrictions: Comply with requirements of authorities having jurisdiction over the area.

1.03 SUBMITTALS

- A. Imported Soil: A geotechnical engineer, retained by the Owner as an Owner Consultant, shall obtain initial product Sample for testing in accordance with the terms of Article 3.05 of this section.

1.04 QUALITY ASSURANCE

- A. Comply with the following as a minimum requirement: Standard Specifications for Public Works construction, current edition except as modified herein.

1.05 PROJECT CONDITIONS

- A. Information on Drawings or in soils report does not constitute a guarantee of accuracy or uniformity of soil conditions over the Project site.

- B. A copy of the foundation investigation and soils report is available for examination at the Architect's office during regular business hours of Architect.

PART 2 - PRODUCTS

2.01 MATERIALS

- A. Bedding material from trench bottom to one foot above the pipe:
 - 1. Sand, gravel, crushed aggregate or native free-draining granular material providing a sand equivalent of at least 30 or a coefficient of permeability greater than 1.4 inches per hour.
 - 2. Sand complying with the Specifications for cement concrete aggregates.
- B. Backfill Materials:
 - 1. Excavated trench material to be installed for backfilling shall be clean, free of large clods, and stones larger than 2 ½-inch in any dimension.
 - 2. Cement-sand slurry shall be provided with one sack of cement per cubic yard of the mixture.
 - 3. Imported Fill Material: Imported fill material shall be a granular material with sufficient binder to form a firm and stable unyielding subgrade and shall not have more than 60 percent of fines passing a 200 mesh sieve. Material shall provide a coefficient of expansion of not more than two percent from air dry to optimum moisture content and not more than six percent from air dry to saturation. Imported materials shall be clean and free of rubbish, debris, and toxic or hazardous contaminants. Adobe or clay soils are not permitted.

PART 3 - EXECUTION

3.01 GENERAL

- A. Before excavation, contact the NY One Call for information on buried public utilities and pipelines. For on-site utilities retain an underground locating service.
- B. Barricade trenches, ditches, pits, sumps, and similar Work outside the barricaded working area with chain link fence as specified in Section 01 5000 - Construction Facilities and Temporary Controls, and in accordance with OSHA standards and requirements.
- C. Saw-cut concrete or bituminous paving for trench installation.
- D. Trenches over 5 feet in depth shall conform to OSHA standards.
- E. Where indicated and required to excavate in lawn areas, protect adjoining lawn areas outside of the Work area. Replace or install removed sod upon completion of backfill by installing sod level with adjacent lawns. If installation of removed sod fails, furnish sod and install to match existing lawns.

- F. Backfill over excavations to the required elevations with earth, gravel, sand, or concrete and compact as required. Provide excavations free from standing water by pumping, draining, or providing protection against water intrusion. Slope adjacent grades away from excavations to minimize entry of water.
- G. Do not install piping lengthwise under concrete walks without review by the Architect.
- H. Do not excavate trenches parallel to footings closer than 18 inches from the face of the footing or below a plane having a downward slope of two horizontal to one vertical, from a line 9 inches above bottom of footings.
 - 1. Unless otherwise indicated on Drawings, depth of excavations outside the buildings shall allow for a minimum coverage above top of pipe, tank, or conduit measured from the lowest adjoining finished grade, as follows:

Steel Pipe	24 inches below finished grade
Copper Water Tube	18 inches below finished grade
Cast-Iron Pressure Pipe	36 inches below finished grade
Plastic Pipe (other than waste)	30 inches below finished grade
Tanks or other structures	36 inches below finished grade
Soil, Sewer & Storm Drain	minimum 18 inches below finished grade, and as required for proper pitch and traffic load. (Install polypropylene sewer pipe with at least 24 inches coverage)
 - 2. Trench width shall provide ample space for fitting and joining. Excavate for piping bells and fittings, bell and spigot pipe and other fittings.
- I. Unless indicated otherwise, excavate trenches to the required depths for utilities, such as pipes, conduit and tanks, with minimum allowances of 6 inches at the bottom and 6 inches at the sides for bedding of unprotected piping or as required for concrete encasement of conduits as indicated on Drawings. Grade bottom of trenches to a uniform smooth surface. Remove loose soil from the excavation before installing sand bedding or concrete encasement.
- J. Provide excavations free from standing water by pumping, draining, or providing protection against water intrusion. If soil becomes soft, soggy, or saturated, excavate to firm undisturbed soil and fill as required. Slope adjacent grades away from excavations to minimize entry of water.
- K. Provide a minimum clear dimension of 2 inches from sides of wall excavation to outer surfaces of buried pipes or conduits installed in the same trench or outside surfaces of containers and tanks.
- L. Do not install backfill until required inspections and testing is completed.
- M. Backfill electrical or other excavated utility trenches located outside of barricaded installation areas within 24 hours after inspection by the Project Inspector.
- N. Install backfill materials in layers not exceeding 4 inches in thickness and compact to 90 percent of the maximum density.
- O. If materials excavated from the Project site are not permitted for trench backfill in paved areas,

backfill trenches with a cement-sand slurry mix. Install backfill to an elevation of the existing undisturbed grade plus one inch.

- P. Install and compact sand bedding to provide a uniform full length bearing under piping and conduits.
- Q. Where portions of existing structures, walks, paving, or other improvements are removed or cut for piping or conduit installation, replace the material with equal quality, finished to match adjoining existing improvements.

A.02 IMPORT/EXPORT OF MATERIALS

- A. Provide fill materials as specified in Part 2- Products. If excavated materials from the Project site are not of required quality or sufficient quantity, import additional materials as necessary.
- B. Imported fill materials shall be sampled by a geotechnical engineer, retained by the Owner as an Owner Consultant, for compliance with the requirements of Part 2 of this section.
- C. The geotechnical engineer, retained by the Owner as an Owner Consultant, shall perform the tests by utilizing an independent approved testing laboratory.
- D. Initial sampling shall be performed by the geotechnical engineer, retained by the Owner as an Owner Consultant, before importing material to the Project site. Identify the location of the source site in addition to the address, name of the person and/or entity responsible for the source site. The geotechnical engineer, retained by the Owner as an Owner Consultant, shall obtain both the initial sample and additional samples from the identified site and shall submit all samples to the approved independent testing laboratory.
- E. The geotechnical engineer, retained by the Owner as an Owner Consultant, shall perform additional sampling during import operations. If the total quantity of import is determined to be greater than 1,000 cubic yards of material, one sample shall be obtained and submitted for testing for each 250 cubic yards of imported material. If the total quantity of import is determined to be less than 1,000 yards, one sample shall be obtained and submitted for testing for each 100 cubic yards of imported material.
- F. The independent approved testing laboratory shall perform the required tests and report results of all tests noting if the tested material passed or failed such tests and shall furnish copies to the Project Inspector, Architect, OAR, DSA, Contractor, and others as required. Report shall state tests were conducted under the responsible charge of a licensed State of California professional engineer and the material was tested in accordance with applicable provisions of the Contract Documents, CBC and the DSA. Upon completion of the Work of this section, the independent testing laboratory and geotechnical engineer shall submit a verified report to the DSA as required by CBC.
- G. Bills of lading or equivalent documentation will be submitted to the Project Inspector on a daily basis.
- H. Upon completion of import operations, provide the OAR a certification statement attesting that imported material has been obtained from the identified source site.

3.03 INSPECTION AND TESTING

A. The geotechnical engineer, retained by the Owner as an Owner Consultant, will inspect and test excavations, sample material quality as required in Part 2, observe installation and compaction of fill materials.

B. Compaction test shall be performed in accordance with ASTM D1557, method "C."

3.04 PROTECTION

A. Protect the Work of this section until Substantial Completion.

3.05 CLEANUP

A. Remove rubbish, debris, and waste materials and legally dispose of off the Project site.

END OF SECTION