

THE WHITING-TURNER CONTRACTING COMPANY
300 EAST JOPPA ROAD | TOWSON, MD 21286

SPECIFIC SCOPE OF WORK

Unit 01B – Temporary Fencing

This work shall include all labor, supervision, material, tools, equipment, shop drawings, submittals, layout, unloading, scaffolding, ladders, hoisting, transportation, taxes, permits, engineering, support functions, insurance, bonds, and any other items or services necessary for and reasonably incidental to the proper execution and completion of the work, whether temporary or permanent, in accordance with all drawings, specifications, addenda, general conditions, requirements, and other related documents as indicated herein. The scope of work shall include but not be limited to the following: (All work shall be furnished and installed unless specifically noted otherwise herein.)

Specific Scope of Work:	Included	Excluded
Subcontractor is to provide unit pricing for the furnish and install of temporary chain link fencing.		
Subcontractor is to provide alternate pricing breakouts for the furnish and install of different variations of scrim (decorative, weight variations, etc.)		
Subcontractor is to provide unit pricing for furnish and install of slide gates		
Subcontractor shall furnish and install a temporary 6'-0" tall chain link fence around the exposed site limits and connect to the existing, permanent site fence in order to fully enclose the project site.		
Subcontractor shall furnish and install 6000 linear feet of 6' post driven fence chain link fence panels. Subcontractor is not to perform this work until a utility locate is performed, by others and written approval to proceed has been provided by Whiting-Turner.		
Fencing installed by this subcontractor to include wind screen.		
Subcontractor to furnish and install 9 ea, 24'-0" wide swing gates.		
Unit rates for removal trips are included.		
Rental extensions will be based on the rates in Exhibit TBD and extended one month at a time or longer based on the projects needs at the end of this duration		
Subcontractor is to furnish and install permanent fencing including but not limited to FN-01, FN-02, FN-03, and FN-07 where indicated in the contract documents.		
Subcontractor is to furnish and install permanent swing gates including but not limited to FN-04, FN-05 and FN-06 where indicated in the contract documents.		
Subcontractor shall furnish and install approximately 2824 LF of steel mesh fence (FN-01) per detail 1/L731 where shown on L211, L212, L213, L214, L215, and L216.		
Subcontractor shall furnish and install approximately 97 LF of timber fence (FN-02) per detail 2/L731 where shown on L210.		
Subcontractor shall furnish and install approximately 232 LF of timber fence (FN-07) per detail 3/L732 where shown on L214.		
Subcontractor shall furnish and install 1 pedestrian gate (FN-04) per detail 1/L732 where shown on L210.		
Subcontractor shall furnish and install 4 vehicular timber gates (FN-05) per detail 1/L733 where shown on L210, L213 and L214.		
Subcontractor shall furnish and install 3 timber boom swing gates (FN-06) per detail 2/L732 where shown on L213 and L215.		
This subcontractor has completed and returned the Owner required Prequalification Form to Whiting-Turner.		

Pricing Breakdown as Follows:

- Wind Screen
- Unit Cost – Temporary Chain Link Fencing
- Unit Cost – Fence Scrim

\$ _____
 \$ _____
 \$ _____

THE WHITING-TURNER CONTRACTING COMPANY
300 EAST JOPPA ROAD | TOWSON, MD 21286

- Unit Cost – Temporary Slide Gates \$ _____
- Alternates – Various Scrim Options \$ _____
- Unit Rate – Removal Trip \$ _____
- Unit Cost – FN-01 \$ _____
- Unit Cost – FN-02 \$ _____
- Unit Cost – FN-03 \$ _____
- Unit Cost – FN-04 \$ _____
- Unit Cost – FN-05 \$ _____
- Unit Cost – FN-06 \$ _____
- Unit Cost – FN-07 \$ _____

Total = \$ _____