

THE WHITING-TURNER CONTRACTING COMPANY

300 EAST JOPPA ROAD | TOWSON, MD 21286

C. SPECIFIC SCOPE OF WORK

Unit 07C – Metal Panels

This work shall include all labor, supervision, material, tools, equipment, shop drawings, submittals, layout, unloading, scaffolding, ladders, hoisting, transportation, taxes, permits, engineering, support functions, insurance, bonds, and any other items or services necessary for and reasonably incidental to the proper execution and completion of the work, whether temporary or permanent, in accordance with all drawings, specifications, addenda, general conditions, requirements, and other related documents as indicated herein. The scope of work shall include but not be limited to the following: (All work shall be furnished and installed unless specifically noted otherwise herein.)

<u>Specific Scope of Work: Fire Protection</u>	Included	Excluded
1. This subcontractor is fully responsible for all drawings and specifications provided during and after the bid phase of this project. This subcontractor is also responsible for any additional/revised drawings & documents formally issued by Whiting-Turner throughout the bid phase via addendum. This includes drawings and specifications directly related to their respective scope, as well as all other drawings and specifications, regardless of their association with this respective scope of work. A complete listing of all drawings and specifications is attached hereto as Exhibit D.		
2. Subcontractor is responsible for all notes in the contract documents related to this scope of work.		
3. Provide all submittals, certifications, reports, source of supply, samples, shop drawings, mock-ups, product data, as-builts, O&Ms and warranties, as required by specifications.		
4. Attend pre-installation meeting		
5. Furnish and install metal panels at CFM building including all supports, fasteners, trims, etc. for a complete installation. Caulking, sealing, backer rod, etc. of all joints, seams, flashings are included in this scope of work.		
6. Furnish and install insulation at metal panel locations.		
7. Furnish and install vapor barrier at metal panel locations. Coordinate installation with other trades.		
8. Touch-up all damages to factory applied finishes.		
9. Subcontractor shall be responsible for all hoisting, scaffolding, lifting, temporary bracing, etc. as needed to complete this scope of work.		
10. Subcontractor has included all mobilizations necessary to accomplish this scope of work in accordance with the project schedule.		
11. All layout is included.		
12. The Subcontractor agrees to participate in a composite project clean-up crew supervised by Whiting-Turner and as outlined Exhibit E - General Scope of Work.		
13. Haul offsite all surplus materials. Place all debris and waste materials in dumpsters provided by WT.		
14. Provide all specified warranties. Warranties are to begin from date of project substantial completion and last for one (1) year. This includes all labor performed and all materials provided and/ or installed in conjunction with this project.		
15. Coordinate with other trades as required.		

THE WHITING-TURNER CONTRACTING COMPANY

300 EAST JOPPA ROAD | TOWSON, MD 21286

Pricing Breakdown as Follows:

- C.F.M \$ _____

Total (Include Bond if Over \$100k) = \$ _____