# COUNTY OF ROCKLAND

# INDEX OF DRAWINGS

|       |  | l = = =  |
|-------|--|----------|
| SHEET | TITLE                                    | REVISION |
| 1     | COVER SHEET                              |          |
| 2     | GENERAL NOTES                            |          |
| 3     | EXISTING CONDITIONS PLAN                 |          |
| 4     | YARD PIPING PLAN                         |          |
| 5     | LANDSCAPE & GRADING PLAN                 |          |
| 6     | PROCESS & INSTRUMENTATION DIAGRAM        |          |
| 8     | GAC TREATMENT BUILDING PLAN AND SECTIONS |          |
| 9     | PROCESS PIPING PLAN AND SECTIONS         |          |
| 10    | GAC TREATMENT BUILDING ELEVATION VIEWS   |          |
| 11    | ELECTRICAL PLAN                          |          |
| 12    | CONSTRUCTION DETAILS I                   |          |
| 13    | CONSTRUCTION DETAILS II                  |          |
| 14    | CONSTRUCTION DETAILS III                 |          |
| 15    | SOIL EROSION & SEDIMENT CONTROL PLAN     |          |

| PUBLIC UTILITIES LIST |                               |  |  |  |
|-----------------------|-------------------------------|--|--|--|
| GAS                   | ORANGE AND ROCKLAND UTILITIES |  |  |  |
| WATER                 | SUEZ WATER NEW YORK           |  |  |  |
| SEWER                 | TOWNSHIP OF RAMAPO            |  |  |  |
| ELECTRICITY           | ORANGE AND ROCKLAND UTILITIES |  |  |  |
| COMMUNICATIONS        | VERIZON                       |  |  |  |


PRELIMINARY SITE PLAN FOR

SUEZ WATER NY PFAS COMPLIANCE

POMONA WELL NO. 38


VILLAGE OF POMONA, TOWN OF RAMAPO, COUNTY OF ROCKLAND, STATE OF NEW YORK

1. TAX MAP - LOT 11, BLOCK 33.13-2, ON THE CURRENT TAX MAP OF THE TOWN OF RAMAPO, SHEET #33.12. 2. AERIAL IMAGERY - © NEARMAP US, INC. http://go.nearmap.com



PRELIMINARY SITE PLAN FOR SUEZ WATER NY PFAS COMPLIANCE **POMONA WELL NO. 38** VILLAGE OF POMONA, TOWN OF RAMAPO, COUNTY OF ROCKLAND, STATE OF NEW YORK

**COVER SHEET** 



PROJECT NUMBER: SCE-12162.002 SHEET 1 OF 15

REVISION\_\_-

CONSULTANT: DATE:XX/XX/2021

#### REFERENCES:

- 1. TAX MAP LOT 11, BLOCK 33.13-2, ON THE CURRENT TAX MAP OF THE TOWN OF RAMAPO, SHEET
- 2. AERIAL IMAGERY © NEARMAP US, INC. http://go.nearmap.com
- 3. SITE PLAN "SPRING VALLEY WATER COMPANY INCORPORATED, SPRING VALLEY, N.Y. -POMONA WELL FIELD, RAMAPO, N.Y. PROPOSED WELL HOUSE" DATED SEPTEMBER 1974 AND LAST REVISED JUNE 7, 1977 AS REVISION 3.

# NOTE:

PRIOR TO ANY EXCAVATION, CONTRACTOR MUST HAVE ALL UTILITIES MARKED OUT BY THE APPROPRIATE UTILITY COMPANIES -> CALL 811

#### **GENERAL NOTES**

**APPLICANT** 

OWNER: **UNITED WATER NEW YORK INC.** 12 CAMP HILL ROAD

**RAMAPO, NY 10970** 

**SUEZ WATER NEW YORK INC.** 

**162 OLD MILL ROAD WEST NYACK, NY 10994** 

- 1. THE SUBJECT PROPERTY IS KNOWN AS LOT 11, BLOCK 33.13-2, ON THE CURRENT TAX MAP OF THE TOWN OF RAMAPO, SHEET #33.12.
- 2. THE SUBJECT PROPERTY CONTAINS 9.514 ACRES (414,432 SF), AND IS SITUATED IN FOLLOWING DISTRICTS:

RURAL-RESIDENTIAL - 80,000 SQ.FT. PER LOT (RR-80) **ZONING:** SCHOOL: EAST RAMAPO CENTRAL SCHOOL DISTRICT

- 3. HORIZONTAL DATUM BASED ON NAD-83 (2011), PER GPS SATELLITE OBSERVATION.
- 4. VERTICAL DATUM IS BASED ON NAVD-88, PER GPS SATELLITE OBSERVATION.
- 5. PARTIAL BOUNDARY & TOPOGRAPHIC SURVEY REFERENCED FROM SUBURBAN ENGINEERING, INC., ENTITLED "SUEZ WATER NEW YORK. INC. - PFAS COMPLIANCE - POMONA #37 & 38" DATED APRIL 8, 2021.
- 6. ALL UTILITIES WILL BE INSTALLED UNDERGROUND.
- 7. ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE TOWN OF RAMAPO STANDARDS AND SPECIFICATIONS, AND ALL STRUCTURES ARE SUBJECT TO REVIEW BY THE CONSTRUCTION CODE OFFICIAL. THE CONSTRUCTION OF ALL SITE IMPROVEMENTS SHALL COMPLY WITH THE NEW YORK STATE CONSTRUCTION CODE.
- 8. A PORTION OF THE SUBJECT PROPERTY IS SUBJECT TO FLOODING FROM THE 100 YEAR STORM, BASED ON THE NATIONAL FLOOD INSURANCE PROGRAM, FLOOD INSURANCE RATE MAP (FIRM) FOR THE TOWN OF RAMAPO, PANEL 97 OF 207, COMMUNITY PANEL NUMBER 365340, LAST REVISED MARCH 3, 2014.
- 9. WORK MAY BE PERFORMED MONDAY THROUGH FRIDAY BETWEEN THE HOURS OF 8:00 AM AND 10:00 PM. THE TOWN MUST APPROVE EARLY STARTS AND WORK ON SATURDAYS, SUNDAYS AND HOLIDAYS. THE COST FOR INSPECTION SERVICES BY THE TOWN CONSTRUCTION DEPARTMENT OR THE OWNER/APPLICANT ENGINEER BEYOND NORMAL WORK DAYS AND HOURS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
- 10. NO MATERIAL OR EQUIPMENT IS TO BE STORED ON ANY AREA THAT HAS NOT BEEN ESTABLISHED AS A DESIGNATED STAGING AREA. ALL EXCAVATIONS SHALL BE PROTECTED AT THE END OF EACH WORK DAY. THE CONTRACTOR IS RESPONSIBLE FOR SITE SAFETY. STAGING AREAS SHALL BE RESTORED TO PRE-CONSTRUCTION CONDITIONS BY THE CONTRACTOR.
- 11. ALL CONSTRUCTION MATERIALS, PRODUCTS, HOURS OF OPERATION, ETC. SHALL BE IN ACCORDANCE WITH THE OWNER, THE ON-SITE ENGINEER, AND THE TOWN OF RAMAPO. CONTRACTOR IS RESPONSIBLE TO PROVIDE ALL AS-BUILT SURVEYS PER TOWN REQUIREMENTS & FOR THE OWNER.
- 12. THE CONTRACTOR SHALL BE RESPONSIBLE TO OBTAIN ALL LOCAL BUILDING PERMITS. THE OWNER WILL OBTAIN ALL PLANNING, ZONING AND LAND DISTURBANCE PERMITS, IF DEEMED NECESSARY.
- 13. BUILDING PERMITS SHALL SHOW LOWEST FLOOR ELEVATIONS SUBJECT TO APPROVAL AND INSPECTION BY DEPARTMENT OF **ENGINEERING & FACILITIES MAINTENANCE.**
- 14. NO BUILDING PERMIT FOR A BUILDING SUBJECT TO SITE PLAN APPROVAL SHALL BE ISSUED BY THE BUILDING INSPECTOR EXCEPT UPON AUTHORIZATION OF AND IN CONFORMITY WITH THE SITE PLAN APPROVED BY THE RAMAPO PLANNING BOARD.
- 15. ALL EXISTING ITEMS NOT DENOTED "TO REMAIN" OR "TO BE REMOVED" SHALL REMAIN AND BE PROTECTED THROUGHOUT
- 16. SUEZ WATER NEW YORK INC.SHALL CONFORM TO SOIL EROSION AND SEDIMENT CONTROL PLAN ON FILE IN DEPARTMENT OF **ENGINEERING & FACILITIES MAINTENANCE.**
- 17. ALL TRAFFIC CONTROL DEVICES SHALL BE IN ACCORDANCE WITH THE NEW YORK STATE MANUAL OF UNIFORM TRAFFIC CONTROL

#### **GENERAL ENVIRONMENTAL NOTES:**

- 1. THE CONTRACTOR MUST PERFORM THE WORK IN ACCORDANCE WITH APPLICABLE PROVISIONS AND CONDITIONS OF THE ROCKLAND COUNTY STANDARDS FOR SOIL EROSION AND SEDIMENT CONTROL.
- 2. THE TRENCH EXCAVATION MAY BE NO WIDER THAN NECESSARY TO COMPLY WITH OSHA SAFETY STANDARDS AND THE CONSTRUCTION DETAILS UNDER THE ACTUAL SURFACE AND SUBSURFACE CONDITIONS AS MAY BE ENCOUNTERED DURING
- 3. AVOID DISTURBANCE OF NATURAL VEGETATION DURING CLEARING OPERATIONS TO THE GREATEST EXTENT PRACTICABLE.
- 4. PERFORM "SOIL EROSION AND SEDIMENT CONTROL" AS DIRECTED BY THE ENGINEER OR SOIL CONSERVATION AGENCY REPRESENTATIVE AS CALLED FOR ON THE PLANS. PERFORM WORK IN ACCORDANCE WITH THE SPECIFICATIONS AS MAY BE WARRANTED BY ACTUAL FIELD CONDITIONS AND THE CONTRACTOR'S MEANS AND METHODS OF CONSTRUCTION. NO SEPARATE PAYMENT WILL BE MADE FOR ADJUSTMENTS, ADDITIONAL MATERIALS AND MAINTENANCE OF THIS WORK.
- 5. THE CONTRACTOR WILL BE RESPONSIBLE FOR THE INSTALLATION, MAINTENANCE, AND REPAIR OF SOIL EROSION AND SEDIMENT CONTROL MEASURES IN ACCORDANCE WITH THE APPROVED SOIL EROSION AND SEDIMENT CONTROL PERMIT. CONTRACTOR IS RESPONSIBLE FOR ANY DAMAGES OR REMEDIATION REQUIRED DUE TO EROSION OR DOWNSTREAM SEDIMENT
- 6. MAINTAIN WORK WITHIN THE DESIGNATED LIMITS OF DISTURBANCE AS DELINEATED AND NOTED ON THE PLANS. RESTORE ANY DISTURBANCE BY WORK CONDUCTED OUTSIDE THOSE LIMITS AT NO ADDITIONAL EXPENSE TO THE OWNER.
- 7. DISPOSE OF ALL WASTE, DEBRIS, AND UNSUITABLE EXCAVATED MATERIALS IN ACCORDANCE WITH THE SPECIFICATIONS, THE STATE AND LOCAL RULES AND REGULATIONS.

#### **GENERAL WATER MAIN CONSTRUCTION NOTES:**

- 1. USE DUCTILE IRON RESTRAINED JOINT FITTINGS WITH MANUFACTURER RETAINER GLANDS ACCORDING TO THE CONTRACT DOCUMENTS. RESTRAIN ALL BENDS, TEES, VALVES, PLUGGED ENDS, ETC. IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS.
- 2. SIZE AND LOCATION OF EXISTING MAINS TO WHICH CONNECTIONS ARE BEING MADE ARE BASED ON THE BEST INFORMATION AVAILABLE AT THE TIME OF DESIGN. THE CONTRACTOR MUST BE PREPARED TO ACCOMMODATE CHANGES IN THE SIZE OR LOCATION OF THE CONNECTION BY MAINTAINING AT THE JOB SITE, ADDITIONAL PIPE, FITTINGS, AND VALVES IN THE RANGE OF SIZES AS MAY EXIST.

#### **GENERAL CONSTRUCTION NOTES:**


- COORDINATE ALL WATER SYSTEM CONNECTIONS. SHUT DOWNS, OR OTHER SYSTEM RELATED OPERATIONS WITH THE OWNER AND NOTIFY AFFECTED RESIDENCES AND BUSINESSES A MINIMUM OF ONE WEEK PRIOR TO THE SCHEDULED DATE FOR SAID SHUT DOWN OPERATIONS. ONLY SUEZ PERSONNEL SHALL OPERATE EXISTING VALVES AND HYDRANTS. THE CONTRACTOR MUST PROVIDE WRITTEN NOTIFICATION OF THE START OF CONSTRUCTION TO PROPERTY OWNERS WITHIN THE PROJECT LIMITS 72 HOURS PRIOR TO CONSTRUCTION OPERATIONS AND 72 HOURS PRIOR TO OPERATIONS THAT MAY AFFECT PROPERTY ACCESS.
- 2. CONSTRUCTION SHALL CONFORM TO APPROPRIATE SECTIONS OF: 1) NATIONAL ELECTRICAL CODE; 2) NATIONAL STANDARD PLUMBING CODE; AND 3) INTERNATIONAL MECHANICAL CODE, LATEST EDITIONS.

ONSULTANT: ANDREW S. HOLT, R.

**DATE: XX/XX/2021** 

UTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE THIS DRAWING MAY NOT BE <u>COPIED</u>, <u>REUSED</u>, <u>DISCLOSED</u>, DISTRIBUTED, OR <u>RELIED UPON</u> FOR ANY OTHER PURPOSE MITHOUT THE WRITTEN CONSENT OF UBURBAN ENGINEERING ELECTRONIC SUBMISSIONS NOT CONTAINING A VALID DIGITAL SEAL OR PAPER COPIES NOT CONTAINING A RAISED SEAL ARE T ORIGINALS AND MAY HAVE BEEN ALTERED. COPYRIGHT 2021 SUBURBAN ENGINEERING

ALL RIGHTS RESERVED





**SUBURBAN ENGINEERING** 

- Civil Engineers -- Landscape Architects -- Land Surveyors -7 Cokesbury Califon Road, Lebanon, N.J. 08833 - 973.398.1776

EXCELLENCE ♦ ECONOMY ♦ ENVIRONMENT

SUEZ WATER NY PFAS COMPLIANCE **POMONA WELL NO. 38** VILLAGE OF POMONA, TOWN OF RAMAPO, COUNTY OF ROCKLAND, STATE OF NEW YORK SUEZ WATER NEW YORK INC.

SCALE: N.T.S.


PROJECT NUMBER


SCE-12162.002

**GENERAL NOTES** 


PRELIMINARY SITE PLAN FOR


SHEET 2 OF 15 **REVISION** -







→ EXISTING EDGE OF WOODS EXISTING WELL NO. 38 PROCESS PIPING
TO BE MODIFIED EXISTING EDGE OF PAVEMENT ANTICIPATED STAGING CHEMICAL STORAGE SHED
TO BE REMOVED EX. HYDRANT —









NOTICE
THIS DRAWING AND ALL INFORMATION CONTAINED HEREIN IS AUTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE WORK WAS CONTRACTED OR TO WHOM IT IS CERTIFIED. THIS DRAWING MAY NOT BE <u>COPIED</u>, <u>REUSED</u>, <u>DISCLOSED</u>, <u>DISTRIBUTED</u>, OR <u>RELIED UPON</u> FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF SUBURBAN ENGINEERING

CHECKED BY: CHECKED BY: DESCRIPTION NO. DATE: BY: CHK: **REVISIONS** 



PRELIMINARY SITE PLAN FOR **SUBURBAN SUEZ WATER NY PFAS COMPLIANCE ENGINEERING POMONA WELL NO. 38** 


VILLAGE OF POMONA, TOWN OF RAMAPO, COUNTY OF ROCKLAND, STATE OF NEW YORK SUEZ WATER NEW YORK INC.


**AS NOTED** SHEET 5 OF 15 LANDSCAPE & GRADING PLAN REVISION\_-


**PROJECT NUMBER** 


SCE-12162.002


SCALE:























— PVC CHECK VALVE **DIFFUSER ASSEMBLY** BY MANUFACTURER

- PLASTIC SOLUTION TUBE BY

DIFFUSER MANUFACTURER

PVC BALL VALVE

— CHEMICAL FEED LINE

**CHEMICAL INJECTION NOTES:** 1. CONTRACTOR SHALL PROVIDE A SAF-T-FLOW RETRACTABLE INJECTION QUILL MODEL, OR APPROVED EQUAL.

2. THE SADDLE FOR TEE FITTING SHALL BE 3/4"Ø FOR INJECTION QUILL, OR OTHERWISE DIRECTED FOR THE PROPER INSTALLATION OF THE QUILL. THE CHEMICAL RESISTANT TUBING FOR THE QUILL IS 3/8", CONTRACTOR SHALL PROVIDE REDUCER TO 1/4" TUBING AS

REQUIRED. 3. INJECTION SHALL BE INSTALLED AT THE 90-DEGREE MARK ON THE PIPE PER **SUEZ PREFERENCE.** 

#### PIPE SUPPORT DETAIL N.T.S.

**FLANGE SUPPORT DETAIL** 

LOAD. SUPPORTS SHALL BE STANDON MODEL S89 AS

GROVE, OR.503-533-5256 P, 503-533-5501 F

MANUFACTURED BY -MATERIAL RESOURCES INC., FOREST

N.T.S.

**WALL PENETRATION DETAIL** SCALE = N.T.S.

**DIP CHEMICAL INJECTION DETAIL** SCALE = N.T.S

RETAINING CHAIN BY DIFFUSER

TAPPING SADDLE —

**CORPORATION COCK BY -**

DIFFUSER MANUFACTURER


EXTEND TUBE 1/3 WAY INTO PIPE -

**TAP FLANGED IN PIPE** 


**DUCTILE IRON** -

**FLANGED PIPE** 


**MANUFACTURER** 




# **TEPID WATER HEATING SYSTEM DETAIL** N.T.S.




CHEMICAL SUPPLY/FEED SYSTEM SCHEMATIC SCALE = N.T.S.





PROPOSED FILTREK BAG FILTER SCALE = N.T.S.



**CALGON MODEL 12 GAC UNIT DETAIL** SCALE = N.T.S.







PRELIMINARY SITE PLAN FOR PROJECT NUMBER **SUEZ WATER NY PFAS COMPLIANCE** SCE-12162.002 **POMONA WELL NO. 38** VILLAGE OF POMONA, TOWN OF RAMAPO, COUNTY OF ROCKLAND, STATE OF NEW YORK FOR CLIENT: **SUEZ WATER NEW YORK INC.** 


**CONSTRUCTION DETAILS II** 

SCALE: N.T.S. SHEET 13OF 15

**REVISION** -


## **EYEWASH AND SHOWER DETAIL**

SCALE = N.T.S.



## TYPICAL UTILITY CROSSING DETAIL

N.T.S.



**UTILITY CROSSING DETAIL** 

N.T.S.

MIN. 6" TOPSOIL, SEED AND MULCH, — MOUND 2" ABOVE EXIST. GRADE SAWCUT EXISTING PAVEMENT IN NEAT LINE FOR PAVEMENT RESTORATION **EXISTING GRADE** -SUITABLE EXCAVATED OR SELECT (TYPE "G") BACKFILL MATERIAL **COMPACTED TO 95% MAX. DENSITY AS REQUIRED** SEE PAVEMENT RESTORATION **DETAILS DENSE GRADED AGGREGATE BACKFILL COMPACTED IN** 12" LIFTS IN PAVED AREAS UTILITY DRY TRENCH: DGA **APPURTENANCE** WET TRENCH: #57 STONE 3" MIN. -12" | OD | 12" - UNDISTURBED SUB-GRADE 24" + O.D.


→ PAVED AREAS

UNPAVED AREAS -

1. NO ADDITIONAL PAYMENT SHALL BE MADE FOR EXTRA DEPTH INSTALLATION.

2. NO SEPARATE PAYMENT WILL BE MADE FOR RESTORATION EXCEEDING TRENCH WIDTHS.

#### **TYPICAL TRENCH DETAIL** N.T.S.




#### **SIDEWALK NOTES:**

- SUBBASE SHALL BE COMPACTED TO THE SATISFACTION OF THE ENGINEER.
- 2. EXPANSION JOINTS OF 1/2" WIDE BITUMINOUS CELLULAR TYPE JOINT FILLER WILL BE PROVIDED EVERY 12'. LONGITUDINAL JOINTS, EVERY 1/4" WIDE, SHALL BE PROVIDED BETWEEN CURBS AND ABUTTING SIDEWALKS AND
- SHALL BE FILLED WITH PRE-MOLDED BITUMINOUS TYPE JOINT FILLER. TRANSVERSE SURFACE GROOVES SHALL BE CUT IN SIDEWALKS BETWEEN EXPANSION JOINTS AT INTERVALS
- **EQUAL TO THE SIDEWALK WIDTH.** ALL JOINTS AND EDGES TO BE TOOLED.
- SURFACE SHALL BE BRUSHED TRANSVERSELY TO A NEAT FINISH.
- ADJACENT GROUND SHALL BE BACKFILLED AND GRADED TO MATCH THE EXISTING GROUND.


## **STANDARD CONCRETE SIDEWALK**

N.T.S.




STANDARD BREAKAWAY **GALVANIZED CHANNEL** SIGN POST FINISH GRADE **CLASS 'B' CONCRETE** SUBBASE

**SIGN INSTALLATION DETAIL** N.T.S.



#### **PAVEMENT BUTTING DETAIL** N.T.S.




#### **PAVEMENT RESTORATION NOTES:**


- NEW PAVEMENT WILL BE INSTALLED WHERE EXISTING ASPHALT: 1) WHERE IT DOES NOT EXIST, 2) IS LESS THAN 2" THICK AFTER MILLING, 3) SHOWS **EXCESSIVE CRACKING AND DAMAGE.**
- 2. SUEZ REPRESENTATIVE WILL PERFORM A VISUAL INSPECTION TO ESTIMATE WHICH AREAS WILL REQUIRE NEW PAVEMENT AND CONFIRM NEW PAVEMENT AREAS WITH THE CONTRACTOR FOLLOWING MILLING.
- 3. ALL THICKNESS SHOWN ABOVE ARE AFTER COMPACTION.
- 4. AFTER PAVEMENT IS COMPLETE, CONTRACTOR WILL RAISE/LOWER SURROUNDING GRADE LEVEL WITH NEW DRIVEWAY SURFACE, INCLUDING REGRADING, RESENDING, AND SOIL EROSION CONTROLS.


# **PAVEMENT DETAIL**

N.T.S.



**PROPOSED 48" DRYWELL DETAIL** N.T.S.







PRELIMINARY SITE PLAN FOR PROJECT NUMBER SUEZ WATER NY PFAS COMPLIANCE SCE-12162.002 **POMONA WELL NO. 38** VILLAGE OF POMONA, TOWN OF RAMAPO, COUNTY OF ROCKLAND, STATE OF NEW YORK SCALE: N.T.S. **SUEZ WATER NEW YORK INC.** SHEET 14OF 15 CONSTRUCTION DETAILS III

**REVISION** -

2. THE SITE AT ALL TIME SHALL BE GRADED AND MAINTAINED SUCH THAT ALL STORMWATER RUNOFF IS DIVERTED TO SOIL EROSION AND SEDIMENT CONTROL FACILITIES.

3. THE CONTRACTOR IS RESPONSIBLE FOR MAINTAINING AND INSPECTING ALL SOIL EROSION AND SEDIMENT CONTROL MEASURES ON REGULAR BASIS, INCLUDING AFTER EVERY STORM EVENT

4. STOCKPILES ARE NOT TO BE LOCATED WITHIN A FLOODPLAIN, BUFFER, ON A SLOPE, ROADWAY, OR DRAINAGE FACILITY. THE BASE OF ALL STOCKPILES SHALL BE CONTAINED BY A HAY BALE SEDIMENT BARRIER OR SILT

5. A CRUSHED STONE, VEHICLE WHEEL-CLEANING BLANKET SHALL BE INSTALLED WHEREVER A CONSTRUCTION ACCESS ROAD INTERSECTS ANY PAVED ROADWAY IN ACCORDANCE WITH NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL

6. ALL SOIL WASHED, DROPPED, SPILLED, OR TRACKED OUTSIDE THE WORK AREA OR ONTO PUBLIC RIGHT-OF-WAY,

SHALL BE REMOVED IMMEDIATELY. PAVED ROADWAYS MUST BE KEPT CLEAN AT ALL TIMES. 7. DUST SHALL BE CONTROLLED AT ALL TIMES IN ACCORDANCE WITH THE NEW YORK STANDARDS AND

SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL.

8. TREES TO REMAIN AFTER CONSTRUCTION WITHIN THE WORK AREA SHALL BE PROTECTED WITH A SUITABLE FENCE INSTALLED AT THE DRIP LINE OR BEYOND IN ACCORDANCE WITH THE NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL.

9. TEMPORARY SEDIMENTATION ENTRAPMENT AREAS SHALL BE PROVIDED AT KEY LOCATIONS TO INTERCEPT AND CLARIFY SILT LADEN RUNOFF FROM THE SITE. THESE MAY BE EXCAVATED OR MAY BE CREATED UTILIZING EARTHEN BERMS, RIP-RAP OR CRUSHED STONE DAMS, HAY BALES, OR OTHER CHANNELIZATION SHALL BE CONSTRUCTED TO INSURE THAT ALL SILT LADEN WATERS ARE DIRECTED INTO THE ENTRAPMENT AREAS, WHICH SHALL NOT BE PERMITTED TO FILL IN, BUT SHALL BE CLEANED PERIODICALLY DURING THE COURSE OF CONSTRUCTION. THE COLLECTION SILT SHALL BE DEPOSITED IN AREAS SAFE FROM FURTHER EROSION.

10. ALL DISTURBED AREAS, EXCEPT ROADWAYS, WHICH WILL REMAIN OPEN OR UNFINISHED FOR MORE THAN 10 DAYS SHALL BE TEMPORARILY SEEDED WITH 1/2 LB. OF RYE GRASS OR MULCHED WITH 100 LBS. OF STRAW OR HAY PER 1,000 SQUARE FEET. ROADWAYS SHALL BE STABILIZED AS RAPIDLY AS PRACTICABLE BY THE INSTALLATION OF THE BASE COURSE. A TEMPORARY SEEDING AND/ OR MULCHING SHOULD BE APPLIED TO DISTURBED AREAS THAT ARE LEFT FOR 15 DAYS UNLESS CONSTRUCTION WILL BEGIN WITHIN 30 DAYS.

11. SILT THAT LEAVES THE SITE SHALL BE COLLECTED AND REMOVED AS DIRECTED BY APPROPRIATE MUNICIPAL **AUTHORITIES.** 

12. AT THE COMPLETION OF THE PROJECT, ALL TEMPORARY SILTATION DEVICES SHALL BE REMOVED AND THE

AFFECTED AREAS RE-GRADED, PLANTED, OR TREATED IN ACCORDANCE WITH APPROVED PLANS. 13. ALL AREAS DISTURBED BY ON SITE GRADING, THAT ILL NOT BE CONSTRUCTED UPON, SHALL BE STABILIZED WITH PERMANENT VEGETATIVE COVER, USING THE FOLLOWING SEEDING SCHEDULE, OR EQUIVALENT:

|                              | 1 LB. PER ACRE | 1 LB PER 1,000 SF |
|------------------------------|----------------|-------------------|
| <b>KENTUCKY BLUE GRASS -</b> | 20             | 0.45              |
| CREEPING RED FESCUE          | 20             | 0.45              |
| PERENNIAL RYE GRASS -        | 5              | 0.10              |

14. ALL SEEDED AREAS TO HAVE AN APPLICATION OF THE FOLLOWING:

LIME - AMOUNT NEEDED TO OBTAIN A pH OF 5.5 FERTILIZER - 15 LBS. PER 1,000 SF OF 10-20-10 FERTILIZER OR APPROVED EQUAL.

IF NOT LANDSCAPED OTHERWISE, ALL NEW CONSTRUCTED STEEP PERMANENT SLOPED LESS THAN 1 (VERTICAL): 2.5 (HORIZONTAL) TO BE SEEDED WITH THE FOLLOWING:

1 LB. PER ACRE **CREEPING RED FESCUE -**TALL FESCUE OR SMOOTH **BROMEGRASS** -

W/ PERENNIAL RYE GRASS 15. ALL SLOPES 1 (VERTICAL): 2.5 (HORIZONTAL) TO BE MULCHED AND STABILIZED WITH CLOTH FABRIC AND PINNED

TO THE GROUND. 16. SOD CAN BE USED INSTEAD OF SEED

CONSTRUCTION SEQUENCE

a. CONSTRUCTION STABILIZING CONSTRUCTION ENTRANCE.

b. INSTALL SEDIMENT BARRIERS AS PER NOTE 1 ABOVE.

c. CONSTRUCT DIVERSIONS SWALES AND DRAINAGE SYSTEMS WITH MINIMUM NECESSARY CLEARING. d. CLEAR EXISTING TREES AND VEGETATION FROM AREAS TO BE EXCAVATED OR FILLED, STRIP AND

STOCKPILE TOPSOIL FROM ALL AREAS O BE DISTURBED.

e. PERFORM NECESSARY EXCAVATION OR FILL OPERATIONS TO BRING SITE TO DESIRED SUBGRADE. INSTALL STORM DRAINAGE SYSTEM.

f. INSTALL SEDIMENT CONTROL BARRIERS AROUND ALL STORM DRAIN INLETS.

g. SEED ALL DISTURBED AREAS WHICH WILL REMAIN UNDISTURBED FOR A PERIOD OR 30 DAYS AS PER

NOTE 2 ABOVE. h. AFTER COMPLETION OF SITE CONSTRUCTION FINE GRADE AND SPREAD TOPSOIL ON ALL LAWN AREAS

AND SEED AS PER NOTES 13 AND 14 ABOVE i. REMOVE SEDIMENT BARRIERS AS PER NOTE 12 ABOVE.

j. MAINTAIN ALL SEEDED AND PLANTED AREAS TO INSURE A VIABLE STABILIZED VEGETATIVE SPECS.

17. ALL CONSTRUCTION TO MEET CURRENT TOWN SPECS. 18. 4" OF TOP SOIL TO BE SPREAD PRIOR TO SEEDING IN ALL DISTURBED AREAS.

#### **SEEDING HIERARCHY**

1. REFER TO PLANTING PLAN FOR AREAS TO RECEIVE "ROADSIDE MIX".

2. REFER TO BASIN PLANTING NOTES FOR BASIN ONLY. 3. REFER TO NOTES 13-15 ABOVE FOR ALL OTHER DISTURBANCE AREAS.

#### **DETENTION BASIN MAINTENANCE NOTES:**

1. THE LONG TERM MAINTENANCE OF THE ON-SITE DETENTION BASIN SHALL BE THE RESPONSIBILITY OF THE OWNER.

2. THE DETENTION BASIN HAS BEEN DESIGNED WITH A POND DRAIN TO ALLOW DEWATERING OF THE BASIN.

3. THE DETENTION BASIN SHOULD BE MAINTAINED IN ACCORDANCE WITH THE PROCEDURES AND GUIDELINES CONTAINED IN THE LATEST EDITION OF THE NEW YORK STATE STORMWATER MANAGEMENT DESIGN MANUAL.

4. THE DETENTION BASIN SHOULD BE INSPECTED ON A MONTHLY BASIS AND IMMEDIATELY AFTER MAJOR STORMS. MAINTENANCE MEASURES SHALL INCLUDE THE FOLLOWING:

4.1. THE POND SHALL BE TREATED FOR MOSQUITO CONTROL PURPOSES IN ACCORDANCE WITH ROCKLAND COUNTY DEPARTMENT OF HEALTH GUIDELINES FOR MOSQUITO SUPPRESSION.

4.2. REMOVE ACCUMULATED TRASH AND DEBRIS FROM INSIDE THE DETENTION BASIN.

4.3. KEEP OUTLET STRUCTURE AND EMERGENCY OVERFLOW CLEAR OF OBSTRUCTIONS AND DEBRIS.

4.4. MAINTAIN ADEQUATE VEGETATION AND GROUND COVER ON THE EMBANKMENTS. SEEDING AND VEGETATION SHALL BE PROVIDED AS NEEDED TO ASSURE 100% COVERAGE

4.5. REMOVE UNDESIRABLE WEEDS AND WOODED VEGETATION GROWTH

4.6. REPAIR AND STABILIZE EMBANKMENT EROSION.

4.7. MAINTAIN AND REPAIR CONCRETE OUTLET STRUCTURE AND PVC UNDERDRAINS.

4.8. REMOVE ACCUMULATED SEDIMENT FROM BASIN INTERIOR.

#### MOSQUITO CONTROL NOTES

1. ALL STORMWATER FACILITIES ON THIS SITE HAVE BEEN DESIGNED TO REMOVE ALL STANDING WATER WITHIN **FIVE DAYS OF A RAIN EVENT.** 

2. ALL STORMWATER FACILITIES SHALL BE INSPECTED AFTER SIGNIFICANT RAINFALLS AND AT LEAST ONCE PER MONTH.

3. IF, UPON INSPECTION, WATER REMAINS IN THE STORMWATER FACILITIES LONGER THAN FIVE DAYS AFTER A

RAIN EVENT, ONE OF THE FOLLOWING MEASURES WILL BE TAKEN: A) THE WATER WILL BE MECHANICALLY REMOVED (I.E. BY VACUUM); OR

B) THE WATER WILL BE MECHANICALLY AGITATED TO PREVENT MOSQUITO BREEDING; OR C) THE WATER WILL BE TREATED WITH MOSQUITO LARVICIDE IN ACCORDANCE WITH NYSDEC AND

ROCKLAND COUNTY HEALTH DEPARTMENT GUIDELINES, REGULATIONS AND PROCEDURES.

4. MOSQUITO BREEDING SUPPRESSION MEASURES MUST BE IMPLEMENTED BETWEEN APRIL 1 AND OCTOBER 31.

5. LARVICIDE TO BE APPLIED SHALL BE "MOSQUITO DUNKS" AS MANUFACTURED BY SUMMIT CHEMICAL CO., BALTIMORE, MD. OR MANUFACTURER'S SPECIFICATIONS.

6. THE LONG TERM MAINTENANCE OF THE ON-SITE STORMWATER SYSTEM SHALL BE THE RESPONSIBILITY OF

SYMBOL PAVEMENT-MOUNTABLE BERM (OPTIONAL) EXISTING GROUND 12'MIN: PAVEMENT PLAN VIEW

# CONSTRUCTION SPECIFICATIONS

STONE SIZE - USE 1-4 INCH STONE, OR RECLAIMED OR RECYCLED CONCRETE

2. LENGTH - NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY).

3. THICKNESS - NOT LESS THAN SIX (6) INCHES.

4. WIDTH - TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT PDINTS WHERE INGRESS OR EGRESS OCCURS, TWENTY-FOUR (24) FOOT IF SINGLE ENTRANCE TO SITE.

5. GEDTEXTILE - WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE.

6. SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CON-STRUCTION ACCESS SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 54 SLOPES WILL BE PERMITTED.


MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY, ALL SEDIMENT SPILLED, DROPPED, VASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.


8. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON A AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.

9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH

ADAPTED FROM DETAILS PROVIDED BY: USDA - NRCS, NEW YORK STATE DEPARTMENT OF TRANSPORTATION, NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION, NEW YORK STATE SOIL & WATER CONSERVATION COMMITTEE

STABILIZED CONSTRUCTION ACCESS






1. CONTRACTOR IS TO CLEAN INLET FILTER AFTER EVERY STORM. 2. IF BOTTOM OF ROADWAY BOX IS BELLOW TOP OF GRATE. CONSTRUCT OPENINGS IN INLET WALL TO

ALLOW WATER TO FLOW IN, COVER OPENINGS WITH WELDED WIRE SUPPORT AND FILTER FABRIC. 3. INSPECTION SHALL BE MADE FREQUENT. MAINTENANCE, REPAIR AND REPLACEMENT SHALL BE MADE

PROMPTLY, AS NEEDED. THE BARRIER SHALL BE REMOVED WHEN THE AREA DRAINING TOWARDS THE INLET HAS BEEN STABILIZED.


# **INLET FILTER DETAIL**

N.T.S.




# TREE PROTECTION IN FILL AREAS

N.T.S.



# TREE PROTECTION-UNDERGROUND **UTILITY INSTALLATION**

N.T.S.



TREE PROTECTION


N.T.S.

**ESTIMATE A TREE'S PROTECTED ROOT ZONE (PRZ) BY CALCULATING THE CRITICAL ROOT RADIUS (CRR).** 


1. MEASURE THE DBH (DIAMETER OF TREE AT BREAST HEIGHT, 4.5 FEET ABOVE GROUND ON THE UPHILL SIDE OF TREE) IN INCHES. 2. MULTIPLY MEASURED DBH BY 1.5 OR 1.0. EXPRESS THE RESULT IN FEET.

**DBH X 1.5: CRITICAL ROOT RADIUS FOR** OLDER, UNHEALTHY, OR SENSITIVE SPECIES.

DBH X 1.0: CRITICAL ROOT RADIUS FOR YOUNGER, HEALTHY, OR TOLERANT SPECIES.



**INLET PROTECTION DEVICE** 



TYPICAL TOPSOIL STOCKPILE



JTHORIZED FOR USE ONLY BY THE PARTY FOR WHOM THE THIS DRAWING MAY NOT BE <u>COPIED</u>, <u>REUSED</u>, <u>DISCLOSED</u>, <u>DISTRIBUTED</u>, OR <u>RELIED UPON</u> FOR ANY OTHER PURPOSE WITHOUT THE WRITTEN CONSENT OF SUBURBAN ENGINEERING LECTRONIC SUBMISSIONS NOT CONTAINING A VALID DIGITA EAL OR PAPER COPIES NOT CONTAINING A RAISED SEAL ARE OT ORIGINALS AND MAY HAVE BEEN ALTERED. COPYRIGHT 2021 SUBURBAN ENGINEERING

**DESCRIPTION** NO. DATE: BY: CHK:

CHECKED B **CHECKED BY:** 

**SUBURBAN ENGINEERING** - Civil Engineers Landscape Architects -- Land Surveyors -7 Cokesbury Califon Road, Lebanon, N.J. 08833 - 973.398.1770

PRELIMINARY SITE PLAN FOR

SUEZ WATER NY PFAS COMPLIANCE **POMONA WELL NO. 38** VILLAGE OF POMONA, TOWN OF RAMAPO, COUNTY OF ROCKLAND, STATE OF NEW YORK

SUEZ WATER NEW YORK INC.

SCE-12162.002 SCALE: N.T.S. SHEET 13OF 15

PROJECT NUMBER

SOIL EROSION & SEDIMENT CONTROL PLAN

DATE: XX/XX/2021

ALL RIGHTS RESERVE

**REVISIONS** 

EXCELLENCE ♦ ECONOMY ♦ ENVIRONMENT

**REVISION** -