



INSTALLATION NOTES:

1. CUT BACK 4'-0"x4'-0" EPDM MEMBRANE, COVER BOARD (IF PRESENT) AND INSULATION.
2. INSTALL WOOD PERIMETER BLOCKING AND ISOCYANURATE INSULATION.
3. INSTALL PVC ROOF MEMBRANE, SEAM TAPE AND SEALANT.
4. INSTALL PIPE PORTAL CURB & HOUSING ASSEMBLY.
5. INSTALL STRIPING AND SEALANT.

S.E.D. CONTROL NUMBER: 66-23-00-01-0-029-012

**FULLER
D'ANGELO
P.C.**

**ARCHITECTS
PLANNERS**

46 KNOLLWOOD ROAD ELMSFORD NEW YORK 10523
TEL 914.893.4444 FAX 914.893.1717
WWW.FULLERDANGELO.COM
Copyright 2022 All Rights Reserved by FULLER & D'ANGELO P.C.

JOB NAME:
YONKERS SCHOOL DISTRICT
PS 29 - WINDOW REPLACEMENT, MASONRY &
SITE IMPROVEMENTS

47 CROYDON ROAD, YONKERS N.Y. 10710

DRAWING TITLE:
DETAIL- PIPE PORTAL

02-22-2022 ADDENDUM #5

DATE ISSUED TO

SCALE: AS NOTED

FILE NO. DRAWING NO.
19359.00 SK-A1.0