



CONTRACTOR SHALL INSTALL CURTAIN DRAINS AND MONITORING TRENCH AND MONITOR THE GROUNDWATER ELEVATION AS OUTLINED IN PDOT REGULATIONS FROM MARCH 15 TO JUNE 30. THE RESULTS OF THE MONITORING SHALL BE PROVIDED TO THE PDOT, NYCDEP AND DESIGN ENGINEER PRIOR TO THE INSTALLATION OF ABSORPTION FIELDS.

1. THE FILL MATERIAL MUST BE STABILIZED PRIOR TO SEPTIC FIELD INSTALLATIONS IN ACCORDANCE WITH SECTION E.13 OF DEC'S DESIGN MANUAL.
2. THE FILL MATERIAL SHALL HAVE A PERCOLATION RATE OF 5-30 MINUTES PER INCH.
3. PERCOLATION TEST IN THE FILL MATERIAL MUST BE CONDUCTED AT THE BORROW PIT AND AFTER PLACEMENT AND SETTLING AT THE SITE. DEP MUST WITNESS THE LATTER.

PROFILES

VERTICAL SCALE: 1" = 30'
SCALE IN FEET

HORIZONTAL SCALE: 1" = 30'
SCALE IN FEET

			03/06/2023	REVISED BUILDING B STORM ROOF LEADERS	8
			02/10/2023	REV. NEW LOT LINE, SITE GRADING & STORM	7
			12/30/2022	REV. BUILDING A UTILITIES	6
04/19/2023	REV. PER RF1 29	9	12/16/2022	REV. PER WATERSHED INSPECTOR GENERAL COMMENTS	5
Date	Description	No.	Date	Description	No.
Revisions			Revisions		

WARNING: IT IS A VIOLATION OF THE NYS EDUCATION LAW ARTICLE 149 FOR ANY PERSON, UNLESS HE IS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, LAND SURVEYOR OR GEOLOGIST, TO ALTER THIS ITEM IN ANY WAY.



05/03/2023

LANGAN
Langan Engineering, Environmental, Surveying,
Landscape Architecture, and Geology, D.P.C.
One North Broadway, Suite #10
White Plains, NY 10601
T: 914.323.7400 F: 914.323.7401 www.langan.com

Project
**LINCOLN LOGISTICS
BREWSTER**
TOWN OF SOUTHEAST
PUTNAM COUNTY NEW YORK

Drawing Title
OWTS PROFILE 'D'

Project No. 190065201	Drawing No. C-327
Date 1/28/2022	
Drawn By JMSK	
Checked By CZ/MF	

Sheet **46** of **96**