

WALL FOOTING SCHEDULE						
RK	FOOTING SIZE  W x D	FOOTING REINFORCEMENT				
=	2'-0"x3'-2"	3 - #4 CONT. TOP & BOT. W/ #3 TIES @ 60" O.C.				
-2	3'-6"x3'-2"	5 - #4 CONT. TOP & BOT. W/ #3 TIES @ 24" O.C.				
=3	3'-6"x3'-2"	SEE DETAIL 5/F2.2				

 COLUMN FOOTING SCHEDULE

 MARK
 FOOTING SIZE W x L x D
 FOOTING REINFORCEMENT

 F5.50
 5'-6"x5'-6"x1'-0"
 6 - #5 E.W. BOT.


 F5.75
 5'-9"x5'-9"x1'-0"
 6 - #6 E.W. BOT.

 F16.00
 16'-0"x16'-0"x3'-4"
 18 - #8 E.W. TOP & BOT.



4. COORDINATE ALL DOOR OPENINGS AND LOCATIONS WITH ARCHITECTURAL DRAWINGS.
 5. VERIFY LOCATION OF ALL FOOTING STEPS WITH PANEL DRAWINGS PRIOR TO CASTING FOOTINGS.
 6. INDICATES IO MIL VAPOR BARRIER UNDER SLAB ON GRADE. REINFORCE WITH W.W.F. 4x4-W2.9xW2.9.
 7. VERIFY LOCATION OF BLOCK OUTS FOR DOWNSPOUTS WITH PLUMBING DRAWINGS PRIOR TO CASTING FOOTINGS.
 8. 8" CMU REINF. W/ #4 @ 24" O.C. FULL HEIGHT. SEE DETAIL SHEET F2.2.
 9. PROVIDE DOWEL BASKETS @ ALL SLAB JOINTS. PROVIDE JOINT FILLER

3. TOP OF EXTERIOR FOOTING ELEVATION = 99'-0" U.N.O.



OVERALL PLAN FOR REFERENCE ONLY. USE SHEETS F1.1 TO F1.2 FOR WORKING DWGS

## DESIGNER / BUILDER ARCO DESIGN/BUILD INDUSTRIAL 44 SOUTH BROADWAY, SUITE 1003

WHITE PLAINS, NY 10601

P: 914.821.5535 F: 914.306.6010

ADBI | DESIGN | SERVICES

PROJECT TITLE

LINCOLN EQUITIES -NY-131- BLDG A

NY-312 & PUGSLEY RD, SOUTHEAST, NY 10509

ARCHITECT
ADBI / DESIGN SERVICES LLC
44 SOUTH BROADWAY, SUITE 1003
WHITE PLAINS, NY 10601

CIVIL ENGINEER LANGAN ENGINEERING 300 KIMBALL DRIVE PARSIPPANY, NJ 07054

STRUCTURAL ENGINEER
SMITH/ ROBERTS AND ASSOCIATES, INC.
6501 BLUFF RD.

INDIANAPOLIS, INDIANA 46217


MECHANICAL ENGINEER
NATIONAL DESIGN/ BUILD SERVICES
11840 BORMAN DRIVE
ST. LOUIS, MO 63146

ELECTRICAL ENGINEER
FXB ENGINEERING
5 CHRISTY DRIVE, SUITE 307
CHADDS FORD, PA 19317

PLUMBING ENGINEER


MCCARTHY ENGINEERING ASSOCIATES,
INC.
315 EAST SECOND STREET
BOYERTOWN, PA 19512

FIRE PROTECTION ENGINEER S A COMUNALE CO. INC. 2900 NEWPARK DRIVE BARBERTON, OH 44203



THOMAS G. SMITH | NY: 042383

KEY PLAN





	SUBMITTALS				
		NO.	DATE	DESCRIPTION	
	_		12.08.21	PROGRESS	
	_		1.28.22	PROGRESS	
	_		2.28.22	95% PROGRESS	
	_		3.9.22	100% PROGRES	
	_		5.24.22	PUMP HOUSE	
I	_		6.9.22	PERMIT	
		1	7.8.22	FTG STEPS & JOIST SEAT	

 PROJECT NO.
 DRAWN

 AS286-21 | NY131 | 21-154
 DTC

SHEET TITLE
OVERALL
FOUNDATION PLAN

SHEET NO.

F1.0