



REINFORCEMENT SCHEDULE	
R1	#5 BARS @ 10' O.C. VERT. #4 BARS @ 10' O.C. HORIZ.
R2	#5 BARS @ 8' O.C. VERT. #4 BARS @ 10' O.C. HORIZ.
R3	#5 BARS @ 12' O.C. VERT. #4 BARS @ 10' O.C. HORIZ.
R4	#4 BARS @ 12' O.C. E.F. VERT. #4 BARS @ 12' O.C. E.F. HORIZ.
R5	#5 BARS @ 10' O.C. VERT. #4 BARS @ 12' O.C. HORIZ.
R6	#4 BARS @ 12' O.C. VERT. #4 BARS @ 12' O.C. HORIZ.

SOUTH ELEVATION (8 1/2" PANEL TYP. U.N.O.)
SCALE: 1/8" = 1'-0"
(LOOKING FROM INSIDE OF BUILDING ALONG COLUMN LINE H)
NOTES:
1. VERIFY ALL PANEL AND OPENING DIMENSIONS W/GENERAL CONTRACTOR & ARCHITECT PRIOR TO CASTING PANELS W/DOORS AND WINDOWS.
2. PROVIDE 1-#5 E.F. AROUND PERIMETER OF PANEL U.N.O.
3. CONTINUE REINFORCING THROUGH KNOCK-OUT OPENINGS.
4. BLOCKING AT TOP OF WALL TO REMAIN AFTER CONSTRUCTION OF PANELS.
5. HORIZONTAL STEEL CONTINUES THROUGH PANEL LESS AT ALL OPENINGS.