



New York State  
Parks, Recreation and  
Historic Preservation

Agency 1290000

# ***PROJECT MANUAL***

TA-JJ-2023-001  
JOHN JAY HOMESTEAD: SITE AND BUILDING ENHANCEMENTS  
JOHN JAY HOMESTEAD STATE HISTORIC SITE

## **BID PROPOSALS FOR THE FOLLOWING CONTRACT(S):**

D006292 GENERAL CONTRACT

**VOLUME 5 of 6**

**Are Due via email at:**

12:30 PM

**on**

October 8, 2024

**Bid proposals will be opened exclusively via Webex at:**

1:00 PM

**on**

October 8, 2024

**Webex Link at attend:**

<https://meetny.webex.com/meetny/j.php?MTID=m40b9689c6ed92a60ec352816a046e233>

---

Contact Persons:

Senior Architect

Amanda Tucker / 518.807.1884

Architectural Conservator

Erin Maroney / 518.268.2173

Capital Facility Manager

Garrett Jobson / 845.889.3840

Contract Administrator

Tammy Murray / 518.474.3831

Contract Administrator

Magen Bauer / 518.474.3258

---



**Technical Specifications Volume 3 of 3**  
**for**  
**JOHN JAY HOMESTEAD**  
**SITE AND BUILDING ENHANCEMENTS**

**John Jay Homestead**  
**400 Jay Street**  
**Katonah, New York**

Prepared for:  
New York State Office of Parks, Recreation and Historic Preservation  
Taconic Region

by:  
Beyer Blinder Belle Architects & Planners LLP  
New York, NY

**100% CD SUBMISSION**

5 June 2024



## CLIENT

New York State Parks, Office of Parks  
Recreation & Historic Preservation (NYSOPRHP)  
625 Broadway  
Albany NY 12207

NYSOPRHP Taconic Region  
PO Box 308- 9 Old Post Road  
Staatsburg, NY 12580

## CONSULTANTS

### ARCHITECT, PRIME

Beyer Blinder Belle, Architects and Planners, LLP  
120 Broadway, 20th Floor  
New York, NY 10271

### STRUCTURE ENGINEERING

Thornton Tomasetti  
120 Broadway, 15th Floor,  
New York, NY 10271

### MEP / FP / IT Engineering

Landmark Facilities Group  
252 East Avenue  
Norwalk, Ct 06855

### CIVIL ENGINEERING

CHA Consulting, Inc.  
575 Broadway, Suite 301,  
Albany, NY 12207

### LANDSCAPE ARCHITECT

Rhodeside Harwell Landscape Architecture  
347 West 36th Street, Suite 1201  
New York, NY 10018

### LIGHTING ENGINEERING

HLB Lighting  
38 East 32nd Street, 11th Floor  
New York, NY 10016

### SIGNAGE

LVCK - A Beyer Blinder Belle Studio  
120 Broadway, 20th Floor,  
New York, NY 10271

### HAZARDOUS MATERIALS

Matrix New World Engineering  
20 West 37th Street, 12th Fl  
New York, NY 10018



SECTION 010000      TABLE OF CONTENTS

VOLUME 1

DIVISION 00 - PROCUREMENT AND CONTRACTING REQUIREMENTS

DIVISION 01 - GENERAL REQUIREMENTS

011000	Summary	Parks
011400	Work Restrictions	Parks
012100	Allowances	Parks
012300	Alternates	Parks
012500	Substitution Procedures	Parks
012600	Contract Modification Procedures	Parks
012700	Unit Prices	Parks
012900	Payment Procedures	Parks
013000	Administrative Requirements	Parks
013100	Project Management and Coordination	Parks
013301	Submittal Procedures	Parks
013500	Special Procedures	Parks
013591	Historic Treatment Procedures	BBB
014200	References	Parks
014300	Quality Assurance	Parks
014500	Quality Assurance: Structural Testing and Inspection	TT
015000	Temporary Construction Facilities and Controls	Parks
015213	Owner's and Construction Manager's Field Office	Arcadis
015639	Temporary Tree and Plant Protection	RHI
016000	Product Requirements	Parks
016600	Specialty/Custom Material Storage and Handling Requirements	Parks
017300	Execution	Parks
017419	Construction Waste Management and Disposal	Parks
017700	Contract Closeout	Parks
017823	Operation and Maintenance Data	Parks
017839	Project Record Documents	Parks
017900	Demonstration and Training	Parks

DIVISION 02 - EXISTING CONDITIONS

020342	Removal and Salvage of Historic Construction Materials	BBB
020344	Shoring	TT
024119	Selective Demolition and Alteration Work	TT+BBB
028200	Asbestos Abatement	Matrix
028304	Incidental Disturbance of Lead Containing Materials	Matrix



028600	Identification and Disposal of Hazardous Waste	Matrix
028700	Biohazard Remediation	Matrix

#### DIVISION 03 - CONCRETE

031000	Concrete Formwork	TT
032000	Concrete Reinforcement and Embedded Assemblies	TT
033000	Cast-In-Place Concrete	TT

#### DIVISION 04 - MASONRY

040300	Restoration Treatments for Historic Masonry	BBB
042000	Unit Masonry	BBB
044101	New and Reconstructed Dry-Laid Stone Walls	RHI
044102	Raised Stone Planter	RHI
047201	Cast Stone Fountain	RHI
049000	Masonry Restoration and Cleaning	BBB

#### DIVISION 05 - METALS

050300	Restoration Treatments for Historic Metals	BBB
054000	Cold Formed Metal Framing	BBB
055000	Miscellaneous Metals	BBB
055213	Pipe and Tube Railings	RHI
057000	Ornamental Metals	BBB
057300	Ornamental Metal Railings	BBB

#### DIVISION 06 - WOOD, PLASTICS, AND COMPOSITES

060312	Restoration Treatment for Historic Woodwork	BBB
061000	Wood Frame Construction	BBB+TT
061005	Wood Stair Construction	BBB
061500	Wood Decking	BBB+TT
062000	Carpentry	BBB
064013	Exterior Architectural Woodwork	BBB
064023	Architectural Woodwork	BBB

#### DIVISION 07 - THERMAL AND MOISTURE PROTECTION

071326	Sheet Membrane Waterproofing	BBB
072100	Thermal Insulation	BBB
072191	Polyethylene Air Barrier	BBB
072711	Non-Permeable Self-Adhered Air/Vapor Barrier Membrane	BBB
073113	Asphalt Shingles	BBB
073129	Wood Shingle Roofing	BBB
074624	Wood Shingle Siding	BBB



075560	Cold Fluid Applied Membrane Roofing	BBB
076200	Sheet Metal Flashing and Trim	BBB
078413	Firestops and Smoke seals	BBB
079200	Joint Sealers	BBB

#### DIVISION 08 - OPENINGS

080300	Restoration Treatment for Period Openings	BBB
081416	Wood Doors	BBB
081433	Stile-and-Rail Wood Doors and Frames	BBB
083113	Access Doors	BBB
085200	Wood Windows	BBB
086300	Metal Framed Skylights	BBB
087100	Finish Hardware	BBB
088000	Glass and Glazing	BBB

#### DIVISION 09 - FINISHES

090120	Restoration Treatment for Historic Plaster	BBB
090160	Restoration, Reuse, and Refinishing of Wood Plank and Strip Flooring	BBB
092300	Lathing and Plastering	BBB
092433	Cement Parging	BBB
092613	Veneer Plastering	BBB
092900	Gypsum Drywall	BBB
093013	Ceramic Tiling	BBB
096283	Glass Floor Panels	BBB
096313	Brick Flooring	BBB
096345	Stone Door Sills	BBB
096400	Wood Plank and Strip Flooring	BBB
096513	Resilient Base and Accessories	BBB
096519	Resilient Tile Flooring	BBB
096816	Specialty Carpeting and Floor Cloth	BBB
097200	Wallcovering	BBB
099000	Painting and Finishing	BBB
099723	Silicate Coating	BBB

#### DIVISION 10 - SPECIALTIES

101400	Interior Signage	LVCK
101426	Post and Panel Signage	LVCK
102113	Toilet Cubicles	BBB
102800	Toilet Accessories	BBB
104416	Fire Extinguishers and Cabinets	BBB



## DIVISION 11 - EQUIPMENT

111233	Parking Gates	CHA
--------	---------------	-----

## DIVISION 12 - FURNISHINGS

122113	Horizontal Louver Blinds	BBB
122413	Window Shades	BBB
123661	Solid Surfacing Countertops and Trim	BBB
129300	Site Furnishings	RHI
129301	Custom Site Furnishings – Raised Timber Planter	RHI

## DIVISION 13 - SPECIAL CONSTRUCTION

## DIVISION 14 - CONVEYING EQUIPMENT

142423	Limited-Use/Limited-Application Elevators (LU/LA)	BBB
144213	Inclined Platform Wheelchair Lift	BBB

# VOLUME 2

## DIVISION 22 - PLUMBING

220518	Escutcheons for Plumbing Piping	LFG
220523.12	Ball Valves for Plumbing Piping	LFG
220529	Hangers and Supports for Plumbing Piping and Equipment	LFG
220719	Plumbing Piping Insulation	LFG
221116	Domestic Water Piping	LFG
221316	Sanitary Waste and Vent Piping	LFG
221429	Sump Pumps	LFG
223300	Electric, Domestic-Water Heaters	LFG
224213.13	Commercial Water Closets	LFG
224216.13	Commercial Lavatories	LFG
224713	Drinking Fountains	LFG

## DIVISION 23 - HEATING, VENTILATING, AND AIR CONDITIONING (HVAC)

230519	Meters and Gauges for HVAC Piping	LFG
230523	General-Duty Valves for HVAC Piping	LFG
230529	Hangers and Supports for HVAC Piping and Equipment	LFG
230553	Identification for HVAC Piping and Equipment	LFG
230593	Testing, Adjusting, and Balancing for HVAC	LFG
230713	Duct Insulation	LFG
230719	HVAC Piping and Equipment Insulation	LFG
230923	Direct Digital Control (DDC) System for HVAC	LFG



230993.11	Sequence of Operations for HVAC	LFG
232113	Hydronic Piping	LFG
232113.33	Ground-Loop Heat-Pump Piping	LFG
232116	Hydronic Piping Specialties	LFG
232123	Hydronic Pumps	LFG
233113	Metal Ducts	LFG
233300	Air Duct Accessories	LFG
233423	HVAC Power Ventilators	LFG
233713	Diffusers, Registers, and Grilles	LFG
238129	Variable-Refrigerant-Flow HVAC Systems	LFG
238146	Water-Source Unitary Heat Pumps	LFG
238146.13	Water-To-Air Heat Pumps	LFG
238239.19	Wall and Ceiling Unit Heaters	LFG
238416	Mechanical Dehumidification Units	LFG

#### DIVISION 26 - ELECTRICAL

260513	Medium-Voltage Cables	LFG
260519	Low-Voltage Electrical Power Conductors and Cables	LFG
260523	Control-Voltage Electrical Power Cables	LFG
260526	Grounding and Bonding for Electrical Systems	LFG
260529	Hangers and Supports for Electrical Systems	LFG
260533	Raceways and Boxes for Electrical Systems	LFG
260543	Underground Ducts and Raceways for Electrical Systems	LFG
260544	Sleeves and Sleeve Seals for Electrical Raceways and Cabling	LFG
260553	Identification for Electrical Systems	LFG
262416	Panelboards	LFG
262713	Electricity Metering	LFG
262726	Wiring Devices	LFG
262813	Fuses	LFG
262816	Enclosed Switches and Circuit Breakers	LFG
264113	Lightning Protection for Structures	LFG
265113	Architectural Luminaires, Sources and Components	HLB

#### DIVISION 27 - COMMUNICATIONS

271323	Communications Optical Fiber Backbone Cabling	LFG
271513	Communications Copper Horizontal Cabling	LFG

#### DIVISION 28 - ELECTRONIC SAFETY AND SECURITY

281600	Intrusion Detection System	LFG
282319	IP-CCTV System	LFG



#### DIVISION 31 - EARTHWORK

310519.13	Geotextiles	CHA
311000	Site Clearing	CHA
312000	Earth Moving	CHA
312319	Dewatering	CHA
312333	Trenching and Backfilling	CHA
312500	Erosion and Sediment Control	CHA
313710	Stone Fill	CHA
316100	Footings	TT

#### DIVISION 32 - EXTERIOR IMPROVEMENTS

321116	Subbase Courses	CHA
321216	Asphalt Paving	CHA
321217	Chip Seal Paving	CHA
321242	Bound Aggregate Stone Surfacing	RHI
321400	Unit Paving	RHI
321500	Crushed Stone Surfacing	CHA
321613.53	Granite Curbs	CHA
321630	Concrete Sidewalks	CHA
321723	Pavement Marking	CHA
323129	Wooden Gates	RHI
329115	Soil Preparation (Performance Specification)	RHI
329200	Lawns and Grasses	RHI
329220	Herbaceous Seeding	RHI
329300	Exterior Plants	RHI
329600	Transplanting	RHI

#### DIVISION 33 - UTILITIES

330500	Common Work Results for Utilities	CHA
330513	Manholes and Structures	CHA
334100.20	High-Density Polyethylene Storm Utility Drainage Piping	CHA
334616.19	Underdrains	CHA



## VOLUME 3 - APPENDIX

APPENDIX 1	Bedford House Doors Photosurvey – 5 June 2024	BBB
APPENDIX 2	Bedford House Finishes –Submittal Sheets Form 107HP	FOJJ
APPENDIX 3	Typical Seaming Plan	BBB
APPENDIX 4	Hazardous Materials Investigation Report –1/31/2024	MATRIX
APPENDIX 5	Tree Survey – 3/3/2024	RHI
APPENDIX 6	TO BE ISSUED AT A LATER DATE: Garden Club Existing Conditions Information	RHI
APPENDIX 7	Stormwater Pollution Prevention Plan – May 2024	CHA
APPENDIX 8	Geotechnical Engineering Report – May 2024	CHA
APPENDIX 9	New Private Primary Underground Service Installation –Rev. 12/1/2023-PFC	NYSEG
APPENDIX 10	Luminaire Schedule	HLB
APPENDIX 11	Light Fixture Product Data Sheets	HLB
APPENDIX 12	Control Narrative	HLB
APPENDIX 13	IT Cable and Conduit Guidelines	LFG

END OF TABLE OF CONTENTS

## ABBREVIATIONS

Parks	New York State Office of Parks, Recreation and Historic Preservation	Division 1
BBB	Beyer Blinder Belle, Architects & Planners, LLP	Architect
TT	Thornton Tomasetti	Structure Engineering
LFG	Landmark Facilities Group	MEP / IT / FP Engineering
CHA	CHA Consulting, Inc.	Civil Engineering
RHI	Rhodeside Harwell Landscape Architecture	Landscape Architect
HLB	HLB Lighting	Lighting Engineering
LVCK	LVCK – A Beyer Blinder Belle Studio	Signage
Matrix	Matrix New World Engineering	Hazardous Materials



THIS PAGE INTENTIONALLY LEFT BLANK.



## APPENDIX 7

### Stormwater Pollution Prevention Plan – May 2024



THIS PAGE INTENTIONALLY LEFT BLANK.



# STORMWATER POLLUTION PREVENTION PLAN

**John Jay Homestead  
Site and Building Enhancements**  
400 Jay Street  
Katonah, New York

CHA Project Number: 080675.000

**May 2024**

**Prepared for:**  
**New York State Parks, Recreation and  
Historic Preservation Taconic Region**  
9 Old Post Road, PO Box 308  
Staatsburg, NY 12580

**Prepared by:**  
**CHA Consulting, Inc.**  
111 Winners Circle  
Albany, New York 12205  
Phone: (518) 453-4500

This document is intended for the use of the individual or entity for which it was prepared and may contain information that is privileged, confidential, and exempt from disclosure under applicable law. Any dissemination, distribution, or copying of this document is strictly prohibited.









## TABLE OF CONTENTS

1.0	PROJECT INFORMATION .....	4
2.0	PROJECT DESCRIPTION .....	4
2.1	Purpose and Extent of Proposed Development.....	4
2.2	Project Disturbance Area .....	5
2.3	Description and Limitations of On-Site Soils.....	5
2.4	Historic Places.....	7
3.0	SEQUENCE OF MAJOR ACTIVITIES .....	8
3.1	Construction Sequence.....	8
3.2	Name of Receiving Waters .....	9
4.0	EROSION AND SEDIMENT CONTROLS .....	10
4.1	Pre-Construction .....	10
4.2	Timing of Controls/Measures .....	10
4.3	Erosion and Sediment Controls / Stabilization Practice .....	10
4.3.1	Temporary Stabilization.....	10
4.3.2	Permanent Stabilization.....	11
4.4	Winter Operations .....	11
4.4.1	Winter Shutdown .....	12
4.5	Final Site Inspection.....	12
4.6	Other Controls .....	12
4.6.1	Waste Disposal .....	12
4.6.2	Sediment Tracking by Vehicles .....	13
4.6.3	Non-Stormwater Discharges.....	13
4.7	Certification of Compliance with Federal, State, and Local Regulations .....	13
5.0	POST CONSTRUCTION STORMWATER MANAGEMENT .....	14
5.1	Hydrologic Evaluation .....	14
5.1.1	Methodology.....	14
5.1.2	Redevelopment Criteria .....	14
5.2	Existing Condition Hydrology .....	15
5.3	Proposed Condition Hydrology.....	16
5.4	Post-Development Stormwater Management Practices .....	18
5.4.1	Runoff Reduction Volume.....	18
5.4.2	Water Quality Volume.....	21
5.4.3	Channel Protection Volume .....	22
5.4.4	Peak Flow Attenuation.....	22
5.4.5	Stormwater Conveyance Systems.....	22
5.5	Floodplains .....	22
6.0	MAINTENANCE/INSPECTION PROCEDURES .....	23
6.1	Erosion and Sediment Control Inspection and Maintenance Practices.....	23
6.1.1	Owner/Operator Inspection Requirements.....	23
6.1.2	Qualified Inspector Inspection Requirements .....	23
6.1.3	General Requirements .....	24
6.1.4	Dewatering Methods.....	25
6.1.5	Dust Control .....	25
6.2	Post-Construction Stormwater Inspection and Maintenance Practices.....	25
7.0	INVENTORY FOR POLLUTION PREVENTION PLAN .....	26
8.0	SPILL PREVENTION .....	26



8.1	Good Housekeeping .....	26
8.2	Hazardous Products .....	26
8.3	Product Specific Practices .....	27
	Petroleum Products.....	27
	Fertilizers .....	27
	Paints .....	27
	Concrete Trucks .....	27
	Watercourse Protection .....	27
8.4	Spill Control Practices .....	27
9.0	UPDATING THE SWPPP .....	28
10.0	SWPPP CERTIFICATION .....	29
	Contractor's Certification .....	29

## LIST OF TABLES

Table 1 – Nature of Construction Project.....	5
Table 2 - Soil Analysis Summary.....	6
Table 3 - Existing Condition Analysis Summary .....	16
Table 4 – Proposed Condition Analysis Summary.....	18
Table 5 - Summary of Required Runoff Reduction Volumes .....	20
Table 6 – Stormwater Management Practices for Runoff Reduction Not Used in Project.....	20
Table 7 - Summary of Water Quality Volumes.....	21
Table 8 – Existing Condition & Mitigated Post-Development Peak Flow Comparison.....	22

## LIST OF FIGURES

Figure 1	Project Location Map
Figure 2	USDA Soils Map
Figure 3	Existing Conditions Watershed Map
Figure 4	Proposed Conditions Watershed Map
Figure 5	FEMA FIRM Map



## LIST OF APPENDICES

Appendix A	Figures
Appendix B	Historic Cultural Resource
Appendix C	Geotechnical Report
Appendix D	Existing Condition PondPack Outputs
Appendix E	Proposed Condition PondPack Outputs
Appendix F	Proposed Mitigated Condition PondPack Outputs
Appendix G	Water Quality Volume and Runoff Reduction Volume Computations
Appendix H	Phasing Plan, Grading and Drainage Plan and ESC Plan and Details
Appendix E	Inspection Forms
Appendix J	Post Construction Operation and Maintenance
Appendix K	Notice of Intent (NOI) and SPDES General Permit (GP-0-20-001)







## 1.0 PROJECT INFORMATION

Project Name and Location	Owner Name and Address
John Jay Homestead Site and Building Enhancements 400 Jay Street Katonah, New York	NYS OPRHP Taconic Region 9 Old Post Road, PO Box 308 Staatsburg, NY 12580

## 2.0 PROJECT DESCRIPTION

### 2.1 Purpose and Extent of Proposed Development

This Stormwater Pollutions Prevention Plan (SWPPP) has been prepared in accordance with the design guidelines and criteria presented in the State Pollutant Discharge Elimination System (SPDES) General Permit for Construction Activities (GP-0-20-001), Chapter 9: Redevelopment Activity and Chapter 10: Enhanced Phosphorus Removal Supplement of the New York State Stormwater Management Design Manual (January 2015), the New York State Standards and Specifications for Erosion and Sediment Control (July 2016), and Rules and Regulations for the Protection from Contamination, Degradation and Pollution of the New York City Water Supply and Its Sources (November 29, 2019) Section 18-39(b)(4).

The proposed project site is located at 400 Jay Street (John Jay Homestead State Historic Site) in Katonah, Westchester County, New York (see Figure 1 – Site Location Map). The John Jay Homestead State Historic Site is an approximately 62-acre site comprised of 10 buildings, including the original 1787 John Jay House, barns, visitor center, access roads, stone walls, and wooded areas throughout the site. Existing wetland areas and a small pond are located to the south and east of the project site. NYS Route 22 is located to the south, and the Cross River Reservoir is located approximately 3,000 feet northeast of the project site.

The project involves the design of repairs to existing pathways, interior and exterior renovation of John Jay house, construction of a new entry access road, a new parking area, and stormwater management practices. The existing main access road, proposed access road and parking lot will be paved with chip seal pavement. The existing access road will not include cuts and will be constructed at grades similar to the existing grade. The new access road and parking area will require changes to the existing topography and new stormwater management practices.

In order to evaluate the potential impacts associated with the development of the site, existing and proposed condition hydrographs were generated using standard NRCS TR-55 methodology. Peak flows were computed using the Bentley Pondpack Hydrology Program (Version V8i) and the required Water Quality Volume (WQv) and Runoff Reduction Volume (RRv) were computed using the Runoff Frequency Spectrum (RFS) Method, discussed in the New York State Stormwater Management Design Manual.

For the purposes of the hydrologic analysis, 2 design points and 5 contributing sub-areas were defined to characterize the drainage patterns of the existing conditions watershed. The proposed improvements will increase impervious area and alter the permeability of the project site. This



increase in impervious area will create the potential for an increase in the amount of stormwater runoff and a need for stormwater treatment. To meet the full stormwater quality (WQv) and minimum runoff reduction volume (RRv) criteria, the project proposes to install three (3) bioretention areas and two (2) dry ponds, and new tree planting to provide WQv and RRv treatment and meet the required 1-, 10-, and 100-year peak flows mitigation criteria.

This SWPPP covers the entire project construction site, scheduled to proceed from June 2024 until March 2026. The project is intended to be constructed in phases and not to disturb greater than 5 acres of soil at any one time. Therefore, the 5 Acre Waiver is not anticipated for this project at this time.

**Table 1 – Nature of Construction Project**

The nature of this construction project is checked below:	
	New construction with proposed standard SMPs, Green Infrastructures, and ESC measures.
X	Redevelopment with increase in impervious areas with proposed standard SMPs and ESC measures. Green Infrastructures are required for the new impervious areas onsite.
	Redevelopment with no increase in impervious areas with proposed ESC measures only and no SMPs.

## 2.2 Project Disturbance Area

Overall Site Area: 62.0± acres  
 Total Disturbed Area: 8.30± acres  
 Existing Total Impervious Area: 2.25± acres  
 Proposed Total Impervious Area: 2.71± acres

## 2.3 Description and Limitations of On-Site Soils

A subsurface investigation was conducted on the project site in January 2024 by CHA which included eleven (11) test borings and two (2) infiltration tests. The Geotechnical Report is included in Appendix C of this SWPPP. Based on the boring logs, the seasonal ground water table was estimated at depths ranging from 3.1 feet to 13.2 feet on site. The two infiltration tests located on the proposed parking lot found an infiltration rate of 0.0 inches per hour.

The soil disturbance for the proposed work is limited to the 8.3 acres and consists of mostly loamy fine sand. Based on a review of the USDA Soil Surveys of Westchester County, New York, soils on the project site are described in the following list (see Figure 2 – USDA Soils Classification Map). A summary of the soil composition is shown in Table 1.



**Table 2 - Soil Analysis Summary**

Soil Name	Hydrologic Soil Group
PnB - Paxton fine sandy loam, 3 to 8 percent slopes	C
PnC - Paxton fine sandy loam, 8 to 15 percent slopes	C
WdA - Woodbridge loam, 0 to 3 percent slopes	C/D

The Natural Resource Conservation Service (NRCS, formerly known as the SCS), as part of their soil classification system, assigns each soil series to a Hydrologic Soil Group (HSG). The HSG is a four-letter index intended to indicate the minimum rate of infiltration obtained after prolonged wetting, and to indicate the relative potential for a soil type to generate runoff. The infiltration rate is the rate at which water enters the soil at the soil surface. The HSG also indicates the transmission rate – the rate at which water moves within the soil. Soil scientists define the four groups as follows:

- HSG 'A' (sand, loamy sand, or sandy loam): Soils have low runoff potential and high infiltration rates even when thoroughly wetted. They consist chiefly of deep, well to excessively drained sands or gravels and have a high rate of water transmission (> than 0.30 inches/hour).
- HSG 'B' (silt loam or loam): Soils have moderate infiltration rates when thoroughly wetted, and consist chiefly of moderately deep to deep, moderately well to well drained soils with moderately fine to fine texture. These soils have a moderate rate of water transmission (0.15 to 0.30 inches/hour).
- HSG 'C' (sandy clay loam): Soils have low infiltration rates when thoroughly wetted and consist chiefly of soils with a layer that impedes downward movement of water, and soils with moderately fine to fine texture. These soils have a low rate of water transmission (0.05 to 0.15 inches/hour).
- HSG 'D' (clay loam, silty clay loam, sandy clay, silty clay, or clay): Soils have high runoff potential. They have very low infiltration rates when thoroughly wetted, and consist chiefly of clay soils with a high swelling potential, soils with a permanent high water table, soils with a clay pan or clay layer at or near the surface, and shallow soils over nearly impervious material. These soils have a very low rate of water transmission (< 0.05 inches/hour).

If a soil is classified to a dual hydrologic group (A/D, B/D, or C/D), the first letter represents drained conditions and the second letter represents undrained conditions.



## 2.4 Historic Places

The New York State Office of Parks, Recreation and Historic Preservation (OPRHP) SHPO has reviewed the recent submission for the John Jay Homestead Historic Site Project and SHPO has indicated that the proposed project will have NO Adverse Effect to historic and cultural resources. A copy of the letter from SHPO dated 04/29/2024 will be included in Appendix B.



## 3.0 SEQUENCE OF MAJOR ACTIVITIES

### 3.1 Construction Sequence

This SWPPP presents erosion and sediment controls, both temporary and permanent, to assist the operator in compliance with the project's SPDES General Permit for construction activity. To the degree practicable, all temporary erosion and sediment control mitigation measures shall be installed immediately before associated project areas are disturbed in anticipation of all soil disturbing activities to follow.

It is the responsibility of the Contractor to ensure that all soils removed from the project site are spoiled in a manner consistent with all local, state, and federal regulations. Appropriate erosion and sediment controls shall be installed at all spoil sites. Additionally, the Contractor is responsible for coordinating the application for a GP-0-20-001 permit (and development of an associated SWPPP) if disturbance associated with any soil spoils area is greater than 0.4 hectares (1 acre). GP-0-20-001 applications must be signed by the owner of the lands on which soils are spoiled. Disturbances associated with offsite spoil areas do not contribute to the total disturbances associated with onsite activities.

This project will be carried out in 3 phases as outlined below, while maintaining the amount of concurrently disturbed soil in compliance with the NYS DEC limit (see appendix H).

#### **Phase 1 (±2.34acres)**

- Establish work area, contractor staging area, and install stabilized temporary construction entrance.
- Install temporary erosion and sediment control measures as shown on plans.
- Remove asphalt entrance drive and subbase as shown on demolition plans.
- Remove entrance gate and other amenities as shown on demolition plans.
- Install topsoil, seed, and mulch for final stabilization.

#### **Phase 2A (±4.96 acres)**

- Establish work area, contractor staging area, and install stabilized temporary construction entrance.
- Install temporary erosion and sediment control measures as shown on plans.
- Rough grade site for proposed access road and parking lot area.
- Grade and construct the proposed stormwater bioretention and dry ponds.
- Fine grade site and install subbase to stabilize disturbed areas.
- Construct the proposed parking lot, gravel road, walkway and ramps as shown on layout plans.
- Install proposed landscaping, topsoil, and seed for final stabilization of all disturbed areas.

#### **Phase 2B (±3.68 acres)**

- Establish work area, contractor staging area, and install stabilized temporary construction entrance.
- Install temporary erosion and sediment control measures as shown on plans.
- Remove existing gravel loop drive and other amenities as shown on demolition plans.
- Grade and install proposed chip seal road as shown on plans.



- Grade and install proposed chip seal walkways as shown on plans.
- Repair and renovate the existing John Jay House.
- Install proposed trees and landscaping, topsoil, and seed for final stabilization of all disturbed areas.

### 3.2 Name of Receiving Waters

Stormwater runoff from the John Jay Homestead campus site will either drain eastwards and discharge into the existing wetlands and unnamed tributary to Cross River Reservoir (Class B, Standards B), or drain westwards into the existing wetlands and unnamed tributary to Stone Hill River (Class C, Standards C(TS)). The Cross River Reservoir (Class AA(T), Standards AA) is located approximately 3,000 feet northeast of the project site and it is identified as an enhanced phosphorus watershed (Appendix C of the GP-0-20-001 permit). However, it is not listed as 303(d) segments impaired by construction related pollutants (Appendix E of the GP-0-20-001 permit).

The water quality of surface waters in New York State is classified by the New York State Department of Environmental Conservation as A, B, C, or D, with special classifications for water supply sources (AA). A "T" used with the classification indicates the stream supports, or may support, a trout population. Water quality standards are also provided. The standards apply the same classification system but, in some cases, are more stringent in an effort to eventually improve the water quality. The higher standard is most often used to reflect the existence or the potential for breeding trout (designation of (T) as discussed above). All surface waters with a Classification and/or a Standard of C (T), or better, are regulated by the State.



## 4.0 EROSION AND SEDIMENT CONTROLS

### 4.1 Pre-Construction

Prior to construction, the Owner shall have the Contractors and subcontractors identify at least one (1) person from their company who meets the requirements of a Trained Contractor. A Trained Contractor will be responsible for installing, constructing, repairing, and replacing the erosion and sediment control (ESC) practices.

In addition, the Trained Contractor will be responsible for the implementation of the Stormwater Pollution Prevention Plan (SWPPP) and the inspection and maintenance in accordance with New York Standards and Specifications for Erosion & Sediment Control (Blue Book). The Owner's Representative shall ensure that at least one (1) Trained Contractor is on-site daily when soil disturbance activities are being performed. The Trained Contractor shall inspect the site's ESC practices daily to ensure these facilities are operational. Pre-construction requirements to be followed by the Owner and Contractors prior to the commencement of any construction activities are described in Appendix E.

### 4.2 Timing of Controls/Measures

The erosion and sediment control measures shall be constructed prior to clearing or grading of any portion of the project. Where land disturbance is necessary, temporary seeding or mulching must be used on areas which will be exposed for more than 14 days. Permanent stabilization should be performed as soon as possible after completion of grading. After the entire project area is stabilized, the accumulated sediment shall be removed from the project area. Erosion control devices shall remain in place until disturbed areas are permanently stabilized. For projects where soil disturbance is greater than five (5) acres, and construction activity has temporarily or permanently ceased, temporary and/or permanent soil stabilization measures shall be installed and/or implemented within seven (7) days from the date the soil disturbance activity ceased. The soil stabilization measures selected shall be in conformance with the most current version of the technical standard, New York Standards and Specifications for Erosion and Sediment Control.

### 4.3 Erosion and Sediment Controls / Stabilization Practice

Applicable erosion and sediment control measures and details are included in Appendix H.

#### 4.3.1 Temporary Stabilization

Topsoil stockpiles, staging areas and disturbed pervious portions of the project area where construction activity temporarily ceases for at least 14 days shall be stabilized with temporary seed and mulch no later than 14 days from the last construction activity in that area.

Temporary seed shall be ryegrass applied at the rates specified below:

- If seeding in spring, summer or early fall then seed with annual or perennial rye at a rate of 30 lbs per acre. If area is to remain stabilized over the winter into the following spring use perennial rye only.



- If seeding in late fall or early winter, use certified Aroostook winter rye (cereal rye) at a rate of 90 lbs per acre.

Any seeding method may be used that will provide uniform application of seed to the area and result in relatively good soil to seed contact. Area must be free of large rocks and debris and seeded within 24 hours of disturbance or scarification of the soil surface will be necessary prior to seeding. Fertilizer or lime is not typically used for temporary plantings.

Mulch shall be applied in conjunction with seeding and applied at the rate of 90 lbs per 1000 square feet. Mulch shall be reapplied as necessary. Areas of the project area, which are to be paved, shall be temporarily stabilized by applying temporary gravel subbase until pavement can be applied.

Bioretention basins shall be built according to the plans provided. Begin by clearing the designated area of any large rocks and debris. Ensure that the seeding method chosen guarantees uniform distribution across the site, enhancing soil-to-seed contact as per the provided plans. Address any soil surface disturbances within 24 hours, utilizing scarification if necessary to facilitate successful seeding.

Tree planting, adhere closely to the provided plans. Follow the recommended seeding or planting method to ensure even distribution and proper soil-to-seed contact as per the provided guidelines. Avoid the use of unnecessary fertilizers or lime, prioritizing natural growth processes as directed.

Sediment control fencing shall be installed around the site where depicted on the attached plan sheets. Prior to commencing any earthwork, a stabilized construction entrance shall be installed as indicated on the attached plans. This entrance shall be utilized as the exclusive construction entrance and exit to the construction areas. Construction traffic shall be limited to the construction entrance.

#### **4.3.2 Permanent Stabilization**

Disturbed portions of the project area where construction activities permanently cease shall be stabilized with permanent seed no later than 14 days after the last construction activity. The permanent seed mix shall be in accordance with the project specifications and plans. Construction and maintenance of erosion and siltation control measures are in accordance with the New York Standards and Specifications for Erosion and Sediment Control.

Where construction activity is complete over areas to be permanently vegetated, stabilize with permanent seeding. Verify seeding dates with engineer. If engineer determines that seed cannot be applied due to climate, topsoil shall not be spread and mulching shall be applied to the exposed surface to stabilize soils until the next recommended seeding period. Other project areas shall be permanently stabilized with pavement, concrete, gravel or building structures.

#### **4.4 Winter Operations**

If construction activities proceed through the winter season, access points should be enlarged and stabilized to provide for snow stockpiling. Drainage structures should be kept open and free of potential snow and ice dams. Inspection and maintenance are necessary to ensure the function of these practices during runoff events. For sites where construction activities temporarily cease,



temporary and/or permanent soil stabilization measures shall be installed within seven (7) days from the date the soil disturbing activity ceased. Disturbed areas should be stabilized with seed and mulch, or other approved methods, even if the ground is covered by significant amounts of snow.

#### **4.4.1 Winter Shutdown**

Site inspections (by the qualified inspector) may be decreased to a minimum of one (1) time every thirty (30) days for sites where soil disturbing activities have ceased and at least 100% of the site has been stabilized by an approved method. Inlet protection should be installed and/or repaired before shutdown of the site. The owner or operator shall provide written notification to the respective DEC regional office prior to reducing the frequency of any site inspections.

#### **4.5 Final Site Inspection**

The qualified inspector shall perform a final inspection of the site to certify that:

- All disturbed areas have achieved final stabilization;
- Temporary erosion and sediment control practices have been removed; and
- Post-construction stormwater management practices (if required) have been constructed in conformance with the SWPPP.

Upon satisfactory completion of the final site inspection, the qualified inspector shall sign the appropriate sections of the Notice of Termination (NOT) form included in Appendix E.

#### **4.6 Other Controls**

##### **4.6.1 Waste Disposal**

**Waste materials** – Foreign waste materials shall be collected and stored in a secured area until removal and disposal by a licensed solid waste management company. All trash and construction debris from the project area shall be disposed of in a portable container unit. No foreign waste materials shall be buried within the project area. All personnel shall be instructed regarding the correct procedure for waste disposal. Notices stating these practices shall be posted in the project trailer and the individual who manages day-to-day project operations will be responsible for seeing that these procedures are followed.

**Petroleum Impacted Waste** – During the excavation activities, there is the potential that petroleum impacted soils may be encountered. In the event that field evidence of contamination is identified during the project, potentially contaminated soils will be segregated and stockpiled on polyethylene sheeting and covered in a predetermined staging area. The potentially impacted, stockpiled soils will then be sampled to determine if the soils are suitable for use as clean backfill. In the event that the soils are not suitable for re-use, the contaminated soil will be properly characterized and disposed of at an off-site NYSDEC permitted facility. The excavation will then be backfilled with clean, imported fill.

**Hazardous Waste** - All hazardous waste materials shall be disposed of in a manner specified by local or state regulations or by the manufacturer. Project personnel shall be instructed in these practices and the individual who manages day-to-day project operations shall be responsible for seeing that these practices are followed.



**Sanitary Waste** - Any sanitary waste from portable units shall be collected from the portable units by a licensed sanitary waste management contractor, as required by NYS DEC regulations.

#### **4.6.2 Sediment Tracking by Vehicles**

A stabilized construction entrance shall be installed (where depicted on attached plan) and maintained as necessary to help reduce vehicular tracking of sediment. The entrance shall be cleaned of sediment and redressed when voids in the crushed stone become filled and vehicular tracking of sediment is occurring. Dump trucks hauling materials to and from the construction project area shall be covered with a tarpaulin to reduce dust. Any sediment and debris tracked from work area along project adjacent roadways shall be immediately removed with a street sweeper or equivalent sweeping method.

#### **4.6.3 Non-Stormwater Discharges**

Non-stormwater discharges are not expected to exit the project area during construction.

#### **4.7 Certification of Compliance with Federal, State, and Local Regulations**

The stormwater pollution prevention plan reflects the New York State requirements for stormwater management and erosion and sediment control. To ensure compliance, this plan was prepared in accordance with New York State Standards. There are no other applicable State or Federal requirements for sediment and erosion plans (or permits), or stormwater management plans (or permits).



## 5.0 POST CONSTRUCTION STORMWATER MANAGEMENT

### 5.1 Hydrologic Evaluation

#### 5.1.1 Methodology

The proposed project has been designed in accordance with the design guidelines and criteria presented in the State Pollutant Discharge Elimination System (SPDES) General Permit for Construction Activities (GP-0-20-001), Chapter 9: Redevelopment Activity and Chapter 10: Enhanced Phosphorus Removal Supplement of the New York State Stormwater Management Design Manual (January 2015), the New York State Standards and Specifications for Erosion and Sediment Control (July 2016), and Rules and Regulations for the Protection from Contamination, Degradation and Pollution of the New York City Water Supply and Its Sources (November 29, 2019) Section 18-39(b)(4).

In order to evaluate the potential impacts associated with the development of the site, existing and proposed condition hydrographs were generated. The conditions were modeled using the SCS unit hydrograph method using a type II rainfall distribution. Rainfall amounts were referenced from the New York State Stormwater Management Design Manual, January 2015. The 24-hour rainfall amounts for the 1-, 10-, and 100-year design storms in Katonah, Westchester County are 2.80-, 5.09- and 9.11-inches respectively.

Runoff curve numbers and times of concentration were computed using standard NRCS TR-55 methodology. Additionally, peak stormwater flows and hydrographs for the existing and post-development conditions were computed using the Bentley Pondpack Hydrology Program (Version V8i).

Since the proposed redevelopment project is located within the New York City Watershed East of the Hudson River as shown in Appendix C of the SPDES General Permit (GP-0-20-001) where enhanced phosphorus removal standards are required, the total Water Quality Volume (WQv) shall be calculated in accordance with Chapter 10 of the New York State Stormwater Management Design Manual (January 2015). The total estimated WQv required is calculated based on the 1-year, 24-hour design storm over the post development disturbed drainage areas using standard NRCS TR-55 methodology to account for runoff volume from the drainage areas.

Moreover, the minimum Runoff Reduction Volume (RRv) is calculated using the 1-year storm event and the amount of new impervious area within the drainage area. The required RRv criteria is applied to the new developed impervious area only.

#### 5.1.2 Redevelopment Criteria

Redevelopment of previously developed sites is encouraged from a watershed protection standpoint because it often provides an opportunity to conserve natural resources in less impacted areas by targeting development to areas with existing services and infrastructure. Redevelopment provides an opportunity to correct existing problems and reduce pollutant discharges from previously developed areas that were constructed without effective stormwater pollution controls.

Because the technical standards contained in the New York State Stormwater Management Design Manual were primarily intended for new development projects, compliance with the



standards may present a challenge on some redevelopment projects. Therefore, Chapter 9 of the New York State Stormwater Management Design Manual give the following definition for redevelopment activity on page 9-2.

**Redevelopment Activity / Activities – Disturbance and reconstruction of existing impervious surfaces. This includes impervious surfaces that were removed within the last five (5) years.**

If the construction project includes both new development and redevelopment activities, treatment would be required for 25% of the existing, disturbed impervious area, however, the stormwater management practices for the new development portion of the project must be designed in accordance with the sizing criteria in Chapter 4.

## **5.2 Existing Condition Hydrology**

For the purpose of this analysis, the extent of the hydrologic model was limited to the areas affected by the proposed improvements. For the existing condition analysis, two design points and five contributing sub-areas were defined to characterize the natural drainage patterns of the watershed (See Figure 3 – Existing Conditions Watershed Map).

Design Point 1 (DP-1) is located along the southern and eastern boundary of the project site discharging into the existing wetlands and unnamed tributary to Cross River Reservoir. Stormwater runoff from DA-1, DA-2, DA-3, and DA-5 will sheet flow and drain towards DP-1, and eventually outfall into the Cross River Reservoir located approximately 3,000 feet northeast of the project site.

Design Point 2 (DP-2) is located southwestern boundary of the project site and collects stormwater runoff from Drainage Area 4 (DA-4), which ultimately drains into the existing wetlands and unnamed tributary to Stone Hill River.

Drainage Area 1 (DA-1) comprises of 3 existing buildings and a large, vegetated area located on the northeastern portion of the project site. Runoff in this sub-area sheet flows overland directed towards the existing wetlands and unnamed tributary to Cross River Reservoir at DP-1.

Drainage Area 2 (DA-2) encompasses of a large, vegetated area, an existing gravel road, and a brick cottage building. Runoff in this drainage area sheet flows overland directed eastwards and southwards into the existing wetlands and unnamed tributary to Cross River Reservoir at DP-1.

Drainage Area 3 (DA-3) contains an existing gravel entrance and access road and some vegetated areas along both sides of the road. Runoff in this sub-area sheet flows overland directed towards the existing wetlands and unnamed tributary to Cross River Reservoir at DP-1.

Drainage Area 4 (DA-4) consists of most of the project site west of the existing gravel entrance road including the original 1787 John Jay House, existing loop gravel drive, sundial garden, herb garden, existing pathways, parking areas, and associated site amenities. Runoff in this drainage area will sheet flow overland directed towards DP-2, which ultimately drains into the existing wetlands and unnamed tributary to Stone Hill River.

Drainage Area 5 (DA-5) comprises of five existing buildings including the Main Barn, an existing gravel road, and some vegetated areas located northeast of the John Jay House. Runoff in this



sub-area sheet flows overland directed towards DA-1 and discharge into the existing wetlands and unnamed tributary to Cross River Reservoir at DP-1.

The results of the existing condition analyses are presented in Table 3, with detailed computations provided in Appendix D.

**Table 3 - Existing Condition Analysis Summary**

Design Point	Watershed	Area (acres)	Tc (hrs)	Curve Number	Peak Flow Rate (cfs)		
					1-yr	10-yr	100-yr
DP-1	DA-1	4.75	0.135	75	3.71	11.8	27.88
	DA-2	3.65	0.105	75	2.99	9.40	22.10
	DA-3	1.36	0.083	82	1.74	4.42	9.29
	DA-5	1.33	0.103	82	1.66	4.25	8.95
	Total	11.09	--	--	10.00	29.72	67.98
DP-2	DA-4	7.63	0.102	79	8.08	22.39	49.29
	Total	7.63	--	--	8.08	22.39	49.29

### 5.3 Proposed Condition Hydrology

The proposed improvements will increase the impervious area and alter the permeability of the project site. This increase in impervious area will potentially lead to an increase in stormwater runoff and necessitate stormwater treatment. The existing condition drainage areas have been revised to reflect the new drainage patterns of the proposed watershed with two design points and ten contributing sub-areas (See Figure 4 – Proposed Conditions Watershed Map).

Design Point 1 (DP-1) continues to be located along the southern and eastern boundary of the project site discharging into the existing wetlands and unnamed tributary to Cross River Reservoir. Stormwater runoff DA 1A, DA-1B, DA-1C, DA-1D, DA-2A, DA-2B, DA-3, DA-5A, and DA-5B will sheet flow and drain towards DP-1, and eventually outfall into the Cross River Reservoir located approximately 3,000 feet northeast of the project site.

Design Point 2 (DP-2) continues to be located at the southwestern boundary of the project site and collects stormwater runoff from Drainage Area 4 (DA-4), which ultimately drains into the existing wetlands and unnamed tributary to Stone Hill River.



Drainage Area 1A (DA-1A) encompasses the proposed parking lot area, where runoff will be directed to drain towards the proposed bioretention area 1 and dry pond 1 and will outlet directly towards DP-1, and eventually discharges into the Cross River Reservoir located approximately 3,000 feet northeast of the project site.

Drainage Area 1B (DA-1B) consists of the northern portion of the proposed access road leading to the new parking lot area, where runoff will be directed to drain towards the proposed bioretention area 2 and dry pond 2 and will outlet directly towards DP-1, and eventually discharges into the Cross River Reservoir located approximately 3,000 feet northeast of the project site.

Drainage Area 1C (DA-1C) receives runoff from DA-5B and contains the cottage fabric building and an old concrete foundation, both surrounded by grassed areas. Stormwater flowing through DA-1C will be conveyed to DA-1B.

Drainage Area 1D (DA-1D) is mainly composed of grassed areas with an old concrete foundation slab and some woods on its northwest portion. Stormwater flowing through DA-1D will be conveyed to DA-1A.

Drainage Area 2A (DA-2A) contains the proposed access drive, the existing brick cottage building surrounded by woods, and a grass field. Runoff will be sheet flow and directed towards the proposed bioretention area 3 located within DA-2B.

Drainage Area 2B (DA-2B) collects water from part of DA-2A, containing the southern portion of the proposed access road and the proposed bioretention basin 3, which will outlet directly towards DP-1, and eventually discharges into the Cross River Reservoir located approximately 3,000 feet northeast of the project site.

Drainage Area 3 (DA-3) contains an existing gravel entrance and access road, which will be widened and reconstructed with chip seal pavement. The project will propose new trees to be planted along the existing trees and vegetated areas along both sides of the road. Runoff in this sub-area sheet flows overland directed towards the existing wetlands and unnamed tributary to Cross River Reservoir at DP-1.

Drainage Area 4 (DA-4) consists of most of the project site west of the existing gravel entrance road including the original 1787 John Jay House, existing loop gravel drive, sundial garden, herb garden, existing pathways, parking areas, and associated site amenities. Runoff in this drainage area will sheet flow overland directed towards DP-2, which ultimately drains into the existing wetlands and unnamed tributary to Stone Hill River.

Drainage Area 5A (DA-5A) consist of the proposed chip seal road, some grassed areas, and four existing buildings. The stormwater runoff will flow into DA-1D, and eventually into DA-1A, where runoff will be directed to drain towards the proposed bioretention area 1 and dry pond 1 and will outlet directly towards DP-1, and eventually discharges into the Cross River Reservoir located approximately 3,000 feet northeast of the project site.

Drainage Area 5B (DA-5B) contains chip seal road, some grass areas, and three existing buildings. The stormwater runoff will flow into DA-1C, and eventually into DA-1B, where runoff will be directed to drain towards the proposed bioretention area 2 and dry pond 2 and will outlet directly towards DP-1, and eventually discharges into the Cross River Reservoir located approximately 3,000 feet northeast of the project site.



**Table 4 – Proposed Condition Analysis Summary**

Design Point	Watershed	Area (acres)	Tc (hrs)	Curve Number	Peak Flow Rate (cfs)		
					1-yr	10-yr	100-yr
DP-1	DA-1A	1.91	0.083	82	2.45	6.20	13.04
	DA-1B	0.60	0.083	81	0.73	1.90	4.04
	DA-1C	1.37	0.134	76	1.15	3.52	8.19
	DA-1D	1.51	0.088	74	1.18	3.83	9.09
	DA-2A	2.53	0.098	76	2.24	6.78	15.64
	DA-2B	0.53	0.083	82	0.68	1.72	3.62
	DA-3	1.41	0.083	84	2.00	4.82	9.86
	DA-5A	0.77	0.104	82	0.96	2.46	5.18
	DA-5B	0.57	0.083	80	0.66	1.75	3.79
	Outfall	11.20	--	--	11.93	32.81	72.17
DP-2	DA-4	7.60	0.104	77	7.11	20.93	47.58
	Outfall	7.60	--	--	7.11	20.93	47.58

## 5.4 Post-Development Stormwater Management Practices

### 5.4.1 Runoff Reduction Volume

In accordance with the New York State Stormwater Management Design Manual (January 2015), further reduction in the water quality volume (WQv) shall be designed to reduce the total amount of runoff leaving the project site and to replicate pre-development hydrology. This volumetric reduction is defined as the Runoff Reduction Volume (RRv). Runoff reduction shall be achieved by infiltration, groundwater recharge, reuse, recycle evaporation or evapotranspiration of 100% of the post-development water quality volumes to replicate pre-development hydrology by maintaining pre-construction infiltration, peak runoff flow, discharge volume, as well as minimizing concentrated flow by using runoff control techniques to provide treatment in a distributed manner before runoff reaches the collection system. This requirement can be accomplished by application of on-site green infrastructure techniques, standard stormwater management practices with runoff reduction capacity, and good operation and maintenance. Runoff reduction can be achieved by three methods: reduction of contributing drainage area, reduction of runoff volume through practice storage, and using standard stormwater practices with runoff reduction capacity.

Projects that cannot meet 100% of runoff reduction requirement must provide a justification that



evaluates each of the green infrastructure planning and reduction techniques and identifies the specific limitations of the site according to which application of this criterion is technically infeasible. Implementation of green infrastructure cannot be considered infeasible unless physical constraints, hydraulic conditions, soil testing, existing and proposed slopes, or other existing technical limitations are objectively documented. And determination of application of none of the runoff reduction options is feasible may not be based on the cost of implementation measures or lack of space for required footprint of the practice.

Project that do not achieve runoff reduction to pre-construction condition must, at a minimum reduce a percentage of the runoff from impervious areas to be constructed on the site. The percent reduction is based on the Hydrologic Soil Group(s) (HSG) of the site and is defined as Specific Reduction Factor (S) and is defined as the following list.

HSG A = 0.55 (55%)  
HSG B = 0.40 (40%)  
HSG C = 0.30 (30%)  
HSG D = 0.20 (20%)

Based on Chapter 10 of the New York State Stormwater Management Design Manual, the required minimum RRv for redevelopment projects within enhanced phosphorous removal watershed areas is computed using the equation presented below.

$$RRv_{min} = \{(P_{1-yr}) (Rv) (Aic)(S)\} / 12$$

Where:

RRv<sub>min</sub> = Minimum runoff reduction volume required from impervious area (acre-feet)  
P1-yr = 1-year storm event rainfall (inches)  
Rv = 0.05 + 0.009 (I), where I is 100% impervious cover  
Aic = total area of new impervious cover  
S = Hydrologic Soil Group (HSG) Specific Reduction Factor

For Katonah, Westchester County, the 1-year storm event is 2.80 inches of rainfall.

### Green Infrastructure Techniques

Runoff reduction was achieved for the proposed project with the application of the green infrastructure techniques including three (3) new bioretention areas and planting new trees for drainage areas (DA-1A,1B,1C,1D,2A,2B,3, 5A, and 5B) contributing runoff to DP-1 of the project site. Since this project proposes a total of 1.10 acres of new impervious area to be constructed within these drainage areas to DP-1, the remaining impervious areas to be replaced within these areas are considered as redevelopment work. Subsequently, the minimum RRv criteria is applied to the new developed impervious area only. Therefore, the three (3) proposed bioretention areas and new trees to be planted are designed to treat the minimum RRv required for 1.10 acre of new developed impervious area.

A summary of the practice used in the project for runoff reduction is provided in Table 5 and detailed worksheets are included in Appendix G. Runoff reduction practices not applicable for the proposed project and justification for each practice is summarized in Table 6.



**Table 5 - Summary of Required Runoff Reduction Volumes**

Design Point	Drainage Areas	Min. RRv Required (ac-ft)	RRv Provided (ac-ft)	Runoff Reduction Techniques
DP-1	DA-1A,1B,1C, 1D,2A,2B,3,5A, and 5B	0.073	0.233	3 Bioretention areas and tree planting
DP-2	DA-4	0.000	0.000	N/A

Since drainage area DA-4 included an existing entrance access road that will be removed and turned into grassed area in post development conditions, resulting in a 37.5% reduction of imperviousness within the disturbed drainage area. Based on the regulations listed in Chapter 9 Redevelopment criteria of the New York State Stormwater Management Design Manual, this over 25 percent of reduction in imperviousness will reduce the volume of stormwater runoff, essentially, providing both water quality and water quantity. Therefore, post-construction stormwater management measures for water quality and runoff reduction treatment are not required for the redevelopment work withing drainage area DA-4, which drains into DP-2.

**Table 6 – Stormwater Management Practices for Runoff Reduction Not Used in Project**

Practice / Technique	Reason for Not Applying the Practice / Technique to Project
Conservation of Natural Areas	Runoff already treated with bioretention and tree planting.
Riparian Buffers / Filter Strips	Runoff already treated with bioretention and tree planting.
Rooftop Disconnection	Not applicable to proposed parking lot and access roads.
Infiltration Trench	Runoff already treated with bioretention and tree planting.
Drywell	Runoff already treated with bioretention and tree planting.
Infiltration Basin	Existing soils onsite does not infiltrate.
Dry Swale	Runoff already treated with bioretention and tree planting.
Vegetated Swale	Runoff already treated with bioretention and tree planting.
Green Roof	Not applicable to proposed parking lot and access roads.
Rain Garden	Runoff already treated with bioretention and tree planting.
Planters	Runoff already treated with bioretention and tree planting.
Cisterns / Rain Barrels	No regular use for the collected water on site.
Porous Pavement	Runoff already treated with bioretention and tree planting.



## 5.4.2 Water Quality Volume

Since the proposed redevelopment project is located within the New York City Watershed East of the Hudson River as shown in Appendix D of the SPDES General Permit (GP-0-20-001) where enhanced phosphorus removal standards are required, the total Water Quality Volume (WQv) shall be calculated in accordance with Chapter 10 of the New York State Stormwater Management Design Manual (January 2015). The total estimated WQv required is calculated based on the 1-year, 24-hour design storm over the post development disturbed drainage areas using standard NYSDEC Green Infrastructure worksheets.

To meet the water quality criteria listed above, three (3) new bioretention areas and new tree planting will be employed for drainage areas (DA-1A, 1B, 1C, 1D, 2A, 2B, 3, 5A, and 5B) contributing runoff to DP-1 of the project site. A summary of the required and provided water quality volumes (WQv) are shown in Table 7 and detailed computations are included in Appendix G.

**Table 7 - Summary of Water Quality Volumes**

Drainage Areas	Total Area (ac)	New Impervious Area (ac)	Required WQv (ac-ft)	Provided RRv (ac-ft)	Remaining WQv Provided (ac-ft)	Treatment Practice
DA-1A	1.91	0.60	0.148	0.069	0.079	Bioretention Area 1
DA-1B	0.60	0.18	0.045	0.019	0.026	Bioretention Area 2
DA-2B	0.53	0.18	0.044	0.020	0.024	Bioretention Area 3
DA1C, 1D, 2A, 3, 5A, AND 5B	8.16	0.14	0.125	0.125	0.000	Tree Planting
Total to DP-1	11.20	1.10	0.362	0.233	0.129	Total Provided = 0.362 ac-ft
DA-4 (DP-2)	7.60	-0.66	0.000	0.000	0.000	Over 25% Impervious Area Reduction

Drainage Area DA-4 included an existing entrance access road that will be removed and turned into grassed area in post development conditions. Thus, the existing impervious area of 1.76 acres will be reduced to 1.10 acres, resulting in a 37% reduction of imperviousness within the disturbed drainage area. Based on the regulations listed in Chapter 9 Redevelopment criteria of the New York State Stormwater Management Design Manual, this over 25 percent of reduction in imperviousness will reduce the volume of stormwater runoff, essentially, providing both water quality and water quantity. Therefore, post-construction stormwater management measures for water quality and runoff reduction treatment are not required and not included as for this portion of the project.



### 5.4.3 Channel Protection Volume

Based on the sizing criteria listed in Chapter 9 of the New York State Stormwater Management Design Manual, channel protection for redevelopment activities is not required if there are no changes to the hydrology that increase the discharge rate from the project site. Since, the hydrology analysis results showed the 1-year 24-hour storm peak flow rate from the project site for post-construction condition is equal to the peak flow rate of existing condition, providing the channel protection volume (Cpv, 1-year storm) criteria is not required for the proposed redevelopment project.

### 5.4.4 Peak Flow Attenuation

Based on a comparison between the existing conditions and the unmitigated proposed peak flow rates, the proposed development will increase peak rates of runoff at DP-1. In accordance with the governing regulations, this increase in peak flows must be mitigated such that the post-development peak runoff rates will be no greater than the existing condition rates for the 10-year and 100-year 24-hour storm events. A summary of the existing conditions and mitigated post-development peak flow comparison is shown in Table 8, and detailed computations are included in Appendix F.

**Table 8 – Existing Condition & Mitigated Post-Development Peak Flow Comparison**

Design Point	Peak Flow Rate (cfs)								
	1-Year Storm			10-Year Storm			100-Year Storm		
	Exist (cfs)	Mitigated (cfs)	Δ (cfs)	Exist (cfs)	Mitigated (cfs)	Δ (cfs)	Exist (cfs)	Mitigated (cfs)	Δ (cfs)
DP-1	10.00	6.15	-3.85	29.72	23.30	-6.42	67.98	48.05	-19.93
DP-2	8.08	7.11	-0.97	22.39	20.93	-1.46	49.29	47.58	-1.71

### 5.4.5 Stormwater Conveyance Systems

The proposed drainage system located in the proposed parking lot and access road have been designed for the 10-year, 24-hour event, while also providing safe conveyance of the 100-year, 24-hour event.

## 5.5 Floodplains

Based on a review of the FEMA Flood Insurance Rate Map for the City of Katonah, Westchester County, NY (dated September 28, 2007); the entire project site is not located in the 100-year floodplain (see Figure 5 – FEMA FIRM).



## 6.0 MAINTENANCE/INSPECTION PROCEDURES

### 6.1 Erosion and Sediment Control Inspection and Maintenance Practices

These are the minimum required inspection and maintenance practices that shall be used to maintain erosion and sediment controls:

#### 6.1.1 Owner/Operator Inspection Requirements

- Prior to construction activity the owner/operator shall have contractors and sub-contractors identify a trained individual responsible for the implementation of the SWPPP. The trained individual must be on-site on a daily basis when soil disturbing activities are occurring.
- The owner/operator shall inspect the erosion and sediment control measures as identified in the SWPPP to ensure that they are being maintained in effective operating conditions at all times. Where soil disturbing activities temporarily cease (e.g. winter shutdown) and temporary stabilization measures have been applied to all disturbed areas, the owner/operator can reduce frequency of inspections, but shall maintain a minimum of monthly inspections, and after significant rain storms and snow thaws. The owner/operator shall resume inspections when soil disturbing activities begin again.
- Where soil disturbing activities have ceased with partial project completion, the owner/operator can stop conducting inspections when disturbed areas have reached final stabilization. The qualified inspector shall coordinate and obtain approval from the Owner and Engineer that final stabilization has been achieved. All post construction stormwater management practices required for the completed areas shall have been constructed in conformance with the SWPPP and be fully operational. Final stabilization means that all soil disturbance activities have ceased and a uniform, perennial vegetative cover with a density of eighty (80) percent over the entire pervious surface has been established; or other equivalent stabilization measures, such as permanent landscape mulches, rock rip-rap or washed/crushed stone have been applied on all disturbed areas that are not covered by permanent structures, concrete or pavement.
- The owner/operator shall notify the DEC Regional Office's stormwater contact person prior to any reduction in the frequency of site inspections.
- The owner/operator shall retain copies of the NOI, NOI acknowledgment letter, SWPPP, MS4 SWPPP acceptance form and any inspection reports submitted in conjunction with this permit and records, or all data used to complete the NOI to be covered by this permit for a period of at least five (5) years from the date that the site is finally stabilized.

#### 6.1.2 Qualified Inspector Inspection Requirements

- The qualified inspector is defined as a person that is knowledgeable in the principles and practices of erosion and sediment control, such as a licensed Professional Engineer, Certified Professional in Erosion and Sediment Control (CPESC), licensed Landscape Architect, or other Department endorsed individual(s). It may also mean someone working



under the direct supervision of the licensed Professional Engineer or licensed Landscape Architect, provided that person has training in the principles and practices of erosion and sediment control. Training in the principles and practices of erosion and sediment control means the person has received four (4) hours of training endorsed by the Department and shall receive four (4) hours of training every three (3) years after the initial training.

- A site inspection shall be conducted at least twice every seven (7) days by the qualified inspector when soil disturbing activities are occurring. The two inspections shall be separated by a minimum of two full calendar days. A copy of the "Construction Duration Inspection Form" is included in the Appendix E section of this plan.
- All measures shall be maintained in good working order; if any repairs or corrective actions are necessary, it is the responsibility of the qualified inspector to notify the owner/operator and appropriate contractor within one business day. The contractor shall begin implementing the corrective action within one business day of being notified.
- All inspection forms must be signed by a qualified inspector.
- For construction sites where soil disturbing activities are temporarily suspended, temporary stabilization measures shall be applied, and the qualified inspector shall conduct a site inspection at least once every thirty (30) calendar days.
- Where soil disturbing activities have ceased with partial project completion the qualified inspector can stop conducting inspections when disturbed areas have reached final stabilization and all post construction stormwater management practices required for the completed areas have been constructed in conformance with the SWPPP and are fully operational.
- Where soil disturbing activities are not resumed within two (2) years, from the date of shut down of partial project completion, the qualified inspector shall perform a final inspection and certify that all disturbed areas have achieved final stabilization, all temporary and permanent erosion control measures have been removed, and post-construction stormwater management practices have been constructed in conformance with the SWPPP. Qualified inspector shall sign the "Final Stabilization" and "Post-Construction Stormwater Management Practice" certification statements on the Notice of Termination (NOT).

### **6.1.3 General Requirements**

- A copy of the SPDES General Permit (GP-0-20-001), the signed Notice of Intent (NOI), NOI acknowledgement letter, SWPPP, and inspection reports shall be maintained onsite until the site has achieved final stabilization.
- Built up sediment shall be removed from any silt fence when it has reached one-third the height of the fence / dike.
- Sediment fencing and wetland protection barrier shall be inspected for depth of sediment, and tears, to see if fabric is securely attached to the fence posts, and to see that the fence posts are firmly in the ground.



- The construction entrance shall be cleaned of sediment and redressed when voids in the crushed stone become filled and vehicular tracking of sediment is occurring.
- Dust shall be controlled on access points and other disturbed areas subject to surface dust movement and blowing.
- Inspection must verify that all practices are adequately operational, maintained properly and that sediment is removed from all control structures.
- Inspection must look for evidence of soil erosion on the site, potential of pollutants entering drainage systems, problems at the discharge points, and signs of soil and mud transport from the site to the public road.

#### **6.1.4 Dewatering Methods**

During the recent geotechnical investigation activities conducted at the Site, the seasonal ground water table was estimated at depths ranging from 3.1 feet to 13.2 feet on site. Dewatering is anticipated for construction of the meadow road. If localized dewatering becomes necessary to conduct the planned construction activities, the water will be evaluated for evidence of potential contamination.

Water that exhibits no visual (e.g. free product/sheens) or olfactory evidence of contamination will be directed to a discharge area established within a vegetated portion of the Site, and will be pumped through filter bags or socks for removal of sediment prior to discharge. The water will be discharged to the ground at a controlled rate in a manner that will prevent significant runoff. Discharge of dewatering effluent into the storm sewer system is not permitted under any circumstance.

#### **6.1.5 Dust Control**

Dust control shall be used through dry weather periods until all disturbed areas are stabilized and will be controlled as needed based on site conditions. Only plain water will be used for dust suppression. Stabilized construction entrances for dust control will be consistent with NYSDEC stabilized construction entrance requirements. All applicable regulations and standards related to dust control will be followed including the New York State Standards and Specifications for Erosion and Sediment Control ("Blue Book") for dust control.

### **6.2 Post-Construction Stormwater Inspection and Maintenance Practices**

Long-term inspection forms for the stormwater management practices are included in Appendix E are referenced from Appendix G of the New York State Stormwater Management Design Manual.



## 7.0 INVENTORY FOR POLLUTION PREVENTION PLAN

The materials or substances listed below are expected to be within the project area during construction:

- Portland cement concrete.
- Fertilizers / seeding materials.
- Stone.
- Chip seal asphalt.
- Petroleum based products.
- Silt fence fabric.
- Lumber.
- Pavement marking paint.
- PVC and HDPE.

## 8.0 SPILL PREVENTION

The following are the material management practices that shall be used to reduce the risk of spills or other accidental exposure of materials and substances to stormwater runoff.

### 8.1 Good Housekeeping

The following good housekeeping practices shall be followed within project areas during construction:

- An effort shall be made to store only enough products required to do the job.
- All materials stored within project areas shall be stored in a neat, orderly manner in their appropriate containers and, if possible, under a roof or other enclosure.
- Products shall be kept in their original containers with the original manufacturer's label.
- Substances shall not be mixed with one another unless recommended by the manufacturer.
- Whenever possible, all of a product shall be used up before disposing of the container.
- Manufacturers' recommendations for proper use and disposal shall be followed.
- The project superintendent shall inspect daily to ensure proper use and disposal of materials.

### 8.2 Hazardous Products

These practices are used to reduce the risks associated with hazardous materials:

- Products shall be kept in original containers unless they are not resealable.
- Original labels and material safety data shall be retained.



- If surplus product must be disposed of, manufacturers' or local and state recommended methods of proper disposal shall be followed.
- Material Safety Data Sheets for all hazardous products shall be within the project area for the duration of construction.

### 8.3 Product Specific Practices

The following product-specific practices shall be followed within the project areas:

#### **Petroleum Products**

All project related vehicles shall be monitored for leaks and receive regular preventive maintenance to reduce the chance of leakage. Petroleum products shall be stored in tightly sealed containers which are clearly labeled. Any asphalt substances used during construction shall be applied according to the manufacturer's recommendations.

#### **Fertilizers**

Fertilizers used shall be applied only in the minimum amounts recommended by the manufacturer. Once applied, fertilizer shall be worked into the soil to limit exposure to stormwater. Fertilizers shall be stored in a covered or other contained area.

#### **Paints**

All containers shall be tightly sealed and stored when not required for use. Excess paint shall not be discharged to the storm sewer system but shall be properly disposed of according to manufacturer's instructions or State regulations.

#### **Concrete Trucks**

Concrete trucks shall be allowed to wash out within project areas provided that the contractor provides an area which collects and contains any concrete / slurry material washed from trucks for recovery and disposal at a later time. No concrete / slurry shall be discharged from the property at any time of construction. If such washing is anticipated, the contractor shall submit a plan detailing the control of concrete / slurry to the engineer for approval.

#### **Watercourse Protection**

Construction operations shall be conducted in such a manner as to prevent damage to watercourses from pollution of debris, sediment, or other foreign material, or from manipulation, from equipment and/or materials in or near the watercourse. The contractor shall not return directly to the watercourse any water used for wash purposes or other similar operations which may cause the water to become polluted with sand, silt, cement, oil or other impurities. If the contractor uses water from the water course, the contractor shall construct an intake or temporary dam to protect and maintain watercourse water quality.

### 8.4 Spill Control Practices

The contractor will be responsible for preparing a project area specific spill control plan in accordance with local and NYS DEC regulations. At a minimum this plan should:

- Reduce stormwater contact if there is a spill.



- Contain the spill.
- Stop the source of the spill.
- Dispose of contaminated material in accordance with manufactures procedures, and NYS DEC regulations.
- Identify responsible and trained personnel.
- Ensure spill area is well ventilated.

## 9.0 UPDATING THE SWPPP

The SWPPP shall be updated/revised as conditions merit or as directed by the regulating authority. The attached inspection forms included with this document allows for the certification of any updates/revisions.







## 10.0 SWPPP CERTIFICATION

### Contracting Firm Information:

---

**Contracting Firm**

---

**Address**

---

**City/Town**

**State**

**Zip**

### Site Location:

John Jay Homestead Historic Site  
400 Jay St, Katonah  
Westchester, New York

### Contractor's Certification

I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the qualified inspector during a site inspection. I also understand that the owner or operator must comply with the terms and conditions of the New York State Pollutant Discharge Elimination System (SPDES) general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

---

**Signature (Contractor/Subcontractor)**

---

**Date**

---

**For**

---

**Responsible For**

---

**Signature (Trained Individual)**

---

**Date**

---

**For**

---

**Responsible For**

---

**Signature (Contractor/Subcontractor)**

---

**Date**

---

**For**

---

**Responsible For**



---

***Signature (Trained Individual)***

---

***Date***

---

***For***

---

***Responsible For***



# APPENDIX A

## Figures

Figure 1 – Project Location Map

Figure 2 – USDA Soils Map

Figure 3 – Existing Conditions Watershed Map

Figure 4 - Proposed Conditions Watershed Map

Figure 5 – FEMA FIRM Map







File: V:\PROJECTS\ANY\K6\080675\000\09\_DESIGN EXHIBITS\STORMWATER\ARCHIVED\066076\_FIG1-SITE LOC MAP - JOHN JAY.DWG Saved: 5/6/2024 11:34:27 AM Plotted: 5/6/2024 11:35:58 AM Current User: Bouillon, Hugo LastSavedBy: 7895



SITE LOCATION MAP  
JOHN JAY HOMESTEAD STATE HISTORIC SITE  
400 JAY ST, KATONAH, 10536  
WESTCHESTER COUNTY, NEW YORK

PROJECT NO.  
080675

DATE: 05/06/24

FIGURE 1







# Hydrologic Soil Group—Westchester County, New York




Figure 2 - USDA Soil Map





## MAP LEGEND

### Area of Interest (AOI)









 Area of Interest (AOI)

### Soils

#### Soil Rating Polygons





 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Lines


 A  
 A/D  
 B  
 B/D  
 C  
 C/D  
 D  
 Not rated or not available

#### Soil Rating Points

 A  
 A/D  
 B  
 B/D

 C  
 C/D  
 D  
 Not rated or not available


### Water Features

 Streams and Canals

### Transportation

 Rails  
 Interstate Highways  
 US Routes  
 Major Roads  
 Local Roads

### Background

 Aerial Photography

## MAP INFORMATION

The soil surveys that comprise your AOI were mapped at 1:12,000.

Warning: Soil Map may not be valid at this scale.

Enlargement of maps beyond the scale of mapping can cause misunderstanding of the detail of mapping and accuracy of soil line placement. The maps do not show the small areas of contrasting soils that could have been shown at a more detailed scale.

Please rely on the bar scale on each map sheet for map measurements.

Source of Map: Natural Resources Conservation Service  
 Web Soil Survey URL:  
 Coordinate System: Web Mercator (EPSG:3857)

Maps from the Web Soil Survey are based on the Web Mercator projection, which preserves direction and shape but distorts distance and area. A projection that preserves area, such as the Albers equal-area conic projection, should be used if more accurate calculations of distance or area are required.

This product is generated from the USDA-NRCS certified data as of the version date(s) listed below.

Soil Survey Area: Westchester County, New York  
 Survey Area Data: Version 19, Sep 6, 2023

Soil map units are labeled (as space allows) for map scales 1:50,000 or larger.

Date(s) aerial images were photographed: Oct 21, 2022—Oct 27, 2022

The orthophoto or other base map on which the soil lines were compiled and digitized probably differs from the background imagery displayed on these maps. As a result, some minor shifting of map unit boundaries may be evident.



## Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
PnB	Paxton fine sandy loam, 3 to 8 percent slopes	C	20.1	86.1%
PnC	Paxton fine sandy loam, 8 to 15 percent slopes	C	2.6	11.0%
WdA	Woodbridge loam, 0 to 3 percent slopes	C/D	0.7	2.9%
<b>Totals for Area of Interest</b>			<b>23.3</b>	<b>100.0%</b>

## Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.




## Rating Options


*Aggregation Method:* Dominant Condition

*Component Percent Cutoff:* None Specified

*Tie-break Rule:* Higher







Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CHA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**Landscape Consultant**  
RHODES HARTWELL LANDSCAPE ARCHITECTURE  
347 WEST 36TH STREET, SUITE 1001, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
35 EAST 30TH STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071


**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**



Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By:  
HB

Design By:  
JJE

Checked By:  
JJE

Approved By:  
SKB

DATE  
04/10/24

Seal and Signature

**Sheet Title**

EXISTING  
CONDITIONS  
WATERSHED MAP


**Drawing Number**

**FIG-3**

Project Number:  
D006292

Sheet:  
XXX of 367





New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy HochulCommissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CHA CONSULTING, INC.  
3 WINNERS CIRCLE, COLOMBE, NY 12026

**Landscape Consultant**  
RHODES HARRIS LANDSCAPE ARCHITECTURE  
347 WEST 36TH STREET, SUITE 1001, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 30TH STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**BEYER BLINDER BELLE**

**Thornton Tomasetti**

**LFC**

**CHA**

**RHI**

**HLB**

**LVCK**

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building  
Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By:  
HB

Design By:  
JJE

Checked By:  
JJE

Approved By:  
SKB

DATE  
04/10/24

**Sheet Title**  
PROPOSED  
CONDITIONS  
WATERSHED MAP

Seal and Signature


**Drawing Number**  
FIG-4

Project Number:  
D006292


Sheet:  
XXX of 367



Town of  
Bedford  
360903



MAP SCALE 1" = 500'



NFIP  
NATIONAL FLOOD INSURANCE PROGRAM

PANEL 0068F

**FIRM**  
FLOOD INSURANCE RATE MAP

for WESTCHESTER COUNTY, NEW YORK  
(ALL JURISDICTIONS)

CONTAINS:

<u>COMMUNITY</u>	<u>NUMBER</u>
BEDFORD, TOWN OF	360903
LEWISBORO, TOWN OF	361227

Figure 5A - FEMA MAP

PANEL 68 OF 426

MAP SUFFIX: F  
(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

Notice to User: The Map Number shown below should be used when placing map orders; the Community Number shown above should be used on insurance applications for the subject community.




MAP NUMBER  
36119C0068F

EFFECTIVE DATE  
SEPTEMBER 28, 2007

Federal Emergency Management Agency

This is an official FIRMette showing a portion of the above-referenced flood map created from the MSC FIRMette Web tool. This map does not reflect changes or amendments which may have been made subsequent to the date on the title block. For additional information about how to make sure the map is current, please see the Flood Hazard Mapping Updates Overview Fact Sheet available on the FEMA Flood Map Service Center home page at <https://msc.fema.gov>.







# APPENDIX B

Historic Cultural Resource









**New York State  
Parks, Recreation and  
Historic Preservation**

**KATHY HOCHUL**  
Governor

**RANDY SIMONS**  
Commissioner *Pro Tempore*

April 29, 2024

Erin Moroney  
NYS OPRHP  
1 Delaware Ave  
Cohoes, NY 12047

Re: OPRHP/14.09  
John Jay Homestead SHS/Building & Site Enhancements  
400 Jay St, Katonah, NY 10536  
23PR07343

Dear Erin Moroney:

Thank you for requesting the comments of the Division for Historic Preservation (DHP). We have reviewed the project in accordance with the New York State Historic Preservation Act of 1980 (Section 14.09 NYSPRHPL) and OPRHP Agency Protocol HP-PCD-002. These comments are those of the DHP and relate only to Historic/ Cultural resources.

We note that John Jay Homestead is a State Historic Site, a National Historic Landmark and listed in the State and National Registers of Historic Places. National Historic Landmarks (NHLs) are nationally significant places designated by the Secretary of the Interior because they possess exceptional value or quality in illustrating or interpreting the heritage of the United States.

We have reviewed the drawings dated 1/31/2024, the e-mails from Erin Moroney dated 3/18, 3/21, 4/24 and meeting notes from the 4/11/2024. For clarity, we understand the project to include:

- 1) Bedford House
  - a. Interior restoration: including period appropriate interior finishes such as flooring and wallpaper as approved by the Bureau of Historic Sites and structural repairs (sistering with steel)
  - b. Exterior restoration: including window restoration and replacement and exterior masonry work, roof replacement, porch repair.
  - c. ADA compliance: Including stair/elevator improvements for access to the second floor, access to the front door via a porch lift.
  - d. Electrical – including museum and exit lighting.
  - e. HVAC – including geothermal.
- 2) Site
  - a. Parking and circulation – new road to parking lot
  - b. Wayfinding and exterior lighting
  - c. Landscape restoration of Haha's and stone walls



- 3) Potting Shed
- 4) Carriage Barn/Visitor Center
  - a. HVAC including Geothermal.
  - b. ADA upgrades including raising of floors to remove interior ramps and leveling of courtyard between Carriage Barn and Coachman's House
- 5) Brick Cottage - Stabilization

Only the work noted above has been reviewed. Any additional work will need to be submitted as a new project for review. We note our Archeology Unit has no archeological concerns with the work as proposed. Based upon our review, it is DHP's opinion that the proposed work will have No Adverse Impact upon historic resources provided the following conditions are met:

1. The potting shed shall be treated as described in the e-mail dated 4/24/2024.
2. The Brick Cottage stabilization plans shall be submitted for review and comment when they are available.
3. Any substantive changes proposed to the project shall be submitted for our review and comment.

If you have any questions, you can call or e-mail me at the contact information below.

Sincerely,

A handwritten signature in black ink, appearing to read 'D McEneny', with a long, sweeping horizontal line extending from the end of the signature.

Daniel McEneny  
Division Director



# APPENDIX C

Geotechnical Report







# Geotechnical Engineering Report

## John Jay Homestead Site and Building Enhancements

Katonah, NY



Prepared for:

**Beyer Blinder Belle  
Architects & Planners LLP**

120 Broadway, 20th Floor  
New York, NY 10271

March 2024, Revised May 2024

CHA Project No.:  
80675




III Winners Circle,  
Albany, NY 12205



---


This report has been prepared and reviewed by the following qualified engineers employed by  
CHA.

Report Prepared By:



Adam J. Bryant, P.E.  
Geotechnical Engineer

Report Reviewed By:



Scott M. Doehla, P.E.  
Senior Geotechnical Engineer





---

## TABLE OF CONTENTS

<b><u>SECTION</u></b>	<b><u>PAGE NUMBER</u></b>
1.0 INTRODUCTION .....	1
2.0 SITE AND PROJECT DESCRIPTION.....	2
3.0 SUBSURFACE EXPLORATION.....	4
3.1 Boring Program.....	4
3.2 Laboratory Analysis.....	6
4.0 SUBSURFACE CONDITIONS .....	7
4.1 Regional Geology .....	7
4.2 Subsurface Stratigraphy .....	7
4.3 Groundwater Observations .....	9
4.4 Infiltration Test Results.....	10
5.0 GEOTECHNICAL RECOMMENDATIONS .....	11
5.1 Shallow Foundations.....	11
5.2 Lateral Earth Pressures .....	12
5.3 Pavement.....	13
5.4 Seismic Site Classification and Design Parameters.....	14
5.5 Site and Subgrade Preparation .....	14
5.6 Structural Fill .....	15
5.7 Groundwater and Control of Water .....	16
6.0 EXCAVATIONS .....	17
7.0 OBSERVATION DURING CONSTRUCTION.....	18
8.0 CLOSURE .....	19

## **TABLES**

Table 1: Groundwater Observation Well Measurements.....	9
Table 2: Infiltration Test Results .....	10
Table 3: Gradation Requirements for Structural Fill .....	15

## **APPENDICES**

APPENDIX A – Figures  
APPENDIX B – Photographs  
APPENDIX C – Boring Logs  
APPENDIX D – Laboratory Test Results



---

## 1.0 INTRODUCTION

CHA was retained by Beyer, Blinder, Belle Architects & Planners, LLP to complete a geotechnical exploration and evaluation for the design of the brick cottage reconstruction at John Jay Homestead State Historic Site located at 400 Jay Street in Katonah, New York. The project site is shown on *Figure 1 - Site Location Map*, included in Appendix A.

The primary objectives of the exploration were to evaluate the subsurface conditions at the site and to provide geotechnical recommendations for the design of the proposed brick cottage reconstruction and paving of the existing access road.



---

## 2.0 SITE AND PROJECT DESCRIPTION

The project site is located in the John Jay Homestead State Historic Site in Katonah, New York. The John Jay Homestead State Historic Site is an approximately 62-acre site comprised of 10 buildings, including the original 1787 John Jay House, with access roads, stone walls, and wooded areas throughout the site. The project site consists of the brick cottage located east of the John Jay House, and an access road and open fields located to the north, east and south of the John Jay House. Wetland areas and a small pond are located to the south and east of the project site. Standing water was observed in the wetland area approximately 100 feet east of the existing access road in April 2024. NYS Route 22 is located to the south, and the Cross River Reservoir is located approximately 3,000 feet northeast of the project site. The ground surface at the project site slopes down from northwest to the southeast from about El. 470 feet to El. 440 feet based on a site survey. The ground surface at the brick cottage slopes down from the northwest to southeast between El. 470 feet to El. 467 feet. The brick cottage has a two-story section with a partially below grade basement of unknown height and a one-story area without a basement. The total approximate footprint of the brick cottage is 3,000 square feet. The brick cottage has a finished floor elevation (FFE) of El. 471.8 feet. An approximately 3-foot-tall stone wall is located to the north of the building. Photographs of the site are included in Appendix B.

The project involves the design of repairs to the existing brick cottage and an existing access road, a new access road, a parking area and stormwater improvements. The repairs to the brick cottage will include partial or full reconstruction of the foundations and basement walls. The existing main access road, proposed access road and parking lot will be paved with asphalt. The existing access road will not include cuts and will be constructed at grades similar to the existing grade. The new access road requires cuts of up to 2 feet and fills of up to 2 feet. The new parking area requires cuts of up to 3 feet and fills of up to 4 feet. The new parking area will have a retaining wall with a north to south orientation, dividing the parking lot in half. The retaining wall will have exposed heights ranging from 2 to 8 feet and a total length of approximately 200 feet. The parking lot area to the east of the retaining wall will have a ground surface elevation of approximately 449 feet and the area to the west will have a ground surface elevation of approximately 459 feet. Stormwater



---

areas will consist of three bioretention ponds located to the east of the proposed new access road and parking area. The bioretention ponds will have footprints of approximately 2,500 to 5,500 square feet. Foundation work was originally being considered at the maintenance garage but was removed from the project scope by the client. Additional park access roads will be paved, the design of which is outside the scope of this report. The existing and proposed site features are shown on *Figure 2 – Subsurface Exploration Plan*, included in Appendix A.



---

### 3.0 SUBSURFACE EXPLORATION

The subsurface explorations and laboratory testing performed for this project are described in the following sections.

#### 3.1 Boring Program

CHA conducted a subsurface exploration program consisting of fourteen total borings designated as B-1 through B-6, B-6A, B-7 through B-10, and B-101 through B-103. Borings B-1 through B-6, B-6A and B-7 through B-10 were completed between January 16 and 19, 2024. Borings B-101 through B-103 were completed on April 15, 2024. CHA retained Underground Surveying, LLC to perform a non-destructive, non-intrusive subsurface utility survey prior to drilling. Borings B-1 and B-2 were performed adjacent to the brick cottage and extended to depths of 20.9 to 22 feet. Boring B-3 was performed adjacent to the maintenance garage and extended to a depth of 22 feet. Borings B-4 and B-5 were performed along the existing access road to depths of 10 feet. Borings B-6, B-6A and B-7 through B-10 were performed for roadway and preliminary stormwater design purposes in the eastern portion of the site to depths of 12 feet. Boring B-7 is located in the vicinity of the parking area site retaining wall, which was added after the completion of the subsurface exploration. Borings B-101 through B-103 were performed for final stormwater design purposes in the eastern portion of the site to depths of 10.5 to 12 feet.

Borings B-1 through B-3 were located onsite by measuring from existing site features. Borings B-4 through B-6, B-6A, B-7 through B-10 and B-101 through B-103 were located onsite using a backpack GPS unit accurate to 1 meter. Ground surface elevations at boring locations were estimated based on interpolation between contours on the site survey and are based on NAVD88. The locations and elevations should be considered accurate only to the degree implied by the method used to determine them. The approximate boring locations are shown on *Figure 2 – Subsurface Exploration Plan*, included in Appendix A.



---

New England Boring Contractors of Glastonbury, Connecticut was retained by CHA to advance the borings. The field exploration was performed under the observation of a CHA geotechnical engineer who confirmed proper drilling and sampling methods were utilized for the exploration, observed and described soil samples, prepared field logs documenting the subsurface conditions, and conducted infiltration testing.

The borings were advanced with a Mobile Drill B53 truck mounted drill rig and Mobile Drill B53 rubber track mounted drill rig using hollow stem augers (HSA) with an inside diameter of 4.25 inches or solid stem augers (SSA) with an inside diameter of 2.25 inches. Continuous split spoon sampling was generally performed to a depth of up to 12 feet below ground surface, and then at standard 5-foot intervals thereafter to the boring termination depths. Standard Penetration Testing (SPT) was utilized during split-spoon sampling in general accordance with ASTM International (ASTM) Standard D-1586 “Standard Test Method for Standard Penetration Test (SPT) and Split-Barrel Sampling of Soils.” The split spoon samples were advanced using an automatic 140 (±) pound hammer falling 30 (±) inches. “Blow counts” recorded on the boring logs indicate the penetration resistance for a 6-inch advancement of the split soon. Initially, the spoon is driven 6 inches to seat the sampler in undisturbed material. The number of blows required to drive the sampler the next 12 inches is taken as the SPT resistance or N-value. This value is indicative of the soil’s in-place density or consistency. The final 6-inch increment that the spoon is driven is not included in the determination of the N-value. Boreholes B-1 through B-6 were backfilled with soil cuttings upon completion.

Infiltration tests were planned adjacent to borings B-6A, B-7 through B-10 and B-101 through B-103. Infiltration tests were not performed adjacent to B-8 through B-10 and B-101 through B-103 due to shallow groundwater. The infiltration tests conducted adjacent to B-6A and B-7 were designated as IT-6 and IT-7, respectively. Infiltration testing was conducted according to Appendix D of the 2022 New York State Stormwater Management Design Manual. After a presoak was conducted, water was added to the infiltration casing to set it to 24 inches above the bottom of the casing. The distance that the water within the casing dropped in an hour was measured and recorded. Water was added to bring the level back to 24 inches above the bottom of casing for the



---

next testing interval. The test was terminated after five test intervals. Infiltration test holes were backfilled with soil cuttings upon completion. A New York City Department of Environmental Conservation (NYCDEP) representative was onsite to oversee the infiltration testing.

Water level observations were made during and upon completion of drilling. Observation wells were installed in borings B-6A and B-7 through B-10 to depths of 12 feet. Details of the observation well construction are shown on the boring logs included in Appendix C. The water levels within the wells were recorded during the subsurface exploration, and are included in *Section 4.3 – Groundwater Conditions* and on the boring logs in Appendix C.

### **3.2 Laboratory Analysis**

Select soil samples were submitted for laboratory analysis to confirm visual descriptions. Testing included five tests for particle-size analysis (ASTM D422), one test for Atterberg Limits analysis (ASTM D4318) and one test for water content of soil (ASTM D2216). The results of the laboratory testing are included in Appendix D.



---

## 4.0 SUBSURFACE CONDITIONS

Subsurface conditions at the site were assessed based on a review of published geologic maps and the results of the subsurface exploration performed on-site and are summarized below.

### 4.1 Regional Geology

According to the *Surficial Geologic Map of New York – Lower Hudson Sheet*, (Cadwell, D.H. 1991), the surficial soil at the site consists of glacial till.

According to the *Geologic Map of New York – Lower Hudson Sheet*, (Fisher, D.W., Isachsen, Y.W., and Rickard, L.V., 1970), the bedrock underlying the site consists of Fordham Gneiss.

### 4.2 Subsurface Stratigraphy

Subsurface conditions encountered in individual borings are detailed and described on the boring logs included in Appendix C. Subsurface conditions can generally be described as follows, in order of increasing depth:

Topsoil – Topsoil was encountered at the ground surface in borings B-1 through B-3, B-6 through B-10 and B-101 through B-103 and extended to depths ranging from 0.1 to 0.2 feet.

Fill – A layer of existing fill was encountered below the topsoil in borings B-1 and B-2 and at the ground surface in borings B-4 and B-5 and extended to depths ranging from 2 to 4 feet. The layer consisted of varying amounts of fine to coarse sand, silt, fine to coarse gravel, wood and organics. The fill was brown or gray and visually classified as moist, and some near-surface samples appeared frozen. The SPT N-values ranged from 4 to 74, indicating a very loose to very compact density, however, the presence of frost likely affected N-values within the samples taken at shallow depths.



---

Silt/Clayey Silt/Silty Clay – A layer of silt, clayey silt or silty clay was encountered below the topsoil layer in boring B-3, B-6, B-7, and B-101 through B-103, and below the fill in borings B-1 and B-5 and extended to depths ranging from 2 to 6 feet. The layer consisted of silt, clayey silt, or silty clay with varying amounts of fine to coarse sand, fine gravel and organics. The soil was brown and visually classified as moist. The SPT N-values ranged from 2 to 8, indicating a medium stiff consistency for cohesive samples and a very loose to loose density for cohesionless samples.

Glacial Till – Glacial till was encountered below the topsoil layer in borings B-8 through B-10, below the fill in borings B-2 and B-4, below the silt, clayey silt and silty clay layer in borings B-1, B-3, B-5 through B-7 and B-101 through B-103. The glacial till layer extended to depths ranging from 10 to 22 feet. Borings B-2, B-4 through B-10 and B-101 through B-103 terminated within the glacial till layer. The layer generally consisted of various proportions of fine to coarse sand, fine to coarse gravel, silt, clay and organics. The soil was brown and visually classified as moist to wet. The SPT N-values ranged from 5 to split spoon refusal, indicating a very stiff to hard consistency for cohesive samples and a loose to very compact density for cohesionless samples.

Completely Weathered Rock – Completely weathered rock was encountered below the glacial till layer in borings B-1 and B-3 and extended to depths of 20.9 to 22 feet. Borings B-1 and B-3 terminated within the completely weathered rock. The layer consisted of fine to coarse sand with little silt and trace fine gravel. The soil was brown and visually classified as wet. The SPT N-values ranged from 85 to split spoon refusal, indicating a very compact density.



### 4.3 Groundwater Observations

Table 1 summarizes the observation well measurements.

**Table 1: Groundwater Observation Well Measurements**

Boring ID	Surface Elevation (Feet)	Screen Interval Elevation (Feet)	Date	Water Depth (Feet)	Water Elevation (Feet)
B-6A	459.5	447.5 to 452.5	1/17/2024	11.7	447.8
			1/18/2024	11.7	447.8
			1/19/2024	11.7	447.8
			4/15/2024	12.4	447.1
			4/16/2024	12.4	447.1
B-7	451.0	439.0 to 444.0	1/18/2024	7.0	444.0
			1/19/2024	7.3	443.7
			4/15/2024	8.2	442.8
			4/16/2024	7.9	443.1
B-8	451.0	439.0 to 444.0	1/18/2024	9.1	441.9
			1/19/2024	3.5	447.5
			4/15/2024	0.1	450.9
			4/16/2024	0.1	450.9
B-9	449.5	437.5 to 442.5	1/18/2024	1.1	448.4
			1/19/2024	0.8	448.7
			4/15/2024	0.7	448.8
			4/16/2024	0.7	448.8
B-10	448.5	436.5 to 441.5	1/18/2024	4.2	444.3
			1/19/2024	3.0	445.5
			4/15/2024	2.5	446
			4/16/2024	2.8	445.7



Groundwater levels were estimated based upon measurements or observed soil sample moisture content in the remaining boreholes during drilling operations and at the completion of drilling. These estimates are indicated on the boring logs included in Appendix C. Groundwater was estimated at depths ranging from 0.4 to 13.2 feet during drilling. Standing water was observed at the ground surface at boring B-101. The boreholes were only open for a short duration and seasonal factors such as temperature and precipitation affect groundwater levels. For these reasons, long-term groundwater levels may differ from those described in this report.

#### 4.4 Infiltration Test Results

NYCDEP requires two phases of subsurface exploration and testing for stormwater management design. Borings for preliminary design consisted of B-6, B-6A and B-7 through B-10 and borings for final design consisted of B-101 through B-103. Infiltration testing was not performed at the B-8, B-9, B-10, B-101, B-102 and B-103 locations due to shallow groundwater. The results of the testing adjacent to borings B-6A and B-7 are outlined in Table 2.

**Table 2: Infiltration Test Results**

Boring Location	Depth Performed (ft)	Approx. Elevation Performed (ft)	Observed Infiltration Rate (in/hour)				
			Infiltration Test Run No.				
			1	2	3	4	5
IT-6A	2.0	457.5	0.0	0.0	0.0	0.0	0.0
IT-7	2.0	449.0	0.0	0.0	0.0	0.0	0.0



---

## 5.0 GEOTECHNICAL RECOMMENDATIONS

The following sections provide geotechnical recommendations for design of the project. These recommendations are based on our review of the results of the subsurface exploration.

### 5.1 Shallow Foundations

Shallow foundations are recommended for support of the reconstruction of the existing brick cottage and the parking area site retaining wall. The foundations should bear on the natural clayey silt or glacial till soil. Spread footings should be designed based on a maximum net allowable bearing capacity of 3 kips per square foot (ksf). Foundations should be founded at a minimum depth of 4.0 feet below finished grade to provide frost protection. We recommend that isolated footings be a minimum of 3.0 feet wide and continuous strip footings be a minimum of 18 inches wide.

Foundations should be constructed as soon as possible after excavation to minimize the risk of disturbance to the bearing surface by exposure to precipitation or other adverse conditions. Foundation excavations should be backfilled with structural fill in accordance with the placement and compaction procedures included in *Section 5.6 - Structural Fill*.

Footing subgrade shall be protected from freezing during construction. Any disturbed, frozen or softened subgrade should be removed and replaced with structural fill as required to minimize detrimental impacts to foundation performance.

The natural soil is moisture sensitive and prone to disturbance when wet or when exposed to excessive foot traffic. Foundations should be constructed as soon as possible after excavation to minimize the risk of disturbance to the bearing surface by exposure to precipitation or other adverse conditions. To protect the footing subgrade and to provide a stable working surface a minimum of 6-inches of crushed stone over separation geotextile fabric or a 2-inch to 3-inch concrete mud mat should be placed below the footing subgrade. The separation geotextile shall be



---

a non-woven geotextile with an apparent opening size (AOS) equal to or smaller than the U.S. Standard sieve size of 70, such as Mirafi 160N. Crushed stone should consist of a 50:50 mix of NYSDOT size designation No. 1 and No. 2 crushed stone.

A detailed settlement analysis was beyond the scope of this report. However, based on the information obtained during the subsurface exploration and the recommendations outlined in this report, we anticipate that total foundation settlement will be less than 1 inch, with differential settlement of about 1/2 inch across a distance of 20 feet. These estimates are based on the assumption that foundations are constructed as recommended herein and that proper site preparation and construction monitoring is performed.

## **5.2 Lateral Earth Pressures**

The new basement walls and the parking area site retaining wall should be designed to resist lateral soil pressure as well as surcharges from adjacent loads. Basement walls restrained against lateral movement should be designed to resist at-rest earth pressures.

New basement walls and the parking area site retaining wall should be backfilled with structural fill meeting the requirements of *Section 5.6 – Structural Fill* for a lateral distance equal to at least one-half of the wall height. Walls backfilled with structural fill should be designed to resist lateral earth pressures based on the following soil properties:

- Total Unit Weight 125 pcf
- Angle of Internal Friction 32 Degrees
- Coefficient of At-Rest Earth Pressure<sup>1</sup> 0.47
- Coefficient of Active Earth Pressure<sup>1</sup> 0.31
- Coefficient of Sliding (Mass concrete on Natural Soil) 0.3



---

Notes:

1. Earth pressure coefficients assume level backfill behind walls and should be adjusted if non-level backfill is proposed.

Design for new basement walls should incorporate drainage measures to prevent hydrostatic build-up and to provide positive drainage. Drainage measures should include a minimum 1-foot-thick horizontal layer of drainage stone from the surrounding soil by a separation geotextile having an AOS equal to or smaller than the U.S. Standard sieve size of 70, such as Mirafi 160N. A prefabricated drainage board may be utilized in lieu of the crushed stone layer. New basement walls that do not include drainage features should be designed for full hydrostatic pressure.

### **5.3 Pavement**

The existing fill, natural clayey silt and silt and glacial till soils anticipated at pavement subgrade elevation are suitable for support of the proposed paved main access road, additional new access road and proposed parking area. The flexible pavement section should be designed using a California Bearing Ratio (CBR) of 5. The anticipated subgrade soils contain a significant amount of fine-grained soil and are poor draining. This soil is considered susceptible to frost heave, particularly if water is available for formation of ice lenses. Subbase course drainage is essential for successful pavement performance and longevity. The subbase course should be maintained in a drained condition at all times. Underdrains should be constructed along portions of the proposed new access road and consist of 4-inch diameter drain, spaced at 15 feet and drained to positive outlet. The underdrains should be a minimum of two feet below the proposed final grade and should be located in the access road areas that have a finished grade of less than or equal to El. 250 feet. Along the existing main access road, drainage may consist of either installing underdrains or sloping the subgrades to planned draining systems or otherwise.

The subgrade should be prepared in accordance with *Section 5.5 – Site and Subgrade Preparation*. The pavement section should include an aggregate subbase course such as NYSDOT Type 2 Subbase. The subbase along the existing access road should be underlain by a woven separation



---

and stabilization geotextile. The geotextile should have an AOS equal to or smaller than the U.S. Standard sieve size of 40, such as Mirafi 600X.

#### **5.4 Seismic Site Classification and Design Parameters**

Based on the site location, and in accordance with the 2020 Building Code of New York State (NYSBC) Section 1613, the following spectral response accelerations should be used for seismic design:

- Mapped Spectral Response Acceleration at Short Periods ( $S_s$ ) .....0.27g
- Mapped Spectral Response Acceleration at 1 Second Period ( $S_1$ ) .....0.06g

The location based spectral response accelerations are based on seismic Site Class B and must be adjusted for the project site class based on subsurface conditions. Site class D is recommended based on the subsurface conditions. In accordance with section 1613 of the NYSBC the following seismic design coefficients shall be used:

- Site Coefficient  $F_a$  .....1.6
- Site Coefficient  $F_v$  .....2.4

The potential for earthquake induced soil liquefaction was not required based on the subsurface conditions encountered and seismic design category of B for the project site.

#### **5.5 Site and Subgrade Preparation**

The areas within the improvements shall be stripped of any vegetation, topsoil and other deleterious materials. Subsequent to excavating to proposed grades, the exposed subgrade should be proofrolled with a smooth drum roller with a minimum static weight of 10 tons. The roller should operate in its vibratory mode, and complete at least six passes over the subgrade at a speed not exceeding 3 feet per second (fps). Areas which pump or weave during proof rolling shall be



---

undercut by a minimum of 12 inches and stabilized with structural fill meeting the requirements of *Section 5.6 - Structural Fill*. If the vibration roller tends to "bring up" moisture, the subgrade should be proof rolled with the roller operating in the static mode.

## **5.6 Structural Fill**

Structural fill should be used for backfilling foundation excavations, for raising grade behind the site retaining wall, and overexcavations. Structural fill shall consist of sound, durable, non-plastic sand and gravel, free of stumps, roots, organics, and any frozen or deleterious materials.

Structural fill shall be placed in loose lifts not exceeding 8 inches in thickness and should be compacted to at least 95 percent of the maximum laboratory dry density as determined by the modified Proctor test (ASTM D-1557). Structural fill shall conform to the gradation requirements in Table 3.

**Table 3: Gradation Requirements for Structural Fill**

<b>Sieve Size</b>	<b>Percent Passing by Weight</b>
4 inch	100
No. 40	0 to 70
No. 200	0 to 10

**The on-site soil generally does not meet the requirements for Structural Fill.**



---

## 5.7 Groundwater and Control of Water

Groundwater may be encountered when excavating during foundation construction and when excavating to establish roadway subgrades. At the brick cottage, a design groundwater elevation of 465 feet is recommended. At the existing access road, a design groundwater elevation of 448 feet is recommended. At proposed parking area, design groundwater elevations of 448 feet for the western side and 444 feet for the eastern side and site retaining wall are recommended. At the new access road, a design groundwater elevation of 449 feet is recommended. Project specifications should require that groundwater be maintained at a minimum depth of 2.0 feet below the excavation bottom at all times. It is the responsibility of the contractor to determine the most appropriate dewatering methods and to maintain dry conditions so that foundation construction may be completed in the dry.



---

## 6.0 EXCAVATIONS

All excavations should be performed in accordance with the Occupational Safety and Health Administration (OSHA) standards, and applicable state and local codes. Where adequate sloping or benching is not possible, excavation support should be provided. The design of a temporary excavation system shall be performed by a registered Professional Engineer licensed in the State of New York.



---

## 7.0 OBSERVATION DURING CONSTRUCTION

A qualified geotechnical engineer should carefully inspect all excavations, backfilling, and final bearing surfaces for foundations to ascertain that subgrades have been properly prepared. The inspection of soil subgrades should include probing of select areas to confirm density. The materials used as fill should be tested by a qualified soils laboratory to verify they meet the specified gradations and to determine their optimum moisture content and maximum dry density for compaction. In-place density tests should be performed to verify that compaction methods and equipment achieve the required densities.



---

## 8.0 CLOSURE

The geotechnical recommendations presented in this report are based, in part, on project and subsurface information available at the time this report was prepared and in accordance with generally accepted soil and foundation engineering practices. No other warranty, expressed or implied, is made. Some variation of subsurface conditions may occur between locations explored that may not become evident until construction. Depending on the nature and extent of the variations, it may be necessary to re-evaluate the data presented in this report.

This report has been prepared solely for design purposes and shall not be incorporated by reference of other means in the Contract Documents. If this report is included in the Contract Documents, it shall be for information only. Specifications shall take precedence.

CHA does not accept responsibility for designs based upon our recommendations unless we are engaged to review the final plans and specifications to determine whether any changes in the project affect the validity of our recommendations and whether our recommendations have been properly implemented in the design.




---

## **APPENDIX A**

### **FIGURES**





SOURCE: U.S.G.S. 7.5' Topographic  
QUADRANGLES: CROTON FALLS AND MOUNT KISCO, NY

SCALE: 1"=2000'

Drawing Copyright © 2024



111 Winners Circle, PO Box 5269  
Albany, NY 12205-0269  
518.453.4500 · www.chacompanies.com

## SITE LOCATION MAP


JOHN JAY HOMESTEAD STATE HISTORIC SITE  
KATONAH, NEW YORK

PROJECT NO.  
080675

DATE: 05/2024

FIGURE 1







---

## **APPENDIX B**

### **PHOTOGRAPHS**



1



Drilling operations at boring B-1, looking south

2



Drilling operations at boring B-2, looking south



CHA # 80675

**John Jay Homestead Site and Building  
Enhancements**

**Katonah, NY**

January 2024 – April 2024



3



Drilling operations at boring B-5, looking northwest

4



Groundwater observation well and infiltration casing installed at boring B-6A, looking west



CHA # 80675

**John Jay Homestead Site and Building  
Enhancements**

**Katonah, NY**

January 2024 – April 2024



5



Drilling operations at boring B-8, looking southeast

6



Groundwater observation well installed at boring B-10, looking southeast



CHA # 80675

**John Jay Homestead Site and Building  
Enhancements**

**Katonah, NY**

January 2024 – April 2024



7



Drilling operations at boring B-101, looking east

8



Drilling operations at boring B-103, looking east



CHA # 80675

**John Jay Homestead Site and Building  
Enhancements**

**Katonah, NY**

January 2024 – April 2024



---

## **APPENDIX C**

### **BORING LOGS**





# LEGEND TO SUBSURFACE LOGS

Page 1 of 2

SAMP./CORE NUMBER	SAMP. ADV (ft) LEN. CORE (ft)	RECOVERY (ft)	Blows per 6" on Split Spoon Sampler	"N" VALUE or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	Remarks on Character of Drilling, water return, etc	WATER LEVELS AND/OR WELL DATA
S1	2.0	1.8	2-3-4-5	7				f. SAND, Some Silt, trace f. gravel, brown, loose, moist (SM)	100		
R1	2.0	2.0	N/A	88%				Mica SCHIST, gray, soft, slightly weathered, closely fractured, good RQD			

Subsurface Logs present material classifications, test data, and observations from subsurface investigations at the subject site as reported by the inspecting geologist or engineer. In some cases, the classifications may be made based on laboratory test data when available. It should be noted that the investigation procedures only recover a small portion of the subsurface materials at the site. Therefore, actual conditions between borings and sampled intervals may differ from those presented on the Subsurface Logs. The information presented on the logs provide a basis for an evaluation of the subsurface conditions and may indicate the need for additional exploration. Any evaluation of the conditions reported on the logs must be performed by Professional Engineers or Geologists.


- SAMP./CORE NUMBER – Samples are numbered for identification on containers, laboratory reports or in text reports.
- SAMP.ADV/LEN.CORE – Length of sampler advance or length of coring run measured in feet.
- RECOVERY – Amount of sample actually recovered after withdrawing sampler or core barrel from bore hole measured in feet.
- SAMPLE BLOWS/6" – Unless otherwise noted, blow counts represent values obtained by driving a 2.0" (O.D.), 1-3/8" (I.D.) split spoon sampler into the subsurface strata with a 140 pound weight falling 30" as per ASTM International D1586. After an initial penetration of 6" to seat the sampler into undisturbed material, the sampler is then driven an additional 2 or 3 six inch increments. Refusal is defined as a resistance greater than 50 blows per 6" of penetration.
- "N" Value or RQD % – "N" VALUE – The sum of the second and third sample blow increments is generally termed the Standard Penetration Test (SPT) "N" value. Refusal (R) is defined as a resistance greater than 50 blows for 6 inches of penetration. CORE RQD – Core Rock Quality Designation, RQD, is defined as the summed length of all pieces of core equal to or longer than 4 inches divided by the total length of the coring run. Fresh, irregular breaks distinguishable as being caused by drilling or recovery operations are ignored and the pieces are counted as intact lengths. RQD values are valid only for cores obtained with NX size core barrels.
- SAMPLE – Graphical presentation of sample type and advance or core run length. See Table 1.
- DEPTH – Depth as measured from the ground surface in feet.
- GRAPHICS – Graphical presentation of subsurface materials. See Table 4. Dual soil classification and rock graphics may vary and are not shown on Table 4.
- DESCRIPTION AND CLASSIFICATION – SOIL – Recovered samples are visually classified in the field by the supervising geologist or engineer unless otherwise noted. Particle size and plasticity classification is based on field observations, and using the Unified Soil Classification System (USCS). See Table 4. USCS symbols are presented in parentheses following the soil description. Where necessary, dual symbols may be used for combinations of soil types. Relative proportions, by weight and/or plasticity, are described in general accordance with "Suggested Methods of Test for Identification of Soils" by D.M. Burmister, ASTM Special Publication 479, 6-1970. See Table 2. Soil density or consistency description is based on the penetration resistance. See Table 3. Soil moisture description is based on the observed wetness of the soil recovered being moist or wet. Water introduced into the boring during drilling may affect the moisture content of the materials. Other geologic terms may also be used to further describe the subsurface materials. ROCK – Rock core descriptions are based on the inspector's observations and may be examined and described in greater detail by the project engineer or geologist. Terms used in the description of rock core are presented in Table 5.
- DIVISION LINES – Division lines between deposits are based on field observations and changes in recovered material. Solid lines depict contacts between two deposits of different geologic depositional environment of known elevation. Dashed lines represent estimated elevation of contacts between two deposits of different geologic depositional environment. Dotted lines depict transitions of deposits within the same depositional environment, such as grain size or density.
- ELEVATION – Elevation of strata changes in feet.
- REMARKS – Miscellaneous observations.
- WATER LEVELS & WELL DATA – Hollow water level symbol, if present, represents level at which first saturated sample or water level was encountered. Solid water level symbol, if present, depicts the most probable static water elevation at the time of drilling or as measured in an installed observation well at a later date. Subsurface water conditions are influenced by factors such as precipitation, stratigraphic composition, and drilling/coring methods. Conditions at other times may differ from those described on the logs. For graphical presentation of observation/monitoring well construction, see Table 6. Elevations of changes in construction are noted at the bottom of each section.





## LEGEND TO SUBSURFACE LOGS

Page 2 of 2

TABLE 1  
TYPICAL SAMPLE TYPESTABLE 2  
SAMPLE MATERIAL PROPORTIONS

ADJECTIVE	PERCENTAGE OF SAMPLE
"and"	35% - 50%
"some"	20% - 35%
"little"	10% - 20%
"trace"	< 10%
Standard split spoon samples may not recover particles with any dimension larger than 1 3/8". Therefore, reported gravel percentages may not reflect actual conditions.	

TABLE 3  
DENSITY/CONSISTENCY

GRANULAR SOILS		COHESIVE SOILS	
Blows/ft.	Density	Blows/ft.	Consistency
< 5	Very Loose	< 2	Very Soft
5-10	Loose	2-4	Soft
11-30	Med. Compact	5-8	Med. Stiff
31-50	Compact	9-15	Stiff
> 50	Very Compact	16-30	Very Stiff
		> 30	Hard

TABLE 4  
USCS CLASSIFICATION, PARTICLE SIZE, & GRAPHICS

MAJOR PARTICLE SIZE DIVISION	USCS SYMBOL	GRAPHIC SYMBOL	GENERAL DESCRIPTION
GRAVEL Coarse: 3" - 3/4" Fine: 3/4" - #4  Classification based on > 50% being gravel	GW		Well graded gravels, gravel & sand mix.
	GP		Poorly graded gravels, gravel & sand mix.
	GM		Gravel, sand and silt mix.
	GC		Gravel, sand and clay mix.
	SW		Well graded sand, sand & gravel mix.
	SP		Poorly graded sand, sand & gravel mix.
	SM		Sand and silt mix.
SAND Coarse: #4 - #10 Med.: #10 - #40 Fine: #40 - #200  Classification based on > 50% being sand	SC		Sand and clay mix.
	ML		Inorganic silt, low plasticity.
	CL		Inorganic clay, low plasticity.
	OL		Organic silt/clay, low plasticity.
	MH		Inorganic silt, high plasticity.
SILT & CLAY  Classification based on > 50% passing #200 sieve.	CH		Inorganic clay, high plasticity.
	OH		Organic silt/clay, high plasticity.
	Pt		Peat and other highly organic soils.
ORGANIC SOILS	Pt		Peat and other highly organic soils.
FILL	Fill		Miscellaneous fill materials.

TABLE 5  
ROCK CLASSIFICATION TERMS

## HARDNESS:

Very Soft	Carves
Soft	Grooves with knife
Med. Hard	Scratched easily with knife
Hard	Scatched with difficulty
Very Hard	Cannot be scratched with knife

## WEATHERING:

Fresh	Slight or no staining of fractures, little or no discoloration, few fractures.
Slightly	Fractures stained, discoloration may extend into rock 1", some soil in fractures.
Moderately	Significant portions of rock stained and discolored, soil in fractures, loss of strength.
Highly	Entire rock discolored and dull except quartz grains, severe loss of strength.
Complete	Weathered to a residual soil.

## BEDDING:


Massive	> 40"
Thick	12' - 40"
Medium	4" - 12"
Thin	< 4"

## FRACTURE SPACING:

Massive/V. Wide	> 6'
Thick/Wide	2' - 6'
Med./Med.	8" - 24"
Thin/Close	2 1/2" - 8"
V. Thin/V. Close	< 2 1/2"

## RQD:

Excellent	> 90%
Good	76% - 90%
Fair	51% - 75%
Poor	25% - 50%
V. Poor	< 25%

TABLE 6  
WELL CONSTRUCTION





PROJECT NUMBER: 080675

4/26/2024

**John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-1**

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 4.25" HSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects &amp; Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 1/18/2024 11:05:00 AM

FINISH: 1/18/2024 12:10:00 PM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: CWS

COORDS. NORTHING: 882013.49

EASTING: 723564.52

SURFACE  
ELEV: 470.0 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPEWATER  
DEPTH  
(ft)CASING  
BOTTOM  
(ft)HOLE  
BOTTOM  
(ft)

1-18-24

12:10 PM

Completion

10.7

20

20.9

1-18-24

1:15 PM

Completion

7.9

20

20.9

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	0.8	10-5-3-2	8				<b>TOPSOIL</b> <b>SILT</b> , Some f.m.c. Sand, trace organics, brown, loose, moist ( <b>FILL</b> )			
S-2	2	1.2	2-2-3-3	5				<b>f.m.c. SAND</b> , Some Silt, brown, loose, moist ( <b>FILL</b> )			
S-3	2	1.4	5-5-3-3	8		5		<b>Clayey SILT</b> , Some f.m.c. Sand, brown, medium stiff, moist ( <b>ML</b> )	465		
S-4	2	1.5	8-16-13-9	29				<b>f.m.c. SAND</b> , Some Silt, brown, medium compact, moist ( <b>SM-TILL</b> )			
S-5	2	1.3	15-34-25-19	59		10		<b>f.m.c. SAND</b> , Some Silt, trace f.c. gravel, brown, very compact, moist ( <b>SM-TILL</b> )			
S-6	2	0.7	14-20-18-16	38				<b>f.m.c. SAND</b> , little silt, brown, compact, brown, moist ( <b>SM-TILL</b> )	460		
S-7	2	1	6-9-10-14	19		15		<b>f.c. GRAVEL</b> , Some Silt, Some f.m.c. Sand, brown, medium compact, wet ( <b>GM-TILL</b> )	455		
S-8	0.9	0.9	51-100/0.4'	R		20		<b>f.m.c. SAND</b> , little silt, brown, very compact, wet ( <b>COMPLETELY WEATHERED ROCK</b> )	450		
								End of Boring at 20.9 ft			

Water level observations  
made during drilling may  
not represent static  
groundwater conditions.

I:\CHA-LLP\COM\PROJECTS\ANY\K6\080675\000\06 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ





John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-2

PROJECT NUMBER: 080675

4/26/2024

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 4.25" HSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects & Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 1/18/2024 1:45:00 PM

FINISH: 1/18/2024 2:40:00 PM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: CWS

COORDS. NORTHING: 881975.48

EASTING: 723552.39

SURFACE  
ELEV: 469.5 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPE

WATER  
DEPTH  
(ft)

CASING  
BOTTOM  
(ft)

HOLE  
BOTTOM  
(ft)

1-18-24

2:15 PM

Estimated

10

8

12

1-18-24

2:40 PM

Completion

12.3

20

22

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	1	2-2-2-3	4				<b>TOPSOIL</b> <b>SILT</b> , Some f.m.c. Sand, trace f. gravel, trace organics, trace wood, brown, very loose, moist ( <b>FILL</b> ) <b>SILT</b> , little f.m.c. sand, trace organics, brown, loose, moist ( <b>FILL</b> )			
S-2	2	1.2	2-2-3-7	5							
S-3	2	1.2	10-10-15-13	25		5		<b>f.m.c. SAND</b> , Some Silt, little f.c. gravel, brown, medium compact, moist ( <b>SM-TILL</b> )  <b>Similar Soil (SM-TILL)</b>  Grades to little silt ( <b>SM-TILL</b> )	465		
S-4	2	1.4	13-13-14-18	27							
S-5	2	0.4	19-16-9-8	25		10		<b>f.m.c. SAND</b> , And Silt, little f. gravel, brown, medium compact, wet ( <b>SM-TILL</b> )	460	Water level estimated based on visual soil sample moisture content. Water level observations made during drilling may not represent static groundwater conditions.	▽
S-6	2	1.7	5-11-12-12	23							
S-7	2	1.4	11-17-10-8	27		15		Grades to little silt, trace f. gravel ( <b>SM-TILL</b> )	455		
S-8	2	0.4	18-17-68-47	85		20		<b>f.m.c. SAND</b> , Some Silt, trace f.c. gravel, brown, very compact, wet ( <b>SM-TILL</b> )	450		
								End of Boring at 22 ft			
									445		

\\CHA-LLP.COM\PROJECTS\ANYK\080675.000\06 PROJECT DATA\FIELD DATA\080675 BORING LOGS.GPJ





John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-3

PROJECT NUMBER: 080675

4/26/2024

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 4.25" HSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects & Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 1/19/2024 9:25:00 AM

FINISH: 1/19/2024 11:15:00 AM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: CWS

COORDS. NORTHING: 882335.02

EASTING: 723379.97

SURFACE

ELEV: 487.0 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPE

WATER  
DEPTH  
(ft)

CASING  
BOTTOM  
(ft)

HOLE  
BOTTOM  
(ft)

1-19-24

10:30 AM

Estimated

10

8

12

1-19-24

11:15 AM

Completion

13.2

20

22

1-19-24

12:30 PM

Completion

11.8

20

22

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	0.3	1-2-3-2	5				<b>TOPSOIL</b> <b>SILT</b> , little f.m. sand, trace organics, brown, loose, moist ( <b>ML</b> )			
S-2	2	0.8	6-5-4-8	9				<b>SILT</b> , Some f. Sand, trace f. gravel, brown, loose, moist ( <b>ML-TILL</b> )	485		
S-3	2	1	12-19-24-24	43		5		<b>f.m.c. SAND</b> , Some Silt, Some f.c. gravel, brown, compact, moist ( <b>SM-TILL</b> )			
S-4	2	1.5	34-31-26-57	57				Becomes very compact ( <b>SM-TILL</b> )	480		
S-5	2	0.5	23-35-36-82	71				Grades to Some f.c. Gravel ( <b>SM-TILL</b> )			
S-6	2	1	27-70-56-78	R		10		<b>f.m.c. SAND</b> , little silt, trace f. gravel, brown, very compact, wet ( <b>COMPLETELY WEATHERED ROCK</b> )	475	Water level estimated based on visual soil sample moisture content. Water level observations made during drilling may not represent static groundwater conditions.	▽
S-7	2	1.5	76-45-40-37	85		15		<b>Similar Soil (COMPLETELY WEATHERED ROCK)</b>	470		
S-8	2	0.6	30-28-78-84	R		20		Grades to no f. gravel ( <b>COMPLETELY WEATHERED ROCK</b> )	465		
								End of Boring at 22 ft			

\\CHA-LLP-COM\PROJECTS\ANYK\080675\000006 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ





PROJECT NUMBER: 080675

4/26/2024

**John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-4**

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 2.25" SSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects &amp; Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 1/18/2024 10:00:00 AM

FINISH: 1/18/2024 10:35:00 AM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: CWS

COORDS. NORTHING: 881500.69

EASTING: 723494.50

SURFACE  
ELEV: 450.0 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPEWATER  
DEPTH  
(ft)CASING  
BOTTOM  
(ft)HOLE  
BOTTOM  
(ft)

1-18-24

10:35 AM

Completion

4

N/A

10

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	1	159-53-21-15	74				<b>f.m.c. SAND</b> , Some Silt, little f.c. gravel, gray, very compact, moist ( <b>FILL</b> )			
S-2	2	0.6	12-9-9-7	18				<b>f.m.c. SAND</b> , Some Silt, brown, medium compact, moist ( <b>SM-TILL</b> )			
S-3	2	2	2-6-10-16	16		5		<b>f.m.c. SAND</b> , Some Silt, brown, medium compact, wet ( <b>SM-TILL</b> )	445		
S-4	2	1.5	14-16-16-16	32				Becomes compact ( <b>SM-TILL</b> )			
S-5	2	2	20-14-15-11	29				Grades to trace f.c. gravel, becomes medium compact ( <b>SM-TILL</b> )			
						10		End of Boring at 10 ft	440		
						15			435		
						20			430		

Water level observations  
made during drilling may  
not represent static  
groundwater conditions.

I:\CHA-LLP\COM\PROJECTS\ANY\K6\080675\000\06 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ





John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-5

PROJECT NUMBER: 080675

4/26/2024

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 2.25" SSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects & Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 1/17/2024 3:00:00 PM

FINISH: 1/17/2024 3:25:00 PM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: CWS

COORDS. NORTHING: 881096.64

EASTING: 723574.13

SURFACE  
ELEV: 450.0 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPE

WATER  
DEPTH  
(ft)

CASING  
BOTTOM  
(ft)

HOLE  
BOTTOM  
(ft)

1-17-24

3:25 PM

Completion

3.1

N/A

10

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	1	82-51-23-17	74				<u>f.m.c. SAND</u> , And f.c. Gravel, Some Silt, gray, very compact, moist ( <b>FILL</b> )			
S-2	2	1.5	3-4-3-6	7				<u>Clayey SILT</u> , little f.m.c. sand, brown, medium stiff, moist ( <b>ML</b> )			
S-3	2	1.1	17-22-20-20	42		5		<u>f.m.c. SAND</u> , little silt, brown, compact, wet ( <b>SM-TILL</b> )	445		
S-4	2	1	18-24-23-24	47				Grades to trace f. gravel ( <b>SM-TILL</b> )			
S-5	2	2	25-23-23-51	46		10		<u>Similar Soil</u> ( <b>SM-TILL</b> )			
								End of Boring at 10 ft	440		
						15			435		
						20			430		



Water level observations  
made during drilling may  
not represent static  
groundwater conditions.

\\CHA-LLP.COM\PROJECTS\ANYK6\080675\000\06 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ





PROJECT NUMBER: 080675 4/26/2024

John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-6

Page 1 of 1

LOCATION: Katonah, New York				DRILL FLUID: None		DRILLING METHOD: 2.25" SSA		ROD SIZE: NW		
CLIENT: Beyer, Blinder, Belle Architects & Planners LLP				HAMMER TYPE: Automatic			DRILL RIG: Rubber Track ATV			
CONTRACTOR: New England Boring Contractors				START: 1/16/2024 10:45:00 AM			FINISH: 1/16/2024 11:15:00 AM			
DRILLER: D. DeAngelis		INSPECTOR: C. Hourigan		WATER LEVEL OBSERVATIONS	DATE	TIME	READING TYPE	WATER DEPTH (ft)	CASING BOTTOM (ft)	HOLE BOTTOM (ft)
CHECKED BY: CWS										
COORDS. NORTHING: 882317.48		EASTING: 723827.65								
SURFACE ELEV: 459.5 (ft; Estimated)		DATUM: NAD83 / NAVD88								

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	0.3	1-2-1-2	3				<b>TOPSOIL</b> <b>SILT</b> , little f.m.c. sand, trace organics, brown, very loose, moist ( <b>ML</b> )			
S-2	2	1.4	5-8-9-8	17				<b>Clayey SILT</b> , little f.m.c. sand, trace organics, brown, medium compact, moist ( <b>ML-TILL</b> )			
S-3	1	0.5	17-50/0.5'	R		5		<b>f.m.c. SAND</b> , Some Silt, trace f. gravel, brown, very compact, moist ( <b>SM-TILL</b> )	455		
End of Boring at 5.5 ft										SSA refusal at 5.5' due to possible boulder. Offset 4 feet east to B-6A.	
									450		
									445		
									440		
									435		

\\CHA-LLP-COM\PROJECTS\ANYK6\080675.000\06 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ





PROJECT NUMBER: 080675

4/26/2024

**John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-6A**

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 2.25" SSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects &amp; Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 1/16/2024 11:15:00 AM

FINISH: 1/16/2024 11:45:00 AM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: CWS

COORDS. NORTHING: 882316.50

EASTING: 723832.82

SURFACE  
ELEV: 459.5 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPEWATER  
DEPTH  
(ft)CASING  
BOTTOM  
(ft)HOLE  
BOTTOM  
(ft)

1-19-24

1:40 PM

Static

11.7

12

12

4-15-24

8:45 AM

Static

12

12

12

4-16-24

9:15 AM

Static

12

12

12

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	1	10-10-13-15	23		5		<b>SILT</b> , And f.m.c. Sand, brown, medium compact, moist ( <b>ML-TILL</b> )	455	Refer to B-6 for subsurface data to a depth of 5.5 feet.	
S-2	2	2	14-16-15-16	31		10		Becomes compact ( <b>ML-TILL</b> )	450		
S-3	2	2	10-12-13-16	25				Becomes medium compact ( <b>ML-TILL</b> )		Installed observation well to a depth of 12 feet upon completion. Infiltration test set adjacent to the borehole at a depth of 2 feet.	
								End of Boring at 12 ft		Water level observations made during drilling may not represent static groundwater conditions.	
						15			445		
						20			440		
									435		

I:\CHA-LLP\COM\PROJECTS\ANYK\080675\000006 PROJECT DATA\FIELD DATA\080675 BORING LOGS.GPJ





John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-7

PROJECT NUMBER: 080675

4/26/2024

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 2.25" SSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects & Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 1/16/2024 1:35:00 PM

FINISH: 1/16/2024 2:10:00 PM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: CWS

COORDS. NORTHING: 882259.83

EASTING: 723902.72

SURFACE  
ELEV: 451.0 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPE

WATER  
DEPTH  
(ft)

CASING  
BOTTOM  
(ft)

HOLE  
BOTTOM  
(ft)

1-19-24

1:45 PM

Static

7.3

12

12

4-15-24

8:40 AM

Static

8.2

12

12

4-16-24

9:10 AM

Static

7.9

12

12

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	1	2-1-1-1	2				<b>TOPSOIL</b> <b>SILT</b> , little f.m.c. sand, trace organics, brown, very loose, moist ( <b>ML</b> )	450		
S-2	2	1.5	8-12-12-16	24				<b>f.m.c. SAND</b> , Some Silt, trace organics, brown, medium compact, moist ( <b>SM-TILL</b> )			
S-3	2	0.8	8-10-16-16	26		5		<b>f.m.c. SAND</b> , Some Silt, brown, medium compact, moist ( <b>SM-TILL</b> )			
S-4	2	1	10-16-14-16	30				<b>Similar Soil (SM-TILL)</b>	445		
S-5	2	0.4	10-14-16-13	30				Grades to And Silt, becomes wet ( <b>SM-TILL</b> )		Water level observations made during drilling may not represent static groundwater conditions.	
S-6	2	1	16-16-12-11	28		10		<b>Similar Soil (SM-TILL)</b>	440	Installed observation well to a depth of 12 feet upon completion. Infiltration test set adjacent to the borehole at a depth of 2 feet.	
								End of Boring at 12 ft			
						15					
									435		
						20					
									430		

\\CHA-LLP.COM\PROJECTS\ANYK\080675.000\06 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ









John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-9

PROJECT NUMBER: 080675

4/26/2024

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 2.25" SSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects & Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 1/17/2024 1:30:00 PM

FINISH: 1/17/2024 2:10:00 PM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: CWS

COORDS. NORTHING: 881680.96

EASTING: 723675.63

SURFACE

ELEV: 449.5 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPE

WATER  
DEPTH  
(ft)

CASING  
BOTTOM  
(ft)

HOLE  
BOTTOM  
(ft)

1-17-24

2:10 PM

Completion

2.7

N/A

12

1-18-24

9:20 AM

24 Hours

1.1

12

12

1-19-24

1:50 PM

Static

0.8

12

12

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
								4-15-24 8:40 AM 4-16-24 9:10 AM		Static Static	0.7 12
S-1	2	0.1	2-1-2-3	3				<u>TOPSOIL</u>			
S-2	2	1.5	3-7-18-26	25				<u>f.m.c. SAND</u> , Some Silt, brown, medium compact, moist ( <b>SM-TILL</b> )		Water level observations made during drilling may not represent static groundwater conditions.	
S-3	2	0.7	20-15-10-9	25		5		<u>f.m.c. SAND</u> , Some Silt, trace f. gravel, brown, medium compact, wet ( <b>SM-TILL</b> )	445		
S-4	2	0.7	12-14-17-16	31				Becomes compact ( <b>SM-TILL</b> )			
S-5	1	0.4	8-50/0.5'	R				Becomes very compact ( <b>SM-TILL</b> )			
S-6	2	0.8	16-19-19-40	38		10		Grades to little silt, becomes compact ( <b>SM-TILL</b> )	440	Installed observation well to a depth of 12 feet upon completion.	
								End of Boring at 12 ft			
						15			435		
						20			430		
									425		

\\CHA-LLP-COM\PROJECTS\ANYK\080675.000\06 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ





John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-10

PROJECT NUMBER: 080675

4/26/2024

Page 1 of 1

LOCATION: Katonah, New York				DRILL FLUID: None		DRILLING METHOD: 2.25" SSA		ROD SIZE: NW		
CLIENT: Beyer, Blinder, Belle Architects & Planners LLP				HAMMER TYPE: Automatic			DRILL RIG: Rubber Track ATV			
CONTRACTOR: New England Boring Contractors				START: 1/17/2024 1:30:00 PM			FINISH: 1/17/2024 2:10:00 PM			
DRILLER: D. DeAngelis		INSPECTOR: C. Hourigan		WATER LEVEL OBSERVATIONS	DATE	TIME	READING TYPE	WATER DEPTH (ft)	CASING BOTTOM (ft)	HOLE BOTTOM (ft)
CHECKED BY: CWS					1-17-24	12:50 PM	Completion	2	N/A	12
COORDS. NORTHING: 881736.79		EASTING: 723773.25			1-18-24	9:15 AM	24 Hours	4.2	12	12
SURFACE ELEV: 448.5 (ft; Estimated)		DATUM: NAD83 / NAVD88			1-19-24	1:50 PM	Static	3	12	12

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	0.2	1-2-2-2	4				<u>TOPSOIL</u>	445		
S-2	2	0.9	2-19-10-8	29				f.m.c. SAND, little silt, brown, medium compact, moist (SM-TILL)	445	Water level observations made during drilling may not represent static groundwater conditions.	
S-3	2	1.4	8-10-11-14	21		5		f.m.c. SAND, Some Silt, trace f. gravel, brown, medium compact, wet (SM-TILL)			
S-4	2	0	23-15-19-16	34				No Recovery			
S-5	1	0.8	13-19-21-18	40				SILT, And f.m.c. Sand, brown, compact, wet (ML-TILL)	440		
S-6	2	2	17-20-22-17	42		10		Grades to Some f.m.c. Sand (ML-TILL)		Installed observation well to a depth of 12 feet upon completion.	
								End of Boring at 12 ft	435		
						15					
									430		
						20					
									425		

\\CHA-LLP-COM\PROJECTS\ANYK\080675\000006 PROJECT DATA\FIELD DATA\080675 BORING LOGS.GPJ





PROJECT NUMBER: 080675

4/26/2024

**John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-101**

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 2.25" SSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects &amp; Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 4/15/2024 1:30:00 PM

FINISH: 4/15/2024 2:20:00 PM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: SMD

COORDS. NORTHING: 881637.41

EASTING: 723666.60

SURFACE

ELEV: 445.5 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPEWATER  
DEPTH  
(ft)CASING  
BOTTOM  
(ft)HOLE  
BOTTOM  
(ft)

4-15-24

2:20 PM

Completion

5.8

None

12

4-15-24

2:55 PM

End of Day

1

None

12

4-16-24

9:30 AM

Start of Day

0.4

None

5

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	1.7	WH-1-4-11	5				<b>TOPSOIL</b> <b>Silty CLAY</b> , little f.m.c. sand, trace organics, brown, medium stiff, moist ( <b>CL</b> )	445	Standing water observed surrounding borehole. Water level observations made during drilling may not represent static groundwater conditions.	
S-2	2	1.5	6-16-17-14	33				<b>f.m.c. SAND</b> , Some Silt, trace f. gravel, trace organics, brown, compact, wet ( <b>SM-TILL</b> )			
S-3	2	1.3	15-18-18-14	36		5		grades to little f.c. gravel, no organics ( <b>SM-TILL</b> )	440		
S-4	2	1	6-8-10-8	18				<b>Clayey SILT</b> , Some f.m.c. Sand, trace f. gravel, brown, very stiff, wet ( <b>ML-TILL</b> )			
S-5	2	0.7	4-10-13-10	23				<b>f.m.c. SAND</b> , Some clayey Silt, trace f. gravel, brown, medium compact, wet ( <b>SM-TILL</b> )			
S-6	0.1	0.1	100/0.1'	R		10		Insufficient recovery End of Boring at 10.5 ft	435	Solid Stem Auger refusal at 10.5 feet. The borehole was backfilled with soil cuttings upon completion.	
						15					
									430		
						20					
									425		

I:\CHA-LLP\COM\PROJECTS\ANYK\080675.000\06 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ





John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-102

PROJECT NUMBER: 080675

4/26/2024

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 2.25" SSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects & Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 4/15/2024 11:10:00 AM

FINISH: 4/15/2024 11:40:00 AM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: SMD

COORDS. NORTHING: 881858.22

EASTING: 723850.49

SURFACE

ELEV: 445.2 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPE

WATER  
DEPTH  
(ft)

CASING  
BOTTOM  
(ft)

HOLE  
BOTTOM  
(ft)

4-15-24

11:40 AM

Completion

2.1

None

12

4-15-24

2:50 PM

End of Day

1.8

None

12

4-16-24

9:25 AM

Start of Day

2.2

None

3.8

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	0.6	WH-WH-4-11	4				<b>TOPSOIL</b> <b>Silty CLAY</b> , little f.m.c. sand, trace organics, brown, soft, moist ( <b>CL</b> )	445		
S-2	2	0.6	9-8-12-14	20				<b>f.m.c. SAND</b> , Some Silt, Some f.c. Gravel, brown, medium compact, wet ( <b>SM-TILL</b> )		Water level observations made during drilling may not represent static groundwater conditions.	
S-3	2	1.4	20-24-25-15	49		5		grades to little f.c. gravel, becomes compact ( <b>SM-TILL</b> )	440		
S-4	2	1.8	11-10-9-11	19				<b>f.m.c. SAND</b> , Some Silt, trace f. gravel, trace organics, brown, medium compact, wet ( <b>SM-TILL</b> )			
S-5	2	1.1	18-18-13-14	31		10		<b>f.m.c. SAND</b> , little silt, trace f.c. gravel, brown, compact, wet ( <b>SM-TILL</b> )			
S-6	2	1.4	14-9-23-22	32				grades to little f.c. gravel ( <b>SM-TILL</b> )	435		
								End of Boring at 12 ft		The borehole was backfilled with soil cuttings upon completion.	
						15			430		
						20			425		

\\CHA-LLP.COM\PROJECTS\ANYK\080675.000\06 PROJECT DATA\FIELD DATA\GEO\080675 BORING LOGS.GPJ





PROJECT NUMBER: 080675

4/26/2024

**John Jay Homestead  
SUBSURFACE LOG  
HOLE NUMBER B-103**

Page 1 of 1

LOCATION: Katonah, New York

DRILL FLUID: None

DRILLING METHOD: 2.25" SSA

ROD SIZE: NW

CLIENT: Beyer, Blinder, Belle Architects &amp; Planners LLP

HAMMER TYPE: Automatic

DRILL RIG: Rubber Track ATV

CONTRACTOR: New England Boring Contractors

START: 4/15/2024 9:25:00 AM

FINISH: 4/15/2024 10:05:00 AM

DRILLER: D. DeAngelis

INSPECTOR: C. Hourigan

CHECKED BY: SMD

COORDS. NORTHING: 882262.66

EASTING: 724003.70

SURFACE

ELEV: 439.8 (ft; Estimated)

DATUM: NAD83 / NAVD88

WATER  
LEVEL  
OBSERVATIONS

DATE

TIME

READING  
TYPEWATER  
DEPTH  
(ft)CASING  
BOTTOM  
(ft)HOLE  
BOTTOM  
(ft)

4-15-24

10:05 AM

Completion

8.1

None

12

4-15-24

2:40 PM

End of Day

3.8

None

12

4-16-24

9:10 AM

Start of Day

3.6

None

7.8

SAMP./CORE NUMBER	SAMP. ADV. (ft) LEN. CORE (ft)	RECOVERY (ft)	BLOWS PER 6" ON SPLIT SPOON SAMPLER	"N" Value or RQD%	SAMPLE	DEPTH (Feet)	GRAPHICS	DESCRIPTION AND CLASSIFICATION	ELEVATION (Feet)	REMARKS ON CHARACTER OF DRILLING, WATER RETURN, ETC.	WATER LEVELS AND/OR WELL DATA
S-1	2	1.5	1-3-2-2	5				<b>TOPSOIL</b> <b>Clayey SILT</b> , little f.m.c. sand, trace f.c. gravel, trace organics, brown, loose, moist ( <b>ML</b> )			
S-2	2	1.4	4-7-9-8	16				<b>f.m.c. SAND</b> , Some Silt, trace f. gravel, brown, compact, moist ( <b>SM-TILL</b> )			
S-3	2	2	8-9-7-4	16		5		<b>f.m.c. SAND</b> , And clayey Silt, trace f. gravel, trace organics, brown, medium compact, moist ( <b>SM-TILL</b> )	435		
S-4	2	2	8-11-13-20	24				<b>f.m.c. SAND</b> , Some clayey Silt, trace f. gravel, trace organics, brown, medium compact, wet ( <b>SM-TILL</b> )			
S-5	2	0.9	26-16-16-14	32		10		<b>f.m.c. SAND</b> , little silt, little f.c. gravel, brown, compact, wet ( <b>SM-TILL</b> )	430		
S-6	2	1.4	13-15-17-14	32				<b>Clayey SILT</b> , Some f.m.c. Sand, trace f.c. gravel, brown, hard, wet ( <b>ML-TILL</b> )			
								End of Boring at 12 ft		The borehole was backfilled with soil cuttings upon completion.	
						15			425		
						20			420		
									415		

I:\CHA-LLP\COM\PROJECTS\ANYK\080675\000106 PROJECT DATA\FIELD DATA\080675 BORING LOGS.GPJ



---

## **APPENDIX D**

### **LABORATORY TEST RESULTS**





3348 Route 208, Campbell Hall, NY 10916

Phone: 845-496-1600 Fax: 845-496-1398

12960 Commerce Lake Drive, A14, Fort Myers, FL 33913

42 Day Farm Road, West Stockbridge, MA 01266

1813 State Route 7, Harpursville, NY 13787

877 US-4, Schuylerville, NY 12871

<b>Client:</b>	CHA, Inc.	<b>Project:</b>	John Jay Homestead Historic Site
<b>Item:</b>	B-4 S-1	<b>Project Number:</b>	240100
<b>Source:</b>	0-2'	<b>Lab Number:</b>	Q24-004E
<b>Date Sampled:</b>	1/29/2024	<b>Sampled By:</b>	Client
<b>Date Tested:</b>	1/30/2024	<b>Tested By:</b>	Michael Thomas

### GRADATION (SIEVE ANALYSIS) OF SOIL OR AGGREGATE

Test Method(s): ASTM D422, C136, C117; AASHTO T88, T27, T11

<b>Lab Number</b>	<b>Sample Type</b>	<b>Sampling Location</b>	<b>Specification</b>
Q24-004E	B-4 S-1	In-Place	No Specification

Sieve Size		% Retained	% Passing	Spec. % Pass
mm	Inches			
100.0 mm	4"	0.0	100	
75.0 mm	3"	0.0	100	
63.0 mm	2 1/2"	0.0	100	
50.0 mm	2"	0.0	100	
37.5 mm	1 1/2"	0.0	100	
25.0 mm	1"	0.0	100	
19.0 mm	3/4"	0.0	100	
12.5 mm	1/2"	10.6	89	
6.3 mm	1/4"	15.1	74	
4.75 mm	#4	3.3	71	
2.00 mm	#10	10.7	60	
0.850 mm	#20	8.1	52	
0.600 mm	#30	2.1	50	
0.425 mm	#40	4.5	46	
0.150 mm	#100	13.4	32	
0.075 mm	#200	8.7	24	
Pan		23.5		

Comments:

Minus #200 by wash-sieve method.

*Emily J. Rodriguez*

Report Reviewed By:

This report shall not be reproduced, except in full, without written permission from Advance Testing Company, Inc.  
The results in this report relate only to the items inspected or tested.

PDF





3348 Route 208, Campbell Hall, NY 10916

Phone: 845-496-1600 Fax: 845-496-1398

12960 Commerce Lake Drive, A14, Fort Myers, FL 33913

42 Day Farm Road, West Stockbridge, MA 01266

1813 State Route 7, Harpursville, NY 13787

877 US-4, Schuylerville, NY 12871

<b>Client:</b>	CHA, Inc.	<b>Project:</b>	John Jay Homestead Historic Site
<b>Item:</b>	B-5 S-1	<b>Project Number:</b>	240100
<b>Source:</b>	0-2'	<b>Lab Number:</b>	Q24-004F
<b>Date Sampled:</b>	1/29/2024	<b>Sampled By:</b>	Client
<b>Date Tested:</b>	1/30/2024	<b>Tested By:</b>	Michael Thomas

### GRADATION (SIEVE ANALYSIS) OF SOIL OR AGGREGATE

Test Method(s): ASTM D422, C136, C117; AASHTO T88, T27, T11

<b>Lab Number</b>	<b>Sample Type</b>	<b>Sampling Location</b>	<b>Specification</b>
Q24-004F	B-5 S-1	In-Place	No Specification

Sieve Size		% Retained	% Passing	Spec. % Pass
mm	Inches			
100.0 mm	4"	0.0	100	
75.0 mm	3"	0.0	100	
63.0 mm	2 1/2"	0.0	100	
50.0 mm	2"	0.0	100	
37.5 mm	1 1/2"	0.0	100	
25.0 mm	1"	0.0	100	
19.0 mm	3/4"	0.0	100	
12.5 mm	1/2"	8.5	92	
6.3 mm	1/4"	20.4	71	
4.75 mm	#4	7.4	64	
2.00 mm	#10	13.0	51	
0.850 mm	#20	10.9	40	
0.600 mm	#30	2.2	38	
0.425 mm	#40	3.7	34	
0.150 mm	#100	6.6	27	
0.075 mm	#200	4.4	23	
Pan		22.9		

Comments:

Minus #200 by wash-sieve method.

*Emily J. Rodriguez*

Report Reviewed By:

This report shall not be reproduced, except in full, without written permission from Advance Testing Company, Inc.  
The results in this report relate only to the items inspected or tested.

PDF





3348 Route 208, Campbell Hall, NY 10916  
Phone: 845-496-1600 Fax: 845-496-1398  
12960 Commerce Lake Drive, A14, Fort Myers, FL 33913  
42 Day Farm Road, West Stockbridge, MA 01266  
1813 State Route 7, Harpursville, NY 13787

<b>Client:</b>	CHA, Inc.	<b>Project:</b>	John Jay Homestead Historic Site
<b>Material:</b>	B-1 S-3	<b>Project #:</b>	240100
<b>Source:</b>	4-6'	<b>Lab No.:</b>	Q24-004A
<b>Location:</b>	In-Place	<b>Item Number:</b>	No Specifications
<b>Date Sampled:</b>	1/29/2024	<b>Sampled By:</b>	Client
<b>Date Tested:</b>	1/30/24	<b>Tested By:</b>	Michael Thomas

### REPORT OF ATTERBERG LIMITS TEST RESULTS

TEST METHOD: ASTM D4318; LL Method B

<b>Lab Number:</b>	Q24-004A	<b>Specification</b>
<b>Liquid Limit:</b>	21	
<b>Plastic Limit:</b>	17	
<b>Plasticity Index:</b>	4	

**Notes:** Values shown are percent moisture.  
Customary procedure is to round results to the nearest whole number.

**Comments:**

Report Reviewed By: \_\_\_\_\_

This report shall not be reproduced, except in full, without the written permission of Advance Testing Company, Inc.

The results in this report relate only to the items inspected or tested.

Page 1 of 1

PDF





3348 Route 208, Campbell Hall, NY 10916

Phone: 845-496-1600 Fax: 845-496-1398

12960 Commerce Lake Drive, A14, Fort Myers, FL 33913

42 Day Farm Road, West Stockbridge, MA 01266

1813 State Route 7, Harpursville, NY 13787

<b>Client:</b>	CHA, Inc.	<b>Project:</b>	John Jay Homestead Historic Site
<b>Material:</b>	B-1 S-3	<b>Project Number:</b>	240100
<b>Source:</b>	4-6'	<b>Lab Number:</b>	Q24-004A
<b>Location:</b>	In-Place	<b>Item Number:</b>	No Specifications
<b>Date Sampled:</b>	1/29/2024	<b>Sampled By:</b>	Client
<b>Date Tested:</b>	1/29/2024	<b>Tested By:</b>	Michael Thomas

### Report of Natural Moisture Content of Soil and Rock

Test Method: ASTM D2216

Wet Weight (g):	299.7
Dry Weight (g):	250.5
<b>% Nat. Moisture:</b>	<b>19.6</b>

#### Specification:

Comments:

No specifications available at time of testing.

Report Reviewed By: \_\_\_\_\_

This report shall not be reproduced, except in full, without written permission from Advance Testing Company, Inc.

The results in this report relate only to the items inspected or tested.

PDF





3348 Route 208, Campbell Hall, NY 10916

Phone: 845-496-1600 Fax: 845-496-1398

12960 Commerce Lake Drive, A14, Fort Myers, FL 33913

42 Day Farm Road, West Stockbridge, MA 01266

1813 State Route 7, Harpursville, NY 13787

877 US-4, Schuylerville, NY 12871

<b>Client:</b>	CHA, Inc.	<b>Project:</b>	John Jay Homestead Historic Site
<b>Item:</b>	B-1 S-7	<b>Project Number:</b>	240100
<b>Source:</b>	15-17'	<b>Lab Number:</b>	Q24-004B
<b>Date Sampled:</b>	1/29/2024	<b>Sampled By:</b>	Client
<b>Date Tested:</b>	1/30/2024	<b>Tested By:</b>	Michael Thomas

### GRADATION (SIEVE ANALYSIS) OF SOIL OR AGGREGATE

Test Method(s): ASTM D422, C136, C117; AASHTO T88, T27, T11

<b>Lab Number</b>	<b>Sample Type</b>	<b>Sampling Location</b>	<b>Specification</b>
Q24-004B	B-1 S-7	In-Place	No Specification

Sieve Size		% Retained	% Passing	Spec. % Pass
mm	Inches			
100.0 mm	4"	0.0	100	
75.0 mm	3"	0.0	100	
63.0 mm	2 1/2"	0.0	100	
50.0 mm	2"	0.0	100	
37.5 mm	1 1/2"	0.0	100	
25.0 mm	1"	0.0	100	
19.0 mm	3/4"	13.6	86	
12.5 mm	1/2"	11.1	75	
6.3 mm	1/4"	12.4	63	
4.75 mm	#4	1.0	62	
2.00 mm	#10	2.9	59	
0.850 mm	#20	3.5	56	
0.600 mm	#30	1.0	55	
0.425 mm	#40	3.4	51	
0.150 mm	#100	12.2	39	
0.075 mm	#200	9.7	29	
Pan		29.2		

Comments:

Minus #200 by wash-sieve method.

*Emily J. Rodriguez*

Report Reviewed By:

This report shall not be reproduced, except in full, without written permission from Advance Testing Company, Inc.  
The results in this report relate only to the items inspected or tested.

PDF





3348 Route 208, Campbell Hall, NY 10916

Phone: 845-496-1600 Fax: 845-496-1398

12960 Commerce Lake Drive, A14, Fort Myers, FL 33913

42 Day Farm Road, West Stockbridge, MA 01266

1813 State Route 7, Harpursville, NY 13787

877 US-4, Schuylerville, NY 12871

<b>Client:</b>	CHA, Inc.	<b>Project:</b>	John Jay Homestead Historic Site
<b>Item:</b>	B-2 S-6	<b>Project Number:</b>	240100
<b>Source:</b>	10-12'	<b>Lab Number:</b>	Q24-004C
<b>Date Sampled:</b>	1/29/2024	<b>Sampled By:</b>	Client
<b>Date Tested:</b>	1/30/2024	<b>Tested By:</b>	Michael Thomas

### GRADATION (SIEVE ANALYSIS) OF SOIL OR AGGREGATE

Test Method(s): ASTM D422, C136, C117; AASHTO T88, T27, T11

<b>Lab Number</b>	<b>Sample Type</b>	<b>Sampling Location</b>	<b>Specification</b>
Q24-004C	B-2 S-6	In-Place	No Specification

Sieve Size		% Retained	% Passing	Spec. % Pass
mm	Inches			
100.0 mm	4"	0.0	100	
75.0 mm	3"	0.0	100	
63.0 mm	2 1/2"	0.0	100	
50.0 mm	2"	0.0	100	
37.5 mm	1 1/2"	0.0	100	
25.0 mm	1"	0.0	100	
19.0 mm	3/4"	0.0	100	
12.5 mm	1/2"	4.5	96	
6.3 mm	1/4"	5.4	90	
4.75 mm	#4	0.1	90	
2.00 mm	#10	3.3	87	
0.850 mm	#20	5.9	81	
0.600 mm	#30	2.3	79	
0.425 mm	#40	6.2	72	
0.150 mm	#100	19.9	52	
0.075 mm	#200	12.4	40	
Pan		40.0		

Comments:

Minus #200 by wash-sieve method.

*Emily J. Rodriguez*

Report Reviewed By:

This report shall not be reproduced, except in full, without written permission from Advance Testing Company, Inc.  
The results in this report relate only to the items inspected or tested.

PDF





3348 Route 208, Campbell Hall, NY 10916

Phone: 845-496-1600 Fax: 845-496-1398

12960 Commerce Lake Drive, A14, Fort Myers, FL 33913

42 Day Farm Road, West Stockbridge, MA 01266

1813 State Route 7, Harpursville, NY 13787

877 US-4, Schuylerville, NY 12871

<b>Client:</b>	CHA, Inc.	<b>Project:</b>	John Jay Homestead Historic Site
<b>Item:</b>	B-3 S-4	<b>Project Number:</b>	240100
<b>Source:</b>	6-8'	<b>Lab Number:</b>	Q24-004D
<b>Date Sampled:</b>	1/29/2024	<b>Sampled By:</b>	Client
<b>Date Tested:</b>	1/30/2024	<b>Tested By:</b>	Michael Thomas

### GRADATION (SIEVE ANALYSIS) OF SOIL OR AGGREGATE

Test Method(s): ASTM D422, C136, C117; AASHTO T88, T27, T11

<b>Lab Number</b>	<b>Sample Type</b>	<b>Sampling Location</b>	<b>Specification</b>
Q24-004D	B-3 S-4	In-Place	No Specification

Sieve Size		% Retained	% Passing	Spec. % Pass
mm	Inches			
100.0 mm	4"	0.0	100	
75.0 mm	3"	0.0	100	
63.0 mm	2 1/2"	0.0	100	
50.0 mm	2"	0.0	100	
37.5 mm	1 1/2"	0.0	100	
25.0 mm	1"	0.0	100	
19.0 mm	3/4"	9.4	91	
12.5 mm	1/2"	4.5	86	
6.3 mm	1/4"	4.2	82	
4.75 mm	#4	1.6	80	
2.00 mm	#10	3.2	77	
0.850 mm	#20	5.1	72	
0.600 mm	#30	1.5	71	
0.425 mm	#40	5.3	65	
0.150 mm	#100	17.6	48	
0.075 mm	#200	14.0	34	
Pan		33.6		

Comments:

Minus #200 by wash-sieve method.

*Emily J. Rodriguez*

Report Reviewed By:

This report shall not be reproduced, except in full, without written permission from Advance Testing Company, Inc.  
The results in this report relate only to the items inspected or tested.

PDF







# APPENDIX D


Existing Condition PondPack Outputs







## Scenario: 1 year









---

**Project Summary**

---

Title	John Jay Homestead Site and Building Enhancements
Engineer	HB / JMC
Company	CHA
Date	3/20/2024

---

---

Notes	400 Jay Street Katonah, Westchester County New York
-------	---

---



## Table of Contents

	Master Network Summary	2
Time-Depth - 1		
	Time-Depth Curve, 1 years	3
	Time-Depth Curve, 10 years	5
	Time-Depth Curve, 100 years	7
DA-1		
	Time of Concentration Calculations, 1 years	9
DA-2		
	Time of Concentration Calculations, 1 years	11
DA-3		
	Time of Concentration Calculations, 1 years	13
DA-4		
	Time of Concentration Calculations, 1 years	15
DA-5		
	Time of Concentration Calculations, 1 years	17
DA-1		
	Runoff CN-Area, 1 years	19
DA-2		
	Runoff CN-Area, 1 years	20
DA-3		
	Runoff CN-Area, 1 years	21
DA-4		
	Runoff CN-Area, 1 years	22
DA-5		
	Runoff CN-Area, 1 years	23



Subsection: Master Network Summary

Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft <sup>3</sup> /s)
DA-1	1 year	1	0.329	12.140	3.71
DA-1	10 years	10	0.997	12.130	11.80
DA-1	100 years	100	2.393	12.120	27.88
DA-2	1 year	1	0.253	12.120	2.99
DA-2	10 years	10	0.766	12.110	9.40
DA-2	100 years	100	1.839	12.110	22.10
DA-3	1 year	1	0.139	12.110	1.74
DA-3	10 years	10	0.358	12.110	4.42
DA-3	100 years	100	0.784	12.100	9.29
DA-4	1 year	1	0.662	12.120	8.08
DA-4	10 years	10	1.826	12.110	22.39
DA-4	100 years	100	4.155	12.110	49.29
DA-5	1 year	1	0.135	12.120	1.66
DA-5	10 years	10	0.350	12.110	4.25
DA-5	100 years	100	0.766	12.100	8.95

Node Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft <sup>3</sup> /s)
DP-1	1 year	1	0.856	12.130	10.00
DP-1	10 years	10	2.471	12.120	29.72
DP-1	100 years	100	5.782	12.120	67.98
DP-2	1 year	1	0.662	12.120	8.08
DP-2	10 years	10	1.826	12.110	22.39
DP-2	100 years	100	4.155	12.110	49.29
J-1	1 year	1	0.464	12.130	5.35
J-1	10 years	10	1.347	12.120	16.02
J-1	100 years	100	3.159	12.110	36.77
J-2	1 year	1	0.253	12.120	2.99
J-2	10 years	10	0.766	12.110	9.40
J-2	100 years	100	1.839	12.110	22.10



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time-Depth Curve: 1 year

Label	1 year
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	1 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.0	0.0	0.0	0.0
1.000	0.0	0.0	0.0	0.0	0.0
1.500	0.0	0.0	0.0	0.1	0.1
2.000	0.1	0.1	0.1	0.1	0.1
2.500	0.1	0.1	0.1	0.1	0.1
3.000	0.1	0.1	0.1	0.1	0.1
3.500	0.1	0.1	0.1	0.1	0.1
4.000	0.1	0.1	0.1	0.1	0.1
4.500	0.1	0.1	0.1	0.2	0.2
5.000	0.2	0.2	0.2	0.2	0.2
5.500	0.2	0.2	0.2	0.2	0.2
6.000	0.2	0.2	0.2	0.2	0.2
6.500	0.2	0.2	0.2	0.2	0.2
7.000	0.3	0.3	0.3	0.3	0.3
7.500	0.3	0.3	0.3	0.3	0.3
8.000	0.3	0.3	0.3	0.3	0.4
8.500	0.4	0.4	0.4	0.4	0.4
9.000	0.4	0.4	0.4	0.4	0.5
9.500	0.5	0.5	0.5	0.5	0.5
10.000	0.5	0.5	0.6	0.6	0.6
10.500	0.6	0.6	0.6	0.7	0.7
11.000	0.7	0.7	0.7	0.8	0.8
11.500	0.8	0.9	1.0	1.0	1.2
12.000	1.4	1.6	1.8	1.8	1.9
12.500	2.0	2.0	2.0	2.1	2.1
13.000	2.1	2.1	2.1	2.2	2.2
13.500	2.2	2.2	2.2	2.2	2.3
14.000	2.3	2.3	2.3	2.3	2.3
14.500	2.3	2.3	2.4	2.4	2.4
15.000	2.4	2.4	2.4	2.4	2.4
15.500	2.4	2.4	2.5	2.5	2.5
16.000	2.5	2.5	2.5	2.5	2.5
16.500	2.5	2.5	2.5	2.5	2.5
17.000	2.5	2.6	2.6	2.6	2.6



Subsection: Time-Depth Curve  
 Label: Time-Depth - 1  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

CUMULATIVE RAINFALL (in)  
 Output Time Increment = 0.100 hours  
 Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	2.6	2.6	2.6	2.6	2.6
18.000	2.6	2.6	2.6	2.6	2.6
18.500	2.6	2.6	2.6	2.6	2.6
19.000	2.6	2.6	2.6	2.7	2.7
19.500	2.7	2.7	2.7	2.7	2.7
20.000	2.7	2.7	2.7	2.7	2.7
20.500	2.7	2.7	2.7	2.7	2.7
21.000	2.7	2.7	2.7	2.7	2.7
21.500	2.7	2.7	2.7	2.7	2.7
22.000	2.7	2.7	2.8	2.8	2.8
22.500	2.8	2.8	2.8	2.8	2.8
23.000	2.8	2.8	2.8	2.8	2.8
23.500	2.8	2.8	2.8	2.8	2.8
24.000	2.8	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 10 years

Return Event: 10 years

Storm Event: 10 years - type 3

Time-Depth Curve: 10 years - type 3

Label	10 years - type 3
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	10 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.0	0.0	0.0	0.0
1.000	0.1	0.1	0.1	0.1	0.1
1.500	0.1	0.1	0.1	0.1	0.1
2.000	0.1	0.1	0.1	0.1	0.1
2.500	0.1	0.1	0.1	0.1	0.2
3.000	0.2	0.2	0.2	0.2	0.2
3.500	0.2	0.2	0.2	0.2	0.2
4.000	0.2	0.2	0.2	0.2	0.2
4.500	0.3	0.3	0.3	0.3	0.3
5.000	0.3	0.3	0.3	0.3	0.3
5.500	0.3	0.3	0.3	0.4	0.4
6.000	0.4	0.4	0.4	0.4	0.4
6.500	0.4	0.4	0.4	0.4	0.5
7.000	0.5	0.5	0.5	0.5	0.5
7.500	0.5	0.5	0.5	0.6	0.6
8.000	0.6	0.6	0.6	0.6	0.6
8.500	0.7	0.7	0.7	0.7	0.7
9.000	0.7	0.8	0.8	0.8	0.8
9.500	0.8	0.9	0.9	0.9	0.9
10.000	1.0	1.0	1.0	1.0	1.1
10.500	1.1	1.1	1.2	1.2	1.2
11.000	1.3	1.3	1.4	1.4	1.5
11.500	1.5	1.6	1.7	1.9	2.1
12.000	2.5	3.0	3.2	3.4	3.5
12.500	3.6	3.6	3.7	3.7	3.8
13.000	3.8	3.9	3.9	3.9	4.0
13.500	4.0	4.0	4.0	4.1	4.1
14.000	4.1	4.2	4.2	4.2	4.2
14.500	4.2	4.3	4.3	4.3	4.3
15.000	4.3	4.4	4.4	4.4	4.4
15.500	4.4	4.5	4.5	4.5	4.5
16.000	4.5	4.5	4.5	4.5	4.6
16.500	4.6	4.6	4.6	4.6	4.6
17.000	4.6	4.6	4.7	4.7	4.7



Subsection: Time-Depth Curve  
 Label: Time-Depth - 1  
 Scenario: 10 years

Return Event: 10 years  
 Storm Event: 10 years - type 3

CUMULATIVE RAINFALL (in)  
 Output Time Increment = 0.100 hours  
 Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	4.7	4.7	4.7	4.7	4.7
18.000	4.7	4.7	4.7	4.7	4.8
18.500	4.8	4.8	4.8	4.8	4.8
19.000	4.8	4.8	4.8	4.8	4.8
19.500	4.8	4.8	4.9	4.9	4.9
20.000	4.9	4.9	4.9	4.9	4.9
20.500	4.9	4.9	4.9	4.9	4.9
21.000	4.9	4.9	4.9	5.0	5.0
21.500	5.0	5.0	5.0	5.0	5.0
22.000	5.0	5.0	5.0	5.0	5.0
22.500	5.0	5.0	5.0	5.0	5.0
23.000	5.0	5.0	5.1	5.1	5.1
23.500	5.1	5.1	5.1	5.1	5.1
24.000	5.1	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 100 years

Return Event: 100 years

Storm Event: 100 years - type 3

Time-Depth Curve: 100 years - type 3

Label	100 years - type 3
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	100 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.1	0.1	0.1	0.1
1.000	0.1	0.1	0.1	0.1	0.1
1.500	0.1	0.1	0.2	0.2	0.2
2.000	0.2	0.2	0.2	0.2	0.2
2.500	0.2	0.2	0.2	0.3	0.3
3.000	0.3	0.3	0.3	0.3	0.3
3.500	0.3	0.3	0.4	0.4	0.4
4.000	0.4	0.4	0.4	0.4	0.4
4.500	0.5	0.5	0.5	0.5	0.5
5.000	0.5	0.5	0.5	0.6	0.6
5.500	0.6	0.6	0.6	0.6	0.6
6.000	0.7	0.7	0.7	0.7	0.7
6.500	0.7	0.8	0.8	0.8	0.8
7.000	0.8	0.8	0.9	0.9	0.9
7.500	0.9	0.9	1.0	1.0	1.0
8.000	1.0	1.1	1.1	1.1	1.1
8.500	1.2	1.2	1.2	1.3	1.3
9.000	1.3	1.4	1.4	1.4	1.5
9.500	1.5	1.6	1.6	1.6	1.7
10.000	1.7	1.8	1.8	1.9	1.9
10.500	2.0	2.0	2.1	2.1	2.2
11.000	2.3	2.3	2.4	2.5	2.6
11.500	2.7	2.9	3.1	3.4	3.8
12.000	4.6	5.3	5.7	6.0	6.2
12.500	6.4	6.5	6.6	6.7	6.8
13.000	6.8	6.9	7.0	7.0	7.1
13.500	7.1	7.2	7.2	7.3	7.3
14.000	7.4	7.4	7.5	7.5	7.6
14.500	7.6	7.6	7.7	7.7	7.7
15.000	7.8	7.8	7.8	7.9	7.9
15.500	7.9	8.0	8.0	8.0	8.0
16.000	8.1	8.1	8.1	8.1	8.2
16.500	8.2	8.2	8.2	8.2	8.3
17.000	8.3	8.3	8.3	8.3	8.4



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 100 years

Return Event: 100 years

Storm Event: 100 years - type 3

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	8.4	8.4	8.4	8.4	8.4
18.000	8.5	8.5	8.5	8.5	8.5
18.500	8.5	8.5	8.6	8.6	8.6
19.000	8.6	8.6	8.6	8.6	8.6
19.500	8.7	8.7	8.7	8.7	8.7
20.000	8.7	8.7	8.7	8.8	8.8
20.500	8.8	8.8	8.8	8.8	8.8
21.000	8.8	8.8	8.9	8.9	8.9
21.500	8.9	8.9	8.9	8.9	8.9
22.000	8.9	8.9	9.0	9.0	9.0
22.500	9.0	9.0	9.0	9.0	9.0
23.000	9.0	9.0	9.0	9.1	9.1
23.500	9.1	9.1	9.1	9.1	9.1
24.000	9.1	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time of Concentration Calculations

Label: DA-1

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	100.00 ft
Manning's n	0.240
Slope	0.120 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.25 ft/s
Segment Time of Concentration	0.113 hours

---

---

Segment #2: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	120.00 ft
Is Paved?	False
Slope	0.058 ft/ft
Average Velocity	3.89 ft/s
Segment Time of Concentration	0.009 hours

---

---

Segment #3: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	266.00 ft
Is Paved?	False
Slope	0.109 ft/ft
Average Velocity	5.33 ft/s
Segment Time of Concentration	0.014 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.135 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations

Label: DA-1

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-2

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	47.00 ft
Manning's n	0.240
Slope	0.085 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.18 ft/s
Segment Time of Concentration	0.071 hours

---

---

Segment #2: TR-55 Sheet Flow

---

Hydraulic Length	53.00 ft
Manning's n	0.011
Slope	0.038 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	1.61 ft/s
Segment Time of Concentration	0.009 hours

---

---

Segment #3: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	361.00 ft
Is Paved?	False
Slope	0.061 ft/ft
Average Velocity	3.98 ft/s
Segment Time of Concentration	0.025 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.105 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations

Label: DA-2

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-3

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations

Label: DA-4

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

Segment #1: TR-55 Sheet Flow	
Hydraulic Length	15.00 ft
Manning's n	0.011
Slope	0.067 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	1.57 ft/s
Segment Time of Concentration	0.003 hours
Segment #2: TR-55 Sheet Flow	
Hydraulic Length	85.00 ft
Manning's n	0.150
Slope	0.106 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.33 ft/s
Segment Time of Concentration	0.071 hours
Segment #3: TR-55 Shallow Concentrated Flow	
Hydraulic Length	108.00 ft
Is Paved?	False
Slope	0.056 ft/ft
Average Velocity	3.82 ft/s
Segment Time of Concentration	0.008 hours
Segment #4: TR-55 Shallow Concentrated Flow	
Hydraulic Length	229.00 ft
Is Paved?	False
Slope	0.039 ft/ft
Average Velocity	3.19 ft/s
Segment Time of Concentration	0.020 hours
Time of Concentration (Composite)	
Time of Concentration (Composite)	0.102 hours



Subsection: Time of Concentration Calculations

Label: DA-4

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-5

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	100.00 ft
Manning's n	0.150
Slope	0.070 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.29 ft/s
Segment Time of Concentration	0.096 hours

---

---

Segment #2: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	112.00 ft
Is Paved?	True
Slope	0.054 ft/ft
Average Velocity	4.72 ft/s
Segment Time of Concentration	0.007 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.103 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations

Label: DA-5

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Runoff CN-Area  
 Label: DA-1  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

# Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	4.540	0.0	0.0	74.000
Woods - Good Cond, HSG C	70.000	0.090	0.0	0.0	70.000
Impervious	98.000	0.120	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	4.750	(N/A)	(N/A)	74.531



Subsection: Runoff CN-Area  
Label: DA-2  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	3.470	0.0	0.0	74.000
Impervious	98.000	0.180	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	3.650	(N/A)	(N/A)	75.184



Subsection: Runoff CN-Area  
Label: DA-3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	0.890	0.0	0.0	74.000
Impervious	98.000	0.470	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.360	(N/A)	(N/A)	82.294



Subsection: Runoff CN-Area  
Label: DA-4  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	4.240	0.0	0.0	74.000
Woods - Good Cond, HSG C	70.000	1.620	0.0	0.0	70.000
Impervious	98.000	1.760	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	7.620	(N/A)	(N/A)	78.693



Subsection: Runoff CN-Area  
Label: DA-5  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	0.860	0.0	0.0	74.000
Impervious	98.000	0.470	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.330	(N/A)	(N/A)	82.481



## Index

### D

DA-1 (Runoff CN-Area, 1 years (1 year))...19

DA-1 (Runoff CN-Area, 1 years)...

DA-1 (Time of Concentration Calculations, 1 years (1 year))...9, 10

DA-1 (Time of Concentration Calculations, 1 years)...

DA-2 (Runoff CN-Area, 1 years (1 year))...20

DA-2 (Runoff CN-Area, 1 years)...

DA-2 (Time of Concentration Calculations, 1 years (1 year))...11, 12

DA-2 (Time of Concentration Calculations, 1 years)...

DA-3 (Runoff CN-Area, 1 years (1 year))...21

DA-3 (Runoff CN-Area, 1 years)...

DA-3 (Time of Concentration Calculations, 1 years (1 year))...13, 14

DA-3 (Time of Concentration Calculations, 1 years)...

DA-4 (Runoff CN-Area, 1 years (1 year))...22

DA-4 (Runoff CN-Area, 1 years)...

DA-4 (Time of Concentration Calculations, 1 years (1 year))...15, 16

DA-4 (Time of Concentration Calculations, 1 years)...

DA-5 (Runoff CN-Area, 1 years (1 year))...23

DA-5 (Runoff CN-Area, 1 years)...

DA-5 (Time of Concentration Calculations, 1 years (1 year))...17, 18

DA-5 (Time of Concentration Calculations, 1 years)...

### M

Master Network Summary...2

### T

Time-Depth - 1 (Time-Depth Curve, 1 years (1 year))...3, 4

Time-Depth - 1 (Time-Depth Curve, 1 years)...

Time-Depth - 1 (Time-Depth Curve, 10 years (10 years))...5, 6

Time-Depth - 1 (Time-Depth Curve, 10 years)...

Time-Depth - 1 (Time-Depth Curve, 100 years (100 years))...7, 8

Time-Depth - 1 (Time-Depth Curve, 100 years)...







# APPENDIX E


Proposed Condition PondPack Outputs







## Scenario: 1 year





---

**Project Summary**

---

Title	John Jay Homestead Site and Building Enhancements
Engineer	HB / JMC
Company	CHA
Date	3/20/2024

---

---

Notes	400 Jay Street Katonah, Westchester County New York
-------	---

---



## Table of Contents

	Master Network Summary	2
Time-Depth - 1		
	Time-Depth Curve, 1 years	4
	Time-Depth Curve, 10 years	6
	Time-Depth Curve, 100 years	8
DA-1A		
	Time of Concentration Calculations, 1 years	10
DA-1B		
	Time of Concentration Calculations, 1 years	12
DA-1C		
	Time of Concentration Calculations, 1 years	14
DA-1D		
	Time of Concentration Calculations, 1 years	16
DA-2A		
	Time of Concentration Calculations, 1 years	18
DA-2B		
	Time of Concentration Calculations, 1 years	20
DA-3		
	Time of Concentration Calculations, 1 years	22
DA-4		
	Time of Concentration Calculations, 1 years	24
DA-5A		
	Time of Concentration Calculations, 1 years	26
DA-5B		
	Time of Concentration Calculations, 1 years	28
DA-1A		
	Runoff CN-Area, 1 years	30
DA-1B		
	Runoff CN-Area, 1 years	31
DA-1C		
	Runoff CN-Area, 1 years	32
DA-1D		
	Runoff CN-Area, 1 years	33



## Table of Contents

DA-2A	Runoff CN-Area, 1 years	34
DA-2B	Runoff CN-Area, 1 years	35
DA-3	Runoff CN-Area, 1 years	36
DA-4	Runoff CN-Area, 1 years	37
DA-5A	Runoff CN-Area, 1 years	38
DA-5B	Runoff CN-Area, 1 years	39



## Subsection: Master Network Summary

### Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft <sup>3</sup> /s)
DA-1A	1 year	1	0.195	12.110	2.45
DA-1A	10 years	10	0.503	12.110	6.20
DA-1A	100 years	100	1.101	12.100	13.04
DA-1C	1 year	1	0.101	12.130	1.15
DA-1C	10 years	10	0.298	12.130	3.52
DA-1C	100 years	100	0.704	12.120	8.19
DA-1D	1 year	1	0.099	12.120	1.18
DA-1D	10 years	10	0.306	12.110	3.83
DA-1D	100 years	100	0.745	12.100	9.09
DA-2A	1 year	1	0.186	12.120	2.24
DA-2A	10 years	10	0.550	12.110	6.78
DA-2A	100 years	100	1.301	12.110	15.64
DA-2B	1 year	1	0.054	12.110	0.68
DA-2B	10 years	10	0.139	12.110	1.72
DA-2B	100 years	100	0.305	12.100	3.62
DA-3	1 year	1	0.159	12.110	2.00
DA-3	10 years	10	0.394	12.100	4.82
DA-3	100 years	100	0.841	12.100	9.86
DA-4	1 year	1	0.591	12.120	7.11
DA-4	10 years	10	1.707	12.110	20.93
DA-4	100 years	100	3.987	12.110	47.58
DA-5A	1 year	1	0.078	12.110	0.96
DA-5A	10 years	10	0.203	12.110	2.46
DA-5A	100 years	100	0.444	12.110	5.18
DA-5B	1 year	1	0.052	12.110	0.66
DA-5B	10 years	10	0.141	12.110	1.75
DA-5B	100 years	100	0.317	12.100	3.79
DA-1B	1 year	1	0.058	12.110	0.73
DA-1B	10 years	10	0.153	12.110	1.90
DA-1B	100 years	100	0.340	12.100	4.04

### Node Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft <sup>3</sup> /s)
BIO 1	1 year	1	0.371	12.110	4.59
BIO 1	10 years	10	1.011	12.110	12.49
BIO 1	100 years	100	2.290	12.100	27.31
BIO 3	1 year	1	0.240	12.120	2.91
BIO 3	10 years	10	0.689	12.110	8.50
BIO 3	100 years	100	1.607	12.110	19.25
DP-1	1 year	1	0.981	12.130	11.93
DP-1	10 years	10	2.685	12.120	32.81
DP-1	100 years	100	6.097	12.120	72.17



Subsection: Master Network Summary

Node Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft <sup>3</sup> /s)
DP-2	1 year	1	0.591	12.120	7.11
DP-2	10 years	10	1.707	12.110	20.93
DP-2	100 years	100	3.987	12.110	47.58
BIO 2	1 year	1	0.211	12.120	2.51
BIO 2	10 years	10	0.592	12.110	7.15
BIO 2	100 years	100	1.361	12.110	15.99
J-1	1 year	1	0.582	12.120	7.10
J-1	10 years	10	1.603	12.120	19.64
J-1	100 years	100	3.650	12.120	43.27



Subsection: Time-Depth Curve  
Label: Time-Depth - 1  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Time-Depth Curve: 1 year

Label	1 year
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	1 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.0	0.0	0.0	0.0
1.000	0.0	0.0	0.0	0.0	0.0
1.500	0.0	0.0	0.0	0.1	0.1
2.000	0.1	0.1	0.1	0.1	0.1
2.500	0.1	0.1	0.1	0.1	0.1
3.000	0.1	0.1	0.1	0.1	0.1
3.500	0.1	0.1	0.1	0.1	0.1
4.000	0.1	0.1	0.1	0.1	0.1
4.500	0.1	0.1	0.1	0.2	0.2
5.000	0.2	0.2	0.2	0.2	0.2
5.500	0.2	0.2	0.2	0.2	0.2
6.000	0.2	0.2	0.2	0.2	0.2
6.500	0.2	0.2	0.2	0.2	0.2
7.000	0.3	0.3	0.3	0.3	0.3
7.500	0.3	0.3	0.3	0.3	0.3
8.000	0.3	0.3	0.3	0.3	0.4
8.500	0.4	0.4	0.4	0.4	0.4
9.000	0.4	0.4	0.4	0.4	0.5
9.500	0.5	0.5	0.5	0.5	0.5
10.000	0.5	0.5	0.6	0.6	0.6
10.500	0.6	0.6	0.6	0.7	0.7
11.000	0.7	0.7	0.7	0.8	0.8
11.500	0.8	0.9	1.0	1.0	1.2
12.000	1.4	1.6	1.8	1.8	1.9
12.500	2.0	2.0	2.0	2.1	2.1
13.000	2.1	2.1	2.1	2.2	2.2
13.500	2.2	2.2	2.2	2.2	2.3
14.000	2.3	2.3	2.3	2.3	2.3
14.500	2.3	2.3	2.4	2.4	2.4
15.000	2.4	2.4	2.4	2.4	2.4
15.500	2.4	2.4	2.5	2.5	2.5
16.000	2.5	2.5	2.5	2.5	2.5
16.500	2.5	2.5	2.5	2.5	2.5
17.000	2.5	2.6	2.6	2.6	2.6



Subsection: Time-Depth Curve  
 Label: Time-Depth - 1  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

CUMULATIVE RAINFALL (in)  
 Output Time Increment = 0.100 hours  
 Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	2.6	2.6	2.6	2.6	2.6
18.000	2.6	2.6	2.6	2.6	2.6
18.500	2.6	2.6	2.6	2.6	2.6
19.000	2.6	2.6	2.6	2.7	2.7
19.500	2.7	2.7	2.7	2.7	2.7
20.000	2.7	2.7	2.7	2.7	2.7
20.500	2.7	2.7	2.7	2.7	2.7
21.000	2.7	2.7	2.7	2.7	2.7
21.500	2.7	2.7	2.7	2.7	2.7
22.000	2.7	2.7	2.8	2.8	2.8
22.500	2.8	2.8	2.8	2.8	2.8
23.000	2.8	2.8	2.8	2.8	2.8
23.500	2.8	2.8	2.8	2.8	2.8
24.000	2.8	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time-Depth Curve  
Label: Time-Depth - 1  
Scenario: 10 years

Return Event: 10 years  
Storm Event: 10 years - type 3

Time-Depth Curve: 10 years - type 3

Label	10 years - type 3
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	10 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.0	0.0	0.0	0.0
1.000	0.1	0.1	0.1	0.1	0.1
1.500	0.1	0.1	0.1	0.1	0.1
2.000	0.1	0.1	0.1	0.1	0.1
2.500	0.1	0.1	0.1	0.1	0.2
3.000	0.2	0.2	0.2	0.2	0.2
3.500	0.2	0.2	0.2	0.2	0.2
4.000	0.2	0.2	0.2	0.2	0.2
4.500	0.3	0.3	0.3	0.3	0.3
5.000	0.3	0.3	0.3	0.3	0.3
5.500	0.3	0.3	0.3	0.4	0.4
6.000	0.4	0.4	0.4	0.4	0.4
6.500	0.4	0.4	0.4	0.4	0.5
7.000	0.5	0.5	0.5	0.5	0.5
7.500	0.5	0.5	0.5	0.6	0.6
8.000	0.6	0.6	0.6	0.6	0.6
8.500	0.7	0.7	0.7	0.7	0.7
9.000	0.7	0.8	0.8	0.8	0.8
9.500	0.8	0.9	0.9	0.9	0.9
10.000	1.0	1.0	1.0	1.0	1.1
10.500	1.1	1.1	1.2	1.2	1.2
11.000	1.3	1.3	1.4	1.4	1.5
11.500	1.5	1.6	1.7	1.9	2.1
12.000	2.5	3.0	3.2	3.4	3.5
12.500	3.6	3.6	3.7	3.7	3.8
13.000	3.8	3.9	3.9	3.9	4.0
13.500	4.0	4.0	4.0	4.1	4.1
14.000	4.1	4.2	4.2	4.2	4.2
14.500	4.2	4.3	4.3	4.3	4.3
15.000	4.3	4.4	4.4	4.4	4.4
15.500	4.4	4.5	4.5	4.5	4.5
16.000	4.5	4.5	4.5	4.5	4.6
16.500	4.6	4.6	4.6	4.6	4.6
17.000	4.6	4.6	4.7	4.7	4.7



Subsection: Time-Depth Curve  
 Label: Time-Depth - 1  
 Scenario: 10 years

Return Event: 10 years  
 Storm Event: 10 years - type 3

CUMULATIVE RAINFALL (in)  
 Output Time Increment = 0.100 hours  
 Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	4.7	4.7	4.7	4.7	4.7
18.000	4.7	4.7	4.7	4.7	4.8
18.500	4.8	4.8	4.8	4.8	4.8
19.000	4.8	4.8	4.8	4.8	4.8
19.500	4.8	4.8	4.9	4.9	4.9
20.000	4.9	4.9	4.9	4.9	4.9
20.500	4.9	4.9	4.9	4.9	4.9
21.000	4.9	4.9	4.9	5.0	5.0
21.500	5.0	5.0	5.0	5.0	5.0
22.000	5.0	5.0	5.0	5.0	5.0
22.500	5.0	5.0	5.0	5.0	5.0
23.000	5.0	5.0	5.1	5.1	5.1
23.500	5.1	5.1	5.1	5.1	5.1
24.000	5.1	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 100 years

Return Event: 100 years

Storm Event: 100 years - type 3

Time-Depth Curve: 100 years - type 3

Label	100 years - type 3
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	100 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.1	0.1	0.1	0.1
1.000	0.1	0.1	0.1	0.1	0.1
1.500	0.1	0.1	0.2	0.2	0.2
2.000	0.2	0.2	0.2	0.2	0.2
2.500	0.2	0.2	0.2	0.3	0.3
3.000	0.3	0.3	0.3	0.3	0.3
3.500	0.3	0.3	0.4	0.4	0.4
4.000	0.4	0.4	0.4	0.4	0.4
4.500	0.5	0.5	0.5	0.5	0.5
5.000	0.5	0.5	0.5	0.6	0.6
5.500	0.6	0.6	0.6	0.6	0.6
6.000	0.7	0.7	0.7	0.7	0.7
6.500	0.7	0.8	0.8	0.8	0.8
7.000	0.8	0.8	0.9	0.9	0.9
7.500	0.9	0.9	1.0	1.0	1.0
8.000	1.0	1.1	1.1	1.1	1.1
8.500	1.2	1.2	1.2	1.3	1.3
9.000	1.3	1.4	1.4	1.4	1.5
9.500	1.5	1.6	1.6	1.6	1.7
10.000	1.7	1.8	1.8	1.9	1.9
10.500	2.0	2.0	2.1	2.1	2.2
11.000	2.3	2.3	2.4	2.5	2.6
11.500	2.7	2.9	3.1	3.4	3.8
12.000	4.6	5.3	5.7	6.0	6.2
12.500	6.4	6.5	6.6	6.7	6.8
13.000	6.8	6.9	7.0	7.0	7.1
13.500	7.1	7.2	7.2	7.3	7.3
14.000	7.4	7.4	7.5	7.5	7.6
14.500	7.6	7.6	7.7	7.7	7.7
15.000	7.8	7.8	7.8	7.9	7.9
15.500	7.9	8.0	8.0	8.0	8.0
16.000	8.1	8.1	8.1	8.1	8.2
16.500	8.2	8.2	8.2	8.2	8.3
17.000	8.3	8.3	8.3	8.3	8.4



Subsection: Time-Depth Curve  
 Label: Time-Depth - 1  
 Scenario: 100 years

Return Event: 100 years  
 Storm Event: 100 years - type 3

CUMULATIVE RAINFALL (in)  
 Output Time Increment = 0.100 hours  
 Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	8.4	8.4	8.4	8.4	8.4
18.000	8.5	8.5	8.5	8.5	8.5
18.500	8.5	8.5	8.6	8.6	8.6
19.000	8.6	8.6	8.6	8.6	8.6
19.500	8.7	8.7	8.7	8.7	8.7
20.000	8.7	8.7	8.7	8.8	8.8
20.500	8.8	8.8	8.8	8.8	8.8
21.000	8.8	8.8	8.9	8.9	8.9
21.500	8.9	8.9	8.9	8.9	8.9
22.000	8.9	8.9	9.0	9.0	9.0
22.500	9.0	9.0	9.0	9.0	9.0
23.000	9.0	9.0	9.0	9.1	9.1
23.500	9.1	9.1	9.1	9.1	9.1
24.000	9.1	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time of Concentration Calculations

Label: DA-1A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-1A  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations

Label: DA-1B

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-1B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations  
Label: DA-1C  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	100.00 ft
Manning's n	0.150
Slope	0.040 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.23 ft/s
Segment Time of Concentration	0.120 hours

---

---

Segment #2: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	213.00 ft
Is Paved?	False
Slope	0.066 ft/ft
Average Velocity	4.15 ft/s
Segment Time of Concentration	0.014 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.134 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-1C  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:  $(L_f / V) / 3600$   
R= Hydraulic radius  
A<sub>q</sub>= Flow area, square feet  
W<sub>p</sub>= Wetted perimeter, feet  
V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
n= Manning's n  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:  $(L_f / V) / 3600$   
V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-1D

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

Segment #1: TR-55 Sheet Flow

Hydraulic Length	100.00 ft
Manning's n	0.150
Slope	0.120 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.36 ft/s
Segment Time of Concentration	0.077 hours

Segment #2: TR-55 Shallow Concentrated Flow

Hydraulic Length	120.00 ft
Is Paved?	False
Slope	0.058 ft/ft
Average Velocity	3.89 ft/s
Segment Time of Concentration	0.009 hours

Segment #3: TR-55 Shallow Concentrated Flow

Hydraulic Length	40.00 ft
Is Paved?	False
Slope	0.100 ft/ft
Average Velocity	5.10 ft/s
Segment Time of Concentration	0.002 hours

Time of Concentration (Composite)

Time of Concentration (Composite)	0.088 hours
-----------------------------------	-------------



Subsection: Time of Concentration Calculations

Label: DA-1D

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-2A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	45.00 ft
Manning's n	0.240
Slope	0.089 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.19 ft/s
Segment Time of Concentration	0.067 hours

---

---

Segment #2: TR-55 Sheet Flow

---

Hydraulic Length	55.00 ft
Manning's n	0.011
Slope	0.018 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	1.21 ft/s
Segment Time of Concentration	0.013 hours

---

---

Segment #3: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	278.00 ft
Is Paved?	False
Slope	0.065 ft/ft
Average Velocity	4.11 ft/s
Segment Time of Concentration	0.019 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.098 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations

Label: DA-2A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
A<sub>q</sub>= Flow area, square feet  
W<sub>p</sub>= Wetted perimeter, feet  
V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
n= Manning's n  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-2B

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-2B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations

Label: DA-3

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations

Label: DA-4

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

Segment #1: TR-55 Sheet Flow	
Hydraulic Length	15.00 ft
Manning's n	0.011
Slope	0.067 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	1.57 ft/s
Segment Time of Concentration	0.003 hours
Segment #2: TR-55 Sheet Flow	
Hydraulic Length	85.00 ft
Manning's n	0.150
Slope	0.106 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.33 ft/s
Segment Time of Concentration	0.071 hours
Segment #3: TR-55 Shallow Concentrated Flow	
Hydraulic Length	125.00 ft
Is Paved?	False
Slope	0.056 ft/ft
Average Velocity	3.82 ft/s
Segment Time of Concentration	0.009 hours
Segment #4: TR-55 Shallow Concentrated Flow	
Hydraulic Length	229.00 ft
Is Paved?	False
Slope	0.035 ft/ft
Average Velocity	3.02 ft/s
Segment Time of Concentration	0.021 hours
Time of Concentration (Composite)	
Time of Concentration (Composite)	0.104 hours



Subsection: Time of Concentration Calculations

Label: DA-4

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
A<sub>q</sub>= Flow area, square feet  
W<sub>p</sub>= Wetted perimeter, feet  
V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
n= Manning's n  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-5A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	100.00 ft
Manning's n	0.150
Slope	0.070 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.29 ft/s
Segment Time of Concentration	0.096 hours

---

---

Segment #2: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	112.00 ft
Is Paved?	False
Slope	0.054 ft/ft
Average Velocity	3.75 ft/s
Segment Time of Concentration	0.008 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.104 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-5A  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:  $(L_f / V) / 3600$   
R= Hydraulic radius  
A<sub>q</sub>= Flow area, square feet  
W<sub>p</sub>= Wetted perimeter, feet  
V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
n= Manning's n  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:  $(L_f / V) / 3600$   
V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-5B

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-5B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Runoff CN-Area  
 Label: DA-1A  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

# Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	1.310	0.0	0.0	74.000
Asphalt	98.000	0.600	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.910	(N/A)	(N/A)	81.539



Subsection: Runoff CN-Area  
Label: DA-1B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open Space - Good Cond - HSG C	74.000	0.420	0.0	0.0	74.000
Asphalt	98.000	0.180	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	0.600	(N/A)	(N/A)	81.200



Subsection: Runoff CN-Area  
Label: DA-1C  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Impervious	98.000	0.110	0.0	0.0	98.000
Grass - Good Cond, HSG C	74.000	1.260	0.0	0.0	74.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.370	(N/A)	(N/A)	75.927



Subsection: Runoff CN-Area  
Label: DA-1D  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	1.380	0.0	0.0	74.000
Woods - Good Cond, HSG C	70.000	0.090	0.0	0.0	70.000
Impervious	98.000	0.040	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.510	(N/A)	(N/A)	74.397



Subsection: Runoff CN-Area  
Label: DA-2A  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	2.300	0.0	0.0	74.000
Impervious	98.000	0.230	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	2.530	(N/A)	(N/A)	76.182



Subsection: Runoff CN-Area  
Label: DA-2B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Impervious	98.000	0.180	0.0	0.0	98.000
Open Space - Good Cond - HSG C	74.000	0.350	0.0	0.0	74.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	0.530	(N/A)	(N/A)	82.151



Subsection: Runoff CN-Area  
Label: DA-3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	0.820	0.0	0.0	74.000
Impervious	98.000	0.590	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.410	(N/A)	(N/A)	84.043



Subsection: Runoff CN-Area  
Label: DA-4  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	4.890	0.0	0.0	74.000
Woods - Good Cond, HSG C	70.000	1.610	0.0	0.0	70.000
Impervious	98.000	1.100	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	7.600	(N/A)	(N/A)	76.626



Subsection: Runoff CN-Area  
Label: DA-5A  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	0.500	0.0	0.0	74.000
Impervious	98.000	0.270	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	0.770	(N/A)	(N/A)	82.416



Subsection: Runoff CN-Area  
Label: DA-5B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	0.430	0.0	0.0	74.000
Impervious	98.000	0.140	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	0.570	(N/A)	(N/A)	79.895



## Index

### D

DA-1A (Runoff CN-Area, 1 years (1 year))...30

DA-1A (Runoff CN-Area, 1 years)...

DA-1A (Time of Concentration Calculations, 1 years (1 year))...10, 11

DA-1A (Time of Concentration Calculations, 1 years)...

DA-1B (Runoff CN-Area, 1 years (1 year))...31

DA-1B (Runoff CN-Area, 1 years)...

DA-1B (Time of Concentration Calculations, 1 years (1 year))...12, 13

DA-1B (Time of Concentration Calculations, 1 years)...

DA-1C (Runoff CN-Area, 1 years (1 year))...32

DA-1C (Runoff CN-Area, 1 years)...

DA-1C (Time of Concentration Calculations, 1 years (1 year))...14, 15

DA-1C (Time of Concentration Calculations, 1 years)...

DA-1D (Runoff CN-Area, 1 years (1 year))...33

DA-1D (Runoff CN-Area, 1 years)...

DA-1D (Time of Concentration Calculations, 1 years (1 year))...16, 17

DA-1D (Time of Concentration Calculations, 1 years)...

DA-2A (Runoff CN-Area, 1 years (1 year))...34

DA-2A (Runoff CN-Area, 1 years)...

DA-2A (Time of Concentration Calculations, 1 years (1 year))...18, 19

DA-2A (Time of Concentration Calculations, 1 years)...

DA-2B (Runoff CN-Area, 1 years (1 year))...35

DA-2B (Runoff CN-Area, 1 years)...

DA-2B (Time of Concentration Calculations, 1 years (1 year))...20, 21

DA-2B (Time of Concentration Calculations, 1 years)...

DA-3 (Runoff CN-Area, 1 years (1 year))...36

DA-3 (Runoff CN-Area, 1 years)...

DA-3 (Time of Concentration Calculations, 1 years (1 year))...22, 23

DA-3 (Time of Concentration Calculations, 1 years)...

DA-4 (Runoff CN-Area, 1 years (1 year))...37

DA-4 (Runoff CN-Area, 1 years)...



DA-4 (Time of Concentration Calculations, 1 years (1 year))...24, 25

DA-4 (Time of Concentration Calculations, 1 years)...

DA-5A (Runoff CN-Area, 1 years (1 year))...38

DA-5A (Runoff CN-Area, 1 years)...

DA-5A (Time of Concentration Calculations, 1 years (1 year))...26, 27

DA-5A (Time of Concentration Calculations, 1 years)...

DA-5B (Runoff CN-Area, 1 years (1 year))...39

DA-5B (Runoff CN-Area, 1 years)...

DA-5B (Time of Concentration Calculations, 1 years (1 year))...28, 29

DA-5B (Time of Concentration Calculations, 1 years)...

M

Master Network Summary...2, 3

T

Time-Depth - 1 (Time-Depth Curve, 1 years (1 year))...4, 5

Time-Depth - 1 (Time-Depth Curve, 1 years)...

Time-Depth - 1 (Time-Depth Curve, 10 years (10 years))...6, 7

Time-Depth - 1 (Time-Depth Curve, 10 years)...

Time-Depth - 1 (Time-Depth Curve, 100 years (100 years))...8, 9

Time-Depth - 1 (Time-Depth Curve, 100 years)...



# APPENDIX F


Proposed Mitigated Condition PondPack Outputs







Scenario: 1 year









---

**Project Summary**

---

Title	John Jay Homestead Site and Building Enhancements
Engineer	HB / JMC
Company	CHA
Date	5/9/2024

---

---

Notes	400 Jay Street Katonah, Westchester County New York
-------	---

---



## Table of Contents

	Master Network Summary	2
Time-Depth - 1		
	Time-Depth Curve, 1 years	4
	Time-Depth Curve, 10 years	6
	Time-Depth Curve, 100 years	8
DA-1A		
	Time of Concentration Calculations, 1 years	10
DA-1B		
	Time of Concentration Calculations, 1 years	12
DA-1C		
	Time of Concentration Calculations, 1 years	14
DA-1D		
	Time of Concentration Calculations, 1 years	16
DA-2A		
	Time of Concentration Calculations, 1 years	18
DA-2B		
	Time of Concentration Calculations, 1 years	20
DA-3		
	Time of Concentration Calculations, 1 years	22
DA-4		
	Time of Concentration Calculations, 1 years	24
DA-5A		
	Time of Concentration Calculations, 1 years	26
DA-5B		
	Time of Concentration Calculations, 1 years	28
DA-1A		
	Runoff CN-Area, 1 years	30
DA-1B		
	Runoff CN-Area, 1 years	31
DA-1C		
	Runoff CN-Area, 1 years	32
DA-1D		
	Runoff CN-Area, 1 years	33
DA-2A		



## Table of Contents

	Runoff CN-Area, 1 years	34
DA-2B		
	Runoff CN-Area, 1 years	35
DA-3		
	Runoff CN-Area, 1 years	36
DA-4		
	Runoff CN-Area, 1 years	37
DA-5A		
	Runoff CN-Area, 1 years	38
DA-5B		
	Runoff CN-Area, 1 years	39
BIO 1		
	Elevation-Area Volume Curve, 1 years	40
BIO 2		
	Elevation-Area Volume Curve, 1 years	41
BIO 3		
	Elevation-Area Volume Curve, 1 years	42
DRY POND 1		
	Elevation-Area Volume Curve, 1 years	43
DRY POND 2		
	Elevation-Area Volume Curve, 1 years	44
BIO 1 UD OUTLET		
	Outlet Input Data, 1 years	45
BIO 2 UD OUTLET		
	Outlet Input Data, 1 years	47
BIO 3 (IN)		
	Multiple Outfall Rating Curves, 1 years	49
BIO 3 UD OUTLET		
	Outlet Input Data, 1 years	50
	Composite Rating Curve, 1 years	52
Composite Outlet Structure - 1		
	Outlet Input Data, 1 years	54
Composite Outlet Structure - 2		
	Outlet Input Data, 1 years	56



## Table of Contents

Composite Outlet Structure - 3		
	Outlet Input Data, 1 years	58
	Composite Rating Curve, 1 years	62
DRY POND 1 OUTLET STRUCTURE		
	Outlet Input Data, 1 years	64
	Composite Rating Curve, 1 years	68
DRY POND 2 OUTLET STRUCTURE		
	Outlet Input Data, 1 years	76
	Composite Rating Curve, 1 years	80
BIO 1		
	Interconnected Pond Routing Summary, 1 years	87
	Interconnected Pond Routing Summary, 10 years	88
	Interconnected Pond Routing Summary, 100 years	89
BIO 2		
	Interconnected Pond Routing Summary, 1 years	90
	Interconnected Pond Routing Summary, 10 years	91
	Interconnected Pond Routing Summary, 100 years	92
DRY POND 1		
	Interconnected Pond Routing Summary, 1 years	93
	Interconnected Pond Routing Summary, 10 years	94
	Interconnected Pond Routing Summary, 100 years	95
DRY POND 2		
	Interconnected Pond Routing Summary, 1 years	96
	Interconnected Pond Routing Summary, 10 years	97
	Interconnected Pond Routing Summary, 100 years	98



## Subsection: Master Network Summary

### Catchments Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft <sup>3</sup> /s)
DA-1A	1 year	1	0.1945	12.110	2.448
DA-1A	10 years	10	0.5025	12.110	6.201
DA-1A	100 years	100	1.1005	12.100	13.041
DA-1C	1 year	1	0.1005	12.160	1.058
DA-1C	10 years	10	0.2973	12.150	3.290
DA-1C	100 years	100	0.7040	12.150	7.684
DA-1D	1 year	1	0.0985	12.120	1.181
DA-1D	10 years	10	0.3062	12.110	3.826
DA-1D	100 years	100	0.7455	12.100	9.094
DA-2A	1 year	1	0.1859	12.120	2.240
DA-2A	10 years	10	0.5497	12.110	6.784
DA-2A	100 years	100	1.3012	12.110	15.641
DA-2B	1 year	1	0.0540	12.110	0.679
DA-2B	10 years	10	0.1394	12.110	1.721
DA-2B	100 years	100	0.3054	12.100	3.619
DA-3	1 year	1	0.1589	12.110	1.998
DA-3	10 years	10	0.3936	12.100	4.816
DA-3	100 years	100	0.8413	12.100	9.859
DA-4	1 year	1	0.5912	12.120	7.113
DA-4	10 years	10	1.7071	12.110	20.933
DA-4	100 years	100	3.9871	12.110	47.577
DA-5A	1 year	1	0.0784	12.110	0.962
DA-5A	10 years	10	0.2025	12.110	2.460
DA-5A	100 years	100	0.4436	12.110	5.185
DA-5B	1 year	1	0.0522	12.140	0.583
DA-5B	10 years	10	0.1409	12.140	1.598
DA-5B	100 years	100	0.3165	12.140	3.491
DA-1B	1 year	1	0.0580	12.110	0.730
DA-1B	10 years	10	0.1531	12.110	1.897
DA-1B	100 years	100	0.3396	12.100	4.045

### Node Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft <sup>3</sup> /s)
DP-1	1 year	1	0.8514	12.130	6.148
DP-1	10 years	10	2.5477	12.150	23.300
DP-1	100 years	100	5.5384	12.120	48.050
DP-2	1 year	1	0.5912	12.120	7.113
DP-2	10 years	10	1.7071	12.110	20.933
DP-2	100 years	100	3.9871	12.110	47.577
J-1	1 year	1	0.2826	12.680	0.966
J-1	10 years	10	0.9172	12.210	7.641
J-1	100 years	100	1.8471	11.960	9.868



## Subsection: Master Network Summary

### Pond Summary

Label	Scenario	Return Event (years)	Hydrograph Volume (ac-ft)	Time to Peak (hours)	Peak Flow (ft <sup>3</sup> /s)	Maximum Water Surface Elevation (ft)	Maximum Pond Storage (ac-ft)
BIO 3 (IN)	1 year	1	0.2399	12.120	2.914	(N/A)	(N/A)
BIO 3 (OUT)	1 year	1	0.2162	12.130	2.879	445.60	0.0292
BIO 3 (IN)	10 years	10	0.6891	12.110	8.505	(N/A)	(N/A)
BIO 3 (OUT)	10 years	10	0.6653	12.120	8.466	445.72	0.0354
BIO 3 (IN)	100 years	100	1.6066	12.110	19.249	(N/A)	(N/A)
BIO 3 (OUT)	100 years	100	1.5825	12.110	19.211	445.87	0.0447
BIO 2 (IN)	1 year	1	0.2108	12.130	2.304	(N/A)	(N/A)
BIO 2 (OUT)	1 year	1	0.1861	12.160	2.232	447.61	0.0306
BIO 2 (IN)	10 years	10	0.5914	12.120	6.656	(N/A)	(N/A)
BIO 2 (OUT)	10 years	10	0.5666	12.140	6.572	447.74	0.0366
BIO 2 (IN)	100 years	100	1.3601	12.120	15.016	(N/A)	(N/A)
BIO 2 (OUT)	100 years	100	1.2654	12.040	11.938	448.00	0.0498
BIO 1 (IN)	1 year	1	0.3715	12.110	4.589	(N/A)	(N/A)
BIO 1 (OUT)	1 year	1	0.2913	12.230	2.794	443.63	0.1019
BIO 1 (IN)	10 years	10	1.0113	12.110	12.487	(N/A)	(N/A)
BIO 1 (OUT)	10 years	10	0.9302	12.100	11.423	443.93	0.1493
BIO 1 (IN)	100 years	100	2.2896	12.100	27.312	(N/A)	(N/A)
BIO 1 (OUT)	100 years	100	1.8659	11.940	11.433	444.00	0.1612
DRY POND 2 (IN)	1 year	1	0.1861	12.160	2.232	(N/A)	(N/A)
DRY POND 2 (OUT)	1 year	1	0.1852	12.290	1.698	445.36	0.0130
DRY POND 2 (IN)	10 years	10	0.5666	12.140	6.572	(N/A)	(N/A)
DRY POND 2 (OUT)	10 years	10	0.5651	12.240	5.290	446.97	0.0469
DRY POND 2 (IN)	100 years	100	1.2654	12.040	11.938	(N/A)	(N/A)
DRY POND 2 (OUT)	100 years	100	1.2633	12.120	9.455	447.98	0.0830
DRY POND 1 (IN)	1 year	1	0.2913	12.230	2.794	(N/A)	(N/A)
DRY POND 1 (OUT)	1 year	1	0.2826	12.680	0.966	442.25	0.0622
DRY POND 1 (IN)	10 years	10	0.9302	12.100	11.423	(N/A)	(N/A)
DRY POND 1 (OUT)	10 years	10	0.9172	12.210	7.641	443.87	0.1842
DRY POND 1 (IN)	100 years	100	1.8659	11.940	11.433	(N/A)	(N/A)
DRY POND 1 (OUT)	100 years	100	1.8471	11.960	9.868	443.96	0.1914



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time-Depth Curve: 1 year

Label	1 year
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	1 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.0	0.0	0.0	0.0
1.000	0.0	0.0	0.0	0.0	0.0
1.500	0.0	0.0	0.0	0.1	0.1
2.000	0.1	0.1	0.1	0.1	0.1
2.500	0.1	0.1	0.1	0.1	0.1
3.000	0.1	0.1	0.1	0.1	0.1
3.500	0.1	0.1	0.1	0.1	0.1
4.000	0.1	0.1	0.1	0.1	0.1
4.500	0.1	0.1	0.1	0.2	0.2
5.000	0.2	0.2	0.2	0.2	0.2
5.500	0.2	0.2	0.2	0.2	0.2
6.000	0.2	0.2	0.2	0.2	0.2
6.500	0.2	0.2	0.2	0.2	0.2
7.000	0.3	0.3	0.3	0.3	0.3
7.500	0.3	0.3	0.3	0.3	0.3
8.000	0.3	0.3	0.3	0.3	0.4
8.500	0.4	0.4	0.4	0.4	0.4
9.000	0.4	0.4	0.4	0.4	0.5
9.500	0.5	0.5	0.5	0.5	0.5
10.000	0.5	0.5	0.6	0.6	0.6
10.500	0.6	0.6	0.6	0.7	0.7
11.000	0.7	0.7	0.7	0.8	0.8
11.500	0.8	0.9	1.0	1.0	1.2
12.000	1.4	1.6	1.8	1.8	1.9
12.500	2.0	2.0	2.0	2.1	2.1
13.000	2.1	2.1	2.1	2.2	2.2
13.500	2.2	2.2	2.2	2.2	2.3
14.000	2.3	2.3	2.3	2.3	2.3
14.500	2.3	2.3	2.4	2.4	2.4
15.000	2.4	2.4	2.4	2.4	2.4
15.500	2.4	2.4	2.5	2.5	2.5
16.000	2.5	2.5	2.5	2.5	2.5
16.500	2.5	2.5	2.5	2.5	2.5
17.000	2.5	2.6	2.6	2.6	2.6



Subsection: Time-Depth Curve  
 Label: Time-Depth - 1  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

CUMULATIVE RAINFALL (in)  
 Output Time Increment = 0.100 hours  
 Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	2.6	2.6	2.6	2.6	2.6
18.000	2.6	2.6	2.6	2.6	2.6
18.500	2.6	2.6	2.6	2.6	2.6
19.000	2.6	2.6	2.6	2.7	2.7
19.500	2.7	2.7	2.7	2.7	2.7
20.000	2.7	2.7	2.7	2.7	2.7
20.500	2.7	2.7	2.7	2.7	2.7
21.000	2.7	2.7	2.7	2.7	2.7
21.500	2.7	2.7	2.7	2.7	2.7
22.000	2.7	2.7	2.8	2.8	2.8
22.500	2.8	2.8	2.8	2.8	2.8
23.000	2.8	2.8	2.8	2.8	2.8
23.500	2.8	2.8	2.8	2.8	2.8
24.000	2.8	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time-Depth Curve  
Label: Time-Depth - 1  
Scenario: 10 years

Return Event: 10 years  
Storm Event: 10 years - type 3

Time-Depth Curve: 10 years - type 3

Label	10 years - type 3
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	10 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.0	0.0	0.0	0.0
1.000	0.1	0.1	0.1	0.1	0.1
1.500	0.1	0.1	0.1	0.1	0.1
2.000	0.1	0.1	0.1	0.1	0.1
2.500	0.1	0.1	0.1	0.1	0.2
3.000	0.2	0.2	0.2	0.2	0.2
3.500	0.2	0.2	0.2	0.2	0.2
4.000	0.2	0.2	0.2	0.2	0.2
4.500	0.3	0.3	0.3	0.3	0.3
5.000	0.3	0.3	0.3	0.3	0.3
5.500	0.3	0.3	0.3	0.4	0.4
6.000	0.4	0.4	0.4	0.4	0.4
6.500	0.4	0.4	0.4	0.4	0.5
7.000	0.5	0.5	0.5	0.5	0.5
7.500	0.5	0.5	0.5	0.6	0.6
8.000	0.6	0.6	0.6	0.6	0.6
8.500	0.7	0.7	0.7	0.7	0.7
9.000	0.7	0.8	0.8	0.8	0.8
9.500	0.8	0.9	0.9	0.9	0.9
10.000	1.0	1.0	1.0	1.0	1.1
10.500	1.1	1.1	1.2	1.2	1.2
11.000	1.3	1.3	1.4	1.4	1.5
11.500	1.5	1.6	1.7	1.9	2.1
12.000	2.5	3.0	3.2	3.4	3.5
12.500	3.6	3.6	3.7	3.7	3.8
13.000	3.8	3.9	3.9	3.9	4.0
13.500	4.0	4.0	4.0	4.1	4.1
14.000	4.1	4.2	4.2	4.2	4.2
14.500	4.2	4.3	4.3	4.3	4.3
15.000	4.3	4.4	4.4	4.4	4.4
15.500	4.4	4.5	4.5	4.5	4.5
16.000	4.5	4.5	4.5	4.5	4.6
16.500	4.6	4.6	4.6	4.6	4.6
17.000	4.6	4.6	4.7	4.7	4.7



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 10 years

Return Event: 10 years

Storm Event: 10 years - type 3

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	4.7	4.7	4.7	4.7	4.7
18.000	4.7	4.7	4.7	4.7	4.8
18.500	4.8	4.8	4.8	4.8	4.8
19.000	4.8	4.8	4.8	4.8	4.8
19.500	4.8	4.8	4.9	4.9	4.9
20.000	4.9	4.9	4.9	4.9	4.9
20.500	4.9	4.9	4.9	4.9	4.9
21.000	4.9	4.9	4.9	5.0	5.0
21.500	5.0	5.0	5.0	5.0	5.0
22.000	5.0	5.0	5.0	5.0	5.0
22.500	5.0	5.0	5.0	5.0	5.0
23.000	5.0	5.0	5.1	5.1	5.1
23.500	5.1	5.1	5.1	5.1	5.1
24.000	5.1	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 100 years

Return Event: 100 years

Storm Event: 100 years - type 3

Time-Depth Curve: 100 years - type 3

Label	100 years - type 3
Start Time	0.000 hours
Increment	0.100 hours
End Time	24.000 hours
Return Event	100 years

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
0.000	0.0	0.0	0.0	0.0	0.0
0.500	0.0	0.1	0.1	0.1	0.1
1.000	0.1	0.1	0.1	0.1	0.1
1.500	0.1	0.1	0.2	0.2	0.2
2.000	0.2	0.2	0.2	0.2	0.2
2.500	0.2	0.2	0.2	0.3	0.3
3.000	0.3	0.3	0.3	0.3	0.3
3.500	0.3	0.3	0.4	0.4	0.4
4.000	0.4	0.4	0.4	0.4	0.4
4.500	0.5	0.5	0.5	0.5	0.5
5.000	0.5	0.5	0.5	0.6	0.6
5.500	0.6	0.6	0.6	0.6	0.6
6.000	0.7	0.7	0.7	0.7	0.7
6.500	0.7	0.8	0.8	0.8	0.8
7.000	0.8	0.8	0.9	0.9	0.9
7.500	0.9	0.9	1.0	1.0	1.0
8.000	1.0	1.1	1.1	1.1	1.1
8.500	1.2	1.2	1.2	1.3	1.3
9.000	1.3	1.4	1.4	1.4	1.5
9.500	1.5	1.6	1.6	1.6	1.7
10.000	1.7	1.8	1.8	1.9	1.9
10.500	2.0	2.0	2.1	2.1	2.2
11.000	2.3	2.3	2.4	2.5	2.6
11.500	2.7	2.9	3.1	3.4	3.8
12.000	4.6	5.3	5.7	6.0	6.2
12.500	6.4	6.5	6.6	6.7	6.8
13.000	6.8	6.9	7.0	7.0	7.1
13.500	7.1	7.2	7.2	7.3	7.3
14.000	7.4	7.4	7.5	7.5	7.6
14.500	7.6	7.6	7.7	7.7	7.7
15.000	7.8	7.8	7.8	7.9	7.9
15.500	7.9	8.0	8.0	8.0	8.0
16.000	8.1	8.1	8.1	8.1	8.2
16.500	8.2	8.2	8.2	8.2	8.3
17.000	8.3	8.3	8.3	8.3	8.4



Subsection: Time-Depth Curve

Label: Time-Depth - 1

Scenario: 100 years

Return Event: 100 years

Storm Event: 100 years - type 3

CUMULATIVE RAINFALL (in)

Output Time Increment = 0.100 hours

Time on left represents time for first value in each row.

Time (hours)	Depth (in)	Depth (in)	Depth (in)	Depth (in)	Depth (in)
17.500	8.4	8.4	8.4	8.4	8.4
18.000	8.5	8.5	8.5	8.5	8.5
18.500	8.5	8.5	8.6	8.6	8.6
19.000	8.6	8.6	8.6	8.6	8.6
19.500	8.7	8.7	8.7	8.7	8.7
20.000	8.7	8.7	8.7	8.8	8.8
20.500	8.8	8.8	8.8	8.8	8.8
21.000	8.8	8.8	8.9	8.9	8.9
21.500	8.9	8.9	8.9	8.9	8.9
22.000	8.9	8.9	9.0	9.0	9.0
22.500	9.0	9.0	9.0	9.0	9.0
23.000	9.0	9.0	9.0	9.1	9.1
23.500	9.1	9.1	9.1	9.1	9.1
24.000	9.1	(N/A)	(N/A)	(N/A)	(N/A)



Subsection: Time of Concentration Calculations

Label: DA-1A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-1A  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations

Label: DA-1B

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-1B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations

Label: DA-1C

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	100.00 ft
Manning's n	0.240
Slope	0.040 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.16 ft/s
Segment Time of Concentration	0.175 hours

---

---

Segment #2: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	213.00 ft
Is Paved?	False
Slope	0.066 ft/ft
Average Velocity	4.15 ft/s
Segment Time of Concentration	0.014 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.189 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations

Label: DA-1C

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-1D

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

Segment #1: TR-55 Sheet Flow

Hydraulic Length	100.00 ft
Manning's n	0.150
Slope	0.120 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.36 ft/s
Segment Time of Concentration	0.077 hours

Segment #2: TR-55 Shallow Concentrated Flow

Hydraulic Length	120.00 ft
Is Paved?	False
Slope	0.058 ft/ft
Average Velocity	3.89 ft/s
Segment Time of Concentration	0.009 hours

Segment #3: TR-55 Shallow Concentrated Flow

Hydraulic Length	40.00 ft
Is Paved?	False
Slope	0.100 ft/ft
Average Velocity	5.10 ft/s
Segment Time of Concentration	0.002 hours

Time of Concentration (Composite)

Time of Concentration (Composite)	0.088 hours
-----------------------------------	-------------



Subsection: Time of Concentration Calculations

Label: DA-1D

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-2A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	45.00 ft
Manning's n	0.240
Slope	0.089 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.19 ft/s
Segment Time of Concentration	0.067 hours

---

---

Segment #2: TR-55 Sheet Flow

---

Hydraulic Length	55.00 ft
Manning's n	0.011
Slope	0.018 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	1.21 ft/s
Segment Time of Concentration	0.013 hours

---

---

Segment #3: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	278.00 ft
Is Paved?	False
Slope	0.065 ft/ft
Average Velocity	4.11 ft/s
Segment Time of Concentration	0.019 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.098 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations

Label: DA-2A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
A<sub>q</sub>= Flow area, square feet  
W<sub>p</sub>= Wetted perimeter, feet  
V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
n= Manning's n  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-2B

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-2B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations

Label: DA-3

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: User Defined Tc

---

Time of Concentration	0.083 hours
-----------------------	-------------

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.083 hours
--------------------------------------	-------------

---



Subsection: Time of Concentration Calculations  
Label: DA-3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

=== User Defined

Tc = Value entered by user  
Where: Tc= Time of concentration, hours



Subsection: Time of Concentration Calculations

Label: DA-4

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

Segment #1: TR-55 Sheet Flow

Hydraulic Length	15.00 ft
Manning's n	0.011
Slope	0.067 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	1.57 ft/s
Segment Time of Concentration	0.003 hours

Segment #2: TR-55 Sheet Flow

Hydraulic Length	85.00 ft
Manning's n	0.150
Slope	0.106 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.33 ft/s
Segment Time of Concentration	0.071 hours

Segment #3: TR-55 Shallow Concentrated Flow

Hydraulic Length	125.00 ft
Is Paved?	False
Slope	0.056 ft/ft
Average Velocity	3.82 ft/s
Segment Time of Concentration	0.009 hours

Segment #4: TR-55 Shallow Concentrated Flow

Hydraulic Length	229.00 ft
Is Paved?	False
Slope	0.035 ft/ft
Average Velocity	3.02 ft/s
Segment Time of Concentration	0.021 hours

Time of Concentration (Composite)

Time of Concentration (Composite)	0.104 hours
-----------------------------------	-------------



Subsection: Time of Concentration Calculations

Label: DA-4

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-5A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	100.00 ft
Manning's n	0.150
Slope	0.070 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.29 ft/s
Segment Time of Concentration	0.096 hours

---

---

Segment #2: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	112.00 ft
Is Paved?	False
Slope	0.054 ft/ft
Average Velocity	3.75 ft/s
Segment Time of Concentration	0.008 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.104 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations

Label: DA-5A

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$$(L_f / V) / 3600$$

R= Hydraulic radius  
A<sub>q</sub>= Flow area, square feet  
W<sub>p</sub>= Wetted perimeter, feet  
V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
n= Manning's n  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$$(L_f / V) / 3600$$

V= Velocity, ft/sec  
S<sub>f</sub>= Slope, ft/ft  
T<sub>c</sub>= Time of concentration, hours  
L<sub>f</sub>= Flow length, feet



Subsection: Time of Concentration Calculations

Label: DA-5B

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Time of Concentration Results

---

Segment #1: TR-55 Sheet Flow

---

Hydraulic Length	72.00 ft
Manning's n	0.240
Slope	0.083 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.20 ft/s
Segment Time of Concentration	0.100 hours

---

---

Segment #2: TR-55 Sheet Flow

---

Hydraulic Length	28.00 ft
Manning's n	0.240
Slope	0.036 ft/ft
2 Year 24 Hour Depth	3.4 in
Average Velocity	0.12 ft/s
Segment Time of Concentration	0.066 hours

---

---

Segment #3: TR-55 Shallow Concentrated Flow

---

Hydraulic Length	57.00 ft
Is Paved?	False
Slope	0.053 ft/ft
Average Velocity	3.71 ft/s
Segment Time of Concentration	0.004 hours

---

---

Time of Concentration (Composite)

---

Time of Concentration (Composite)	0.171 hours
-----------------------------------	-------------

---



Subsection: Time of Concentration Calculations

Label: DA-5B

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

==== SCS Channel Flow

$$T_c = \frac{R = Q_a / W_p}{V = (1.49 * (R^{2/3}) * (S_f^{-0.5})) / n}$$

Where:

$(L_f / V) / 3600$

R= Hydraulic radius  
Aq= Flow area, square feet  
Wp= Wetted perimeter, feet  
V= Velocity, ft/sec  
Sf= Slope, ft/ft  
n= Manning's n  
Tc= Time of concentration, hours  
Lf= Flow length, feet

==== SCS TR-55 Shallow Concentration Flow

$$T_c = \frac{\text{Unpaved surface:}}{V = 16.1345 * (S_f^{0.5})}$$

$$\text{Paved Surface:}$$
$$V = 20.3282 * (S_f^{0.5})$$

Where:

$(L_f / V) / 3600$

V= Velocity, ft/sec  
Sf= Slope, ft/ft  
Tc= Time of concentration, hours  
Lf= Flow length, feet



Subsection: Runoff CN-Area  
 Label: DA-1A  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

# Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	1.310	0.0	0.0	74.000
Asphalt	98.000	0.600	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.910	(N/A)	(N/A)	81.539



Subsection: Runoff CN-Area  
Label: DA-1B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open Space - Good Cond - HSG C	74.000	0.420	0.0	0.0	74.000
Asphalt	98.000	0.180	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	0.600	(N/A)	(N/A)	81.200



Subsection: Runoff CN-Area  
 Label: DA-1C  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Impervious	98.000	0.110	0.0	0.0	98.000
Grass - Good Cond, HSG C	74.000	1.260	0.0	0.0	74.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.370	(N/A)	(N/A)	75.927



Subsection: Runoff CN-Area  
Label: DA-1D  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	1.380	0.0	0.0	74.000
Woods - Good Cond, HSG C	70.000	0.090	0.0	0.0	70.000
Impervious	98.000	0.040	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.510	(N/A)	(N/A)	74.397



Subsection: Runoff CN-Area  
Label: DA-2A  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	2.300	0.0	0.0	74.000
Impervious	98.000	0.230	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	2.530	(N/A)	(N/A)	76.182



Subsection: Runoff CN-Area  
 Label: DA-2B  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Impervious	98.000	0.180	0.0	0.0	98.000
Open Space - Good Cond - HSG C	74.000	0.350	0.0	0.0	74.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	0.530	(N/A)	(N/A)	82.151



Subsection: Runoff CN-Area  
Label: DA-3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	0.820	0.0	0.0	74.000
Impervious	98.000	0.590	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	1.410	(N/A)	(N/A)	84.043



Subsection: Runoff CN-Area  
 Label: DA-4  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	4.890	0.0	0.0	74.000
Woods - Good Cond, HSG C	70.000	1.610	0.0	0.0	70.000
Impervious	98.000	1.100	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	7.600	(N/A)	(N/A)	76.626



Subsection: Runoff CN-Area  
Label: DA-5A  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	0.500	0.0	0.0	74.000
Impervious	98.000	0.270	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	0.770	(N/A)	(N/A)	82.416



Subsection: Runoff CN-Area  
Label: DA-5B  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Runoff Curve Number Data

Soil/Surface Description	CN	Area (acres)	C (%)	UC (%)	Adjusted CN
Open space - Good Cond, HSG C	74.000	0.430	0.0	0.0	74.000
Impervious	98.000	0.140	0.0	0.0	98.000
COMPOSITE AREA & WEIGHTED CN --->	(N/A)	0.570	(N/A)	(N/A)	79.895



Subsection: Elevation-Area Volume Curve

Label: BIO 1

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Elevation (ft)	Planimeter (ft <sup>2</sup> )	Area (acres)	A1+A2+sqr (A1*A2) (acres)	Volume (ac-ft)	Volume (Total) (ac-ft)
443.00	0.0	0.145	0.000	0.0000	0.0000
444.00	0.0	0.178	0.484	0.1612	0.1612



Subsection: Elevation-Area Volume Curve

Label: BIO 2

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Elevation (ft)	Planimeter (ft <sup>2</sup> )	Area (acres)	A1+A2+sqr (A1*A2) (acres)	Volume (ac-ft)	Volume (Total) (ac-ft)
447.00	0.0	0.040	0.000	0.0000	0.0000
448.00	0.0	0.060	0.149	0.0498	0.0498



Subsection: Elevation-Area Volume Curve

Label: BIO 3

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Elevation (ft)	Planimeter (ft <sup>2</sup> )	Area (acres)	A1+A2+sqr (A1*A2) (acres)	Volume (ac-ft)	Volume (Total) (ac-ft)
445.00	0.0	0.041	0.000	0.0000	0.0000
446.00	0.0	0.065	0.159	0.0530	0.0530



Subsection: Elevation-Area Volume Curve

Label: DRY POND 1

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Elevation (ft)	Planimeter (ft <sup>2</sup> )	Area (acres)	A1+A2+sqr (A1*A2) (acres)	Volume (ac-ft)	Volume (Total) (ac-ft)
441.00	0.0	0.037	0.000	0.0000	0.0000
442.00	0.0	0.055	0.138	0.0460	0.0460
443.00	0.0	0.075	0.194	0.0646	0.1106
444.00	0.0	0.095	0.254	0.0846	0.1951
444.50	0.0	0.113	0.312	0.0519	0.2471



Subsection: Elevation-Area Volume Curve

Label: DRY POND 2

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Elevation (ft)	Planimeter (ft <sup>2</sup> )	Area (acres)	A1+A2+sqr (A1*A2) (acres)	Volume (ac-ft)	Volume (Total) (ac-ft)
444.00	0.0	0.005	0.000	0.0000	0.0000
445.00	0.0	0.011	0.023	0.0076	0.0076
446.00	0.0	0.020	0.045	0.0151	0.0226
447.00	0.0	0.031	0.075	0.0249	0.0475
448.00	0.0	0.043	0.109	0.0364	0.0839
448.50	0.0	0.049	0.137	0.0229	0.1067



Subsection: Outlet Input Data  
Label: BIO 1 UD OUTLET  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Requested Pond Water Surface Elevations	
Minimum (Headwater)	443.00 ft
Increment (Headwater)	0.05 ft
Maximum (Headwater)	444.00 ft

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
User Defined Table	User Defined Rating Table - 1	Forward	TW	0.00	444.00
Tailwater Settings	Tailwater			(N/A)	(N/A)



Subsection: Outlet Input Data  
Label: BIO 1 UD OUTLET  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

---

Structure ID: User Defined Rating Table - 1  
Structure Type: User Defined Table

---

Elevation (ft)		Flow (ft <sup>3</sup> /s)	
	443.00		0.029
	443.50		0.029
	444.00		0.029



Subsection: Outlet Input Data  
Label: BIO 2 UD OUTLET  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Requested Pond Water Surface Elevations	
Minimum (Headwater)	446.00 ft
Increment (Headwater)	0.05 ft
Maximum (Headwater)	447.00 ft

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
User Defined Table	User Defined Rating Table - 1	Forward	TW	0.00	448.00
Tailwater Settings	Tailwater			(N/A)	(N/A)



Subsection: Outlet Input Data  
Label: BIO 2 UD OUTLET  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

---

Structure ID: User Defined Rating Table - 1  
Structure Type: User Defined Table

---

Elevation (ft)		Flow (ft <sup>3</sup> /s)	
	446.00		0.010
	446.50		0.010
	447.00		0.010



Subsection: Multiple Outfall Rating Curves

Label: BIO 3 (IN)

Scenario: 1 year

Return Event: 1 years

Storm Event: 1 year

Total Pond Outflow Curve for Multiple  
Outfalls

Headwater Elevation (ft)	Outfall: OUTFALL 3 (ft <sup>3</sup> /s)	Outfall: OF BIO 3 UD (ft <sup>3</sup> /s)	Total Flow (ft <sup>3</sup> /s)
445.00	0.000	0.010	0.010
445.05	0.000	0.010	0.010
445.10	0.000	0.010	0.010
445.15	0.000	0.010	0.010
445.20	0.000	0.010	0.010
445.25	0.000	0.010	0.010
445.30	0.000	0.010	0.010
445.35	0.000	0.010	0.010
445.40	0.000	0.010	0.010
445.45	0.000	0.010	0.010
445.50	0.000	0.010	0.010
445.55	0.937	0.010	0.948
445.60	2.652	0.010	2.663
445.65	4.877	0.010	4.887
445.70	7.530	0.010	7.540
445.75	10.561	0.010	10.571
445.80	13.932	0.010	13.942
445.85	17.616	0.010	17.626
445.90	21.589	0.010	21.600
445.95	24.587	0.010	24.598
446.00	27.779	0.010	27.789



Subsection: Outlet Input Data  
Label: BIO 3 UD OUTLET  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

---

**Requested Pond Water Surface Elevations**

---

Minimum (Headwater)	445.00 ft
Increment (Headwater)	0.05 ft
Maximum (Headwater)	446.00 ft

---

**Outlet Connectivity**

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
User Defined Table	User Defined Rating Table - 1	Forward	TW	0.00	446.00
Tailwater Settings	Tailwater			(N/A)	(N/A)



Subsection: Outlet Input Data  
Label: BIO 3 UD OUTLET  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: User Defined Rating Table - 1  
Structure Type: User Defined Table

Elevation (ft)	Flow (ft <sup>3</sup> /s)
445.00	0.010
445.50	0.010
446.00	0.010

Structure ID: TW  
Structure Type: TW Setup, DS Channel

Tailwater Type Free Outfall

Convergence Tolerances

Maximum Iterations	30
Tailwater Tolerance (Minimum)	0.01 ft
Tailwater Tolerance (Maximum)	0.50 ft
Headwater Tolerance (Minimum)	0.01 ft
Headwater Tolerance (Maximum)	0.50 ft
Flow Tolerance (Minimum)	0.001 ft <sup>3</sup> /s
Flow Tolerance (Maximum)	10.000 ft <sup>3</sup> /s



Subsection: Composite Rating Curve  
 Label: BIO 3 UD OUTLET  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft <sup>3</sup> /s)	Tailwater Elevation (ft)	Convergence Error (ft)
445.00	0.010	(N/A)	0.00
445.05	0.010	(N/A)	0.00
445.10	0.010	(N/A)	0.00
445.15	0.010	(N/A)	0.00
445.20	0.010	(N/A)	0.00
445.25	0.010	(N/A)	0.00
445.30	0.010	(N/A)	0.00
445.35	0.010	(N/A)	0.00
445.40	0.010	(N/A)	0.00
445.45	0.010	(N/A)	0.00
445.50	0.010	(N/A)	0.00
445.55	0.010	(N/A)	0.00
445.60	0.010	(N/A)	0.00
445.65	0.010	(N/A)	0.00
445.70	0.010	(N/A)	0.00
445.75	0.010	(N/A)	0.00
445.80	0.010	(N/A)	0.00
445.85	0.010	(N/A)	0.00
445.90	0.010	(N/A)	0.00
445.95	0.010	(N/A)	0.00
446.00	0.010	(N/A)	0.00

Contributing Structures

User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1



Subsection: Composite Rating Curve  
Label: BIO 3 UD OUTLET  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1
User Defined Rating Table - 1



Subsection: Outlet Input Data  
Label: Composite Outlet Structure - 1  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Requested Pond Water Surface Elevations	
Minimum (Headwater)	443.00 ft
Increment (Headwater)	0.05 ft
Maximum (Headwater)	444.00 ft

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Irregular Weir Tailwater Settings	Weir bio 1 Tailwater	Forward	TW	443.50 (N/A)	444.00 (N/A)



Subsection: Outlet Input Data  
Label: Composite Outlet Structure - 1  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: Weir bio 1  
Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
0.00	444.00
1.50	443.50
21.50	443.50
23.00	444.00

Lowest Elevation 443.50 ft  
Weir Coefficient 2.80 (ft<sup>0.5</sup>)/s



Subsection: Outlet Input Data  
Label: Composite Outlet Structure - 2  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Requested Pond Water Surface Elevations	
Minimum (Headwater)	447.00 ft
Increment (Headwater)	0.05 ft
Maximum (Headwater)	448.00 ft

Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Irregular Weir Tailwater Settings	Weir bio 2 Tailwater	Forward	TW	447.50 (N/A)	448.00 (N/A)



Subsection: Outlet Input Data  
Label: Composite Outlet Structure - 2  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: Weir bio 2  
Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
0.00	448.00
1.50	447.50
21.50	447.50
23.00	448.00

Lowest Elevation 447.50 ft  
Weir Coefficient 2.80 (ft<sup>0.5</sup>)/s



Subsection: Outlet Input Data  
 Label: Composite Outlet Structure - 3  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Requested Pond Water Surface Elevations	
Minimum (Headwater)	445.00 ft
Increment (Headwater)	0.05 ft
Maximum (Headwater)	446.00 ft

#### Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Inlet Box	Riser bio 3	Forward	Culvert bio 3	445.50	446.00
Culvert-Circular	Culvert bio 3	Forward	TW	442.00	446.00
Irregular Weir	Weir bio 3	Forward	TW	445.50	446.00
Tailwater Settings	Tailwater			(N/A)	(N/A)



Subsection: Outlet Input Data  
 Label: Composite Outlet Structure - 3  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Structure ID: Weir bio 3  
 Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
0.00	446.00
1.50	445.50
21.50	445.50
23.00	446.00

Lowest Elevation 445.50 ft  
 Weir Coefficient 2.80 (ft<sup>0.5</sup>)/s

Structure ID: Riser bio 3  
 Structure Type: Inlet Box

Number of Openings 1  
 Elevation 445.50 ft  
 Orifice Area 5.0 ft<sup>2</sup>  
 Orifice Coefficient 0.600  
 Weir Length 10.00 ft  
 Weir Coefficient 2.70 (ft<sup>0.5</sup>)/s  
 K Reverse 1.000  
 Manning's n 0.000  
 Kev, Charged Riser 0.000  
 Weir Submergence False  
 Orifice H to crest False

Structure ID: Culvert bio 3  
 Structure Type: Culvert-Circular

Number of Barrels 1  
 Diameter 12.0 in  
 Length 40.00 ft  
 Length (Computed Barrel) 40.00 ft  
 Slope (Computed) 0.005 ft/ft

Outlet Control Data

Manning's n 0.013  
 Ke 0.400  
 Kb 0.031  
 Kr 0.400  
 Convergence Tolerance 0.00 ft

Inlet Control Data

Equation Form Form 2  
 K 0.5340



Subsection: Outlet Input Data  
Label: Composite Outlet Structure - 3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Inlet Control Data	
M	0.5550
C	0.0196
Y	0.9000
T1 ratio (HW/D)	1.070
T2 ratio (HW/D)	1.211
Slope Correction Factor	-0.500

Use unsubmerged inlet control 1 equation below T1 elevation.

Use submerged inlet control 1 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control,  
interpolate between flows at T1 & T2...

T1 Elevation	443.07 ft	T1 Flow	2.749 ft <sup>3</sup> /s
T2 Elevation	443.21 ft	T2 Flow	3.142 ft <sup>3</sup> /s



Subsection: Outlet Input Data  
Label: Composite Outlet Structure - 3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: TW	
Structure Type: TW Setup, DS Channel	
Tailwater Type	Free Outfall
Convergence Tolerances	
Maximum Iterations	30
Tailwater Tolerance (Minimum)	0.05 ft
Tailwater Tolerance (Maximum)	0.50 ft
Headwater Tolerance (Minimum)	0.05 ft
Headwater Tolerance (Maximum)	0.50 ft
Flow Tolerance (Minimum)	0.001 ft <sup>3</sup> /s
Flow Tolerance (Maximum)	10.000 ft <sup>3</sup> /s



Return Event: 1 years  
Storm Event: 1 year

Water Surface Elevation (ft)	Flow (ft <sup>3</sup> /s)	Tailwater Elevation (ft)	Convergence Error (ft)
445.00	0.000	(N/A)	0.00
445.05	0.000	(N/A)	0.00
445.10	0.000	(N/A)	0.00
445.15	0.000	(N/A)	0.00
445.20	0.000	(N/A)	0.00
445.25	0.000	(N/A)	0.00
445.30	0.000	(N/A)	0.00
445.35	0.000	(N/A)	0.00
445.40	0.000	(N/A)	0.00
445.45	0.000	(N/A)	0.00
445.50	0.000	(N/A)	0.00
445.55	0.937	(N/A)	0.00
445.60	2.652	(N/A)	0.00
445.65	4.877	(N/A)	0.00
445.70	7.530	(N/A)	0.00
445.75	10.561	(N/A)	0.00
445.80	13.932	(N/A)	0.00
445.85	17.616	(N/A)	0.00
445.90	21.589	(N/A)	0.00
445.95	24.587	(N/A)	0.00
446.00	27.779	(N/A)	0.00

[illegible]



Subsection: Composite Rating Curve  
Label: Composite Outlet Structure - 3  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3
Riser bio 3,Culvert bio 3,Weir bio 3



Subsection: Outlet Input Data  
Label: DRY POND 1 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Requested Pond Water Surface Elevations	
Minimum (Headwater)	441.00 ft
Increment (Headwater)	0.05 ft
Maximum (Headwater)	444.50 ft

#### Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Inlet Box	Riser DRY POND 1	Forward	Culvert DRY POND 1	443.50	444.50
Orifice-Circular	Orifice DRY POND 1	Forward	Culvert DRY POND 1	441.00	444.50
Culvert-Circular	Culvert DRY POND 1	Forward	TW	436.00	444.50
Irregular Weir	Weir DRY POND 1	Forward	TW	444.00	444.50
Tailwater Settings	Tailwater			(N/A)	(N/A)



Subsection: Outlet Input Data  
 Label: DRY POND 1 OUTLET STRUCTURE  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

---

Structure ID: Riser DRY POND 1  
 Structure Type: Inlet Box

---

Number of Openings	1
Elevation	443.50 ft
Orifice Area	5.0 ft <sup>2</sup>
Orifice Coefficient	0.600
Weir Length	10.00 ft
Weir Coefficient	2.70 (ft <sup>0.5</sup> )/s
K Reverse	1.000
Manning's n	0.000
Kev, Charged Riser	0.000
Weir Submergence	False
Orifice H to crest	False

---

Structure ID: Weir DRY POND 1  
 Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
0.00	444.50
1.50	444.00
21.50	444.00
23.00	444.50

Lowest Elevation	444.00 ft
Weir Coefficient	2.80 (ft <sup>0.5</sup> )/s



Subsection: Outlet Input Data  
Label: DRY POND 1 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: Culvert DRY POND 1	
Structure Type: Culvert-Circular	
Number of Barrels	1
Diameter	18.0 in
Length	35.00 ft
Length (Computed Barrel)	35.01 ft
Slope (Computed)	0.023 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.000
Kb	0.018
Kr	0.400
Convergence Tolerance	0.00 ft
Inlet Control Data	
Equation Form	Form 2
K	0.5340
M	0.5550
C	0.0196
Y	0.9000
T1 ratio (HW/D)	1.070
T2 ratio (HW/D)	1.202
Slope Correction Factor	-0.500

Use unsubmerged inlet control 1 equation below T1 elevation.

Use submerged inlet control 1 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control, interpolate between flows at T1 & T2...

T1 Elevation	437.61 ft	T1 Flow	7.575 ft <sup>3</sup> /s
T2 Elevation	437.80 ft	T2 Flow	8.657 ft <sup>3</sup> /s



Subsection: Outlet Input Data  
Label: DRY POND 1 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: Orifice DRY POND 1	
Structure Type: Orifice-Circular	
Number of Openings	1
Elevation	441.00 ft
Orifice Diameter	6.0 in
Orifice Coefficient	0.600
Structure ID: TW	
Structure Type: TW Setup, DS Channel	
Tailwater Type	Free Outfall
Convergence Tolerances	
Maximum Iterations	30
Tailwater Tolerance (Minimum)	0.01 ft
Tailwater Tolerance (Maximum)	0.50 ft
Headwater Tolerance (Minimum)	0.01 ft
Headwater Tolerance (Maximum)	0.50 ft
Flow Tolerance (Minimum)	0.001 ft <sup>3</sup> /s
Flow Tolerance (Maximum)	10.000 ft <sup>3</sup> /s



Subsection: Composite Rating Curve  
 Label: DRY POND 1 OUTLET STRUCTURE  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft <sup>3</sup> /s)	Tailwater Elevation (ft)	Convergence Error (ft)
441.00	0.000	(N/A)	0.00
441.05	0.007	(N/A)	0.00
441.10	0.022	(N/A)	0.00
441.15	0.053	(N/A)	0.00
441.20	0.089	(N/A)	0.00
441.25	0.135	(N/A)	0.00
441.30	0.196	(N/A)	0.00
441.35	0.251	(N/A)	0.00
441.40	0.326	(N/A)	0.00
441.45	0.393	(N/A)	0.00
441.50	0.495	(N/A)	0.00
441.55	0.519	(N/A)	0.00
441.60	0.560	(N/A)	0.00
441.65	0.626	(N/A)	0.00
441.70	0.662	(N/A)	0.00
441.75	0.668	(N/A)	0.00
441.80	0.703	(N/A)	0.00
441.85	0.733	(N/A)	0.00
441.90	0.763	(N/A)	0.00
441.95	0.793	(N/A)	0.00
442.00	0.852	(N/A)	0.00
442.05	0.846	(N/A)	0.00
442.10	0.888	(N/A)	0.00
442.15	0.912	(N/A)	0.00
442.20	0.936	(N/A)	0.00
442.25	0.966	(N/A)	0.00
442.30	0.983	(N/A)	0.00
442.35	1.007	(N/A)	0.00
442.40	1.013	(N/A)	0.00
442.45	1.037	(N/A)	0.00
442.50	1.073	(N/A)	0.00
442.55	1.079	(N/A)	0.00
442.60	1.121	(N/A)	0.00
442.65	1.121	(N/A)	0.00
442.70	1.138	(N/A)	0.00
442.75	1.156	(N/A)	0.00
442.80	1.180	(N/A)	0.00
442.85	1.216	(N/A)	0.00
442.90	1.216	(N/A)	0.00
442.95	1.234	(N/A)	0.00
443.00	1.252	(N/A)	0.00
443.05	1.270	(N/A)	0.00
443.10	1.287	(N/A)	0.00
443.15	1.323	(N/A)	0.00



Subsection: Composite Rating Curve  
 Label: DRY POND 1 OUTLET STRUCTURE  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft <sup>3</sup> /s)	Tailwater Elevation (ft)	Convergence Error (ft)
443.20	1.323	(N/A)	0.00
443.25	1.359	(N/A)	0.00
443.30	1.353	(N/A)	0.00
443.35	1.371	(N/A)	0.00
443.40	1.407	(N/A)	0.00
443.45	1.401	(N/A)	0.00
443.50	1.419	(N/A)	0.00
443.55	1.734	(N/A)	0.00
443.60	2.301	(N/A)	0.00
443.65	3.064	(N/A)	0.00
443.70	3.898	(N/A)	0.00
443.75	4.911	(N/A)	0.00
443.80	5.949	(N/A)	0.00
443.85	7.117	(N/A)	0.00
443.90	8.369	(N/A)	0.00
443.95	9.704	(N/A)	0.00
444.00	11.110	(N/A)	0.00
444.05	13.218	(N/A)	0.00
444.10	15.934	(N/A)	0.00
444.15	19.065	(N/A)	0.00
444.20	22.555	(N/A)	0.00
444.25	26.359	(N/A)	0.00
444.30	30.466	(N/A)	0.00
444.35	34.846	(N/A)	0.00
444.40	39.180	(N/A)	0.00
444.45	42.696	(N/A)	0.00
444.50	46.391	(N/A)	0.00

Contributing Structures

(no Q: Riser DRY POND  
 1,Orifice DRY POND  
 1,Culvert DRY POND  
 1,Weir DRY POND 1)  
 Orifice DRY POND  
 1,Culvert DRY POND 1  
 (no Q: Riser DRY POND  
 1,Weir DRY POND 1)  
 Orifice DRY POND  
 1,Culvert DRY POND 1  
 (no Q: Riser DRY POND  
 1,Weir DRY POND 1)  
 Orifice DRY POND  
 1,Culvert DRY POND 1  
 (no Q: Riser DRY POND  
 1,Weir DRY POND 1)



Return Event: 1 years  
Storm Event: 1 year



Subsection: Composite Rating Curve  
Label: DRY POND 1 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)



Subsection: Composite Rating Curve  
Label: DRY POND 1 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)
Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Riser DRY POND 1,Weir DRY POND 1)



Return Event: 1 years  
Storm Event: 1 year



Subsection: Composite Rating Curve  
Label: DRY POND 1 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1 (no Q: Weir DRY POND 1)
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1



Subsection: Composite Rating Curve  
Label: DRY POND 1 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Composite Outflow Summary

Contributing Structures
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1
Riser DRY POND 1,Orifice DRY POND 1,Culvert DRY POND 1,Weir DRY POND 1



Subsection: Outlet Input Data  
 Label: DRY POND 2 OUTLET STRUCTURE  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Requested Pond Water Surface Elevations	
Minimum (Headwater)	444.00 ft
Increment (Headwater)	0.10 ft
Maximum (Headwater)	448.50 ft

#### Outlet Connectivity

Structure Type	Outlet ID	Direction	Outfall	E1 (ft)	E2 (ft)
Orifice-Area	Orifice DRY POND 2B	Forward	Culvert DRY POND 2	445.75	448.50
Inlet Box	Riser DRY POND 2	Forward	Culvert DRY POND 2	447.75	448.50
Orifice-Circular	Orifice DRY POND 2A	Forward	Culvert DRY POND 2	444.00	448.50
Culvert-Circular	Culvert DRY POND 2	Forward	TW	443.30	448.50
Irregular Weir	Weir DRY POND 2 ES	Forward	TW	448.00	448.50
Tailwater Settings	Tailwater			(N/A)	(N/A)



Subsection: Outlet Input Data  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: Culvert DRY POND 2	
Structure Type: Culvert-Circular	
Number of Barrels	1
Diameter	24.0 in
Length	22.00 ft
Length (Computed Barrel)	22.00 ft
Slope (Computed)	0.014 ft/ft
Outlet Control Data	
Manning's n	0.013
Ke	0.400
Kb	0.012
Kr	0.400
Convergence Tolerance	0.00 ft
Inlet Control Data	
Equation Form	Form 2
K	0.5340
M	0.5550
C	0.0196
Y	0.9000
T1 ratio (HW/D)	1.070
T2 ratio (HW/D)	1.207
Slope Correction Factor	-0.500

Use unsubmerged inlet control 1 equation below T1 elevation.

Use submerged inlet control 1 equation above T2 elevation

In transition zone between unsubmerged and submerged inlet control,  
interpolate between flows at T1 & T2...

T1 Elevation	445.44 ft	T1 Flow	15.550 ft <sup>3</sup> /s
T2 Elevation	445.71 ft	T2 Flow	17.772 ft <sup>3</sup> /s



Subsection: Outlet Input Data  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: Riser DRY POND 2  
Structure Type: Inlet Box

Number of Openings	1
Elevation	447.75 ft
Orifice Area	5.0 ft <sup>2</sup>
Orifice Coefficient	0.600
Weir Length	10.00 ft
Weir Coefficient	2.70 (ft <sup>0.5</sup> )/s
K Reverse	1.000
Manning's n	0.000
Kev, Charged Riser	0.000
Weir Submergence	False
Orifice H to crest	False

Structure ID: Weir DRY POND 2 ES  
Structure Type: Irregular Weir

Station (ft)	Elevation (ft)
0.00	448.50
1.50	448.00
21.50	448.00
23.00	448.50

Lowest Elevation	448.00 ft
Weir Coefficient	2.80 (ft <sup>0.5</sup> )/s

Structure ID: Orifice DRY POND 2A  
Structure Type: Orifice-Circular

Number of Openings	1
Elevation	444.00 ft
Orifice Diameter	8.0 in
Orifice Coefficient	0.600

Structure ID: Orifice DRY POND 2B  
Structure Type: Orifice-Area

Number of Openings	1
Elevation	445.75 ft
Orifice Area	0.5 ft <sup>2</sup>
Top Elevation	446.25 ft
Datum Elevation	445.75 ft
Orifice Coefficient	0.600

Structure ID: TW  
Structure Type: TW Setup, DS Channel



Subsection: Outlet Input Data  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Structure ID: TW	
Structure Type: TW Setup, DS Channel	
Tailwater Type	Free Outfall
Convergence Tolerances	
Maximum Iterations	30
Tailwater Tolerance (Minimum)	0.01 ft
Tailwater Tolerance (Maximum)	0.50 ft
Headwater Tolerance (Minimum)	0.01 ft
Headwater Tolerance (Maximum)	0.50 ft
Flow Tolerance (Minimum)	0.001 ft <sup>3</sup> /s
Flow Tolerance (Maximum)	10.000 ft <sup>3</sup> /s



Subsection: Composite Rating Curve  
 Label: DRY POND 2 OUTLET STRUCTURE  
 Scenario: 1 year

Return Event: 1 years  
 Storm Event: 1 year

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft <sup>3</sup> /s)	Tailwater Elevation (ft)	Convergence Error (ft)
444.00	0.000	(N/A)	0.00
444.10	0.028	(N/A)	0.00
444.20	0.107	(N/A)	0.00
444.30	0.228	(N/A)	0.00
444.40	0.386	(N/A)	0.00
444.50	0.576	(N/A)	0.00
444.60	0.787	(N/A)	0.00
444.70	1.017	(N/A)	0.00
444.80	1.147	(N/A)	0.00
444.90	1.266	(N/A)	0.00
445.00	1.372	(N/A)	0.00
445.10	1.468	(N/A)	0.00
445.20	1.565	(N/A)	0.00
445.30	1.648	(N/A)	0.00
445.40	1.732	(N/A)	0.00
445.50	1.813	(N/A)	0.00
445.60	1.891	(N/A)	0.00
445.70	1.964	(N/A)	0.00
445.75	2.000	(N/A)	0.00
445.80	2.205	(N/A)	0.00
445.90	2.613	(N/A)	0.00
446.00	3.023	(N/A)	0.00
446.10	3.425	(N/A)	0.00
446.20	3.822	(N/A)	0.00
446.30	4.112	(N/A)	0.00
446.40	4.311	(N/A)	0.00
446.50	4.499	(N/A)	0.00
446.60	4.675	(N/A)	0.00
446.70	4.849	(N/A)	0.00
446.80	5.012	(N/A)	0.00
446.90	5.176	(N/A)	0.00
447.00	5.328	(N/A)	0.00
447.10	5.470	(N/A)	0.00
447.20	5.623	(N/A)	0.00
447.30	5.753	(N/A)	0.00
447.40	5.895	(N/A)	0.00
447.50	6.026	(N/A)	0.00
447.60	6.157	(N/A)	0.00
447.70	6.287	(N/A)	0.00
447.75	6.353	(N/A)	0.00
447.80	6.698	(N/A)	0.00
447.90	8.023	(N/A)	0.00
448.00	9.875	(N/A)	0.00
448.10	13.879	(N/A)	0.00



Subsection: Composite Rating Curve  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Composite Outflow Summary

Water Surface Elevation (ft)	Flow (ft <sup>3</sup> /s)	Tailwater Elevation (ft)	Convergence Error (ft)
448.20	19.761	(N/A)	0.00
448.30	26.928	(N/A)	0.00
448.40	35.063	(N/A)	0.00
448.50	44.211	(N/A)	0.00

Contributing Structures

(no Q: Orifice DRY  
POND 2B,Riser DRY POND  
2,Orifice DRY POND  
2A,Culvert DRY POND  
2,Weir DRY POND 2 ES)  
Orifice DRY POND  
2A,Culvert DRY POND 2  
(no Q: Orifice DRY POND  
2B,Riser DRY POND  
2,Weir DRY POND 2 ES)  
Orifice DRY POND  
2A,Culvert DRY POND 2  
(no Q: Orifice DRY POND  
2B,Riser DRY POND  
2,Weir DRY POND 2 ES)  
Orifice DRY POND  
2A,Culvert DRY POND 2  
(no Q: Orifice DRY POND  
2B,Riser DRY POND  
2,Weir DRY POND 2 ES)  
Orifice DRY POND  
2A,Culvert DRY POND 2  
(no Q: Orifice DRY POND  
2B,Riser DRY POND  
2,Weir DRY POND 2 ES)  
Orifice DRY POND  
2A,Culvert DRY POND 2  
(no Q: Orifice DRY POND  
2B,Riser DRY POND  
2,Weir DRY POND 2 ES)  
Orifice DRY POND  
2A,Culvert DRY POND 2  
(no Q: Orifice DRY POND  
2B,Riser DRY POND  
2,Weir DRY POND 2 ES)  
Orifice DRY POND  
2A,Culvert DRY POND 2  
(no Q: Orifice DRY POND  
2B,Riser DRY POND  
2,Weir DRY POND 2 ES)



Subsection: Composite Rating Curve  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)



Subsection: Composite Rating Curve  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Orifice DRY POND 2B,Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)



Subsection: Composite Rating Curve  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)



Subsection: Composite Rating Curve  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Riser DRY POND 2,Weir DRY POND 2 ES)
Orifice DRY POND 2B,Riser DRY POND 2,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Weir DRY POND 2 ES)
Orifice DRY POND 2B,Riser DRY POND 2,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Weir DRY POND 2 ES)
Orifice DRY POND 2B,Riser DRY POND 2,Orifice DRY POND 2A,Culvert DRY POND 2 (no Q: Weir DRY POND 2 ES)
Orifice DRY POND 2B,Riser DRY POND 2,Orifice DRY POND 2A,Culvert DRY POND 2,Weir DRY POND 2 ES
Orifice DRY POND 2B,Riser DRY POND 2,Orifice DRY POND 2A,Culvert DRY POND 2,Weir DRY POND 2 ES
Orifice DRY POND 2B,Riser DRY POND 2,Orifice DRY POND 2A,Culvert DRY POND 2,Weir DRY POND 2 ES
Orifice DRY POND 2B,Riser DRY POND 2,Orifice DRY POND 2A,Culvert DRY POND 2,Weir DRY POND 2 ES



Subsection: Composite Rating Curve  
Label: DRY POND 2 OUTLET STRUCTURE  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

#### Composite Outflow Summary

Contributing Structures
Orifice DRY POND
2B,Riser DRY POND
2,Orifice DRY POND
2A,Culvert DRY POND
2,Weir DRY POND 2 ES



Subsection: Interconnected Pond Routing Summary  
Label: BIO 1  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	443.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.029	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.230	443.63	0.1019	
		Forward Flow Peaks		Reverse Flow Peaks	
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	12.110	4.589	0.000	0.000	
Pond Outflow...	12.230	2.794	0.000	0.000	
		Total Volume In		Total Volume Out	
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	0.3715	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	0.2913	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		0.3715 ac-ft			
Volume (Total Out ICPM)		0.2913 ac-ft			
Volume (Ending)		0.0812 ac-ft			
Elevation (Ending)		443.50 ft			
Difference		-0.0011 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.3 %			



Subsection: Interconnected Pond Routing Summary  
Label: BIO 1  
Scenario: 10 years

Return Event: 10 years  
Storm Event: 10 years - type 3

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	443.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.029	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.210	443.93	0.1493	
		Forward Flow Peaks		Reverse Flow Peaks	
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	12.110	12.487	0.000	0.000	
Pond Outflow...	12.100	11.423	0.000	0.000	
		Total Volume In		Total Volume Out	
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	1.0113	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	0.9302	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		1.0113 ac-ft			
Volume (Total Out ICPM)		0.9302 ac-ft			
Volume (Ending)		0.0823 ac-ft			
Elevation (Ending)		443.51 ft			
Difference		-0.0013 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.1 %			



Subsection: Interconnected Pond Routing Summary  
Label: BIO 1  
Scenario: 100 years

Return Event: 100 years  
Storm Event: 100 years - type 3

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	443.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.029	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		11.950	444.00	0.1612	
		Forward Flow Peaks Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Reverse Flow Peaks Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)
Pond Inflow....		12.100	27.312	0.000	0.000
Pond Outflow...		11.940	11.433	0.000	0.000
		Total Volume In Volume (ac-ft)	Direction	Total Volume Out Volume (ac-ft)	Direction
Pond Inflow....		2.2896	Forward	0.0000	Reverse
Pond Outflow...		0.0000	Reverse	1.8659	Forward
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		2.2896 ac-ft			
Volume (Total Out ICPM)		1.8659 ac-ft			
Volume (Ending)		0.0843 ac-ft			
Elevation (Ending)		443.52 ft			
Difference		0.3393 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		14.8 %			



Subsection: Interconnected Pond Routing Summary  
Label: BIO 2  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	447.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.010	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.160	447.61	0.0306	
		Forward Flow Peaks		Reverse Flow Peaks	
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	12.130	2.304	0.000	0.000	
Pond Outflow...	12.160	2.232	0.000	0.000	
		Total Volume In		Total Volume Out	
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	0.2108	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	0.1861	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		0.2108 ac-ft			
Volume (Total Out ICPM)		0.1861 ac-ft			
Volume (Ending)		0.0250 ac-ft			
Elevation (Ending)		447.50 ft			
Difference		-0.0004 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.2 %			



Subsection: Interconnected Pond Routing Summary  
Label: BIO 2  
Scenario: 10 years

Return Event: 10 years  
Storm Event: 10 years - type 3

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	447.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.010	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.140	447.74	0.0366	
		Forward Flow Peaks Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Reverse Flow Peaks Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)
Pond Inflow....		12.120	6.656	0.000	0.000
Pond Outflow...		12.140	6.572	0.000	0.000
		Total Volume In Volume (ac-ft)	Direction	Total Volume Out Volume (ac-ft)	Direction
Pond Inflow....		0.5914	Forward	0.0000	Reverse
Pond Outflow...		0.0000	Reverse	0.5666	Forward
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		0.5914 ac-ft			
Volume (Total Out ICPM)		0.5666 ac-ft			
Volume (Ending)		0.0253 ac-ft			
Elevation (Ending)		447.51 ft			
Difference		-0.0005 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.1 %			



Subsection: Interconnected Pond Routing Summary  
Label: BIO 2  
Scenario: 100 years

Return Event: 100 years  
Storm Event: 100 years - type 3

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	447.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.010	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.090	448.00	0.0498	
		Forward Flow Peaks		Reverse Flow Peaks	
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	12.120	15.016	0.000	0.000	
Pond Outflow...	12.040	11.938	0.000	0.000	
		Total Volume In		Total Volume Out	
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	1.3601	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	1.2654	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		1.3601 ac-ft			
Volume (Total Out ICPM)		1.2654 ac-ft			
Volume (Ending)		0.0256 ac-ft			
Elevation (Ending)		447.52 ft			
Difference		0.0690 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		5.1 %			



Subsection: Interconnected Pond Routing Summary  
Label: DRY POND 1  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	441.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.000	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.680	442.25	0.0622	
		Forward Flow Peaks Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Reverse Flow Peaks Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)
Pond Inflow....		12.230	2.794	0.000	0.000
Pond Outflow...		12.680	0.966	0.000	0.000
		Total Volume In Volume (ac-ft)	Direction	Total Volume Out Volume (ac-ft)	Direction
Pond Inflow....		0.2913	Forward	0.0000	Reverse
Pond Outflow...		0.0000	Reverse	0.2826	Forward
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		0.2913 ac-ft			
Volume (Total Out ICPM)		0.2826 ac-ft			
Volume (Ending)		0.0087 ac-ft			
Elevation (Ending)		441.19 ft			
Difference		0.0000 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.0 %			



Subsection: Interconnected Pond Routing Summary  
Label: DRY POND 1  
Scenario: 10 years

Return Event: 10 years  
Storm Event: 10 years - type 3

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	441.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.000	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.210	443.87	0.1842	
		Forward Flow Peaks		Reverse Flow Peaks	
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	12.100	11.423	0.000	0.000	
Pond Outflow...	12.210	7.641	0.000	0.000	
		Total Volume In		Total Volume Out	
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	0.9302	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	0.9172	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		0.9302 ac-ft			
Volume (Total Out ICPM)		0.9172 ac-ft			
Volume (Ending)		0.0129 ac-ft			
Elevation (Ending)		441.28 ft			
Difference		0.0001 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.0 %			



Subsection: Interconnected Pond Routing Summary  
Label: DRY POND 1  
Scenario: 100 years

Return Event: 100 years  
Storm Event: 100 years - type 3

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	441.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.000	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		11.960	443.96	0.1914	
		Forward Flow Peaks	Reverse Flow Peaks		
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	11.940	11.433	0.000	0.000	
Pond Outflow...	11.960	9.868	0.000	0.000	
		Total Volume In	Total Volume Out		
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	1.8659	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	1.8471	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		1.8659 ac-ft			
Volume (Total Out ICPM)		1.8471 ac-ft			
Volume (Ending)		0.0187 ac-ft			
Elevation (Ending)		441.41 ft			
Difference		0.0001 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.0 %			



Subsection: Interconnected Pond Routing Summary  
Label: DRY POND 2  
Scenario: 1 year

Return Event: 1 years  
Storm Event: 1 year

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	444.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.000	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.290	445.36	0.0130	
		Forward Flow Peaks		Reverse Flow Peaks	
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	12.160	2.232	0.000	0.000	
Pond Outflow...	12.290	1.698	0.000	0.000	
		Total Volume In		Total Volume Out	
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	0.1861	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	0.1852	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		0.1861 ac-ft			
Volume (Total Out ICPM)		0.1852 ac-ft			
Volume (Ending)		0.0009 ac-ft			
Elevation (Ending)		444.12 ft			
Difference		0.0000 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.0 %			



Subsection: Interconnected Pond Routing Summary  
Label: DRY POND 2  
Scenario: 10 years

Return Event: 10 years  
Storm Event: 10 years - type 3

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	444.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.000	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.240	446.97	0.0469	
		Forward Flow Peaks		Reverse Flow Peaks	
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	12.140	6.572	0.000	0.000	
Pond Outflow...	12.240	5.290	0.000	0.000	
		Total Volume In		Total Volume Out	
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	0.5666	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	0.5651	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		0.5666 ac-ft			
Volume (Total Out ICPM)		0.5651 ac-ft			
Volume (Ending)		0.0014 ac-ft			
Elevation (Ending)		444.19 ft			
Difference		0.0000 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.0 %			



Subsection: Interconnected Pond Routing Summary  
Label: DRY POND 2  
Scenario: 100 years

Return Event: 100 years  
Storm Event: 100 years - type 3

Infiltration					
Infiltration Method (Computed)	No Infiltration				
Initial Conditions			Calculation Tolerances		
Elevation (Starting Water Surface Computed)	444.00	ft	Flow Tolerance (Minimum)	0.000	ft <sup>3</sup> /s
Volume (Starting)	0.0000	ac-ft	Maximum Iterations	35	
Outflow (Starting)	0.000	ft <sup>3</sup> /s	ICPM Time Step	0.010	hours
		Time to Peak (hours)	Maximum Storage Elevation (ft)	Volume (ac-ft)	
		12.120	447.98	0.0830	
		Forward Flow Peaks		Reverse Flow Peaks	
	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	Time to Peak (hours)	Flow (Peak) (ft <sup>3</sup> /s)	
Pond Inflow....	12.040	11.938	0.000	0.000	
Pond Outflow...	12.120	9.455	0.000	0.000	
		Total Volume In		Total Volume Out	
	Volume (ac-ft)	Direction	Volume (ac-ft)	Direction	
Pond Inflow....	1.2654	Forward	0.0000	Reverse	
Pond Outflow...	0.0000	Reverse	1.2633	Forward	
Mass Balance (ac-ft)					
Volume (Initial ICPM)		0.0000 ac-ft			
Volume (Total In ICPM)		1.2654 ac-ft			
Volume (Total Out ICPM)		1.2633 ac-ft			
Volume (Ending)		0.0020 ac-ft			
Elevation (Ending)		444.27 ft			
Difference		0.0001 ac-ft			
Percent of Inflow Volume (Interconnected Pond Mass Balance)		0.0 %			



## Index

### B

BIO 1 (Elevation-Area Volume Curve, 1 years (1 year))...40

BIO 1 (Elevation-Area Volume Curve, 1 years)...

BIO 1 (Interconnected Pond Routing Summary, 1 years (1 year))...87

BIO 1 (Interconnected Pond Routing Summary, 1 years)...

BIO 1 (Interconnected Pond Routing Summary, 10 years (10 years))...88

BIO 1 (Interconnected Pond Routing Summary, 10 years)...

BIO 1 (Interconnected Pond Routing Summary, 100 years (100 years))...89

BIO 1 (Interconnected Pond Routing Summary, 100 years)...

BIO 1 UD OUTLET (Outlet Input Data, 1 years (1 year))...45, 46

BIO 1 UD OUTLET (Outlet Input Data, 1 years)...

BIO 2 (Elevation-Area Volume Curve, 1 years (1 year))...41

BIO 2 (Elevation-Area Volume Curve, 1 years)...

BIO 2 (Interconnected Pond Routing Summary, 1 years (1 year))...90

BIO 2 (Interconnected Pond Routing Summary, 1 years)...

BIO 2 (Interconnected Pond Routing Summary, 10 years (10 years))...91

BIO 2 (Interconnected Pond Routing Summary, 10 years)...

BIO 2 (Interconnected Pond Routing Summary, 100 years (100 years))...92

BIO 2 (Interconnected Pond Routing Summary, 100 years)...

BIO 2 UD OUTLET (Outlet Input Data, 1 years (1 year))...47, 48

BIO 2 UD OUTLET (Outlet Input Data, 1 years)...

BIO 3 (Elevation-Area Volume Curve, 1 years (1 year))...42

BIO 3 (Elevation-Area Volume Curve, 1 years)...

BIO 3 (IN) (Multiple Outfall Rating Curves, 1 years (1 year))...49

BIO 3 (IN) (Multiple Outfall Rating Curves, 1 years)...

BIO 3 UD OUTLET (Composite Rating Curve, 1 years (1 year))...52, 53

BIO 3 UD OUTLET (Composite Rating Curve, 1 years)...

BIO 3 UD OUTLET (Outlet Input Data, 1 years (1 year))...50, 51

BIO 3 UD OUTLET (Outlet Input Data, 1 years)...

### C

Composite Outlet Structure - 1 (Outlet Input Data, 1 years (1 year))...54, 55

Composite Outlet Structure - 1 (Outlet Input Data, 1 years)...



Composite Outlet Structure - 2 (Outlet Input Data, 1 years (1 year))...56, 57

Composite Outlet Structure - 2 (Outlet Input Data, 1 years)...

Composite Outlet Structure - 3 (Composite Rating Curve, 1 years (1 year))...62, 63

Composite Outlet Structure - 3 (Composite Rating Curve, 1 years)...

Composite Outlet Structure - 3 (Outlet Input Data, 1 years (1 year))...58, 59, 60, 61

Composite Outlet Structure - 3 (Outlet Input Data, 1 years)...

D

DA-1A (Runoff CN-Area, 1 years (1 year))...30

DA-1A (Runoff CN-Area, 1 years)...

DA-1A (Time of Concentration Calculations, 1 years (1 year))...10, 11

DA-1A (Time of Concentration Calculations, 1 years)...

DA-1B (Runoff CN-Area, 1 years (1 year))...31

DA-1B (Runoff CN-Area, 1 years)...

DA-1B (Time of Concentration Calculations, 1 years (1 year))...12, 13

DA-1B (Time of Concentration Calculations, 1 years)...

DA-1C (Runoff CN-Area, 1 years (1 year))...32

DA-1C (Runoff CN-Area, 1 years)...

DA-1C (Time of Concentration Calculations, 1 years (1 year))...14, 15

DA-1C (Time of Concentration Calculations, 1 years)...

DA-1D (Runoff CN-Area, 1 years (1 year))...33

DA-1D (Runoff CN-Area, 1 years)...

DA-1D (Time of Concentration Calculations, 1 years (1 year))...16, 17

DA-1D (Time of Concentration Calculations, 1 years)...

DA-2A (Runoff CN-Area, 1 years (1 year))...34

DA-2A (Runoff CN-Area, 1 years)...

DA-2A (Time of Concentration Calculations, 1 years (1 year))...18, 19

DA-2A (Time of Concentration Calculations, 1 years)...

DA-2B (Runoff CN-Area, 1 years (1 year))...35

DA-2B (Runoff CN-Area, 1 years)...

DA-2B (Time of Concentration Calculations, 1 years (1 year))...20, 21

DA-2B (Time of Concentration Calculations, 1 years)...

DA-3 (Runoff CN-Area, 1 years (1 year))...36

DA-3 (Runoff CN-Area, 1 years)...



DA-3 (Time of Concentration Calculations, 1 years (1 year))...22, 23

DA-3 (Time of Concentration Calculations, 1 years)...

DA-4 (Runoff CN-Area, 1 years (1 year))...37

DA-4 (Runoff CN-Area, 1 years)...

DA-4 (Time of Concentration Calculations, 1 years (1 year))...24, 25

DA-4 (Time of Concentration Calculations, 1 years)...

DA-5A (Runoff CN-Area, 1 years (1 year))...38

DA-5A (Runoff CN-Area, 1 years)...

DA-5A (Time of Concentration Calculations, 1 years (1 year))...26, 27

DA-5A (Time of Concentration Calculations, 1 years)...

DA-5B (Runoff CN-Area, 1 years (1 year))...39

DA-5B (Runoff CN-Area, 1 years)...

DA-5B (Time of Concentration Calculations, 1 years (1 year))...28, 29

DA-5B (Time of Concentration Calculations, 1 years)...

DRY POND 1 (Elevation-Area Volume Curve, 1 years (1 year))...43

DRY POND 1 (Elevation-Area Volume Curve, 1 years)...

DRY POND 1 (Interconnected Pond Routing Summary, 1 years (1 year))...93

DRY POND 1 (Interconnected Pond Routing Summary, 1 years)...

DRY POND 1 (Interconnected Pond Routing Summary, 10 years (10 years))...94

DRY POND 1 (Interconnected Pond Routing Summary, 10 years)...

DRY POND 1 (Interconnected Pond Routing Summary, 100 years (100 years))...95

DRY POND 1 (Interconnected Pond Routing Summary, 100 years)...

DRY POND 1 OUTLET STRUCTURE (Composite Rating Curve, 1 years (1 year))...68, 69, 70, 71, 72, 73, 74, 75

DRY POND 1 OUTLET STRUCTURE (Composite Rating Curve, 1 years)...

DRY POND 1 OUTLET STRUCTURE (Outlet Input Data, 1 years (1 year))...64, 65, 66, 67

DRY POND 1 OUTLET STRUCTURE (Outlet Input Data, 1 years)...

DRY POND 2 (Elevation-Area Volume Curve, 1 years (1 year))...44

DRY POND 2 (Elevation-Area Volume Curve, 1 years)...

DRY POND 2 (Interconnected Pond Routing Summary, 1 years (1 year))...96

DRY POND 2 (Interconnected Pond Routing Summary, 1 years)...

DRY POND 2 (Interconnected Pond Routing Summary, 10 years (10 years))...97

DRY POND 2 (Interconnected Pond Routing Summary, 10 years)...

DRY POND 2 (Interconnected Pond Routing Summary, 100 years (100 years))...98



DRY POND 2 (Interconnected Pond Routing Summary, 100 years)...

DRY POND 2 OUTLET STRUCTURE (Composite Rating Curve, 1 years (1 year))...80, 81, 82, 83, 84, 85, 86

DRY POND 2 OUTLET STRUCTURE (Composite Rating Curve, 1 years)...

DRY POND 2 OUTLET STRUCTURE (Outlet Input Data, 1 years (1 year))...76, 77, 78, 79

DRY POND 2 OUTLET STRUCTURE (Outlet Input Data, 1 years)...

M

Master Network Summary...2, 3

T

Time-Depth - 1 (Time-Depth Curve, 1 years (1 year))...4, 5

Time-Depth - 1 (Time-Depth Curve, 1 years)...

Time-Depth - 1 (Time-Depth Curve, 10 years (10 years))...6, 7

Time-Depth - 1 (Time-Depth Curve, 10 years)...

Time-Depth - 1 (Time-Depth Curve, 100 years (100 years))...8, 9

Time-Depth - 1 (Time-Depth Curve, 100 years)...







# APPENDIX G

Water Quality Volume and Runoff Reduction Volume Computations







Is this project subject to Chapter 10 of the NYS Design Manual (i.e. WQv is equal to post-development 1 year runoff volume)?.....

Design Point:	1					
P=	2.80	inch				
Breakdown of Subcatchments						
Catchment Number	Total Area (Acres)	Impervious Area (Acres)	Percent Impervious %	Rv	WQv (ft <sup>3</sup> )	Description
1	1.91	0.60	31%	0.33	6,459	Bioretention 1A
2	0.60	0.18	30%	0.32	1,951	Bioretention 1B
3	0.53	0.18	34%	0.36	1,916	Bioretention2B
4	8.16	0.14	2%	0.07	5,428	Tree Planting/Tree Pit DA 1C+1D+2A+3+5A+5B
5						
6						
7						
8						
9						
10						
Subtotal (1-30)	11.20	1.10	10%	0.14	15,754	Subtotal 1
Total	11.20	1.10	10%	0.14	15,754	Initial WQv

Identify Runoff Reduction Techniques By Area			
Technique	Total Contributing Area	Contributing Impervious Area	Notes
	(Acre)	(Acre)	
Conservation of Natural Areas	0.00	0.00	minimum 10,000 sf
Riparian Buffers	0.00	0.00	maximum contributing length 75 feet to 150 feet
Filter Strips	0.00	0.00	
Tree Planting	8.16	0.14	Up to 100 sf directly connected impervious area may be subtracted per tree
Total	8.16	0.14	

Recalculate WQv after application of Area Reduction Techniques					
	Total Area (Acres)	Impervious Area (Acres)	Percent Impervious %	Runoff Coefficient Rv	WQv (ft <sup>3</sup> )
"<<Initial WQv"	11.20	1.10	10%	0.14	15,754
Subtract Area	-8.16	-0.14			
WQv adjusted after Area Reductions	3.04	0.96	32%	0.33	10,327
Disconnection of Rooftops		0.00			



Runoff Reduction Volume and Treated volumes						
	Runoff Reduction Techniques/Standard SMPs		Total Contributing Area	Total Contributing Impervious Area	WQv Reduced (RRv)	WQv Treated
			(acres)	(acres)	cf	cf
Area/Volume Reduction	Conservation of Natural Areas	RR-1	0.00	0.00		
	Sheetflow to Riparian Buffers/Filter Strips	RR-2	0.00	0.00		
	Tree Planting/Tree Pit	RR-3	8.16	0.14		
	Disconnection of Rooftop Runoff	RR-4		0.00		
	Vegetated Swale	RR-5	0.00	0.00	0	
	Rain Garden	RR-6	0.00	0.00	0	
	Stormwater Planter	RR-7	0.00	0.00	0	
	Rain Barrel/Cistern	RR-8	0.00	0.00	0	
	Porous Pavement	RR-9	0.00	0.00	0	
	Green Roof (Intensive & Extensive)	RR-10	0.00	0.00	0	
Standard SMPs w/RRv Capacity	Infiltration Trench	I-1	0.00	0.00	0	0
	Infiltration Basin	I-2	0.00	0.00	0	0
	Dry Well	I-3	0.00	0.00	0	0
	Underground Infiltration System	I-4				
	Bioretention & Infiltration Bioretention	F-5	3.04	0.96	4723	5603
	Dry swale	O-1	0.00	0.00	0	0
Standard SMPs	Micropool Extended Detention (P-1)	P-1				
	Wet Pond (P-2)	P-2				
	Wet Extended Detention (P-3)	P-3				
	Multiple Pond system (P-4)	P-4				
	Pocket Pond (p-5)	P-5				
	Surface Sand filter (F-1)	F-1				
	Underground Sand filter (F-2)	F-2				
	Perimeter Sand Filter (F-3)	F-3				
	Organic Filter (F-4)	F-4				
	Shallow Wetland (W-1)	W-1				
	Extended Detention Wetland (W-2)	W-2				
	Pond/Wetland System (W-3)	W-3				
	Pocket Wetland (W-4)	W-4				
	Wet Swale (O-2)	O-2				
Totals by Area Reduction →			8.16	0.14	5428	
Totals by Volume Reduction →			0.00	0.00	0	
Totals by Standard SMP w/RRV →			3.04	0.96	4723	5603
Totals by Standard SMP →			0.00	0.00		0
Totals ( Area + Volume + all SMPs) →			11.20	1.10	10,151	5,603
	Impervious Cover v	okay				



# Minimum RRv

Enter the Soils Data for the site

Soil Group	Acres	S
A		55%
B		40%
C	100.00	30%
D		20%
Total Area	100	

Calculate the Minimum RRv

S =	0.30	
Impervious =	1.10	<i>acre</i>
Precipitation	2.8	<i>in</i>
Rv	0.95	
Minimum RRv	3,186	<i>ft3</i>
	0.07	<i>af</i>



# NOI QUESTIONS

#	NOI Question	Reported Value	
		cf	af
28	Total Water Quality Volume (WQv) Required	15754	0.362
30	Total RRV Provided	10151	0.233
31	Is RRV Provided $\geq$ WQv Required?	No	
32	Minimum RRV	3186	0.073
32a	Is RRV Provided $\geq$ Minimum RRV Required?	Yes	
33a	Total WQv Treated	5603	0.129
34	Sum of Volume Reduced & Treated	15754	0.362
34	Sum of Volume Reduced and Treated	15754	0.362
35	Is Sum RRV Provided and WQv Provided $\geq$ WQv Required?	Yes	

Apply Peak Flow Attenuation			
36	Channel Protection	$C_{pv}$	
37	Overbank	$Q_p$	
37	Extreme Flood Control	$Q_f$	
	Are Quantity Control requirements met?		



# Bioretention Worksheet

(For use on HSG C or D Soils with underdrains)

$$Af = WQv * (df) / [k * (hf + df)(tf)]$$

<i>Af</i>	Required Surface Area (ft <sup>2</sup> )		The hydraulic conductivity [ft/day], can be varied depending on the properties of the soil media. Some reported conductivity values are: <i>Sand</i> - 3.5 ft/day (City of Austin 1988); <i>Peat</i> - 2.0 ft/day (Galli 1990); <i>Leaf Compost</i> - 8.7 ft/day (Claytor and Schueler, 1996); <i>Bioretention Soil</i> (0.5 ft/day (Claytor &
<i>WQv</i>	Water Quality Volume (ft <sup>3</sup> )		
<i>df</i>	Depth of the Soil Medium (feet)	<i>k</i>	
<i>hf</i>	Average height of water above the planter bed		
<i>tf</i>	Volume Through the Filter Media (days)		

Design Point:	1						
Enter Site Data For Drainage Area to be Treated by Practice							
Catchment Number	Total Area (Acres)	Impervious Area (Acres)	Percent Impervious %	Rv	WQv (ft <sup>3</sup> )	Precipitation (in)	Description
1	1.91	0.60	0.31	0.33	6459.22	2.80	Bioretention 1A
Enter Impervious Area Reduced by Disconnection of Rooftops			31%	0.33	6,459	<<WQv after adjusting for Disconnected Rooftops	
Enter the portion of the WQv that is not reduced for all practices routed to this practice.						ft <sup>3</sup>	
Soil Information							
Soil Group		C					
Soil Infiltration Rate		0.00	in/hour	Okay			
Using Underdrains?		Yes	Okay				
Calculate the Minimum Filter Area							
				Value	Units	Notes	
WQv				6,459	ft <sup>3</sup>		
Enter Depth of Soil Media			<i>df</i>	2.5	ft	2.5-4 ft	
Enter Hydraulic Conductivity			<i>k</i>	0.5	ft/day		
Enter Average Height of Ponding			<i>hf</i>	0.5	ft	6 inches max.	
Enter Filter Time			<i>tf</i>	2	days		
Required Filter Area			<i>Af</i>	5383	ft <sup>2</sup>		
Determine Actual Bio-Retention Area							
Filter Width		30	ft				
Filter Length		210	ft				
Filter Area		6300	ft <sup>2</sup>				
Actual Volume Provided		7560	ft <sup>3</sup>				
Determine Runoff Reduction							
Is the Bioretention contributing flow to another practice?				Select Practice			
RRv		3,024					
RRv applied		3,024	ft <sup>3</sup>	This is 40% of the storage provided or WQv whichever is less.			
Volume Treated		3,435	ft <sup>3</sup>	This is the portion of the WQv that is not reduced in the practice.			
Volume Directed		0	ft <sup>3</sup>	This volume is directed another practice			
Sizing v		OK	Check to be sure Area provided ≥ Af				



# Bioretention Worksheet

(For use on HSG C or D Soils with underdrains)

$$Af = WQv * (df) / [k * (hf + df)(tf)]$$

**Af** Required Surface Area (ft<sup>2</sup>)  
**WQv** Water Quality Volume (ft<sup>3</sup>)  
**df** Depth of the Soil Medium (feet)  
**hf** Average height of water above the planter bed  
**tf** Volume Through the Filter Media (days)

**k** The hydraulic conductivity [ft/day], can be varied depending on the properties of the soil media. Some reported conductivity values are: *Sand* - 3.5 ft/day (City of Austin 1988); *Peat* - 2.0 ft/day (Galli 1990); *Leaf Compost* - 8.7 ft/day (Claytor and Schueler, 1996); *Bioretention Soil* (0.5 ft/day (Claytor & Schueler, 1996)

Design Point:	1						
Enter Site Data For Drainage Area to be Treated by Practice							
Catchment Number	Total Area (Acres)	Impervious Area (Acres)	Percent Impervious %	Rv	WQv (ft <sup>3</sup> )	Precipitation (in)	Description
2	0.60	0.18	0.30	0.32	1951.49	2.80	Bioretention 1B
Enter Impervious Area Reduced by Disconnection of Rooftops			30%	0.32	1,951	<<WQv after adjusting for Disconnected Rooftops	
Enter the portion of the WQv that is not reduced for all practices routed to this practice.						ft <sup>3</sup>	
Soil Information							
Soil Group	C						
Soil Infiltration Rate	0.00	in/hour	Okay				
Using Underdrains?	Yes	Okay					
Calculate the Minimum Filter Area							
			Value	Units	Notes		
WQv			1,951	ft <sup>3</sup>			
Enter Depth of Soil Media			df	2.5	ft	2.5-4 ft	
Enter Hydraulic Conductivity			k	0.5	ft/day		
Enter Average Height of Ponding			hf	0.5	ft	6 inches max.	
Enter Filter Time			tf	2	days		
Required Filter Area			Af	1626	ft <sup>2</sup>		
Determine Actual Bio-Retention Area							
Filter Width	15	ft					
Filter Length	116	ft					
Filter Area	1740	ft <sup>2</sup>					
Actual Volume Provided	2088	ft <sup>3</sup>					
Determine Runoff Reduction							
Is the Bioretention contributing flow to another practice?				Select Practice			
RRv	835						
RRv applied	835	ft <sup>3</sup>	This is 40% of the storage provided or WQv whichever is less.				
Volume Treated	1,116	ft <sup>3</sup>	This is the portion of the WQv that is not reduced in the practice.				
Volume Directed	0	ft <sup>3</sup>	This volume is directed another practice				
Sizing v	OK	Check to be sure Area provided ≥ Af					



# Bioretention Worksheet

(For use on HSG C or D Soils with underdrains)

$$Af = WQv * (df) / [k * (hf + df)(tf)]$$

<i>Af</i>	Required Surface Area (ft <sup>2</sup> )	<i>k</i>	The hydraulic conductivity [ft/day], can be varied depending on the properties of the soil media. Some reported conductivity values are: <i>Sand</i> - 3.5 ft/day (City of Austin 1988); <i>Peat</i> - 2.0 ft/day (Galli 1990); <i>Leaf Compost</i> - 8.7 ft/day (Claytor and Schueler, 1996); <i>Bioretention Soil</i> (0.5 ft/day (Claytor &
<i>WQv</i>	Water Quality Volume (ft <sup>3</sup> )		
<i>df</i>	Depth of the Soil Medium (feet)		
<i>hf</i>	Average height of water above the planter bed		
<i>tf</i>	Volume Through the Filter Media (days)		

Design Point:	1						
Enter Site Data For Drainage Area to be Treated by Practice							
Catchment Number	Total Area (Acres)	Impervious Area (Acres)	Percent Impervious %	Rv	WQv (ft <sup>3</sup> )	Precipitation (in)	Description
3	0.53	0.18	0.34	0.36	1915.91	2.80	Bioretention2B
Enter Impervious Area Reduced by Disconnection of Rooftops			34%	0.36	1,916	<<WQv after adjusting for Disconnected Rooftops	
Enter the portion of the WQv that is not reduced for all practices routed to this practice.						ft <sup>3</sup>	
Soil Information							
Soil Group	C						
Soil Infiltration Rate	0.00	in/hour	Okay				
Using Underdrains?	Yes	Okay					
Calculate the Minimum Filter Area							
			Value	Units	Notes		
WQv			1,916	ft <sup>3</sup>			
Enter Depth of Soil Media			<i>df</i>	2.5	ft	2.5-4 ft	
Enter Hydraulic Conductivity			<i>k</i>	0.5	ft/day		
Enter Average Height of Ponding			<i>hf</i>	0.5	ft	6 inches max.	
Enter Filter Time			<i>tf</i>	2	days		
Required Filter Area			<i>Af</i>	1597	ft <sup>2</sup>		
Determine Actual Bio-Retention Area							
Filter Width	15	ft					
Filter Length	120	ft					
Filter Area	1800	ft <sup>2</sup>					
Actual Volume Provided	2160	ft <sup>3</sup>					
Determine Runoff Reduction							
Is the Bioretention contributing flow to another practice?				Select Practice			
RRv	864						
RRv applied	864	ft <sup>3</sup>	This is 40% of the storage provided or WQv whichever is less.				
Volume Treated	1,052	ft <sup>3</sup>	This is the portion of the WQv that is not reduced in the practice.				
Volume Directed	0	ft <sup>3</sup>	This volume is directed another practice				
Sizing v	OK	Check to be sure Area provided ≥ Af					



# Tree Planting/Tree Pits

Design Point:	1						
Enter Site Data For Drainage Area to be Treated by Practice							
Catchment Number	Total Area (Acres)	Impervious Area (Acres)	Percent Impervious %	Rv	WQv (ft <sup>3</sup> )	Precipitation (in)	Description
4	8.16	0.14	0.02	0.07	5427.58	2.80	Tree Planting/Tree Pit DA 1C+1D+2A+3+5A+5B
Do you intend to use this practice for area reduction or volume reduction?			Area	Design practice using criteria below			
Design Elements							
Is another area based practice applied to this area?			No				
Diameter of Mature Canopy			16	ft			
Area Reduced per Tree			100	sf	For up to a 16-foot diameter canopy of a mature tree, the area considered for reduction shall be ½ the area of the tree		
Number of Trees			61				
Total Area Reduced			6129.28	sf			
			0.14	af	Okay		
Area Ratio: Total to Impervious area			58.3		Okay		
Are All Criteria in Section 5.3.4 met?			Yes				
Area Reduction Adjustments							
Subtract			8.16	Acres from total Area			
Subtract			0.14	Acres from total Impervious Area			



Completed By: JMC  
 Checked By:  
 Project Name: John Jay

Job No 80675  
 Page 1 of  
 Date: May-24

Subject: Precast Concrete Structures - Buoyancy Calculations

#### Outlet Control Structure Dry Pond #1

Structure Characteristics		
Diameter =	5.0	feet
Height =	8.5	feet
Wall Thickness =	0.67	feet
Extended Base =	0.5	feet
Top Slab Thickness =	0.67	feet
Base Thickness =	0.5	feet
Access Opening Dia. =	4	feet
Hatch Opening Length =	0	feet
Ground Water Depth =	3.8	feet
Unit Weight of Concrete =	150.0	lbs/cf
Unit Weight of Soil =	120.0	lbs/cf
Unit Weight of Water =	62.4	lbs/cf

Structure Top Slab Weight Calculation		
Area =	32	sf
Area of Hatch Opening =	13	sf
Net Area =	19	sf
Volume =	13	cf
Weight =	1,904	lbs

Structure Body Weight Calculation		
Area =	12	sf
Volume =	93	cf
Weight =	13,947	lbs

Manhole Base Weight Calculation		
Area =	42	sf
Volume =	21	cf
Weight =	3,168	lbs


Total Weight of Wetwell = 19019 lbs

Soil Weight Calculation (buoyancy on soil is subtracted)		
Area =	11	sf
Volume =	91	cf
Weight =	5,256	lbs

Total Resistant Force = 24,275 lbs

Buoyancy Force Calculation		
Volume Displaced By Structure =	206	cf
Weight =	12,879	lbs

Factor of Safety = 1.88 O.K.





Completed By: JMC  
 Checked By:  
 Project Name: John Jay

Job No 80675  
 Page 2 of  
 Date: May-24

Subject: Precast Concrete Structures - Buoyancy Calculations

Outlet Control Structure Dry Pond #2

Structure Characteristics			
Diameter =	5.0	feet	
Height =	5.5	feet	
Wall Thickness =	0.67	feet	
Extended Base =	0.5	feet	
Top Slab Thickness =	0.67	feet	
Base Thickness =	0.5	feet	
Access Opening Dia. =	4	feet	
Hatch Opening Length =	0	feet	
Ground Water Depth =	1.8	feet	
Unit Weight of Concrete =	150.0	lbs/cf	
Unit Weight of Soil =	120.0	lbs/cf	
Unit Weight of Water =	62.4	lbs/cf	

Structure Top Slab Weight Calculation			
Area =	32	sf	
Area of Hatch Opening =	13	sf	
Net Area =	19	sf	
Volume =	13	cf	
Weight =	1,904	lbs	

Structure Body Weight Calculation			
Area =	12	sf	
Volume =	57	cf	
Weight =	8,514	lbs	

Manhole Base Weight Calculation			
Area =	42	sf	
Volume =	21	cf	
Weight =	3,168	lbs	


Total Weight of Wetwell = 13586 lbs

Soil Weight Calculation (buoyancy on soil is subtracted)			
Area =	11	sf	
Volume =	59	cf	
Weight =	3,370	lbs	

Total Resistant Force = 16,956 lbs

Buoyancy Force Calculation			
Volume Displaced By Structure =	150	cf	
Weight =	9,332	lbs	

Factor of Safety = 1.82 O.K.





<b>Completed By:</b>	JMC	<b>Job No</b>	80675
<b>Checked By:</b>		<b>Page</b>	3 of
<b>Project Name:</b>	John Jay	<b>Date:</b>	May-24
<b>Subject:</b>			

### Outlet Control Structure Bioretention #3

Worst case scenario for the purposes of this design is a water surface elevation equal to the top of structure.

Outfall Structure Characteristics		
Width (ID) =	4	feet
Length (ID) =	4	feet
Height =	4.50	feet
Wall Thickness =	0.67	feet
Extended Base =	0.5	feet
Top Slab Thickness =	0.667	feet
Base Thickness =	0.5	feet
Hatch Opening Width =	3.5	feet
Hatch Opening Length =	3.5	feet
Unit Weight of Concrete =	150.0	lbs/cf
Unit Weight of Soil =	120.0	lbs/cf
Unit Weight of Water =	62.4	lbs/cf

Top Slab Weight Calculation		
Area =	28.5	sf
Area of Hatch Opening =	12	sf
Net Area =	16	sf
Volume =	11	cf
Weight =	1,621	lbs

Outfall Structure Body Weight Calculation		
Area =	12.5	
Volume =	56	cf
Weight =	8,405	lbs

Base Weight Calculation		
Area =	40.1	sf
Volume =	20	cf
Weight =	3,009	lbs

**Total Weight of Structure = 13035 lbs**


<sup>1</sup> Soil Weight Calculation (buoyancy on soil is subtracted)		
Area =	11.7	sf
Volume =	26	cf
Weight =	1,512	lbs

**Total Resistant Force = 14,547 lbs**

Buoyancy Force Calculation		
Volume Displaced By Wetwell =	148	cf
Weight =	9,241	lbs

**Factor of Safety = 1.57 O.K.**

<sup>1</sup> Weight of soil is conservatively estimated as a rectangular column over the footprint of the extended base.









# APPENDIX H

Phasing Plan, Grading and Drainage Plan  
and ESC Plan and Details











Gouverneur Kathy HochulCommissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ADDRESS, AND SIGNATURE OF THE ARCHITECT/ENGINEER.

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 10TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06858

**Civil Consultant**  
CHA CONSULTING, INC.  
3 WINNERS CIRCLE, COLONIE, NY 12526

**Landscape Consultant**  
RHODES HARTWELL LANDSCAPE ARCHITECTURE  
347 WEST 30TH STREET, SUITE 1201, NEW YORK, NY 10001

**Lighting Consultant**  
HLB LIGHTING  
30 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10001

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071




**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson


**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536



REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

- Phase 1 (22.94 acres)**
- Establish work area, contractor staging area, and install stabilized temporary construction entrance.
  - Install temporary erosion and sediment control measures as shown on plans.
  - Remove asphalt entrance drive and subbase as shown on demolition plans.
  - Remove entrance gate and other amenities as shown on demolition plans.
  - Install topsoil, seed, and mulch for final stabilization.
- Phase 2A (14.96 acres)**
- Establish work area, contractor staging area, and install stabilized temporary construction entrance.
  - Install temporary erosion and sediment control measures as shown on plans.
  - Rough grade site for proposed access road and parking lot area.
  - Grade and construct the proposed stormwater bioretention and dry ponds.
  - Fine grade site and install subbase to stabilize disturbed areas.
  - Construct the proposed parking lot, gravel road, walkway and ramps as shown on layout plans.
  - Install proposed landscaping, topsoil, and seed for final stabilization of all disturbed areas.
- Phase 2B (13.68 acres)**
- Establish work area, contractor staging area, and install stabilized temporary construction entrance.
  - Install temporary erosion and sediment control measures as shown on plans.
  - Remove existing gravel loop drive and other amenities as shown on demolition plans.
  - Grade and install proposed chip seal road as shown on plans.
  - Grade and install proposed chip seal walkways as shown on plans.
  - Repair and renovate the existing John Jay House.
  - Install proposed trees and landscaping, topsoil, and seed for final stabilization of all disturbed areas.
- Note: Contractor shall not disturb more than 5 acres at one time.



Drawn By: HB	Seal and Signature
Design By: JJE	
Checked By: JJE	
Approved By: SKB	
DATE 04/10/24	<b>Drawing Number</b>  <b>C-002</b>
<b>Sheet Title</b>  Phasing plan	
Project Number: D006292	Sheet: XXX of 367





Gouverneur Kathy HochulCommissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CHA CONSULTING, INC.  
3 WINNERS CIRCLE, COLOMBE, NY 12028

**Landscape Consultant**  
RHODES HARTWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1001, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
35 EAST 30TH STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By:  
HB

Design By:  
JJE

Checked By:  
JJE

Approved By:  
SKB

DATE  
04/10/24

Seal and Signature

**Sheet Title**

SITE GRADING,  
DRAINAGE AND  
EROSION CONTROL  
PLAN (1 OF 6)


**Drawing Number**

C-301

Project Number:  
D006292

Sheet:  
XXX of 367







New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy HochulCommissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

Architectural Consultant

BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

BEYER  
BLINDER  
BELLE

Structural Consultant

THORNTON TOMASETTI  
100 BROADWAY, 16TH FLOOR, NEW YORK, NY 10071

Thornton  
Tomasetti

MEP / FP / IT Consultant

LANDMARKS FACILITIES GROUP  
250 EAST AVENUE, NORWALK, CT 06855

LFG  
LANDMARKS  
FACILITIES  
GROUP, INC.

Civil Consultant

CNA CONSULTING, INC.  
3 WINNERS CIRCLE, COLONE, NY 12026

CNA

Landscape Consultant

RHODESSE HANWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

RHI

Lighting Consultant

HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

HLB

Signage Consultant

LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

LVCK

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building  
Enhancements

**Project Location:**  
Katonah  
NY 10536


**Key Plan**

REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By: HB	Seal and Signature
Design By JJE	
Checked By: JJE	
Approved By: SKB	
DATE 04/10/24	
<b>Sheet Title</b>  SITE GRADING, DRAINAGE AND EROSION CONTROL PLAN (2 OF 6)	<b>Drawing Number</b>  C-302
Project Number: D006292	Sheet: XXX of 367

Volume 5: Page 326 of 492





New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06850

**Civil Consultant**  
CHA CONSULTING, INC.  
3 WINNERS CIRCLE, COLOMBE, NY 12028

**Landscape Consultant**  
RHODES HARTWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1001, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
30 EAST 30TH STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By: HB	Seal and Signature
Design By: JJE	
Checked By: JJE	
Approved By: SKB	
DATE 04/10/24	
<b>Sheet Title</b>  SITE GRADING, DRAINAGE AND EROSION CONTROL PLAN (3 OF 6)	<b>Drawing Number</b>  <b>C-303</b>

Project Number: D006292      Sheet: XXX of 367



**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

BEYER  
BLINDER  
BELLE

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

Thornton  
Tomasetti

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06855

LFG  
LANDMARKS  
FACILITIES  
GROUP

**Civil Consultant**  
CHA CONSULTING, INC.  
3 WINNERS CIRCLE, COLOMBE, NY 12028

CHA

**Landscape Consultant**  
RHODESIE HANWELL LANDSCAPE ARCHITECTURE  
341 WEST 30TH STREET, SUITE 1201, NEW YORK, NY 10018

RHI

**Lighting Consultant**  
HLB LIGHTING  
30 EAST 30TH STREET, 11TH FLOOR, NEW YORK, NY 10018

HLB

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071


LVCK

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building  
Enhancements

**Project Location:**  
Katonah  
NY 10536



REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By:  
HB

Design By:  
JJE

Checked By:  
JJE

Approved By:  
SKB

DATE  
04/10/24

Seal and Signature

**Sheet Title**


SITE GRADING,  
DRAINAGE AND  
EROSION CONTROL  
PLAN (4 OF 6)

**Drawing Number**

C-304

Project Number:  
D006292

Sheet:  
XXX of 367



0 20 40  
Scale in feet





New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy HochulCommissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, AFFIXED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
202 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CHA CONSULTING, INC.  
3 WINNERS CIRCLE, COLOMBE, NY 12028

**Landscape Consultant**  
RHODESIE HANWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
35 EAST 30TH STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**BEYER BLINDER BELLE**

**Thornton Tomasetti**

**LFG**

**CHA**

**RHI**

**HLB**

**LVCK**

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements


**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By: HB	Seal and Signature
Design By JJE	
Checked By: JJE	
Approved By: SKB	
DATE 04/10/24	
<b>Sheet Title</b>  SITE GRADING, DRAINAGE AND EROSION CONTROL PLAN (5 OF 6)	<b>Drawing Number</b>  <b>C-305</b>
Project Number: D006292	Sheet: XXX of 367





Gouverneur Kathy HochulCommissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

Architectural Consultant

BEYER BLINDER BELLE

Structural Consultant

Thornton Tomasetti

MEP / FP / IT Consultant

LFC

Civil Consultant

CNA

Landscape Consultant

RHI

Lighting Consultant

HLB

Signage Consultant


LVCK

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements



**Project Location:**  
Katonah  
NY 10536



REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By: HB	Seal and Signature
Design By: JJE	
Checked By: JJE	
Approved By: SKB	
DATE 04/10/24	
<b>Sheet Title</b>  SITE GRADING, DRAINAGE AND EROSION CONTROL PLAN (6 OF 6)	<b>Drawing Number</b>  C-306
Project Number: D006292	Sheet: XXX of 367






- NOTES:
- CONTRACTOR SHALL INSTALL SURFACE AGGREGATE IN SINGLE COURSE AS SHOWN, WITH FINAL IN-PLACE COMPACTED DEPTH  $\frac{1}{4}$ "- $\frac{3}{8}$ ".
  - PROVIDE FLUSH AND SMOOTH TRANSITION WHERE CHIP SEAL MEETS ADJACENT SURFACES.
  - PROVIDE MOCK UP FOR DIRECTOR'S REPRESENTATIVE APPROVAL.

#### 1 TAR AND CHIP ASPHALT PAVEMENT

SCALE: N.T.S.




#### NOTES:

- ALL MATERIALS AND INSTALLATION SHALL CONFORM TO MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), LATEST EDITION.
- ALL SIGNS SHALL BE MIN. 3'-0" OFF EDGE OF GRAVEL OR PAVEMENT ABOE.
- U-CHANNEL POSTS TO BE USED FOR ALL SIGNS WITHIN RIGHT-OF-WAY AND SHALL BE DRIVEN INTO GROUND.
- REFER TO WAYFINDING DRAWINGS FOR SIGNAGE ARTWORK AND PAINT COLOR.

#### 2 SIGN POST INSTALLATION DETAIL


SCALE: N.T.S.

SITE SIGN TABLE			
SIGN NO.	DESCRIPTION	M.U.T.C.D. NO./SIZE	QUANTITY
1	STOP	R1-1 30"x30"	X
2	RESERVED PARKING	R7-1 12"x18"	4
3	VAN ACCESSIBLE	R7-8 (12"x18")	2
4	NO PARKING	R7-1 12"x18"	2
5	ELECTRIC VEHICLE CHARGING STATION	R7-1 12"x18"	8



#### 3 ACCESSIBLE PARKING SPACE & TYPICAL STRIPING DETAIL


SCALE: NO SCALE



- NOTES:
- INSTALL SO THAT LONG DIRECTION OF UNITS IS PERPENDICULAR TO THE DIRECTION OF TRAFFIC. DEVELOP STAGGERED LAYING PATTERN USING HALF GEOBLOCK UNITS MADE BY FIELD CUTTING A FULL UNIT.
  - INSTALL WITH SQUARE HOLE TOWARD GROUND.
  - UNITS SHOULD HAVE FULL TONGUE-AND-GROOVE INTERLOCK AS INSTALLED.


#### 4 REINFORCED TURF DETAIL

SCALE: N.T.S.




#### 5 PAVEMENT TRANSITION DETAIL

SCALE: N.T.S.




#### 6 GRANITE CURB DETAIL

SCALE: N.T.S.



#### 7 FLUSH GRANITE CURB

SCALE: N.T.S.



#### 8 GRANITE CURB TERMINATION DETAIL

SCALE: N.T.S.

Gouverneur Kathy HochulCommissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, AFFIXED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CHA CONSULTING, INC.  
3 WINNERS CIRCLE, COLOMBE, NY 12038

**Landscape Consultant**  
RHODESSE HAWWELL LANDSCAPE ARCHITECTURE  
347 WEST 36TH STREET, SUITE 1001, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
35 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By:  
HB

Design By:  
JJE

Checked By:  
JJE

Approved By:  
SKB

DATE  
04/10/24

Seal and Signature

**Sheet Title**

DETAILS (1 OF 5)


**Drawing Number**

C-600

Project Number:  
D006292

Sheet:  
XXX of 367






NOTE:  
EROSION CONTROL BLANKETS TO BE INSTALLED ON SLOPES 3:1 OR GREATER (TYP.)

#### 1 EROSION CONTROL BANK STABILIZATION DETAIL


SCALE: N.T.S.

TYPICAL BERM FOR MINIMAL GRADES SHOWN.  
FOR STEEPER GRADES, I.E. 2:1 SLOPES  
INCREASE BERM SIZE AS DETERMINED ON  
SITE BY REPRESENTATIVE.



#### 2 TEMPORARY STOCK PILE

NOT TO SCALE



#### 3 CONCRETE WASHOUT AREA


SCALE: N.T.S.

#### MAINTENANCE NOTES:

1. ALL CONCRETE WASHOUT FACILITIES SHALL BE INSPECTED DAILY. DAMAGED OR LEAKING FACILITIES SHALL BE DEACTIVATED AND REPAIRED OR REPLACED IMMEDIATELY. EXCESS RAINWATER THAT HAS ACCUMULATED OVER HARDENED CONCRETE SHALL BE PUMPED TO A STABILIZED AREA SUCH AS A GRASS FILTER STRIP.
2. ACCUMULATED HARDENED MATERIAL SHALL BE REMOVED WHEN 75% OF THE STORAGE CAPACITY OF THE STRUCTURE IS FILLED. ANY EXCESS WASH WATER SHALL BE PUMPED INTO A CONTAINMENT VESSEL AND PROPERLY DISPOSED OF OFF-SITE.
3. DISPOSAL OF THE HARDENED MATERIAL SHALL BE OFF-SITE IN A CONSTRUCTION/DEMOLITION LANDFILL.
4. THE PLASTIC LINER SHALL BE REPLACED WITH EACH CLEANING OF THE WASHOUT FACILITY.
5. INSPECT THE PROJECT SITE FREQUENTLY TO ENSURE THAT NO CONCRETE DISCHARGES ARE TAKING PLACE IN NON-DESIGNATED AREAS.
6. LOCATION(S) TO BE DETERMINED IN THE FIELD BY THE OWNER'S REPRESENTATIVE.
7. CONCRETE WASHOUTS SHALL NOT BE LOCATED WITHIN 200' OF ANY KNOWN WELL.


#### NOTES:

1. ALL MATERIAL TO MEET MANUFACTURER SPECIFICATIONS.
2. ALL FILTER SOCKS SHALL BE 12" DIAMETER UNLESS INDICATED OTHERWISE.
3. THE CONTRACTOR SHALL MAINTAIN THE COMPOST FILTER BERM IN A FUNCTIONAL CONDITION AT ALL TIMES AND IT SHALL BE ROUTINELY INSPECTED.
4. WHERE THE BERM REQUIRES REPAIR, IT WILL BE ROUTINELY REPAIRED.
5. THE CONTRACTOR SHALL REMOVE SEDIMENTS COLLECTED AT THE BASE OF THE BERM WHEN THEY REACH 1/3 OF THE EXPOSED HEIGHT OF THE BERM, OR AS DIRECTED BY THE REPRESENTATIVE.
6. THE COMPOST FILTER BERM WILL BE DISPERSED ON SITE WHEN NO LONGER REQUIRED, AS DETERMINED BY THE REPRESENTATIVE.
7. INSTALL PERPENDICULAR TO FLOW.



#### 4 COMPOST FILTER SOCK DETAIL

NOT TO SCALE




#### 5 WETLAND PROTECTION FENCE

SCALE: N.T.S.



#### 6 PROTECTED AREA FENCE


NOT TO SCALE



1. STONE SIZE—USE AASHTO M43 SIZE 3 COARSE AGGREGATE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
2. LENGTH — NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY).
3. THICKNESS — NOT LESS THAN 12".
4. WIDTH — TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS. TWENTY-FOUR (24) FOOT IF SINGLE ACCESS TO SITE.
5. WOVEN GEOTEXTILE FABRIC WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE.
6. EXISTING ROAD SIDE DRAINAGE SHALL BE MAINTAINED.
7. SURFACE WATER — ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CONSTRUCTION ENTRANCES SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
8. MAINTENANCE—THE ACCESS SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT OR STONE SPILLED, DROPPED, WASHED, OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY.
9. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON A AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
10. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH RAIN.

#### 7 STABILIZED CONSTRUCTION ACCESS

SCALE: N.T.S.



#### 8 INLET PROTECTION DETAIL

SCALE: N.T.S.

Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06850

**Civil Consultant**  
CHA CONSULTING, INC.  
3 WINNERS CIRCLE, COLOMBE, NY 12028

**Landscape Consultant**  
RHODESIE HARRIS LANDSCAPE ARCHITECTURE  
347 WEST 30TH STREET, SUITE 1001, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
30 EAST 30ND STREET, 11TH FLOOR, NEW YORK, NY 10018

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**BEYER BLINDER BELLE**

**Thornton Tomasetti**

**LFC**

**CNA**

**RHI**

**HLB**

**LVCK**

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024


Drawn By:	Seal and Signature
HB	
Design By:	
JJE	
Checked By:	
JJE	
Approved By:	
SKB	
DATE	04/10/24
Sheet Title	Drawing Number
DETAILS (2 OF 5)	C-601

Project Number:	Sheet:
D006292	XXX of 367






# 10 TYPICAL STANDARD END HOOK FOR PRIMARY REINFORCEMENT



**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

## Key Plan



Drawn By: HB	Seal and Signature
Design By JJE	
Checked By: JJE	
Approved By: SKB	
DATE 04/10/24	
<b>Sheet Title</b>	<b>Drawing Number</b>

DETAILS (3 OF 5)


**C-602**

Project Number: D006292	Sheet: XXX of 367
----------------------------	----------------------











1 OUTLET CONTROL STRUCTURE 2  
SCALE: N.T.S.



3 BIORETENTION AND DETENTION POND 2  
NOT TO SCALE



NOTE: EMERGENCY SPILLWAY SHALL BR GROUTED IN PLACE.

SPILLWAY DESIGN DATA				
	CREST ELEV (FT)	CREST WIDTH (FT)	TOP ELEV (FT)	TOP WIDTH (FT)
BIORETENTION 2	446.5'	20.0	447.0'	23.0
DRY POND 2	447.0'	23.0	447.5'	23.0

2 BIORETENTION AND DRY POND 2 OVERFLOW SPILLWAYS  
SCALE: N.T.S.

Gouverneur Kathy Hochul  
Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
200 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CNA CONSULTING, INC.  
3 WINNERS CIRCLE, COLOMBUS, IN 47203

**Landscape Consultant**  
RHODES HAWELL LANDSCAPE ARCHITECTURE  
347 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
35 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	10/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024

Drawn By:  
HB

Design By:  
JJE

Checked By:  
JJE

Approved By:  
SKB

DATE  
04/10/24


**Sheet Title**  
DETAILS (5 OF 5)

**Drawing Number**  
C-604

Project Number:  
D006292

Sheet:  
XXX of 367







**LINETYPES AND EXISTING SITE FEATURES**

- LOW — LIMIT OF WORK
- - - - - GRAVEL ROAD / PATH
- - - - - APPROX. PARK BOUNDARY
- x - x - x - FENCELINE
- — — — — STONE WALL
- o — o — o — TREE PROTECTION FENCE
- — — — — LIMIT OF WOODLAND
- - - - - WETLAND
- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)

**PLANT REMOVAL LEGEND**

- TREE REMOVAL BY NYS PARKS PRIOR TO CONSTRUCTION. CONTRACTOR TO REMOVE STUMPS
- UNDERSTORY AND GROUND COVER PLANT REMOVAL SYMBOL





New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
120 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
252 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CNA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**Landscape Consultant**  
RHODESSE MARWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**BEYER BLINDER BELLE**

**Thornton Tomasetti**

**LFG**  
LANDMARKS FACILITIES GROUP

**CNA**

**RH**

**HLB**

**LVCK** | A Beyer Blinder Belle Studio


**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**



REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By:

Design By:

Checked By:

Approved By:

DATE  
04/10/24

**Sheet Title**  
SITE TREE PROTECTION AND PLANT REMOVAL PLAN


Project Number:  
D006292

Seal and Signature

**Drawing Number**  
**L-100**

Sheet:  
of 367





**LINETYPES AND EXISTING SITE FEATURES**

- LOW — LIMIT OF WORK
- - - GRAVEL ROAD / PATH
- - - - - APPROX. PARK BOUNDARY
- x - x - x FENCELINE
- — — — — STONE WALL
- o — o — o TREE PROTECTION FENCE
- — — — — LIMIT OF WOODLAND
- WETLAND
- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)

**PLANT REMOVAL LEGEND**

- TREE REMOVAL BY NYS PARKS PRIOR TO CONSTRUCTION. CONTRACTOR TO REMOVE STUMPS
- UNDERSTORY AND GROUND COVER PLANT REMOVAL SYMBOL

New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
120 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
252 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CNA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**Landscape Consultant**  
RHODESSE MARWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By:

Design By:

Checked By:

Approved By:

DATE  
04/10/24

**Sheet Title**  
TREE PROTECTION AND PLANT REMOVAL PLAN


Project Number:  
D006292

Seal and Signature

**Drawing Number**  
L-101

Sheet:  
of 367





LINETYPES AND EXISTING SITE FEATURES

- LOW — LIMIT OF WORK
- - - GRAVEL ROAD / PATH
- - - - - APPROX. PARK BOUNDARY
- x - x - x FENCELINE
- — — — — STONE WALL
- o — o — TREE PROTECTION FENCE
- — — — — LIMIT OF WOODLAND
- WETLAND
- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)

- PLANT REMOVAL LEGEND
- TREE REMOVAL BY NYS PARKS PRIOR TO CONSTRUCTION. CONTRACTOR TO REMOVE STUMPS
  - UNDERSTORY AND GROUNDCOVER PLANT REMOVAL SYMBOL

Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
120 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
252 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CNA CONSULTING, INC.  
515 BROADWAY, SUITE 301, ALBANY, NY 12207

**Landscape Consultant**  
RHODESSE MARWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By:  
  
Design By:  
  
Checked By:  
  
Approved By:  
  
DATE  
04/10/24

Seal and Signature

Sheet Title  
**TREE PROTECTION AND PLANT REMOVAL PLAN**

Drawing Number  
**L-102**


Project Number:  
D006292

Sheet:  
of 367









LINETYPES AND EXISTING SITE FEATURES

- LOW — LIMIT OF WORK
- - - GRAVEL ROAD / PATH
- - - - - APPROX. PARK BOUNDARY
- x - x - x FENCELINE
- — — — — STONE WALL
- o - o - o TREE PROTECTION FENCE
- ~ ~ ~ ~ ~ LIMIT OF WOODLAND
- WETLAND
- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)

PLANT REMOVAL LEGEND

- TREE REMOVAL BY NYS PARKS PRIOR TO CONSTRUCTION. CONTRACTOR TO REMOVE STUMPS
- UNDERSTORY AND GROUNDCOVER PLANT REMOVAL SYMBOL

Gouverneur Kathy HochulCommissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
120 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
252 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CNA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**Landscape Consultant**  
RHODESSE MARWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By:  
Design By:  
Checked By:  
Approved By:  
DATE  
04/10/24

Seal and Signature


Sheet Title  
**TREE PROTECTION AND PLANT REMOVAL PLAN**

Project Number:  
D006292

Drawing Number  
**L-104**

Sheet:  
of 367



















<b>New York State Parks, Recreation and Historic Preservation</b>	<b>Gouverneur Kathy Hochul</b>	
<b>Commissioner Pro Tempore Randy Simons</b>		
IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER, TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL AFFIXED ALONG WITH A DESCRIPTION OF THE ALTERATIONS. DATE AND ARCHITECT/ENGINEERS SIGNATURE. COPYRIGHT © 2015		
<b>Architectural Consultant</b> <b>BEYER BLINDER BELLE ARCHITECTS &amp; PLANNERS</b> 120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10271		
<b>Structural Consultant</b> THORNTON TOMASETTI 120 BROADWAY, 15TH FLOOR, NEW YORK, NY 10271		
<b>MEP / EP / IT Consultant</b> LANDMARKS FACILITIES GROUP 252 EAST AVENUE, NORWALK, CT 06855		
<b>Civil Consultant</b> CHA CONSULTING, INC 575 BROADWAY, SUITE 301, ALBANY, NY 12207		
<b>Landscape Consultant</b> RHODES HAMELLE 347 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018		
<b>Lighting Consultant</b> HLB LIGHTING 38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016		
<b>Signature Consultant</b> LVCK - A BEYER BLINDER BELLE STUDIO 120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10271		
<b><u>NYS OPRHP Taconic Region</u></b> 9 Old Post Rd, PO Box 308 Staatsburg, NY 12580 (845) 889 - 4100		
Regional Director: Linda Cooper Capital District Manager: Garrett Jobson		
<b><u>Project Title:</u></b> John Jay Homestead Site And Building Enhancements		
<b><u>Project Location:</u></b> Katonah NY 10536		
<b><u>REVISIONS</u></b>		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	11/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024
Drawn By: _____		Seal and Signature _____
Design By: _____		<div style="border: 1px solid black; height: 100px; width: 100%;"></div>
Checked By: _____		
Approved By: _____		
DATE 04/10/24		
<b><u>Sheet Title</u></b> <div style="font-size: 2em; font-weight: bold; text-align: center;">PLANTING PLAN</div>		<b><u>Drawing Number</u></b> <div style="font-size: 4em; font-weight: bold; text-align: center;">L-201</div>
Project Number: D006292		Sheet: of 367






LINETYPES AND EXISTING SITE FEATURES

- LOW — LIMIT OF WORK
- - - - - GRAVEL ROAD / PATH
- - - - - APPROX. PARK BOUNDARY
- x - x - x FENCELINE
- — — — — STONE WALL
- o — o — TREE PROTECTION FENCE
- — — — — LIMIT OF WOODLAND
- WETLAND
- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)

PROPOSED PLANTING LEGEND

- DECIDUOUS TREE
- MULTI-STEM UNDERSTORY TREE
- EVERGREEN TREE
- SHRUB PLANTINGS
- PERENNIAL/GROUNDCOVER
- MEADOW SEED MIX
- BIORETENTION SEED MIX
- LAWN RESTORATION

NOTE: SEE SHEET L-002 FOR PLANT SCHEDULE  
AND SHEET L-602 FOR PLANT DETAILS



New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
120 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
252 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CNA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**Landscape Consultant**  
RHODESSE MARWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**BEYER BLINDER BELLE**

**Thornton Tomasetti**

**LFG**

**CNA**

**RHI**

**HLB**

**LVCK** | A Beyer Blinder Belle Studio

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building  
Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By:  
  
Design By:  
  
Checked By:  
  
Approved By:  
  
DATE  
04/10/24

Seal and Signature

Sheet Title  
**PLANTING  
PLAN**


Drawing Number  
**L-202**

Project Number:  
D006292

Sheet:  
of 367

Volume 5: Page 345 of 492





LINETYPES AND EXISTING SITE FEATURES

- LOW — LIMIT OF WORK
- GRAVEL ROAD / PATH
- - - - - APPROX. PARK BOUNDARY
- x - x - FENCELINE
- STONE WALL
- TREE PROTECTION FENCE
- LIMIT OF WOODLAND
- WETLAND

- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL
- CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL
- CRITICAL ROOT ZONE (CRZ)
- PROPOSED PLANTING LEGEND
- DECIDUOUS TREE
- MULTI-STEM UNDERSTORY TREE

- EVERGREEN TREE
- SHRUB PLANTINGS
- PERENNIAL/GROUND COVER
- MEADOW SEED MIX
- BIORETENTION SEED MIX
- LAWN RESTORATION

NOTE: SEE SHEET L-002 FOR PLANT SCHEDULE AND SHEET L-602 FOR PLANT DETAILS

Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, AFFIXED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
100 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
252 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CNA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**Landscape Consultant**  
RHODESSE MARVELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
100 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By: \_\_\_\_\_ Seal and Signature \_\_\_\_\_

Design By: \_\_\_\_\_

Checked By: \_\_\_\_\_

Approved By: \_\_\_\_\_


DATE  
04/10/24

**Sheet Title**  
PLANTING PLAN

**Drawing Number**  
L-203

Project Number: D006292      Sheet: 367 of 367






LINETYPES AND EXISTING SITE FEATURES

- LOW — LIMIT OF WORK
- - - - - GRAVEL ROAD / PATH
- - - - - APPROX. PARK BOUNDARY
- x - x - x FENCELINE
- — — — — STONE WALL
- o — o — o TREE PROTECTION FENCE
- — — — — LIMIT OF WOODLAND
- WETLAND
- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)

PROPOSED PLANTING LEGEND

- + DECIDUOUS TREE
- MULTI-STEM UNDERSTORY TREE
- EVERGREEN TREE
- SHRUB PLANTINGS
- PERENNIAL/GROUNDCOVER
- MEADOW SEED MIX
- BIORETENTION SEED MIX
- LAWN RESTORATION

NOTE: SEE SHEET L-002 FOR PLANT SCHEDULE  
AND SHEET L-602 FOR PLANT DETAILS



0' 10' 20' 40'  
Scale: 1"=20'



New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy Hochul

Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A  
LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE  
SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S  
SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**BEYER  
BLINDER  
BELLE**

**Structural Consultant**  
THORNTON TOMASETTI  
120 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**Thornton  
Tomasetti**

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
252 EAST AVENUE, NORWALK, CT 06855

**LFG**  
LANDMARKS  
FACILITIES  
GROUP, INC.

**Civil Consultant**  
CNA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**CNA**

**Landscape Consultant**  
RHODESSE MARWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**RHI**

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**HLB**

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**LVCK** | A Beyer Blinder Belle Studio

**NYS OPRHP Taconic Region**

9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100


Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building  
Enhancements

**Project Location:**

Katonah  
NY 10536

**Key Plan**



**REVISIONS**

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By:	Seal and Signature
Design By:	
Checked By:	
Approved By:	
DATE 04/10/24	Drawing Number
<b>Sheet Title</b>  PLANTING PLAN	
Project Number: D006292	Sheet: of 367

**L-204**





**LINETYPES AND EXISTING SITE FEATURES**

- LOW — LIMIT OF WORK
- - - GRAVEL ROAD / PATH
- - - - - APPROX. PARK BOUNDARY
- x - x - x - FENCELINE
- — — — — STONE WALL
- o — o — TREE PROTECTION FENCE
- — — — — LIMIT OF WOODLAND
- WETLAND
- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)

**PROPOSED PLANTING LEGEND**

- + DECIDUOUS TREE
- MULTI-STEM UNDERSTORY TREE
- + EVERGREEN TREE
- SHRUB PLANTINGS
- PERENNIAL/GROUNDCOVER
- MEADOW SEED MIX
- BIORETENTION SEED MIX
- LAWN RESTORATION

NOTE: SEE SHEET L-002 FOR PLANT SCHEDULE  
AND SHEET L-602 FOR PLANT DETAILS

New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy Hochul      Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL, AFFIXED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**Structural Consultant**  
THORNTON TOMASETTI  
120 BROADWAY, 15TH FLOOR, NEW YORK, NY 10071

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
232 EAST AVENUE, NORWALK, CT 06855

**Civil Consultant**  
CNA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**Landscape Consultant**  
RHODESSE MARWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**BEYER BLINDER BELLE**

**Thornton Tomasetti**

**LFG**

**CNA**

**RHI**

**HLB**

**LVCK** | A Beyer Blinder Belle Studio

**NYS OPRHP Taconic Region**  
9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100

Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building  
Enhancements

**Project Location:**  
Katonah  
NY 10536

**Key Plan**

REVISIONS		
Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By:

Design By:

Checked By:

Approved By:

DATE  
04/10/24

**Sheet Title**  
  
PLANTING  
PLAN


Project Number:  
D006292

Seal and Signature

**Drawing Number**  
  
L-205

Sheet:  
of 367





LINETYPES AND EXISTING SITE FEATURES

- LOW LIMIT OF WORK
- GRAVEL ROAD / PATH
- APPROX. PARK BOUNDARY
- FENCELINE
- STONE WALL
- TREE PROTECTION FENCE
- LIMIT OF WOODLAND
- WETLAND
- STRUCTURAL FOUNDATION / REMAINS
- EXISTING DECIDUOUS TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)
- EXISTING EVERGREEN TREE SYMBOL  
CRITICAL ROOT ZONE (CRZ)

PROPOSED PLANTING LEGEND

- DECIDUOUS TREE
- MULTI-STEM UNDERSTORY TREE
- EVERGREEN TREE
- SHRUB PLANTINGS
- PERENNIAL/GROUND COVER
- MEADOW SEED MIX
- BIORETENTION SEED MIX
- LAWN RESTORATION

NOTE: SEE SHEET L-002 FOR PLANT SCHEDULE  
AND SHEET L-802 FOR PLANT DETAILS



New York State  
Parks, Recreation and  
Historic Preservation

Gouverneur Kathy Hochul Commissioner Pro Tempore Randy Simons

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A  
LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE  
SEAL, ATTACHED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT/ENGINEER'S  
SIGNATURE. COPYRIGHT © 2015

**Architectural Consultant**  
BEYER BLINDER BELLE ARCHITECTS & PLANNERS  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**BEYER  
BLINDER  
BELLE**

**Structural Consultant**  
THORNTON TOMASETTI  
120 BROADWAY, 19TH FLOOR, NEW YORK, NY 10071

**Thornton  
Tomasetti**

**MEP / FP / IT Consultant**  
LANDMARKS FACILITIES GROUP  
252 EAST AVENUE, NORWALK, CT 06855

**LFG**  
LANDMARKS  
FACILITIES  
GROUP, INC.

**Civil Consultant**  
CNA CONSULTING, INC.  
575 BROADWAY, SUITE 301, ALBANY, NY 12207

**CNA**

**Landscape Consultant**  
RHODESSE MARWELL LANDSCAPE ARCHITECTURE  
341 WEST 36TH STREET, SUITE 1201, NEW YORK, NY 10018

**RHI**

**Lighting Consultant**  
HLB LIGHTING  
38 EAST 32ND STREET, 11TH FLOOR, NEW YORK, NY 10016

**HLB**

**Signage Consultant**  
LVCK - A BEYER BLINDER BELLE STUDIO  
120 BROADWAY, 20TH FLOOR, NEW YORK, NY 10071

**LVCK** | A Beyer Blinder Belle  
Studio

**NYS OPRHP Taconic Region**

9 Old Post Rd, PO Box 308  
Staatsburg, NY 12580  
(845) 889 - 4100


Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson

**Project Title:**  
John Jay Homestead Site And Building  
Enhancements

**Project Location:**

Katonah  
NY 10536

**Key Plan**



REVISIONS

Rev No	Description	Date
1	SCHEMATIC DESIGN SUBMISSION	10/2/2023
2	DESIGN DEVELOPMENT SUBMISSION	1/31/2024
3	PROGRESS CD SUBMISSION	4/10/2024
4	PROGRESS CD SUBMISSION	5/22/2024

Drawn By: \_\_\_\_\_  
Design By: \_\_\_\_\_  
Checked By: \_\_\_\_\_  
Approved By: \_\_\_\_\_

Seal and Signature

DATE

04/10/24

**Sheet Title**

**PLANTING  
PLAN**

**Drawing Number**

**L-206**

Project Number:  
D006292

Sheet:  
of 367







Regional Director: Linda Cooper  
Capital District Manager: Garrett Jobson










**Project Title:**  
John Jay Homestead Site And Building  
Enhancements

**Project Location:**  
Katonah  
NY 10536

## Key Plan

Drawn By:	Seal and Signature
Design By	
Checked By:	
Approved By:	
DATE 04/10/24	

## PLANTING DETAILS





# APPENDIX I

Inspection Forms







**John Jay Homestead Site and Building Enhancements**

**PERMIT NUMBER: NYR-**

**PRE-CONSTRUCTION MEETING DOCUMENTS**

**Project Name** John Jay Homestead Site and Building Enhancements

**GP-0-20-001 Permit No.** NYR **Date of Authorization** \_\_\_\_\_

**Name of** \_\_\_\_\_

**Owner/Operator** \_\_\_\_\_

**General Contractor** \_\_\_\_\_

**The Following Information To Be Read By All Person's Involved in The Construction of Stormwater Related Activities:**

**Site Assessment and Inspections -**

- a. The Owner or Operator agrees to have a Qualified Inspector<sup>1</sup> conduct an assessment of the site prior to the commencement of construction. The Qualified Inspector shall certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP have been adequately installed or implemented to ensure overall preparedness of the site for the commencement of construction.
- b. For construction sites where soil disturbance activities have been temporarily suspended (e.g. winter shutdown) and temporary stabilization measures have been applied to all disturbed areas, the owner or operator can stop conducting inspections. The owner or operator shall resume inspections as soon as soil disturbance activities are reinitiated.
- c. For construction sites where soil disturbance activities have been shut down with partial project completion, the owner or operator can stop conducting inspections if all areas disturbed (as of the project shutdown date) have achieved final stabilization and all post-construction stormwater management practices, required for the completed portion of the project, have been constructed in conformance with the SWPPP and are operational.
- d. Following the commencement of construction, site inspections shall be conducted by the Qualified Inspector to ensure that erosion and sediment controls are being maintained in effective operating condition at all times. Inspections shall occur at least: (i) once every 7 calendar days for construction sites where soil disturbance activities are occurring; (ii) twice every 7 calendar days for construction sites where soil disturbance activities are occurring and the Owner/Operator has received authorization to disturb greater than five (5) acres of soil at any one time; (iii) once every thirty (30) calendar days for construction sites where soil disturbance activities have been temporarily suspended and temporary stabilization measures have been applied to all disturbed areas; and (iv) for construction sites where soil disturbance activities have been shut down with partial project completion, the Qualified Inspector can stop conducting inspections if all areas disturbed as of the project shutdown date have achieved final stabilization, and all post-construction stormwater management practices for the completed portion of the project have been constructed in conformance with the SWPPP and are operational.
- e. The owner or operator shall notify the Regional Office stormwater contact person in writing prior to reducing the frequency of any inspections.



## John Jay Homestead Site and Building Enhancements

- f. The Owner/Operator shall maintain a record of all inspection reports in the site log book. The site log book shall be maintained on site and be made available to the permitting authorities upon request. Prior to the commencement of construction,<sup>2</sup> the Owner/Operator shall certify in the site log book that the SWPPP is prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements.
- g. Prior to filing of the Notice of Termination or the end of permit term, the Owner/Operator shall have the Qualified Inspector perform a final site inspection. The Qualified Inspector shall certify that the site has undergone final stabilization<sup>3</sup> using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed.

<sup>1</sup>"Qualified Inspector" means a person knowledgeable in the principles and practice of erosion and sediment controls, such as a Certified Professional in Erosion and Sediment Control (CPESC), soil scientist, licensed Professional Engineer (PE), licensed Landscape Architect, or other Department endorsed individual(s). It may also mean someone working under the direct supervision of, and at the same company as, the licensed Professional Engineer, Certified Professional in Erosion and Sediment Control (CPESC), or soil scientist provided that person has training in the principles and practices of erosion and sediment control. Training means that person has received four (4) hours of training endorsed by the Department and shall receive four (4) hours of training every three (3) years after the initial training session.

<sup>2</sup>"Commencement of construction" means the initial removal of vegetation and disturbance of soils associated with clearing, grading or excavating activities or other construction activities.

<sup>3</sup>"Final stabilization" means that all soil disturbance activities at the site have been completed and a uniform, perennial vegetative cover with a density of eighty (80) percent over the entire pervious surface has been established, or equivalent stabilization measures (such as the use of mulches or geotextiles, rock rip-rap or washed/crushed stone) have been employed on all disturbed areas that are not covered by permanent structures, concrete or pavement.



## PRE-CONSTRUCTION SITE ASSESSMENT FORM

---

Inspector Name and Title

---

Date and Time of Inspection

---

**Qualified Inspector**

---

**Qualified Inspector Signature**

*The above signed acknowledges that, to the best of his/her knowledge, all information provided on the following forms is accurate and complete.*

**a. Notice of Intent, SWPPP, and Contractors' Certification:**

**Yes No NA**

- ☒ ☐ ☐ Has a Notice of Intent been filed with the NYS Department of Conservation?
- ☐ ☐ ☐ Is the SWPPP on-site? Where? \_\_\_\_\_
- ☐ ☐ ☐ Is the Plan current? What is the latest revision date? \_\_\_\_\_
- ☐ ☐ ☐ Have all contractors involved with implementing the erosion and sediment control portions of the SWPPP signed the contractor's certification?

**b. Resource Protection**

**Yes No NA**

- ☐ ☐ ☐ Are construction limits clearly flagged or fenced?
- ☐ ☐ ☐ Important trees and associated rooting zones, on-site septic system absorption fields, existing vegetated areas suitable for filter strips, especially in perimeter areas, etc. have been flagged for protection.
- ☐ ☐ ☐ Creek crossings installed prior to land-disturbing activity, including clearing and blasting.

**c. Surface Water Protection**

**Yes No NA**

- ☐ ☐ ☐ Clean stormwater runoff has been diverted away from areas to be disturbed.
- ☐ ☐ ☐ Bodies of water located either on site or in the vicinity of the site have been identified and protected.
- ☐ ☐ ☐ Appropriate practices to protect on-site or downstream surface waters are installed.

**d. Stabilized Construction Entrance**

**Yes No NA**

- ☐ ☐ ☐ A temporary construction entrance to capture mud and debris from construction vehicles before they enter the public highway has been installed.
- ☐ ☐ ☐ Other access areas (entrances, construction routes, equipment parking areas) are stabilized immediately as work takes place with gravel or other cover.
- ☐ ☐ ☐ Sediment tracked onto public streets is removed or cleaned on a regular basis.

**e. Perimeter Sediment Controls**

**Yes No NA**

- ☐ ☐ ☐ Silt fence material and installation comply with the standard drawing and specifications.
- ☐ ☐ ☐ Silt fences are installed at appropriate spacing intervals
- ☐ ☐ ☐ Sediment/detention basin was installed
- ☐ ☐ ☐ Sediment traps and barriers are installed.







PERMIT NUMBER: NYR-

INSPECTION REPORT #\_\_ :

John Jay Homestead Historic Site, Katonah, NY 10536

Location

Date and Time of Inspection

Qualified Inspector (name and title)

Qualified Inspector Signature

*The above signed acknowledges that, to the best of his/her knowledge, all information provided on the following forms is accurate and complete.*

☐ Weekly Inspection

Current Phase of Construction (if applicable):

Estimated Current Total Disturbed Area:

### IMMEDIATE ACTION ITEMS / INSPECTION SUMMARY:

It is the responsibility of the Qualified Inspector to notify the owner/operator and appropriate contractor of any corrective actions that need to be taken within one (1) business day of the completion of an inspection. It is the responsibility of the contractor (subcontractor) to begin implementing the corrective actions within one (1) business day of this notification and complete the corrective action within a reasonable time frame. If there are action items from the previous inspection which have not been addressed, so note.

Per the GP-0-20-001, Digital photographs with date stamp, that clearly show the condition of all practices that have been identified as needing corrective actions shall be included with each inspection report. The qualified inspector shall attach paper color copies of the digital photographs to the inspection report being maintained onsite within seven (7) calendar days of the date of the inspection. The qualified inspector shall also take digital photographs, with date stamp, that clearly show the condition of the practice(s) after the corrective action has been completed. Paper color copies of these digital photographs shall be attached to the inspection report, documenting the completion of the corrective action work within seven (7) calendar days of that inspection.



## John Jay Homestead Site and Building Enhancements

### 1. GENERAL HOUSEKEEPING

*Includes description of the weather and soil conditions (e.g. dry, wet, saturated) during the time of the inspection, a description of the condition of the runoff at all points of discharge from the construction site (including identification of any discharges of sediments from construction site), inspection for stream/pond turbidity, oil and floating substances, visible oil film, or globules or grease, contractor preparedness for implementation of erosion and sediment control, impact on adjacent property, and dust control.*

Yes      No

☐☐

Is there immediate action required regarding General Housekeeping?

Notes:

### 2. EXCAVATION DEWATERING

*Includes inspection ensuring that clean water from upstream pool is being pumped to the downstream pool, that sediment laden water from work area is being discharged to a silt-trapping device, and that constructed upstream berm has one-foot minimum freeboard.*

Yes      No

☐☐

Is there immediate action required regarding Excavation Dewatering?

Notes:

### 3. INTERCEPTOR DIKES AND SWALES

*Includes inspection ensuring that dikes and swales are installed per plan with minimum side slopes 2H:1V or flatter, are stabilized by geotextile fabric, seed, or mulch with no erosion occurring, and that sediment-laden runoff is directed to sediment trapping structure.*

Yes      No

☐☐

Is there immediate action required regarding an Interceptor Dike or Swale?

Notes:



## John Jay Homestead Site and Building Enhancements

### 4. EROSION & SEDIMENT CONTROL

*Includes inspection ensuring that erosion and sediment control practices are located and installed correctly, BMPs are maintained per specifications, stockpiles are stabilized and contained, de-watering operations prevent direct discharges to sensitive features, and that clearing and grading operations are divided into stages for large areas. Identification of all erosion and sediment control practices that need repair or maintenance.*

Yes      No

☐☐

Is there immediate action required regarding Erosion & Sediment Control?

Notes:

### 5. AREAS OF DISTURBANCE

*Includes description and sketch of areas that are disturbed at the time of the inspection and areas that have been stabilized (temporary and/or final) since last inspection.*

Yes      No

☐☐

Is there immediate action required regarding stabilizing disturbed areas?

Notes:

### 6. STABILIZED CONSTRUCTION ACCESS

*Includes inspection ensuring that stone is clean enough to effectively remove mud from vehicles, is installed per standards and specifications, that all traffic use the stabilized entrance to enter and leave site, and that adequate drainage is provided to prevent ponding at entrance.*

Yes      No

☐☐

Is there immediate action required regarding a Stabilized Construction Entrance?

Notes:



## 7. REINFORCED SILT FENCE

*Includes inspection ensuring that silt fence is installed on contour, 10 feet from toe of slope, joints are constructed by wrapping the two ends together for continuous support, steel posts installed ( if applicable), installed on downstream side of slope, maximum 6' intervals with 6 x 6 inch 14 gage wire, fabric is buried minimum of 6 inches, posts are stable, fabric is tight and without rips or frayed areas, and that sediment accumulation is less than 1/3 the height of the silt fence.*

Yes      No

☐☐

Is there immediate action required regarding Silt Fence?

Notes:

## 8. STONE CHECK DAM

*Includes inspection ensuring that stone check dam channels are without erosion (i.e., flow is not eroding soil underneath or around the structure), that check dam is in good condition (i.e., rocks have not been displaced and no permanent pools behind the structure), and that sediment accumulation is less than design capacity.*

Yes      No

☐☐

Is there immediate action required regarding a Stone Check Dam?

Notes:



## John Jay Homestead Site and Building Enhancements

### 9. COMPOST FILTER SOCK

*Includes inspection ensuring that compost filter sock is anchored in earth with 2"x2" wooden stakes driven 12" into the soil on 10 foot centers on the centerline of the sock. On uneven terrain, effective ground contact can be enhanced by the placement of a fillet of filter media on the disturbed area side of the compost sock. Damaged filter socks shall be replaced or repaired according the manufacturer's recommendations.*

Yes      No

☐☐

Is there immediate action required regarding Compost Filter Sock?

Notes:

### 10. FILTER FABRIC (DROP) INLET PROTECTION

*Includes inspection ensuring that protection is installed with 2-inch x 4-inch wood frame and wood posts, with maximum 3-foot spacing, is buried a minimum of 8 inches and secured to frame/posts with staples at max 8-inch spacing, has posts with 3-foot maximum spacing between posts, has posts that are stable, fabric is tight and without rips or frayed areas, and that sediment accumulation is within design capacity.*

Yes      No

☐☐

Is there immediate action required regarding Filter Fabric (Drop) Inlet Protection?

Notes:

### 11. TEMPORARY SEDIMENT TRAP

*Includes inspection ensuring that outlet structure is constructed per the approved plan or drawing, that geotextile fabric has been placed beneath rock fill, and that sediment accumulation is within design capacity.*

Yes      No

☐☐

Is there immediate action required regarding Temporary Sediment Traps?

Notes:



## John Jay Homestead Site and Building Enhancements

### 12.CONCRETE WASHOUT

*Includes inspection ensuring that the concrete washout is constructed and maintained per the approved plan or drawing.*

**Yes**      **No**

☐☐

Is there immediate action required regarding Concrete Washouts?

**Notes:**

### 13.STORMWATER BASIN

*Includes inspection ensuring that Permanent Stormwater Basins are installed per plans and specifications.*

**Yes**      **No**

☐☐

Is there immediate action required regarding Stormwater Basins?

**Notes:**

### 14.CURRENT PHASE OF POST-CONSTRUCTION STORMWATER PRACTICES

*Includes inspection of current phase of all post-construction stormwater management practices, identification of all construction that is not in conformance with the SWPPP and technical standards, identify corrective action(s) that must be taken to install, repair, replace or maintain erosion and sediment control practices, and to correct deficiencies identified with the construction of post-construction stormwater management practice(s).*

**Yes**      **No**

☐☐

Is there immediate action required regarding the current phase of post-construction stormwater management practices?

**Notes:**



**John Jay Homestead Site and Building Enhancements**  
**ADDITIONAL NOTES / MODIFICATIONS**







**New York State Department of Environmental Conservation  
Division of Water  
625 Broadway, 4th Floor  
Albany, New York 12233-3505**

\*(NOTE: Submit completed form to address above)\*

**NOTICE OF TERMINATION** for Storm Water Discharges Authorized  
under the SPDES General Permit for Construction Activity

**Please indicate your permit identification number:** NYR \_\_\_\_ \_

**I. Owner or Operator Information**

1. Owner/Operator Name:

2. Street Address:

3. City/State/Zip:

4. Contact Person:

4a. Telephone:

4b. Contact Person E-Mail:

**II. Project Site Information**

5. Project/Site Name:

6. Street Address:

7. City/Zip:

8. County:

**III. Reason for Termination**

9a. ☐ All disturbed areas have achieved final stabilization in accordance with the general permit and SWPPP. **\*Date final stabilization completed** (month/year): \_\_\_\_\_

9b. ☐ Permit coverage has been transferred to new owner/operator. Indicate new owner/operator's permit identification number: NYR \_\_\_\_ \_

(Note: Permit coverage can not be terminated by owner identified in I.1. above until new owner/operator obtains coverage under the general permit)

9c. ☐ Other (Explain on Page 2)

**IV. Final Site Information:**

10a. Did this construction activity require the development of a SWPPP that includes post-construction stormwater management practices? ☐ yes ☐ no (If no, go to question 10f.)

10b. Have all post-construction stormwater management practices included in the final SWPPP been constructed? ☐ yes ☐ no (If no, explain on Page 2)

10c. Identify the entity responsible for long-term operation and maintenance of practice(s)?

\_\_\_\_\_



**NOTICE OF TERMINATION for Storm Water Discharges Authorized under the  
SPDES General Permit for Construction Activity - continued**

10d. Has the entity responsible for long-term operation and maintenance been given a copy of the operation and maintenance plan required by the general permit?    ☐ yes    ☐ no

10e. Indicate the method used to ensure long-term operation and maintenance of the post-construction stormwater management practice(s):

- ☐ Post-construction stormwater management practice(s) and any right-of-way(s) needed to maintain practice(s) have been deeded to the municipality.
- ☐ Executed maintenance agreement is in place with the municipality that will maintain the post-construction stormwater management practice(s).
- ☐ For post-construction stormwater management practices that are privately owned, a mechanism is in place that requires operation and maintenance of the practice(s) in accordance with the operation and maintenance plan, such as a deed covenant in the owner or operator's deed of record.
- ☐ For post-construction stormwater management practices that are owned by a public or private institution (e.g. school, university or hospital), government agency or authority, or public utility; policy and procedures are in place that ensures operation and maintenance of the practice(s) in accordance with the operation and maintenance plan.

10f. Provide the total area of impervious surface (i.e. roof, pavement, concrete, gravel, etc.) constructed within the disturbance area? \_\_\_\_\_  
(acres)

11. Is this project subject to the requirements of a regulated, traditional land use control MS4?    ☐ yes  
☐ no  
(If Yes, complete section VI - "MS4 Acceptance" statement)

**V. Additional Information/Explanation:**  
(Use this section to answer questions 9c. and 10b., if applicable)

**VI. MS4 Acceptance - MS4 Official (principal executive officer or ranking elected official) or Duly Authorized Representative** (Note: Not required when 9b. is checked -transfer of coverage)

I have determined that it is acceptable for the owner or operator of the construction project identified in question 5 to submit the Notice of Termination at this time.

Printed Name:

Title/Position:

Signature:

Date:



**NOTICE OF TERMINATION** for Storm Water Discharges Authorized under the  
SPDES General Permit for Construction Activity - continued

**VII. Qualified Inspector Certification - Final Stabilization:**

I hereby certify that all disturbed areas have achieved final stabilization as defined in the current version of the general permit, and that all temporary, structural erosion and sediment control measures have been removed. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

Printed Name:

Title/Position:

Signature:

Date:

**VIII. Qualified Inspector Certification - Post-construction Stormwater Management Practice(s):**

I hereby certify that all post-construction stormwater management practices have been constructed in conformance with the SWPPP. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

Printed Name:

Title/Position:

Signature:

Date:

**IX. Owner or Operator Certification**

I hereby certify that this document was prepared by me or under my direction or supervision. My determination, based upon my inquiry of the person(s) who managed the construction activity, or those persons directly responsible for gathering the information, is that the information provided in this document is true, accurate and complete. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

Printed Name:

Title/Position:

Signature:

Date:

(NYS DEC Notice of Termination - January 2015)







# APPENDIX J

Post Construction Operation and Maintenance









## Bioretention Operation and Maintenance

Project: \_\_\_\_\_  
 Location: \_\_\_\_\_  
 Site Status: \_\_\_\_\_  
 \_\_\_\_\_

Date: \_\_\_\_\_  
 Time: \_\_\_\_\_

Inspector: \_\_\_\_\_

Maintenance Item	Maintenance Required	Comments
<b>1. Debris Cleanout (Monthly)</b>		
1. Bioretention and contributing areas clean of debris	YES <input type="checkbox"/> NO <input type="checkbox"/>	
2. No dumping of yard wastes into practice	YES <input type="checkbox"/> NO <input type="checkbox"/>	
3. Litter (branches, etc.) have been removed	YES <input type="checkbox"/> NO <input type="checkbox"/>	
<b>2. Vegetation (Monthly)</b>		
1. Plant height not less than water depth	YES <input type="checkbox"/> NO <input type="checkbox"/>	
2. Fertilized per specifications	YES <input type="checkbox"/> NO <input type="checkbox"/>	
3. Plant composition according to Approved plans	YES <input type="checkbox"/> NO <input type="checkbox"/>	
4. No placement of inappropriate plants	YES <input type="checkbox"/> NO <input type="checkbox"/>	
5. Grass height not greater than 6 inches	YES <input type="checkbox"/> NO <input type="checkbox"/>	
6. No evidence of erosion	YES <input type="checkbox"/> NO <input type="checkbox"/>	





## Bioretention Operation and Maintenance

Maintenance Item	Maintenance Required	Comments
<b>3. Check Dams/Energy Dissipaters/sumps (Annual, After Major Storms)</b>		
1. No evidence of structural deterioration	YES <input type="checkbox"/> NO <input type="checkbox"/>	
2. Any grates are in good condition	YES <input type="checkbox"/> NO <input type="checkbox"/>	
3. No evidence of spalling or cracking of Structural parts	YES <input type="checkbox"/> NO <input type="checkbox"/>	
<b>4. Outlet/Overflow Spillway (Annual)</b>		
1. Good Condition, no need for repairs	YES <input type="checkbox"/> NO <input type="checkbox"/>	
2. No evidence of erosion (if draining into a Natural channel)	YES <input type="checkbox"/> NO <input type="checkbox"/>	
<b>5. Overall Function of Facility (Annual)</b>		
1. Evidence of flow bypassing facility	YES <input type="checkbox"/> NO <input type="checkbox"/>	
2. No noticeable odors outside of facility	YES <input type="checkbox"/> NO <input type="checkbox"/>	

### Comments:

---

---

---

---

---

### Actions to be Taken:

---

---

---

---

---





## Tree Planting / Tree Pit Operation and Maintenance

Project: \_\_\_\_\_  
Location: \_\_\_\_\_  
Site Status: \_\_\_\_\_  
\_\_\_\_\_

Date: \_\_\_\_\_  
Time: \_\_\_\_\_

Inspector: \_\_\_\_\_

Maintenance Item	Maintenance Required	Comments
<b>1. Assess Tree Health (Quarterly, After Major Storms )</b>		
1. Provide necessary mulching, watering, and fertilized per specifications	YES <input type="checkbox"/> NO <input type="checkbox"/>	
2. Inspect tree for damages or dead limbs; prune as necessary	YES <input type="checkbox"/> NO <input type="checkbox"/>	
3. Inspect tree for evidence of insect and disease damage; treat as necessary	YES <input type="checkbox"/> NO <input type="checkbox"/>	
4. No evidence of erosion and dumping of yard wastes	YES <input type="checkbox"/> NO <input type="checkbox"/>	

### Comments:

---

---

---

---

### Actions to be Taken:

---

---

---

---







# APPENDIX K

Notice of Intent (NOI) and  
SPDES General Permit (GP-0-20-001)







# NOI for coverage under Stormwater General Permit for Construction Activity

version 1.37

(Submission #: HQ0-KM9J-F68EM, version 1)

## Details

---

**Originally Started By** hugo bouillon

**Alternate Identifier** John Jay Homestead Site and Building Enhancements

**Submission ID** HQ0-KM9J-F68EM

**Submission Reason** New

**Status** Draft

## Form Input

---

### Owner/Operator Information

**Owner/Operator Name (Company/Private Owner/Municipality/Agency/Institution, etc.)**  
NYS Parks, Recreation and Historic Preservation Taconic Region

**Owner/Operator Contact Person Last Name (NOT CONSULTANT)**  
Cooper

**Owner/Operator Contact Person First Name**  
Linda

**Owner/Operator Mailing Address**  
9 Old Post Road, PO Box 308

**City**  
Staatsburg

**State**  
NY

**Zip**  
12580



**Phone**

8458893811

**Email**

Linda.Cooper@parks.ny.gov

**Federal Tax ID**

14-601-3200

If the owner/operator is an organization, provide the Federal Tax ID number, or Employer Identification Number (EIN), in the format xx-xxxxxxx. If the owner/operator is an individual and not an organization, enter "Not Applicable" or "N/A" and do not provide the individual's social security number.

**Project Location****Project/Site Name**

John Jay Homestead Site and Building Enhancements

**Street Address (Not P.O. Box)**

400 Jay St

**Side of Street**

North

**City/Town/Village (THAT ISSUES BUILDING PERMIT)**

Bedford

**State**

NY

**Zip**

10536

**DEC Region**

3

The DEC Region must be provided. Please use the NYSDEC Stormwater Interactive Map (<https://gisservices.dec.ny.gov/gis/stormwater/>) to confirm which DEC Region this site is located in. To view the DEC Regions, click on "Other Useful Reference Layers" on the left side of the map, then click on "DEC Administrative Boundary." Zoom out as needed to see the Region boundaries.

For projects that span multiple Regions, please select a primary Region and then provide the additional Regions as a note in Question 39.



**County**

WESTCHESTER

**Name of Nearest Cross Street**

Katonah Woods Road

**Distance to Nearest Cross Street (Feet)**

200

**Project In Relation to Cross Street**

South

**Tax Map Numbers Section-Block-Parcel**

61.5-1-6

**Tax Map Numbers**

NONE PROVIDED

If the project does not have tax map numbers (e.g. linear projects), enter "Not Applicable" or "N/A".

**1. Coordinates**

---

Provide the Geographic Coordinates for the project site. The two methods are:

- Navigate to the project location on the map (below) and click to place a marker and obtain the XY coordinates.
- The "Find Me" button will provide the lat/long for the person filling out this form. Then pan the map to the correct location and click the map to place a marker and obtain the XY coordinates.

**Navigate to your location and click on the map to get the X,Y coordinates**

41.251574,-73.66010779999999

**Project Details****2. What is the nature of this project?**

Redevelopment with increase in impervious area

For the purposes of this eNOI, "New Construction" refers to any project that does not involve the disturbance of existing impervious area (i.e. 0 acres). If existing impervious area will be disturbed on the project site, it is considered redevelopment with either increase in impervious area or no increase in impervious area.

**3. Select the predominant land use for both pre and post development conditions.**



**Pre-Development Existing Landuse**

Other: Historical, Educational, Recreational Land

**Post-Development Future Land Use**

Other: Historical, Educational, Recreational Land

**3a. If Single Family Subdivision was selected in question 3, enter the number of subdivision lots.**

NONE PROVIDED

---

4. In accordance with the larger common plan of development or sale, enter the total project site acreage, the acreage to be disturbed and the future impervious area (acreage) within the disturbed area.

\*\*\* ROUND TO THE NEAREST TENTH OF AN ACRE. \*\*\*

**Total Site Area (acres)**

62.0

**Total Area to be Disturbed (acres)**

8.3

**Existing Impervious Area to be Disturbed (acres)**

2.2

**Future Impervious Area Within Disturbed Area (acres)**

2.7

**5. Do you plan to disturb more than 5 acres of soil at any one time?**

No

---

6. Indicate the percentage (%) of each Hydrologic Soil Group(HSG) at the site.

**A (%)**

0

**B (%)**

0

**C (%)**

97

**D (%)**

3

**7. Is this a phased project?**

Yes



**8. Enter the planned start and end dates of the disturbance activities.**

**Start Date**

06/03/2024

**End Date**

03/31/2026

**9. Identify the nearest surface waterbody(ies) to which construction site runoff will discharge.**

Wetlands and tributary to Cross River Reservoir and tributary to Stone Hill River

Drainage ditches and storm sewer systems are not considered surface waterbodies. Please identify the surface waterbody that they discharge to. If the nearest surface waterbody is unnamed, provide a description of the waterbody, such as, "Unnamed tributary to Niagara River."

**9a. Type of waterbody identified in question 9?**

Lake Off Site

Stream/Creek On Site

Wetland/State Jurisdiction On Site (Answer 9b)

**Other Waterbody Type Off Site Description**

NONE PROVIDED

**9b. If "wetland" was selected in 9A, how was the wetland identified?**

Delineated by Consultant

**10. Has the surface waterbody(ies) in question 9 been identified as a 303(d) segment in Appendix E of GP-0-20-001?**

No

**11. Is this project located in one of the Watersheds identified in Appendix C of GP-0-20-001?**

Yes

**12. Is the project located in one of the watershed areas associated with AA and AA-S classified waters?**

Yes

Please use the DEC Stormwater Interactive Map (<https://gisservices.dec.ny.gov/gis/stormwater/>) to confirm if this site is located in one of the watersheds of an AA or AA-S classified water. To view the watershed areas, click on "Permit Related Layers" on the left side of the map, then click on "Class AA AAS Watersheds."

**If No, skip question 13.**



**13. Does this construction activity disturb land with no existing impervious cover and where the Soil Slope Phase is identified as D (provided the map unit name is inclusive of slopes greater than 25%), E or F on the USDA Soil Survey?**

No

**If Yes, what is the acreage to be disturbed?**

NONE PROVIDED

**14. Will the project disturb soils within a State regulated wetland or the protected 100 foot adjacent area?**

No

**15. Does the site runoff enter a separate storm sewer system (including roadside drains, swales, ditches, culverts, etc)?**

No

**16. What is the name of the municipality/entity that owns the separate storm sewer system?**

NONE PROVIDED

**17. Does any runoff from the site enter a sewer classified as a Combined Sewer?**

No

**18. Will future use of this site be an agricultural property as defined by the NYS Agriculture and Markets Law?**

No

**19. Is this property owned by a state authority, state agency, federal government or local government?**

Yes

**20. Is this a remediation project being done under a Department approved work plan? (i.e. CERCLA, RCRA, Voluntary Cleanup Agreement, etc.)**

No

## **Required SWPPP Components**

**21. Has the required Erosion and Sediment Control component of the SWPPP been developed in conformance with the current NYS Standards and Specifications for Erosion and Sediment Control (aka Blue Book)?**

Yes

**22. Does this construction activity require the development of a SWPPP that includes the post-construction stormwater management practice component (i.e. Runoff Reduction, Water Quality and Quantity Control practices/techniques)?**

Yes

**If you answered No in question 22, skip question 23 and the Post-construction Criteria and Post-construction SMP Identification sections.**



**23. Has the post-construction stormwater management practice component of the SWPPP been developed in conformance with the current NYS Stormwater Management Design Manual?**

Yes

**24. The Stormwater Pollution Prevention Plan (SWPPP) was prepared by:**

Professional Engineer (P.E.)

**SWPPP Preparer**

CHA Consulting

**Contact Name (Last, First)**

Bennett, Samuel

**Mailing Address**

3 Winners Circle

**City**

Albany

**State**

New York

**Zip**

12205

**Phone**

(518) 453-8254

**Email**

sbennett@chasolutions.com

**Download SWPPP Preparer Certification Form**

Please take the following steps to prepare and upload your preparer certification form:

- 1) Click on the link below to download a blank certification form
- 2) The certified SWPPP preparer should sign this form
- 3) Scan the signed form
- 4) Upload the scanned document

[Download SWPPP Preparer Certification Form](#)

**Please upload the SWPPP Preparer Certification**

NONE PROVIDED

**Comment**

NONE PROVIDED

**Erosion & Sediment Control Criteria**



**25. Has a construction sequence schedule for the planned management practices been prepared?**

Yes

**26. Select all of the erosion and sediment control practices that will be employed on the project site:**

**Temporary Structural**

Dust Control

Stabilized Construction Entrance

Silt Fence

Straw/Hay Bale Dike

Storm Drain Inlet Protection

**Biotechnical**

None

**Vegetative Measures**

Topsoiling

Straw/Hay Bale Dike

Seeding

Protecting Vegetation

Mulching

**Permanent Structural**

Land Grading

Retaining Wall

Rock Outlet Protection

**Other**

NONE PROVIDED

**Post-Construction Criteria**

**\* IMPORTANT: Completion of Questions 27-39 is not required if response to Question 22 is No.**

**27. Identify all site planning practices that were used to prepare the final site plan/layout for the project.**

Preservation of Undisturbed Area

Reduction of Clearing and Grading

Parking Reduction

**27a. Indicate which of the following soil restoration criteria was used to address the requirements in Section 5.1.6("Soil Restoration") of the Design Manual (2010 version).**

All disturbed areas will be restored in accordance with the Soil Restoration requirements in Table 5.3 of the Design Manual (see page 5-22).

**28. Provide the total Water Quality Volume (WQv) required for this project (based on final site plan/layout). (Acre-feet)**

0.362



## 29. Post-construction SMP Identification

Use the Post-construction SMP Identification section to identify the RR techniques (Area Reduction), RR techniques (Volume Reduction) and Standard SMPs with RRv Capacity that were used to reduce the Total WQv Required (#28).

Identify the SMPs to be used by providing the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

Note: Redevelopment projects shall use the Post-Construction SMP Identification section to identify the SMPs used to treat and/or reduce the WQv required. If runoff reduction techniques will not be used to reduce the required WQv, skip to question 33a after identifying the SMPs.

## 30. Indicate the Total RRv provided by the RR techniques (Area/Volume Reduction) and Standard SMPs with RRv capacity identified in question 29. (acre-feet)

0.233

## 31. Is the Total RRv provided (#30) greater than or equal to the total WQv required (#28)?

No

If Yes, go to question 36. If No, go to question 32.

## 32. Provide the Minimum RRv required based on HSG. [Minimum RRv Required = (P) (0.95) (Ai) / 12, Ai=(s) (Aic)] (acre-feet)

0.073

## 32a. Is the Total RRv provided (#30) greater than or equal to the Minimum RRv Required (#32)?

Yes

If Yes, go to question 33.

Note: Use the space provided in question #39 to summarize the specific site limitations and justification for not reducing 100% of WQv required (#28). A detailed evaluation of the specific site limitations and justification for not reducing 100% of the WQv required (#28) must also be included in the SWPPP.

If No, sizing criteria has not been met; therefore, NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

## 33. SMPs

Use the Post-construction SMP Identification section to identify the Standard SMPs and, if applicable, the Alternative SMPs to be used to treat the remaining total WQv (=Total WQv Required in #28 - Total RRv Provided in #30).

Also, provide the total impervious area that contributes runoff to each practice selected.



NOTE: Use the Post-construction SMP Identification section to identify the SMPs used on Redevelopment projects.

**33a. Indicate the Total WQv provided (i.e. WQv treated) by the SMPs identified in question #33 and Standard SMPs with RRv Capacity identified in question #29. (acre-feet)**

0.129

Note: For the standard SMPs with RRv capacity, the WQv provided by each practice = the WQv calculated using the contributing drainage area to the practice - provided by the practice. (See Table 3.5 in Design Manual)

**34. Provide the sum of the Total RRv provided (#30) and the WQv provided (#33a).**

0.362

**35. Is the sum of the RRv provided (#30) and the WQv provided (#33a) greater than or equal to the total WQv required (#28)?**

Yes

If Yes, go to question 36.

If No, sizing criteria has not been met; therefore, NOI can not be processed. SWPPP preparer must modify design to meet sizing criteria.

**36. Provide the total Channel Protection Storage Volume (CPv required and provided or select waiver (#36a), if applicable.**

**CPv Required (acre-feet)**

0.0

**CPv Provided (acre-feet)**

0.0

**36a. The need to provide channel protection has been waived because:**

NONE PROVIDED

**37. Provide the Overbank Flood (Qp) and Extreme Flood (Qf) control criteria or select waiver (#37a), if applicable.**

**Overbank Flood Control Criteria (Qp)**

**Pre-Development (CFS)**

52.11

**Post-Development (CFS)**

44.23

**Total Extreme Flood Control Criteria (Qf)**

**Pre-Development (CFS)**

117.27



## **Post-Development (CFS)**

95.63

**37a. The need to meet the Qp and Qf criteria has been waived because:**

NONE PROVIDED

**38. Has a long term Operation and Maintenance Plan for the post-construction stormwater management practice(s) been developed?**

Yes

**If Yes, Identify the entity responsible for the long term Operation and Maintenance**

NYS OPRHP Taconic Region

**39. Use this space to summarize the specific site limitations and justification for not reducing 100% of WQv required (#28). (See question #32a) This space can also be used for other pertinent project information.**

Since the proposed redevelopment project is located within the NYC Watershed East of the Hudson River as shown in Appendix C of the SPDES Permit, the WQv and RRv required were calculated based on the 1-year, 24-hour storm over the new impervious areas within the disturbance limits. The project proposes to install 3 new bioretention areas, 2 dry ponds, and new tree planting to provide WQv and RRv treatment and peak flow mitigation to discharge into the existing wetlands and unnamed tributary to Cross River Reservoir. Also, the project proposes to remove an existing entrance drive that will reduce over 25% impervious area within the disturbed drainage sub-area discharging into the existing wetlands and unnamed tributary to Stone Hill River. The SWPPP will be reviewed and approved by the NYCDEP prior to submission of the NOI.

## **Post-Construction SMP Identification**

### **Runoff Reduction (RR) Techniques, Standard Stormwater Management Practices (SMPs) and Alternative SMPs**

Identify the Post-construction SMPs to be used by providing the total impervious area that contributes runoff to each technique/practice selected. For the Area Reduction Techniques, provide the total contributing area (includes pervious area) and, if applicable, the total impervious area that contributes runoff to the technique/practice.

### **RR Techniques (Area Reduction)**

---

Round to the nearest tenth

#### **Total Contributing Acres for Conservation of Natural Area (RR-1)**

NONE PROVIDED

#### **Total Contributing Impervious Acres for Conservation of Natural Area (RR-1)**

NONE PROVIDED

#### **Total Contributing Acres for Sheetflow to Riparian Buffers/Filter Strips (RR-2)**

NONE PROVIDED



**Total Contributing Impervious Acres for Sheetflow to Riparian Buffers/Filter Strips (RR-2)**

NONE PROVIDED

**Total Contributing Acres for Tree Planting/Tree Pit (RR-3)**

8.16

**Total Contributing Impervious Acres for Tree Planting/Tree Pit (RR-3)**

0.14

**Total Contributing Acres for Disconnection of Rooftop Runoff (RR-4)**

NONE PROVIDED

#### **RR Techniques (Volume Reduction)**

---

**Total Contributing Impervious Acres for Disconnection of Rooftop Runoff (RR-4)**

NONE PROVIDED

**Total Contributing Impervious Acres for Vegetated Swale (RR-5)**

NONE PROVIDED

**Total Contributing Impervious Acres for Rain Garden (RR-6)**

NONE PROVIDED

**Total Contributing Impervious Acres for Stormwater Planter (RR-7)**

NONE PROVIDED

**Total Contributing Impervious Acres for Rain Barrel/Cistern (RR-8)**

NONE PROVIDED

**Total Contributing Impervious Acres for Porous Pavement (RR-9)**

NONE PROVIDED

**Total Contributing Impervious Acres for Green Roof (RR-10)**

NONE PROVIDED

#### **Standard SMPs with RRv Capacity**

---

**Total Contributing Impervious Acres for Infiltration Trench (I-1)**

NONE PROVIDED

**Total Contributing Impervious Acres for Infiltration Basin (I-2)**

NONE PROVIDED

**Total Contributing Impervious Acres for Dry Well (I-3)**

NONE PROVIDED

**Total Contributing Impervious Acres for Underground Infiltration System (I-4)**

NONE PROVIDED



**Total Contributing Impervious Acres for Bioretention (F-5)**

0.88

**Total Contributing Impervious Acres for Dry Swale (O-1)**

NONE PROVIDED

**Standard SMPs**

---

**Total Contributing Impervious Acres for Micropool Extended Detention (P-1)**

NONE PROVIDED

**Total Contributing Impervious Acres for Wet Pond (P-2)**

NONE PROVIDED

**Total Contributing Impervious Acres for Wet Extended Detention (P-3)**

NONE PROVIDED

**Total Contributing Impervious Acres for Multiple Pond System (P-4)**

NONE PROVIDED

**Total Contributing Impervious Acres for Pocket Pond (P-5)**

NONE PROVIDED

**Total Contributing Impervious Acres for Surface Sand Filter (F-1)**

NONE PROVIDED

**Total Contributing Impervious Acres for Underground Sand Filter (F-2)**

NONE PROVIDED

**Total Contributing Impervious Acres for Perimeter Sand Filter (F-3)**

NONE PROVIDED

**Total Contributing Impervious Acres for Organic Filter (F-4)**

NONE PROVIDED

**Total Contributing Impervious Acres for Shallow Wetland (W-1)**

NONE PROVIDED

**Total Contributing Impervious Acres for Extended Detention Wetland (W-2)**

NONE PROVIDED

**Total Contributing Impervious Acres for Pond/Wetland System (W-3)**

NONE PROVIDED

**Total Contributing Impervious Acres for Pocket Wetland (W-4)**

NONE PROVIDED

**Total Contributing Impervious Acres for Wet Swale (O-2)**

NONE PROVIDED



**Alternative SMPs (DO NOT INCLUDE PRACTICES BEING USED FOR PRETREATMENT ONLY)**

---

**Total Contributing Impervious Area for Hydrodynamic**

NONE PROVIDED

**Total Contributing Impervious Area for Wet Vault**

NONE PROVIDED

**Total Contributing Impervious Area for Media Filter**

NONE PROVIDED

**"Other" Alternative SMP?**

NONE PROVIDED

**Total Contributing Impervious Area for "Other"**

NONE PROVIDED

**Provide the name and manufacturer of the alternative SMPs (i.e. proprietary practice(s)) being used for WQv treatment.**

**Note: Redevelopment projects which do not use RR techniques, shall use questions 28, 29, 33 and 33a to provide SMPs used, total WQv required and total WQv provided for the project.**

**Manufacturer of Alternative SMP**

NONE PROVIDED

**Name of Alternative SMP**

NONE PROVIDED

## **Other Permits**

**40. Identify other DEC permits, existing and new, that are required for this project/facility.**

None

**If SPDES Multi-Sector GP, then give permit ID**

NONE PROVIDED

**If Other, then identify**

NONE PROVIDED

**41. Does this project require a US Army Corps of Engineers Wetland Permit?**

No

**If "Yes," then indicate Size of Impact, in acres, to the nearest tenth**

NONE PROVIDED



**42. If this NOI is being submitted for the purpose of continuing or transferring coverage under a general permit for stormwater runoff from construction activities, please indicate the former SPDES number assigned.**  
NONE PROVIDED

## **MS4 SWPPP Acceptance**

**43. Is this project subject to the requirements of a regulated, traditional land use control MS4?**  
No

**If No, skip question 44**

**44. Has the "MS4 SWPPP Acceptance" form been signed by the principal executive officer or ranking elected official and submitted along with this NOI?**  
No

Please note that per Part VII.H.4. of GP-0-20-001, the MS4 SWPPP Acceptance Form must be signed by a principal executive officer or ranking elected official of the MS4, or a duly authorized representative of that person.

## **MS4 SWPPP Acceptance Form Download**

Download form from the link below. Complete, sign, and upload.  
[MS4 SWPPP Acceptance Form](#)

## **MS4 Acceptance Form Upload**

NONE PROVIDED

**Comment**

NONE PROVIDED

## **Owner/Operator Certification**

### **Owner/Operator Certification Form Download**

Download the certification form by clicking the link below. Complete, sign, scan, and upload the form.

[Owner/Operator Certification Form \(PDF, 45KB\)](#)

### **Upload Owner/Operator Certification Form**

NONE PROVIDED

**Comment**

NONE PROVIDED









# SWPPP Preparer Certification Form

*SPDES General Permit for Stormwater  
Discharges From Construction Activity  
(GP-0-20-001)*

## Project Site Information

### Project/Site Name

John Jay Homestead Site and Building Enhancements

## Owner/Operator Information

### Owner/Operator (Company Name/Private Owner/Municipality Name)

NYS Parks, Recreation and Historic Preservation Taconic Region

## Certification Statement – SWPPP Preparer

I hereby certify that the Stormwater Pollution Prevention Plan (SWPPP) for this project has been prepared in accordance with the terms and conditions of the GP-0-20-001. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of this permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

Samuel

First name

K.

MI

Bennett

Last Name

Signature

Date









# **Owner/Operator Certification Form**

## **SPDES General Permit For Stormwater Discharges From Construction Activity (GP-0-20-001)**

Project/Site Name: John Jay Homestead State Historic Site

eNOI Submission Number: HQ0-KM9J-F68EM

eNOI Submitted by: ☐ Owner/Operator ☒ SWPPP Preparer ☐ Other

### **Certification Statement - Owner/Operator**

I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I hereby certify that this document and the corresponding documents were prepared under my direction or supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgment that I will receive as a result of submitting this NOI and can be as long as sixty (60) business days as provided for in the general permit. I also understand that, by submitting this NOI, I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction, and agreeing to comply with all the terms and conditions of the general permit for which this NOI is being submitted.

Owner/Operator First Name

M.I. Last Name

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Date









Department of  
Environmental  
Conservation

NEW YORK STATE  
DEPARTMENT OF ENVIRONMENTAL CONSERVATION

SPDES GENERAL PERMIT  
FOR STORMWATER DISCHARGES

From

**CONSTRUCTION ACTIVITY**

Permit No. GP- 0-20-001

Issued Pursuant to Article 17, Titles 7, 8 and Article 70  
of the Environmental Conservation Law

Effective Date: January 29, 2020

Expiration Date: January 28, 2025

John J. Ferguson

Chief Permit Administrator



Authorized Signature

1-23-20  
Date

Address: NYS DEC  
Division of Environmental Permits  
625 Broadway, 4th Floor  
Albany, N.Y. 12233-1750



## PREFACE

Pursuant to Section 402 of the Clean Water Act (“CWA”), stormwater *discharges* from certain *construction activities* are unlawful unless they are authorized by a *National Pollutant Discharge Elimination System (“NPDES”)* permit or by a state permit program. New York administers the approved State Pollutant Discharge Elimination System (SPDES) program with permits issued in accordance with the New York State Environmental Conservation Law (ECL) Article 17, Titles 7, 8 and Article 70.

An *owner or operator* of a *construction activity* that is eligible for coverage under this permit must obtain coverage prior to the *commencement of construction activity*. Activities that fit the definition of “*construction activity*”, as defined under 40 CFR 122.26(b)(14)(x), (15)(i), and (15)(ii), constitute construction of a *point source* and therefore, pursuant to ECL section 17-0505 and 17-0701, the *owner or operator* must have coverage under a SPDES permit prior to *commencing construction activity*. The *owner or operator* cannot wait until there is an actual *discharge* from the *construction site* to obtain permit coverage.

**\*Note: The italicized words/phrases within this permit are defined in Appendix A.**



**NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION  
SPDES GENERAL PERMIT FOR STORMWATER DISCHARGES FROM  
CONSTRUCTION ACTIVITIES**

**Table of Contents**

Part 1. PERMIT COVERAGE AND LIMITATIONS .....	1
A. Permit Application .....	1
B. Effluent Limitations Applicable to Discharges from Construction Activities .....	1
C. Post-construction Stormwater Management Practice Requirements .....	4
D. Maintaining Water Quality .....	8
E. Eligibility Under This General Permit.....	9
F. Activities Which Are Ineligible for Coverage Under This General Permit .....	9
Part II. PERMIT COVERAGE .....	12
A. How to Obtain Coverage .....	12
B. Notice of Intent (NOI) Submittal .....	13
C. Permit Authorization .....	13
D. General Requirements For Owners or Operators With Permit Coverage .....	15
E. Permit Coverage for Discharges Authorized Under GP-0-15-002.....	17
F. Change of Owner or Operator .....	17
Part III. STORMWATER POLLUTION PREVENTION PLAN (SWPPP).....	18
A. General SWPPP Requirements .....	18
B. Required SWPPP Contents .....	20
C. Required SWPPP Components by Project Type.....	24
Part IV. INSPECTION AND MAINTENANCE REQUIREMENTS .....	24
A. General Construction Site Inspection and Maintenance Requirements .....	24
B. Contractor Maintenance Inspection Requirements .....	24
C. Qualified Inspector Inspection Requirements .....	25
Part V. TERMINATION OF PERMIT COVERAGE .....	29
A. Termination of Permit Coverage .....	29
Part VI. REPORTING AND RETENTION RECORDS .....	31
A. Record Retention .....	31
B. Addresses .....	31
Part VII. STANDARD PERMIT CONDITIONS.....	31
A. Duty to Comply.....	31
B. Continuation of the Expired General Permit.....	32
C. Enforcement.....	32
D. Need to Halt or Reduce Activity Not a Defense.....	32
E. Duty to Mitigate .....	33
F. Duty to Provide Information.....	33
G. Other Information .....	33
H. Signatory Requirements.....	33
I. Property Rights .....	35
J. Severability.....	35



K.	Requirement to Obtain Coverage Under an Alternative Permit .....	35
L.	Proper Operation and Maintenance .....	36
M.	Inspection and Entry .....	36
N.	Permit Actions .....	37
O.	Definitions .....	37
P.	Re-Opener Clause .....	37
Q.	Penalties for Falsification of Forms and Reports .....	37
R.	Other Permits .....	38
APPENDIX A – Acronyms and Definitions .....		39
Acronyms.....		39
Definitions.....		40
APPENDIX B – Required SWPPP Components by Project Type .....		48
Table 1.....		48
Table 2.....		50
APPENDIX C – Watersheds Requiring Enhanced Phosphorus Removal .....		52
APPENDIX D – Watersheds with Lower Disturbance Threshold .....		58
APPENDIX E – 303(d) Segments Impaired by Construction Related Pollutant(s) .....		59
APPENDIX F – List of NYS DEC Regional Offices .....		65



## Part 1. PERMIT COVERAGE AND LIMITATIONS

### A. Permit Application

This permit authorizes stormwater *discharges* to *surface waters of the State* from the following *construction activities* identified within 40 CFR Parts 122.26(b)(14)(x), 122.26(b)(15)(i) and 122.26(b)(15)(ii), provided all of the eligibility provisions of this permit are met:

1. *Construction activities* involving soil disturbances of one (1) or more acres; including disturbances of less than one acre that are part of a *larger common plan of development or sale* that will ultimately disturb one or more acres of land; excluding *routine maintenance activity* that is performed to maintain the original line and grade, hydraulic capacity or original purpose of a facility;
2. *Construction activities* involving soil disturbances of less than one (1) acre where the Department has determined that a *SPDES* permit is required for stormwater *discharges* based on the potential for contribution to a violation of a *water quality standard* or for significant contribution of *pollutants* to *surface waters of the State*.
3. *Construction activities* located in the watershed(s) identified in Appendix D that involve soil disturbances between five thousand (5,000) square feet and one (1) acre of land.

### B. Effluent Limitations Applicable to Discharges from Construction Activities

*Discharges* authorized by this permit must achieve, at a minimum, the effluent limitations in Part I.B.1. (a) – (f) of this permit. These limitations represent the degree of effluent reduction attainable by the application of best practicable technology currently available.

1. Erosion and Sediment Control Requirements - The *owner or operator* must select, design, install, implement and maintain control measures to *minimize* the *discharge of pollutants* and prevent a violation of the *water quality standards*. The selection, design, installation, implementation, and maintenance of these control measures must meet the non-numeric effluent limitations in Part I.B.1.(a) – (f) of this permit and be in accordance with the New York State Standards and Specifications for Erosion and Sediment Control, dated November 2016, using sound engineering judgment. Where control measures are not designed in conformance with the design criteria included in the technical standard, the *owner or operator* must include in the *Stormwater Pollution Prevention Plan* (“SWPPP”) the reason(s) for the



deviation or alternative design and provide information which demonstrates that the deviation or alternative design is *equivalent* to the technical standard.

- a. **Erosion and Sediment Controls.** Design, install and maintain effective erosion and sediment controls to *minimize* the *discharge* of *pollutants* and prevent a violation of the *water quality standards*. At a minimum, such controls must be designed, installed and maintained to:
  - (i) *Minimize* soil erosion through application of runoff control and soil stabilization control measure to *minimize pollutant discharges*;
  - (ii) Control stormwater *discharges*, including both peak flowrates and total stormwater volume, to *minimize* channel and *streambank* erosion and scour in the immediate vicinity of the *discharge* points;
  - (iii) *Minimize* the amount of soil exposed during *construction activity*;
  - (iv) *Minimize* the disturbance of *steep slopes*;
  - (v) *Minimize* sediment *discharges* from the site;
  - (vi) Provide and maintain *natural buffers* around surface waters, direct stormwater to vegetated areas and maximize stormwater infiltration to reduce *pollutant discharges*, unless *infeasible*;
  - (vii) *Minimize* soil compaction. Minimizing soil compaction is not required where the intended function of a specific area of the site dictates that it be compacted;
  - (viii) Unless *infeasible*, preserve a sufficient amount of topsoil to complete soil restoration and establish a uniform, dense vegetative cover; and
  - (ix) *Minimize* dust. On areas of exposed soil, *minimize* dust through the appropriate application of water or other dust suppression techniques to control the generation of pollutants that could be discharged from the site.
- b. **Soil Stabilization.** In areas where soil disturbance activity has temporarily or permanently ceased, the application of soil stabilization measures must be initiated by the end of the next business day and completed within fourteen (14) days from the date the current soil disturbance activity ceased. For construction sites that *directly discharge* to one of the 303(d) segments



listed in Appendix E or is located in one of the watersheds listed in Appendix C, the application of soil stabilization measures must be initiated by the end of the next business day and completed within seven (7) days from the date the current soil disturbance activity ceased. See Appendix A for definition of *Temporarily Ceased*.

- c. **Dewatering.** *Discharges* from *dewatering* activities, including *discharges* from *dewatering* of trenches and excavations, must be managed by appropriate control measures.
- d. **Pollution Prevention Measures.** Design, install, implement, and maintain effective pollution prevention measures to *minimize* the *discharge* of *pollutants* and prevent a violation of the *water quality standards*. At a minimum, such measures must be designed, installed, implemented and maintained to:
  - (i) *Minimize* the *discharge* of *pollutants* from equipment and vehicle washing, wheel wash water, and other wash waters. This applies to washing operations that use clean water only. Soaps, detergents and solvents cannot be used;
  - (ii) *Minimize* the exposure of building materials, building products, construction wastes, trash, landscape materials, fertilizers, pesticides, herbicides, detergents, sanitary waste, hazardous and toxic waste, and other materials present on the site to precipitation and to stormwater. Minimization of exposure is not required in cases where the exposure to precipitation and to stormwater will not result in a *discharge* of *pollutants*, or where exposure of a specific material or product poses little risk of stormwater contamination (such as final products and materials intended for outdoor use) ; and
  - (iii) Prevent the *discharge* of *pollutants* from spills and leaks and implement chemical spill and leak prevention and response procedures.
- e. **Prohibited Discharges.** The following *discharges* are prohibited:
  - (i) Wastewater from washout of concrete;
  - (ii) Wastewater from washout and cleanout of stucco, paint, form release oils, curing compounds and other construction materials;



- (iii) Fuels, oils, or other *pollutants* used in vehicle and equipment operation and maintenance;
  - (iv) Soaps or solvents used in vehicle and equipment washing; and
  - (v) Toxic or hazardous substances from a spill or other release.
- f. Surface Outlets. When discharging from basins and impoundments, the outlets shall be designed, constructed and maintained in such a manner that sediment does not leave the basin or impoundment and that erosion at or below the outlet does not occur.

### **C. Post-construction Stormwater Management Practice Requirements**

1. The *owner or operator* of a *construction activity* that requires post-construction stormwater management practices pursuant to Part III.C. of this permit must select, design, install, and maintain the practices to meet the *performance criteria* in the New York State Stormwater Management Design Manual (“Design Manual”), dated January 2015, using sound engineering judgment. Where post-construction stormwater management practices (“SMPs”) are not designed in conformance with the *performance criteria* in the Design Manual, the *owner or operator* must include in the SWPPP the reason(s) for the deviation or alternative design and provide information which demonstrates that the deviation or alternative design is *equivalent* to the technical standard.
2. The *owner or operator* of a *construction activity* that requires post-construction stormwater management practices pursuant to Part III.C. of this permit must design the practices to meet the applicable *sizing criteria* in Part I.C.2.a., b., c. or d. of this permit.

#### **a. Sizing Criteria for New Development**

- (i) Runoff Reduction Volume (“RRv”): Reduce the total Water Quality Volume (“WQv”) by application of RR techniques and standard SMPs with RRv capacity. The total WQv shall be calculated in accordance with the criteria in Section 4.2 of the Design Manual.
- (ii) Minimum RRv and Treatment of Remaining Total WQv: Construction activities that cannot meet the criteria in Part I.C.2.a.(i) of this permit due to site limitations shall direct runoff from all newly constructed impervious areas to a RR technique or standard SMP with RRv capacity unless infeasible. The specific site limitations that prevent the reduction of 100% of the WQv shall be documented in the SWPPP.



For each impervious area that is not directed to a RR technique or standard SMP with RRv capacity, the SWPPP must include documentation which demonstrates that all options were considered and for each option explains why it is considered infeasible.

**In no case shall the runoff reduction achieved from the newly constructed impervious areas be less than the Minimum RRv as calculated using the criteria in Section 4.3 of the Design Manual.** The remaining portion of the total WQv that cannot be reduced shall be treated by application of standard SMPs.

- (iii) Channel Protection Volume (“Cpv”): Provide 24 hour extended detention of the post-developed 1-year, 24-hour storm event; remaining after runoff reduction. The Cpv requirement does not apply when:
  - (1) Reduction of the entire Cpv is achieved by application of runoff reduction techniques or infiltration systems, or
  - (2) The site discharges directly to tidal waters, or fifth order or larger streams.
- (iv) *Overbank* Flood Control Criteria (“Qp”): Requires storage to attenuate the post-development 10-year, 24-hour peak discharge rate (Qp) to predevelopment rates. The Qp requirement does not apply when:
  - (1) the site discharges directly to tidal waters or fifth order or larger streams, or
  - (2) A downstream analysis reveals that *overbank* control is not required.
- (v) Extreme Flood Control Criteria (“Qf”): Requires storage to attenuate the post-development 100-year, 24-hour peak discharge rate (Qf) to predevelopment rates. The Qf requirement does not apply when:
  - (1) the site discharges directly to tidal waters or fifth order or larger streams, or
  - (2) A downstream analysis reveals that *overbank* control is not required.

**b. Sizing Criteria for New Development in Enhanced Phosphorus Removal Watershed**

- (i) Runoff Reduction Volume (RRv): Reduce the total Water Quality Volume (WQv) by application of RR techniques and standard SMPs with RRv capacity. The total WQv is the runoff volume from the 1-year, 24 hour design storm over the post-developed watershed and shall be



calculated in accordance with the criteria in Section 10.3 of the Design Manual.

- (ii) Minimum RRv and Treatment of Remaining Total WQv: *Construction activities* that cannot meet the criteria in Part I.C.2.b.(i) of this permit due to *site limitations* shall direct runoff from all newly constructed *impervious areas* to a RR technique or standard SMP with RRv capacity unless *infeasible*. The specific *site limitations* that prevent the reduction of 100% of the WQv shall be documented in the SWPPP. For each *impervious area* that is not directed to a RR technique or standard SMP with RRv capacity, the SWPPP must include documentation which demonstrates that all options were considered and for each option explains why it is considered *infeasible*.

**In no case shall the runoff reduction achieved from the newly constructed *impervious areas* be less than the Minimum RRv as calculated using the criteria in Section 10.3 of the Design Manual.** The remaining portion of the total WQv that cannot be reduced shall be treated by application of standard SMPs.

- (iii) Channel Protection Volume (Cpv): Provide 24 hour extended detention of the post-developed 1-year, 24-hour storm event; remaining after runoff reduction. The Cpv requirement does not apply when:
  - (1) Reduction of the entire Cpv is achieved by application of runoff reduction techniques or infiltration systems, or
  - (2) The site *discharges* directly to tidal waters, or fifth order or larger streams.
- (iv) Overbank Flood Control Criteria (Qp): Requires storage to attenuate the post-development 10-year, 24-hour peak *discharge* rate (Qp) to predevelopment rates. The Qp requirement does not apply when:
  - (1) the site *discharges* directly to tidal waters or fifth order or larger streams, or
  - (2) A downstream analysis reveals that *overbank* control is not required.
- (v) Extreme Flood Control Criteria (Qf): Requires storage to attenuate the post-development 100-year, 24-hour peak *discharge* rate (Qf) to predevelopment rates. The Qf requirement does not apply when:
  - (1) the site *discharges* directly to tidal waters or fifth order or larger streams, or
  - (2) A downstream analysis reveals that *overbank* control is not required.



### c. Sizing Criteria for Redevelopment Activity

- (i) Water Quality Volume (WQv): The WQv treatment objective for *redevelopment activity* shall be addressed by one of the following options. *Redevelopment activities* located in an Enhanced Phosphorus Removal Watershed (see Part III.B.3. and Appendix C of this permit) shall calculate the WQv in accordance with Section 10.3 of the Design Manual. All other *redevelopment activities* shall calculate the WQv in accordance with Section 4.2 of the Design Manual.
  - (1) Reduce the existing *impervious cover* by a minimum of 25% of the total disturbed, *impervious area*. The Soil Restoration criteria in Section 5.1.6 of the Design Manual must be applied to all newly created pervious areas, or
  - (2) Capture and treat a minimum of 25% of the WQv from the disturbed, *impervious area* by the application of standard SMPs; or reduce 25% of the WQv from the disturbed, *impervious area* by the application of RR techniques or standard SMPs with RRv capacity., or
  - (3) Capture and treat a minimum of 75% of the WQv from the disturbed, *impervious area* as well as any additional runoff from tributary areas by application of the alternative practices discussed in Sections 9.3 and 9.4 of the Design Manual., or
  - (4) Application of a combination of 1, 2 and 3 above that provide a weighted average of at least two of the above methods. Application of this method shall be in accordance with the criteria in Section 9.2.1(B) (IV) of the Design Manual.

If there is an existing post-construction stormwater management practice located on the site that captures and treats runoff from the *impervious area* that is being disturbed, the WQv treatment option selected must, at a minimum, provide treatment equal to the treatment that was being provided by the existing practice(s) if that treatment is greater than the treatment required by options 1 – 4 above.

- (ii) Channel Protection Volume (Cpv): Not required if there are no changes to hydrology that increase the *discharge* rate from the project site.
- (iii) *Overbank* Flood Control Criteria (Qp): Not required if there are no changes to hydrology that increase the *discharge* rate from the project site.
- (iv) Extreme Flood Control Criteria (Qf): Not required if there are no changes to hydrology that increase the *discharge* rate from the project site



**d. Sizing Criteria for Combination of Redevelopment Activity and New Development**

Construction projects that include both New Development and Redevelopment Activity shall provide post-construction stormwater management controls that meet the sizing criteria calculated as an aggregate of the Sizing Criteria in Part I.C.2.a. or b. of this permit for the New Development portion of the project and Part I.C.2.c of this permit for Redevelopment Activity portion of the project.

**D. Maintaining Water Quality**

The Department expects that compliance with the conditions of this permit will control *discharges* necessary to meet applicable *water quality standards*. It shall be a violation of the *ECL* for any discharge to either cause or contribute to a violation of *water quality standards* as contained in Parts 700 through 705 of Title 6 of the Official Compilation of Codes, Rules and Regulations of the State of New York, such as:

1. There shall be no increase in turbidity that will cause a substantial visible contrast to natural conditions;
2. There shall be no increase in suspended, colloidal or settleable solids that will cause deposition or impair the waters for their best usages; and
3. There shall be no residue from oil and floating substances, nor visible oil film, nor globules of grease.

If there is evidence indicating that the stormwater *discharges* authorized by this permit are causing, have the reasonable potential to cause, or are contributing to a violation of the *water quality standards*; the *owner or operator* must take appropriate corrective action in accordance with Part IV.C.5. of this general permit and document in accordance with Part IV.C.4. of this general permit. To address the *water quality standard* violation the *owner or operator* may need to provide additional information, include and implement appropriate controls in the SWPPP to correct the problem, or obtain an individual SPDES permit.

If there is evidence indicating that despite compliance with the terms and conditions of this general permit it is demonstrated that the stormwater *discharges* authorized by this permit are causing or contributing to a violation of *water quality standards*, or if the Department determines that a modification of the permit is necessary to prevent a violation of *water quality standards*, the authorized *discharges* will no longer be eligible for coverage under this permit. The Department may require the *owner or operator* to obtain an individual SPDES permit to continue discharging.



## E. Eligibility Under This General Permit

1. This permit may authorize all *discharges* of stormwater from *construction activity* to *surface waters of the State* and *groundwaters* except for ineligible *discharges* identified under subparagraph F. of this Part.
2. Except for non-stormwater *discharges* explicitly listed in the next paragraph, this permit only authorizes stormwater *discharges*; including stormwater runoff, snowmelt runoff, and surface runoff and drainage, from *construction activities*.
3. Notwithstanding paragraphs E.1 and E.2 above, the following non-stormwater discharges are authorized by this permit: those listed in 6 NYCRR 750-1.2(a)(29)(vi), with the following exception: "Discharges from firefighting activities are authorized only when the firefighting activities are emergencies/unplanned"; waters to which other components have not been added that are used to control dust in accordance with the SWPPP; and uncontaminated *discharges* from *construction site* de-watering operations. All non-stormwater discharges must be identified in the SWPPP. Under all circumstances, the *owner or operator* must still comply with *water quality standards* in Part I.D of this permit.
4. The *owner or operator* must maintain permit eligibility to *discharge* under this permit. Any *discharges* that are not compliant with the eligibility conditions of this permit are not authorized by the permit and the *owner or operator* must either apply for a separate permit to cover those ineligible *discharges* or take steps necessary to make the *discharge* eligible for coverage.

## F. Activities Which Are Ineligible for Coverage Under This General Permit

All of the following are **not** authorized by this permit:

1. *Discharges* after *construction activities* have been completed and the site has undergone *final stabilization*;
2. *Discharges* that are mixed with sources of non-stormwater other than those expressly authorized under subsection E.3. of this Part and identified in the SWPPP required by this permit;
3. *Discharges* that are required to obtain an individual SPDES permit or another SPDES general permit pursuant to Part VII.K. of this permit;
4. *Construction activities* or *discharges* from *construction activities* that may adversely affect an *endangered or threatened species* unless the *owner or*



*operator* has obtained a permit issued pursuant to 6 NYCRR Part 182 for the project or the Department has issued a letter of non-jurisdiction for the project. All documentation necessary to demonstrate eligibility shall be maintained on site in accordance with Part II.D.2 of this permit;

5. *Discharges* which either cause or contribute to a violation of *water quality standards* adopted pursuant to the *ECL* and its accompanying regulations;
6. *Construction activities* for residential, commercial and institutional projects:
  - a. Where the *discharges* from the *construction activities* are tributary to waters of the state classified as AA or AA-s; and
  - b. Which are undertaken on land with no existing *impervious cover*; and
  - c. Which disturb one (1) or more acres of land designated on the current United States Department of Agriculture ("USDA") Soil Survey as Soil Slope Phase "D", (provided the map unit name is inclusive of slopes greater than 25%), or Soil Slope Phase "E" or "F" (regardless of the map unit name), or a combination of the three designations.
7. *Construction activities* for linear transportation projects and linear utility projects:
  - a. Where the *discharges* from the *construction activities* are tributary to waters of the state classified as AA or AA-s; and
  - b. Which are undertaken on land with no existing *impervious cover*; and
  - c. Which disturb two (2) or more acres of land designated on the current USDA Soil Survey as Soil Slope Phase "D" (provided the map unit name is inclusive of slopes greater than 25%), or Soil Slope Phase "E" or "F" (regardless of the map unit name), or a combination of the three designations.



8. *Construction activities* that have the potential to affect an *historic property*, unless there is documentation that such impacts have been resolved. The following documentation necessary to demonstrate eligibility with this requirement shall be maintained on site in accordance with Part II.D.2 of this permit and made available to the Department in accordance with Part VII.F of this permit:
- a. Documentation that the *construction activity* is not within an archeologically sensitive area indicated on the sensitivity map, and that the *construction activity* is not located on or immediately adjacent to a property listed or determined to be eligible for listing on the National or State Registers of Historic Places, and that there is no new permanent building on the *construction site* within the following distances from a building, structure, or object that is more than 50 years old, or if there is such a new permanent building on the *construction site* within those parameters that NYS Office of Parks, Recreation and Historic Preservation (OPRHP), a Historic Preservation Commission of a Certified Local Government, or a qualified preservation professional has determined that the building, structure, or object more than 50 years old is not historically/archeologically significant.
    - 1-5 acres of disturbance - 20 feet
    - 5-20 acres of disturbance - 50 feet
    - 20+ acres of disturbance - 100 feet, or
  - b. DEC consultation form sent to OPRHP, and copied to the NYS DEC Agency Historic Preservation Officer (APO), and
    - (i) the State Environmental Quality Review (SEQR) Environmental Assessment Form (EAF) with a negative declaration or the Findings Statement, with documentation of OPRHP's agreement with the resolution; or
    - (ii) documentation from OPRHP that the *construction activity* will result in No Impact; or
    - (iii) documentation from OPRHP providing a determination of No Adverse Impact; or
    - (iv) a Letter of Resolution signed by the owner/operator, OPRHP and the DEC APO which allows for this *construction activity* to be eligible for coverage under the general permit in terms of the State Historic Preservation Act (SHPA); or
  - c. Documentation of satisfactory compliance with Section 106 of the National Historic Preservation Act for a coterminous project area:



- (i) No Affect
- (ii) No Adverse Affect
- (iii) Executed Memorandum of Agreement, or

d. Documentation that:

- (i) SHPA Section 14.09 has been completed by NYS DEC or another state agency.

9. *Discharges from construction activities* that are subject to an existing SPDES individual or general permit where a SPDES permit for *construction activity* has been terminated or denied; or where the *owner or operator* has failed to renew an expired individual permit.

## Part II. PERMIT COVERAGE

### A. How to Obtain Coverage

1. An *owner or operator* of a *construction activity* that is not subject to the requirements of a regulated, traditional land use control MS4 must first prepare a SWPPP in accordance with all applicable requirements of this permit and then submit a completed Notice of Intent (NOI) to the Department to be authorized to discharge under this permit.
2. An *owner or operator* of a *construction activity* that is subject to the requirements of a *regulated, traditional land use control MS4* must first prepare a SWPPP in accordance with all applicable requirements of this permit and then have the SWPPP reviewed and accepted by the *regulated, traditional land use control MS4* prior to submitting the NOI to the Department. The *owner or operator* shall have the "MS4 SWPPP Acceptance" form signed in accordance with Part VII.H., and then submit that form along with a completed NOI to the Department.
3. The requirement for an *owner or operator* to have its SWPPP reviewed and accepted by the *regulated, traditional land use control MS4* prior to submitting the NOI to the Department does not apply to an *owner or operator* that is obtaining permit coverage in accordance with the requirements in Part II.F. (Change of Owner or Operator) or where the *owner or operator* of the *construction activity* is the *regulated, traditional land use control MS4*. This exemption does not apply to *construction activities* subject to the New York City Administrative Code.



## **B. Notice of Intent (NOI) Submittal**

1. Prior to December 21, 2020, an owner or operator shall use either the electronic (eNOI) or paper version of the NOI that the Department prepared. Both versions of the NOI are located on the Department's website (<http://www.dec.ny.gov/>). The paper version of the NOI shall be signed in accordance with Part VII.H. of this permit and submitted to the following address:

**NOTICE OF INTENT  
NYS DEC, Bureau of Water Permits  
625 Broadway, 4<sup>th</sup> Floor  
Albany, New York 12233-3505**

2. Beginning December 21, 2020 and in accordance with EPA's 2015 NPDES Electronic Reporting Rule (40 CFR Part 127), the *owner or operator* must submit the NOI electronically using the *Department's* online NOI.
3. The *owner or operator* shall have the SWPPP preparer sign the "SWPPP Preparer Certification" statement on the NOI prior to submitting the form to the Department.
4. As of the date the NOI is submitted to the Department, the *owner or operator* shall make the NOI and SWPPP available for review and copying in accordance with the requirements in Part VII.F. of this permit.

## **C. Permit Authorization**

1. An *owner or operator* shall not *commence construction activity* until their authorization to *discharge* under this permit goes into effect.
2. Authorization to *discharge* under this permit will be effective when the *owner or operator* has satisfied all of the following criteria:
  - a. project review pursuant to the State Environmental Quality Review Act ("SEQRA") have been satisfied, when SEQRA is applicable. See the Department's website (<http://www.dec.ny.gov/>) for more information,
  - b. where required, all necessary Department permits subject to the *Uniform Procedures Act* ("UPA") (see 6 NYCRR Part 621), or the equivalent from another New York State agency, have been obtained, unless otherwise notified by the Department pursuant to 6 NYCRR 621.3(a)(4). *Owners or operators of construction activities* that are required to obtain UPA permits



must submit a preliminary SWPPP to the appropriate DEC Permit Administrator at the Regional Office listed in Appendix F at the time all other necessary *UPA* permit applications are submitted. The preliminary SWPPP must include sufficient information to demonstrate that the *construction activity* qualifies for authorization under this permit,

- c. the final SWPPP has been prepared, and
  - d. a complete NOI has been submitted to the Department in accordance with the requirements of this permit.
3. An *owner or operator* that has satisfied the requirements of Part II.C.2 above will be authorized to *discharge* stormwater from their *construction activity* in accordance with the following schedule:
- a. For *construction activities* that are not subject to the requirements of a *regulated, traditional land use control MS4*:
    - (i) Five (5) business days from the date the Department receives a complete electronic version of the NOI (eNOI) for *construction activities* with a SWPPP that has been prepared in conformance with the design criteria in the technical standard referenced in Part III.B.1 and the *performance criteria* in the technical standard referenced in Parts III.B., 2 or 3, for *construction activities* that require post-construction stormwater management practices pursuant to Part III.C.; or
    - (ii) Sixty (60) business days from the date the Department receives a complete NOI (electronic or paper version) for *construction activities* with a SWPPP that has not been prepared in conformance with the design criteria in technical standard referenced in Part III.B.1. or, for *construction activities* that require post-construction stormwater management practices pursuant to Part III.C., the *performance criteria* in the technical standard referenced in Parts III.B., 2 or 3, or;
    - (iii) Ten (10) business days from the date the Department receives a complete paper version of the NOI for *construction activities* with a SWPPP that has been prepared in conformance with the design criteria in the technical standard referenced in Part III.B.1 and the *performance criteria* in the technical standard referenced in Parts III.B., 2 or 3, for *construction activities* that require post-construction stormwater management practices pursuant to Part III.C.



- b. For *construction activities* that are subject to the requirements of a *regulated, traditional land use control MS4*:
  - (i) Five (5) business days from the date the Department receives both a complete electronic version of the NOI (eNOI) and signed “MS4 SWPPP Acceptance” form, or
  - (ii) Ten (10) business days from the date the Department receives both a complete paper version of the NOI and signed “MS4 SWPPP Acceptance” form.
4. Coverage under this permit authorizes stormwater *discharges* from only those areas of disturbance that are identified in the NOI. If an *owner or operator* wishes to have stormwater *discharges* from future or additional areas of disturbance authorized, they must submit a new NOI that addresses that phase of the development, unless otherwise notified by the Department. The *owner or operator* shall not *commence construction activity* on the future or additional areas until their authorization to *discharge* under this permit goes into effect in accordance with Part II.C. of this permit.

#### **D. General Requirements For Owners or Operators With Permit Coverage**

1. The *owner or operator* shall ensure that the provisions of the SWPPP are implemented from the *commencement of construction activity* until all areas of disturbance have achieved *final stabilization* and the Notice of Termination (“NOT”) has been submitted to the Department in accordance with Part V. of this permit. This includes any changes made to the SWPPP pursuant to Part III.A.4. of this permit.
2. The *owner or operator* shall maintain a copy of the General Permit (GP-0-20-001), NOI, *NOI Acknowledgment Letter*, SWPPP, MS4 SWPPP Acceptance form, inspection reports, responsible contractor’s or subcontractor’s certification statement (see Part III.A.6.), and all documentation necessary to demonstrate eligibility with this permit at the *construction site* until all disturbed areas have achieved *final stabilization* and the NOT has been submitted to the Department. The documents must be maintained in a secure location, such as a job trailer, on-site construction office, or mailbox with lock. The secure location must be accessible during normal business hours to an individual performing a compliance inspection.
3. The *owner or operator* of a *construction activity* shall not disturb greater than five (5) acres of soil at any one time without prior written authorization from the Department or, in areas under the jurisdiction of a *regulated, traditional land*



*use control MS4, the regulated, traditional land use control MS4 (provided the regulated, traditional land use control MS4 is not the owner or operator of the construction activity). At a minimum, the owner or operator must comply with the following requirements in order to be authorized to disturb greater than five (5) acres of soil at any one time:*

- a. The *owner or operator* shall have a *qualified inspector* conduct **at least** two (2) site inspections in accordance with Part IV.C. of this permit every seven (7) calendar days, for as long as greater than five (5) acres of soil remain disturbed. The two (2) inspections shall be separated by a minimum of two (2) full calendar days.
  - b. In areas where soil disturbance activity has temporarily or permanently ceased, the application of soil stabilization measures must be initiated by the end of the next business day and completed within seven (7) days from the date the current soil disturbance activity ceased. The soil stabilization measures selected shall be in conformance with the technical standard, New York State Standards and Specifications for Erosion and Sediment Control, dated November 2016.
  - c. The *owner or operator* shall prepare a phasing plan that defines maximum disturbed area per phase and shows required cuts and fills.
  - d. The *owner or operator* shall install any additional site-specific practices needed to protect water quality.
  - e. The *owner or operator* shall include the requirements above in their SWPPP.
4. In accordance with statute, regulations, and the terms and conditions of this permit, the Department may suspend or revoke an *owner's or operator's* coverage under this permit at any time if the Department determines that the SWPPP does not meet the permit requirements or consistent with Part VII.K..
  5. Upon a finding of significant non-compliance with the practices described in the SWPPP or violation of this permit, the Department may order an immediate stop to all activity at the site until the non-compliance is remedied. The stop work order shall be in writing, describe the non-compliance in detail, and be sent to the *owner or operator*.
  6. For *construction activities* that are subject to the requirements of a *regulated, traditional land use control MS4*, the *owner or operator* shall notify the



*regulated, traditional land use control MS4* in writing of any planned amendments or modifications to the post-construction stormwater management practice component of the SWPPP required by Part III.A. 4. and 5. of this permit. Unless otherwise notified by the *regulated, traditional land use control MS4*, the *owner or operator* shall have the SWPPP amendments or modifications reviewed and accepted by the *regulated, traditional land use control MS4* prior to commencing construction of the post-construction stormwater management practice.

#### **E. Permit Coverage for Discharges Authorized Under GP-0-15-002**

1. Upon renewal of SPDES General Permit for Stormwater Discharges from *Construction Activity* (Permit No. GP-0-15-002), an *owner or operator* of a *construction activity* with coverage under GP-0-15-002, as of the effective date of GP- 0-20-001, shall be authorized to *discharge* in accordance with GP- 0-20-001, unless otherwise notified by the Department.

An *owner or operator* may continue to implement the technical/design components of the post-construction stormwater management controls provided that such design was done in conformance with the technical standards in place at the time of initial project authorization. However, they must comply with the other, non-design provisions of GP-0-20-001.

#### **F. Change of Owner or Operator**

1. When property ownership changes or when there is a change in operational control over the construction plans and specifications, the original *owner or operator* must notify the new *owner or operator*, in writing, of the requirement to obtain permit coverage by submitting a NOI with the Department. For *construction activities* subject to the requirements of a *regulated, traditional land use control MS4*, the original *owner or operator* must also notify the MS4, in writing, of the change in ownership at least 30 calendar days prior to the change in ownership.
2. Once the new *owner or operator* obtains permit coverage, the original *owner or operator* shall then submit a completed NOT with the name and permit identification number of the new *owner or operator* to the Department at the address in Part II.B.1. of this permit. If the original *owner or operator* maintains ownership of a portion of the *construction activity* and will disturb soil, they must maintain their coverage under the permit.
3. Permit coverage for the new *owner or operator* will be effective as of the date the Department receives a complete NOI, provided the original *owner or*



*operator* was not subject to a sixty (60) business day authorization period that has not expired as of the date the Department receives the NOI from the new *owner or operator*.

### Part III. STORMWATER POLLUTION PREVENTION PLAN (SWPPP)

#### A. General SWPPP Requirements

1. A SWPPP shall be prepared and implemented by the *owner or operator* of each *construction activity* covered by this permit. The SWPPP must document the selection, design, installation, implementation and maintenance of the control measures and practices that will be used to meet the effluent limitations in Part I.B. of this permit and where applicable, the post-construction stormwater management practice requirements in Part I.C. of this permit. The SWPPP shall be prepared prior to the submittal of the NOI. The NOI shall be submitted to the Department prior to the *commencement of construction activity*. A copy of the completed, final NOI shall be included in the SWPPP.
2. The SWPPP shall describe the erosion and sediment control practices and where required, post-construction stormwater management practices that will be used and/or constructed to reduce the *pollutants* in stormwater *discharges* and to assure compliance with the terms and conditions of this permit. In addition, the SWPPP shall identify potential sources of pollution which may reasonably be expected to affect the quality of stormwater *discharges*.
3. All SWPPPs that require the post-construction stormwater management practice component shall be prepared by a *qualified professional* that is knowledgeable in the principles and practices of stormwater management and treatment.
4. The *owner or operator* must keep the SWPPP current so that it at all times accurately documents the erosion and sediment controls practices that are being used or will be used during construction, and all post-construction stormwater management practices that will be constructed on the site. At a minimum, the *owner or operator* shall amend the SWPPP, including construction drawings:
  - a. whenever the current provisions prove to be ineffective in minimizing *pollutants* in stormwater *discharges* from the site;



- b. whenever there is a change in design, construction, or operation at the *construction site* that has or could have an effect on the *discharge* of *pollutants*;
  - c. to address issues or deficiencies identified during an inspection by the *qualified inspector*, the Department or other regulatory authority; and
  - d. to document the final construction conditions.
5. The Department may notify the *owner or operator* at any time that the SWPPP does not meet one or more of the minimum requirements of this permit. The notification shall be in writing and identify the provisions of the SWPPP that require modification. Within fourteen (14) calendar days of such notification, or as otherwise indicated by the Department, the *owner or operator* shall make the required changes to the SWPPP and submit written notification to the Department that the changes have been made. If the *owner or operator* does not respond to the Department's comments in the specified time frame, the Department may suspend the *owner's or operator's* coverage under this permit or require the *owner or operator* to obtain coverage under an individual SPDES permit in accordance with Part II.D.4. of this permit.
6. Prior to the *commencement of construction activity*, the *owner or operator* must identify the contractor(s) and subcontractor(s) that will be responsible for installing, constructing, repairing, replacing, inspecting and maintaining the erosion and sediment control practices included in the SWPPP; and the contractor(s) and subcontractor(s) that will be responsible for constructing the post-construction stormwater management practices included in the SWPPP. The *owner or operator* shall have each of the contractors and subcontractors identify at least one person from their company that will be responsible for implementation of the SWPPP. This person shall be known as the *trained contractor*. The *owner or operator* shall ensure that at least one *trained contractor* is on site on a daily basis when soil disturbance activities are being performed.

The *owner or operator* shall have each of the contractors and subcontractors identified above sign a copy of the following certification statement below before they commence any *construction activity*:

"I hereby certify under penalty of law that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the *qualified inspector* during a site inspection. I also understand that the *owner or operator* must comply with



the terms and conditions of the most current version of the New York State Pollutant Discharge Elimination System ("SPDES") general permit for stormwater *discharges* from *construction activities* and that it is unlawful for any person to cause or contribute to a violation of *water quality standards*. Furthermore, I am aware that there are significant penalties for submitting false information, that I do not believe to be true, including the possibility of fine and imprisonment for knowing violations"

In addition to providing the certification statement above, the certification page must also identify the specific elements of the SWPPP that each contractor and subcontractor will be responsible for and include the name and title of the person providing the signature; the name and title of the *trained contractor* responsible for SWPPP implementation; the name, address and telephone number of the contracting firm; the address (or other identifying description) of the site; and the date the certification statement is signed. The *owner or operator* shall attach the certification statement(s) to the copy of the SWPPP that is maintained at the *construction site*. If new or additional contractors are hired to implement measures identified in the SWPPP after construction has commenced, they must also sign the certification statement and provide the information listed above.

7. For projects where the Department requests a copy of the SWPPP or inspection reports, the *owner or operator* shall submit the documents in both electronic (PDF only) and paper format within five (5) business days, unless otherwise notified by the Department.

## **B. Required SWPPP Contents**

1. Erosion and sediment control component - All SWPPPs prepared pursuant to this permit shall include erosion and sediment control practices designed in conformance with the technical standard, New York State Standards and Specifications for Erosion and Sediment Control, dated November 2016. Where erosion and sediment control practices are not designed in conformance with the design criteria included in the technical standard, the *owner or operator* must demonstrate *equivalence* to the technical standard. At a minimum, the erosion and sediment control component of the SWPPP shall include the following:
  - a. Background information about the scope of the project, including the location, type and size of project



- b. A site map/construction drawing(s) for the project, including a general location map. At a minimum, the site map shall show the total site area; all improvements; areas of disturbance; areas that will not be disturbed; existing vegetation; on-site and adjacent off-site surface water(s); floodplain/floodway boundaries; wetlands and drainage patterns that could be affected by the *construction activity*; existing and final contours ; locations of different soil types with boundaries; material, waste, borrow or equipment storage areas located on adjacent properties; and location(s) of the stormwater *discharge(s)*;
- c. A description of the soil(s) present at the site, including an identification of the Hydrologic Soil Group (HSG);
- d. A construction phasing plan and sequence of operations describing the intended order of *construction activities*, including clearing and grubbing, excavation and grading, utility and infrastructure installation and any other activity at the site that results in soil disturbance;
- e. A description of the minimum erosion and sediment control practices to be installed or implemented for each *construction activity* that will result in soil disturbance. Include a schedule that identifies the timing of initial placement or implementation of each erosion and sediment control practice and the minimum time frames that each practice should remain in place or be implemented;
- f. A temporary and permanent soil stabilization plan that meets the requirements of this general permit and the technical standard, New York State Standards and Specifications for Erosion and Sediment Control, dated November 2016, for each stage of the project, including initial land clearing and grubbing to project completion and achievement of *final stabilization*;
- g. A site map/construction drawing(s) showing the specific location(s), size(s), and length(s) of each erosion and sediment control practice;
- h. The dimensions, material specifications, installation details, and operation and maintenance requirements for all erosion and sediment control practices. Include the location and sizing of any temporary sediment basins and structural practices that will be used to divert flows from exposed soils;
- i. A maintenance inspection schedule for the contractor(s) identified in Part III.A.6. of this permit, to ensure continuous and effective operation of the erosion and sediment control practices. The maintenance inspection



schedule shall be in accordance with the requirements in the technical standard, New York State Standards and Specifications for Erosion and Sediment Control, dated November 2016;

- j. A description of the pollution prevention measures that will be used to control litter, construction chemicals and construction debris from becoming a *pollutant* source in the stormwater *discharges*;
  - k. A description and location of any stormwater *discharges* associated with industrial activity other than construction at the site, including, but not limited to, stormwater *discharges* from asphalt plants and concrete plants located on the *construction site*; and
  - l. Identification of any elements of the design that are not in conformance with the design criteria in the technical standard, New York State Standards and Specifications for Erosion and Sediment Control, dated November 2016. Include the reason for the deviation or alternative design and provide information which demonstrates that the deviation or alternative design is *equivalent* to the technical standard.
2. Post-construction stormwater management practice component – The *owner or operator* of any construction project identified in Table 2 of Appendix B as needing post-construction stormwater management practices shall prepare a SWPPP that includes practices designed in conformance with the applicable *sizing criteria* in Part I.C.2.a., c. or d. of this permit and the *performance criteria* in the technical standard, New York State Stormwater Management Design Manual dated January 2015

Where post-construction stormwater management practices are not designed in conformance with the *performance criteria* in the technical standard, the *owner or operator* must include in the SWPPP the reason(s) for the deviation or alternative design and provide information which demonstrates that the deviation or alternative design is *equivalent* to the technical standard.

The post-construction stormwater management practice component of the SWPPP shall include the following:

- a. Identification of all post-construction stormwater management practices to be constructed as part of the project. Include the dimensions, material specifications and installation details for each post-construction stormwater management practice;



- b. A site map/construction drawing(s) showing the specific location and size of each post-construction stormwater management practice;
- c. A Stormwater Modeling and Analysis Report that includes:
  - (i) Map(s) showing pre-development conditions, including watershed/subcatchments boundaries, flow paths/routing, and design points;
  - (ii) Map(s) showing post-development conditions, including watershed/subcatchments boundaries, flow paths/routing, design points and post-construction stormwater management practices;
  - (iii) Results of stormwater modeling (i.e. hydrology and hydraulic analysis) for the required storm events. Include supporting calculations (model runs), methodology, and a summary table that compares pre and post-development runoff rates and volumes for the different storm events;
  - (iv) Summary table, with supporting calculations, which demonstrates that each post-construction stormwater management practice has been designed in conformance with the *sizing criteria* included in the Design Manual;
  - (v) Identification of any *sizing criteria* that is not required based on the requirements included in Part I.C. of this permit; and
  - (vi) Identification of any elements of the design that are not in conformance with the *performance criteria* in the Design Manual. Include the reason(s) for the deviation or alternative design and provide information which demonstrates that the deviation or alternative design is *equivalent* to the Design Manual;
- d. Soil testing results and locations (test pits, borings);
- e. Infiltration test results, when required; and
- f. An operations and maintenance plan that includes inspection and maintenance schedules and actions to ensure continuous and effective operation of each post-construction stormwater management practice. The plan shall identify the entity that will be responsible for the long term operation and maintenance of each practice.



3. Enhanced Phosphorus Removal Standards - All construction projects identified in Table 2 of Appendix B that are located in the watersheds identified in Appendix C shall prepare a SWPPP that includes post-construction stormwater management practices designed in conformance with the applicable *sizing criteria* in Part I.C.2. b., c. or d. of this permit and the *performance criteria*, Enhanced Phosphorus Removal Standards included in the Design Manual. At a minimum, the post-construction stormwater management practice component of the SWPPP shall include items 2.a - 2.f. above.

### **C. Required SWPPP Components by Project Type**

Unless otherwise notified by the Department, *owners or operators of construction activities* identified in Table 1 of Appendix B are required to prepare a SWPPP that only includes erosion and sediment control practices designed in conformance with Part III.B.1 of this permit. *Owners or operators of the construction activities* identified in Table 2 of Appendix B shall prepare a SWPPP that also includes post-construction stormwater management practices designed in conformance with Part III.B.2 or 3 of this permit.

## **Part IV. INSPECTION AND MAINTENANCE REQUIREMENTS**

### **A. General Construction Site Inspection and Maintenance Requirements**

1. The *owner or operator* must ensure that all erosion and sediment control practices (including pollution prevention measures) and all post-construction stormwater management practices identified in the SWPPP are inspected and maintained in accordance with Part IV.B. and C. of this permit.
2. The terms of this permit shall not be construed to prohibit the State of New York from exercising any authority pursuant to the ECL, common law or federal law, or prohibit New York State from taking any measures, whether civil or criminal, to prevent violations of the laws of the State of New York or protect the public health and safety and/or the environment.

### **B. Contractor Maintenance Inspection Requirements**

1. The *owner or operator* of each *construction activity* identified in Tables 1 and 2 of Appendix B shall have a *trained contractor* inspect the erosion and sediment control practices and pollution prevention measures being implemented within the active work area daily to ensure that they are being maintained in effective operating condition at all times. If deficiencies are identified, the contractor shall



begin implementing corrective actions within one business day and shall complete the corrective actions in a reasonable time frame.

2. For construction sites where soil disturbance activities have been temporarily suspended (e.g. winter shutdown) and *temporary stabilization* measures have been applied to all disturbed areas, the *trained contractor* can stop conducting the maintenance inspections. The *trained contractor* shall begin conducting the maintenance inspections in accordance with Part IV.B.1. of this permit as soon as soil disturbance activities resume.
3. For construction sites where soil disturbance activities have been shut down with partial project completion, the *trained contractor* can stop conducting the maintenance inspections if all areas disturbed as of the project shutdown date have achieved *final stabilization* and all post-construction stormwater management practices required for the completed portion of the project have been constructed in conformance with the SWPPP and are operational.

### C. Qualified Inspector Inspection Requirements

The *owner or operator* shall have a *qualified inspector* conduct site inspections in conformance with the following requirements:

[Note: The *trained contractor* identified in Part III.A.6. and IV.B. of this permit **cannot** conduct the *qualified inspector* site inspections unless they meet the *qualified inspector* qualifications included in Appendix A. In order to perform these inspections, the *trained contractor* would have to be a:

- licensed Professional Engineer,
- Certified Professional in Erosion and Sediment Control (CPESC),
- New York State Erosion and Sediment Control Certificate Program holder
- Registered Landscape Architect, or
- someone working under the direct supervision of, and at the same company as, the licensed Professional Engineer or Registered Landscape Architect, provided they have received four (4) hours of Department endorsed training in proper erosion and sediment control principles from a Soil and Water Conservation District, or other Department endorsed entity].

1. A *qualified inspector* shall conduct site inspections for all *construction activities* identified in Tables 1 and 2 of Appendix B, with the exception of:
  - a. the construction of a single family residential subdivision with 25% or less *impervious cover* at total site build-out that involves a soil disturbance of one (1) or more acres of land but less than five (5) acres and is not located



in one of the watersheds listed in Appendix C and not directly discharging to one of the 303(d) segments listed in Appendix E;

- b. the construction of a single family home that involves a soil disturbance of one (1) or more acres of land but less than five (5) acres and is not located in one of the watersheds listed in Appendix C and not directly discharging to one of the 303(d) segments listed in Appendix E;
  - c. construction on agricultural property that involves a soil disturbance of one (1) or more acres of land but less than five (5) acres; and
  - d. *construction activities* located in the watersheds identified in Appendix D that involve soil disturbances between five thousand (5,000) square feet and one (1) acre of land.
2. Unless otherwise notified by the Department, the *qualified inspector* shall conduct site inspections in accordance with the following timetable:
- a. For construction sites where soil disturbance activities are on-going, the *qualified inspector* shall conduct a site inspection at least once every seven (7) calendar days.
  - b. For construction sites where soil disturbance activities are on-going and the *owner or operator* has received authorization in accordance with Part II.D.3 to disturb greater than five (5) acres of soil at any one time, the *qualified inspector* shall conduct at least two (2) site inspections every seven (7) calendar days. The two (2) inspections shall be separated by a minimum of two (2) full calendar days.
  - c. For construction sites where soil disturbance activities have been temporarily suspended (e.g. winter shutdown) and *temporary stabilization* measures have been applied to all disturbed areas, the *qualified inspector* shall conduct a site inspection at least once every thirty (30) calendar days. The *owner or operator* shall notify the DOW Water (SPDES) Program contact at the Regional Office (see contact information in Appendix F) or, in areas under the jurisdiction of a *regulated, traditional land use control MS4*, the *regulated, traditional land use control MS4* (provided the *regulated, traditional land use control MS4* is not the *owner or operator* of the *construction activity*) in writing prior to reducing the frequency of inspections.



- d. For construction sites where soil disturbance activities have been shut down with partial project completion, the *qualified inspector* can stop conducting inspections if all areas disturbed as of the project shutdown date have achieved *final stabilization* and all post-construction stormwater management practices required for the completed portion of the project have been constructed in conformance with the SWPPP and are operational. The *owner or operator* shall notify the DOW Water (SPDES) Program contact at the Regional Office (see contact information in Appendix F) or, in areas under the jurisdiction of a *regulated, traditional land use control MS4*, the *regulated, traditional land use control MS4* (provided the *regulated, traditional land use control MS4* is not the *owner or operator* of the *construction activity*) in writing prior to the shutdown. If soil disturbance activities are not resumed within 2 years from the date of shutdown, the *owner or operator* shall have the *qualified inspector* perform a final inspection and certify that all disturbed areas have achieved *final stabilization*, and all temporary, structural erosion and sediment control measures have been removed; and that all post-construction stormwater management practices have been constructed in conformance with the SWPPP by signing the “*Final Stabilization*” and “*Post-Construction Stormwater Management Practice*” certification statements on the NOT. The *owner or operator* shall then submit the completed NOT form to the address in Part II.B.1 of this permit.
  - e. For construction sites that directly *discharge* to one of the 303(d) segments listed in Appendix E or is located in one of the watersheds listed in Appendix C, the *qualified inspector* shall conduct at least two (2) site inspections every seven (7) calendar days. The two (2) inspections shall be separated by a minimum of two (2) full calendar days.
3. At a minimum, the *qualified inspector* shall inspect all erosion and sediment control practices and pollution prevention measures to ensure integrity and effectiveness, all post-construction stormwater management practices under construction to ensure that they are constructed in conformance with the SWPPP, all areas of disturbance that have not achieved *final stabilization*, all points of *discharge* to natural surface waterbodies located within, or immediately adjacent to, the property boundaries of the *construction site*, and all points of *discharge* from the *construction site*.
  4. The *qualified inspector* shall prepare an inspection report subsequent to each and every inspection. At a minimum, the inspection report shall include and/or address the following:



- a. Date and time of inspection;
- b. Name and title of person(s) performing inspection;
- c. A description of the weather and soil conditions (e.g. dry, wet, saturated) at the time of the inspection;
- d. A description of the condition of the runoff at all points of *discharge* from the *construction site*. This shall include identification of any *discharges* of sediment from the *construction site*. Include *discharges* from conveyance systems (i.e. pipes, culverts, ditches, etc.) and overland flow;
- e. A description of the condition of all natural surface waterbodies located within, or immediately adjacent to, the property boundaries of the *construction site* which receive runoff from disturbed areas. This shall include identification of any *discharges* of sediment to the surface waterbody;
- f. Identification of all erosion and sediment control practices and pollution prevention measures that need repair or maintenance;
- g. Identification of all erosion and sediment control practices and pollution prevention measures that were not installed properly or are not functioning as designed and need to be reinstalled or replaced;
- h. Description and sketch of areas with active soil disturbance activity, areas that have been disturbed but are inactive at the time of the inspection, and areas that have been stabilized (temporary and/or final) since the last inspection;
- i. Current phase of construction of all post-construction stormwater management practices and identification of all construction that is not in conformance with the SWPPP and technical standards;
- j. Corrective action(s) that must be taken to install, repair, replace or maintain erosion and sediment control practices and pollution prevention measures; and to correct deficiencies identified with the construction of the post-construction stormwater management practice(s);
- k. Identification and status of all corrective actions that were required by previous inspection; and



- I. Digital photographs, with date stamp, that clearly show the condition of all practices that have been identified as needing corrective actions. The *qualified inspector* shall attach paper color copies of the digital photographs to the inspection report being maintained onsite within seven (7) calendar days of the date of the inspection. The *qualified inspector* shall also take digital photographs, with date stamp, that clearly show the condition of the practice(s) after the corrective action has been completed. The *qualified inspector* shall attach paper color copies of the digital photographs to the inspection report that documents the completion of the corrective action work within seven (7) calendar days of that inspection.
5. Within one business day of the completion of an inspection, the *qualified inspector* shall notify the *owner or operator* and appropriate contractor or subcontractor identified in Part III.A.6. of this permit of any corrective actions that need to be taken. The contractor or subcontractor shall begin implementing the corrective actions within one business day of this notification and shall complete the corrective actions in a reasonable time frame.
6. All inspection reports shall be signed by the *qualified inspector*. Pursuant to Part II.D.2. of this permit, the inspection reports shall be maintained on site with the SWPPP.

## Part V. TERMINATION OF PERMIT COVERAGE

### A. Termination of Permit Coverage

1. An *owner or operator* that is eligible to terminate coverage under this permit must submit a completed NOT form to the address in Part II.B.1 of this permit. The NOT form shall be one which is associated with this permit, signed in accordance with Part VII.H of this permit.
2. An *owner or operator* may terminate coverage when one or more the following conditions have been met:
  - a. Total project completion - All *construction activity* identified in the SWPPP has been completed; and all areas of disturbance have achieved *final stabilization*; and all temporary, structural erosion and sediment control measures have been removed; and all post-construction stormwater management practices have been constructed in conformance with the SWPPP and are operational;



- b. Planned shutdown with partial project completion - All soil disturbance activities have ceased; and all areas disturbed as of the project shutdown date have achieved *final stabilization*; and all temporary, structural erosion and sediment control measures have been removed; and all post-construction stormwater management practices required for the completed portion of the project have been constructed in conformance with the SWPPP and are operational;
  - c. A new *owner or operator* has obtained coverage under this permit in accordance with Part II.F. of this permit.
  - d. The *owner or operator* obtains coverage under an alternative SPDES general permit or an individual SPDES permit.
3. For *construction activities* meeting subdivision 2a. or 2b. of this Part, the *owner or operator* shall have the *qualified inspector* perform a final site inspection prior to submitting the NOT. The *qualified inspector* shall, by signing the “*Final Stabilization*” and “Post-Construction Stormwater Management Practice certification statements on the NOT, certify that all the requirements in Part V.A.2.a. or b. of this permit have been achieved.
4. For *construction activities* that are subject to the requirements of a *regulated, traditional land use control MS4* and meet subdivision 2a. or 2b. of this Part, the *owner or operator* shall have the *regulated, traditional land use control MS4* sign the “MS4 Acceptance” statement on the NOT in accordance with the requirements in Part VII.H. of this permit. The *regulated, traditional land use control MS4* official, by signing this statement, has determined that it is acceptable for the *owner or operator* to submit the NOT in accordance with the requirements of this Part. The *regulated, traditional land use control MS4* can make this determination by performing a final site inspection themselves or by accepting the *qualified inspector’s* final site inspection certification(s) required in Part V.A.3. of this permit.
5. For *construction activities* that require post-construction stormwater management practices and meet subdivision 2a. of this Part, the *owner or operator* must, prior to submitting the NOT, ensure one of the following:
- a. the post-construction stormwater management practice(s) and any right-of-way(s) needed to maintain such practice(s) have been deeded to the municipality in which the practice(s) is located,



- b. an executed maintenance agreement is in place with the municipality that will maintain the post-construction stormwater management practice(s),
- c. for post-construction stormwater management practices that are privately owned, the *owner or operator* has a mechanism in place that requires operation and maintenance of the practice(s) in accordance with the operation and maintenance plan, such as a deed covenant in the *owner or operator's* deed of record,
- d. for post-construction stormwater management practices that are owned by a public or private institution (e.g. school, university, hospital), government agency or authority, or public utility; the *owner or operator* has policy and procedures in place that ensures operation and maintenance of the practices in accordance with the operation and maintenance plan.

## **Part VI. REPORTING AND RETENTION RECORDS**

### **A. Record Retention**

The *owner or operator* shall retain a copy of the NOI, NOI Acknowledgment Letter, SWPPP, MS4 SWPPP Acceptance form and any inspection reports that were prepared in conjunction with this permit for a period of at least five (5) years from the date that the Department receives a complete NOT submitted in accordance with Part V. of this general permit.

### **B. Addresses**

With the exception of the NOI, NOT, and MS4 SWPPP Acceptance form (which must be submitted to the address referenced in Part II.B.1 of this permit), all written correspondence requested by the Department, including individual permit applications, shall be sent to the address of the appropriate DOW Water (SPDES) Program contact at the Regional Office listed in Appendix F.

## **Part VII. STANDARD PERMIT CONDITIONS**

### **A. Duty to Comply**

The *owner or operator* must comply with all conditions of this permit. All contractors and subcontractors associated with the project must comply with the terms of the SWPPP. Any non-compliance with this permit constitutes a violation of the Clean Water



Act (CWA) and the ECL and is grounds for an enforcement action against the *owner or operator* and/or the contractor/subcontractor; permit revocation, suspension or modification; or denial of a permit renewal application. Upon a finding of significant non-compliance with this permit or the applicable SWPPP, the Department may order an immediate stop to all *construction activity* at the site until the non-compliance is remedied. The stop work order shall be in writing, shall describe the non-compliance in detail, and shall be sent to the *owner or operator*.

If any human remains or archaeological remains are encountered during excavation, the *owner or operator* must immediately cease, or cause to cease, all *construction activity* in the area of the remains and notify the appropriate Regional Water Engineer (RWE). *Construction activity* shall not resume until written permission to do so has been received from the RWE.

## **B. Continuation of the Expired General Permit**

This permit expires five (5) years from the effective date. If a new general permit is not issued prior to the expiration of this general permit, an *owner or operator* with coverage under this permit may continue to operate and *discharge* in accordance with the terms and conditions of this general permit, if it is extended pursuant to the State Administrative Procedure Act and 6 NYCRR Part 621, until a new general permit is issued.

## **C. Enforcement**

Failure of the *owner or operator*, its contractors, subcontractors, agents and/or assigns to strictly adhere to any of the permit requirements contained herein shall constitute a violation of this permit. There are substantial criminal, civil, and administrative penalties associated with violating the provisions of this permit. Fines of up to \$37,500 per day for each violation and imprisonment for up to fifteen (15) years may be assessed depending upon the nature and degree of the offense.

## **D. Need to Halt or Reduce Activity Not a Defense**

It shall not be a defense for an *owner or operator* in an enforcement action that it would have been necessary to halt or reduce the *construction activity* in order to maintain compliance with the conditions of this permit.



## **E. Duty to Mitigate**

The *owner or operator* and its contractors and subcontractors shall take all reasonable steps to *minimize* or prevent any *discharge* in violation of this permit which has a reasonable likelihood of adversely affecting human health or the environment.

## **F. Duty to Provide Information**

The *owner or operator* shall furnish to the Department, within a reasonable specified time period of a written request, all documentation necessary to demonstrate eligibility and any information to determine compliance with this permit or to determine whether cause exists for modifying or revoking this permit, or suspending or denying coverage under this permit, in accordance with the terms and conditions of this permit. The NOI, SWPPP and inspection reports required by this permit are public documents that the *owner or operator* must make available for review and copying by any person within five (5) business days of the *owner or operator* receiving a written request by any such person to review these documents. Copying of documents will be done at the requester's expense.

## **G. Other Information**

When the *owner or operator* becomes aware that they failed to submit any relevant facts, or submitted incorrect information in the NOI or in any of the documents required by this permit, or have made substantive revisions to the SWPPP (e.g. the scope of the project changes significantly, the type of post-construction stormwater management practice(s) changes, there is a reduction in the sizing of the post-construction stormwater management practice, or there is an increase in the disturbance area or *impervious area*), which were not reflected in the original NOI submitted to the Department, they shall promptly submit such facts or information to the Department using the contact information in Part II.A. of this permit. Failure of the *owner or operator* to correct or supplement any relevant facts within five (5) business days of becoming aware of the deficiency shall constitute a violation of this permit.

## **H. Signatory Requirements**

1. All NOIs and NOTs shall be signed as follows:
  - a. For a corporation these forms shall be signed by a responsible corporate officer. For the purpose of this section, a responsible corporate officer means:



- (i) a president, secretary, treasurer, or vice-president of the corporation in charge of a principal business function, or any other person who performs similar policy or decision-making functions for the corporation; or
    - (ii) the manager of one or more manufacturing, production or operating facilities, provided the manager is authorized to make management decisions which govern the operation of the regulated facility including having the explicit or implicit duty of making major capital investment recommendations, and initiating and directing other comprehensive measures to assure long term environmental compliance with environmental laws and regulations; the manager can ensure that the necessary systems are established or actions taken to gather complete and accurate information for permit application requirements; and where authority to sign documents has been assigned or delegated to the manager in accordance with corporate procedures;
  - b. For a partnership or sole proprietorship these forms shall be signed by a general partner or the proprietor, respectively; or
  - c. For a municipality, State, Federal, or other public agency these forms shall be signed by either a principal executive officer or ranking elected official. For purposes of this section, a principal executive officer of a Federal agency includes:
    - (i) the chief executive officer of the agency, or
    - (ii) a senior executive officer having responsibility for the overall operations of a principal geographic unit of the agency (e.g., Regional Administrators of EPA).
2. The SWPPP and other information requested by the Department shall be signed by a person described in Part VII.H.1. of this permit or by a duly authorized representative of that person. A person is a duly authorized representative only if:
- a. The authorization is made in writing by a person described in Part VII.H.1. of this permit;
  - b. The authorization specifies either an individual or a position having responsibility for the overall operation of the regulated facility or activity, such as the position of plant manager, operator of a well or a well field,



superintendent, position of *equivalent* responsibility, or an individual or position having overall responsibility for environmental matters for the company. (A duly authorized representative may thus be either a named individual or any individual occupying a named position) and,

- c. The written authorization shall include the name, title and signature of the authorized representative and be attached to the SWPPP.
3. All inspection reports shall be signed by the *qualified inspector* that performs the inspection.
4. The MS4 SWPPP Acceptance form shall be signed by the principal executive officer or ranking elected official from the *regulated, traditional land use control MS4*, or by a duly authorized representative of that person.

It shall constitute a permit violation if an incorrect and/or improper signatory authorizes any required forms, SWPPP and/or inspection reports.

## **I. Property Rights**

The issuance of this permit does not convey any property rights of any sort, nor any exclusive privileges, nor does it authorize any injury to private property nor any invasion of personal rights, nor any infringement of Federal, State or local laws or regulations. *Owners or operators* must obtain any applicable conveyances, easements, licenses and/or access to real property prior to *commencing construction activity*.

## **J. Severability**

The provisions of this permit are severable, and if any provision of this permit, or the application of any provision of this permit to any circumstance, is held invalid, the application of such provision to other circumstances, and the remainder of this permit shall not be affected thereby.

## **K. Requirement to Obtain Coverage Under an Alternative Permit**

1. The Department may require any owner or operator authorized by this permit to apply for and/or obtain either an individual SPDES permit or another SPDES general permit. When the Department requires any discharger authorized by a general permit to apply for an individual SPDES permit, it shall notify the discharger in writing that a permit application is required. This notice shall



include a brief statement of the reasons for this decision, an application form, a statement setting a time frame for the owner or operator to file the application for an individual SPDES permit, and a deadline, not sooner than 180 days from owner or operator receipt of the notification letter, whereby the authorization to discharge under this general permit shall be terminated. Applications must be submitted to the appropriate Permit Administrator at the Regional Office. The Department may grant additional time upon demonstration, to the satisfaction of the Department, that additional time to apply for an alternative authorization is necessary or where the Department has not provided a permit determination in accordance with Part 621 of this Title.

2. When an individual SPDES permit is issued to a discharger authorized to *discharge* under a general SPDES permit for the same *discharge(s)*, the general permit authorization for outfalls authorized under the individual SPDES permit is automatically terminated on the effective date of the individual permit unless termination is earlier in accordance with 6 NYCRR Part 750.

## **L. Proper Operation and Maintenance**

The *owner or operator* shall at all times properly operate and maintain all facilities and systems of treatment and control (and related appurtenances) which are installed or used by the *owner or operator* to achieve compliance with the conditions of this permit and with the requirements of the SWPPP.

## **M. Inspection and Entry**

The *owner or operator* shall allow an authorized representative of the Department, EPA, applicable county health department, or, in the case of a *construction site* which *discharges* through an *MS4*, an authorized representative of the *MS4* receiving the discharge, upon the presentation of credentials and other documents as may be required by law, to:

1. Enter upon the owner's or operator's premises where a regulated facility or activity is located or conducted or where records must be kept under the conditions of this permit;
2. Have access to and copy at reasonable times, any records that must be kept under the conditions of this permit; and



3. Inspect at reasonable times any facilities or equipment (including monitoring and control equipment), practices or operations regulated or required by this permit.
4. Sample or monitor at reasonable times, for purposes of assuring permit compliance or as otherwise authorized by the Act or ECL, any substances or parameters at any location.

## **N. Permit Actions**

This permit may, at any time, be modified, suspended, revoked, or renewed by the Department in accordance with 6 NYCRR Part 621. The filing of a request by the *owner or operator* for a permit modification, revocation and reissuance, termination, a notification of planned changes or anticipated noncompliance does not limit, diminish and/or stay compliance with any terms of this permit.

## **O. Definitions**

Definitions of key terms are included in Appendix A of this permit.

## **P. Re-Opener Clause**

1. If there is evidence indicating potential or realized impacts on water quality due to any stormwater discharge associated with construction activity covered by this permit, the owner or operator of such discharge may be required to obtain an individual permit or alternative general permit in accordance with Part VII.K. of this permit or the permit may be modified to include different limitations and/or requirements.
2. Any Department initiated permit modification, suspension or revocation will be conducted in accordance with 6 NYCRR Part 621, 6 NYCRR 750-1.18, and 6 NYCRR 750-1.20.

## **Q. Penalties for Falsification of Forms and Reports**

In accordance with 6NYCRR Part 750-2.4 and 750-2.5, any person who knowingly makes any false material statement, representation, or certification in any application, record, report or other document filed or required to be maintained under this permit, including reports of compliance or noncompliance shall, upon conviction, be punished in accordance with ECL §71-1933 and or Articles 175 and 210 of the New York State Penal Law.



## **R. Other Permits**

Nothing in this permit relieves the *owner or operator* from a requirement to obtain any other permits required by law.



## **APPENDIX A – Acronyms and Definitions**

### **Acronyms**

APO – Agency Preservation Officer  
BMP – Best Management Practice  
CPESC – Certified Professional in Erosion and Sediment Control  
Cpv – Channel Protection Volume  
CWA – Clean Water Act (or the Federal Water Pollution Control Act, 33 U.S.C. §1251 et seq)  
DOW – Division of Water  
EAF – Environmental Assessment Form  
ECL - Environmental Conservation Law  
EPA – U. S. Environmental Protection Agency  
HSG – Hydrologic Soil Group  
MS4 – Municipal Separate Storm Sewer System  
NOI – Notice of Intent  
NOT – Notice of Termination  
NPDES – National Pollutant Discharge Elimination System  
OPRHP – Office of Parks, Recreation and Historic Places  
Qf – Extreme Flood  
Qp – Overbank Flood  
RRv – Runoff Reduction Volume  
RWE – Regional Water Engineer  
SEQR – State Environmental Quality Review  
SEQRA - State Environmental Quality Review Act  
SHPA – State Historic Preservation Act  
SPDES – State Pollutant Discharge Elimination System  
SWPPP – Stormwater Pollution Prevention Plan  
TMDL – Total Maximum Daily Load  
UPA – Uniform Procedures Act  
USDA – United States Department of Agriculture  
WQv – Water Quality Volume



## Definitions

All definitions in this section are solely for the purposes of this permit.

**Agricultural Building** – a structure designed and constructed to house farm implements, hay, grain, poultry, livestock or other horticultural products; excluding any structure designed, constructed or used, in whole or in part, for human habitation, as a place of employment where agricultural products are processed, treated or packaged, or as a place used by the public.

**Agricultural Property** – means the land for construction of a barn, *agricultural building*, silo, stockyard, pen or other structural practices identified in Table II in the “Agricultural Management Practices Catalog for Nonpoint Source Pollution in New York State” prepared by the Department in cooperation with agencies of New York Nonpoint Source Coordinating Committee (dated June 2007).

**Alter Hydrology from Pre to Post-Development Conditions** - means the post-development peak flow rate(s) has increased by more than 5% of the pre-developed condition for the design storm of interest (e.g. 10 yr and 100 yr).

**Combined Sewer** - means a sewer that is designed to collect and convey both “sewage” and “stormwater”.

**Commence (Commencement of) Construction Activities** - means the initial disturbance of soils associated with clearing, grading or excavation activities; or other construction related activities that disturb or expose soils such as demolition, stockpiling of fill material, and the initial installation of erosion and sediment control practices required in the SWPPP. See definition for “*Construction Activity(ies)*” also.

**Construction Activity(ies)** - means any clearing, grading, excavation, filling, demolition or stockpiling activities that result in soil disturbance. Clearing activities can include, but are not limited to, logging equipment operation, the cutting and skidding of trees, stump removal and/or brush root removal. Construction activity does not include routine maintenance that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of a facility.

**Construction Site** – means the land area where *construction activity(ies)* will occur. See definition for “*Commence (Commencement of) Construction Activities*” and “*Larger Common Plan of Development or Sale*” also.

**Dewatering** – means the act of draining rainwater and/or groundwater from building foundations, vaults or excavations/trenches.

**Direct Discharge (to a specific surface waterbody)** - means that runoff flows from a *construction site* by overland flow and the first point of discharge is the specific surface waterbody, or runoff flows from a *construction site* to a separate storm sewer system



and the first point of discharge from the separate storm sewer system is the specific surface waterbody.

**Discharge(s)** - means any addition of any pollutant to waters of the State through an outlet or *point source*.

**Embankment** – means an earthen or rock slope that supports a road/highway.

**Endangered or Threatened Species** – see 6 NYCRR Part 182 of the Department’s rules and regulations for definition of terms and requirements.

**Environmental Conservation Law (ECL)** - means chapter 43-B of the Consolidated Laws of the State of New York, entitled the Environmental Conservation Law.

**Equivalent (Equivalence)** – means that the practice or measure meets all the performance, longevity, maintenance, and safety objectives of the technical standard and will provide an equal or greater degree of water quality protection.

**Final Stabilization** - means that all soil disturbance activities have ceased and a uniform, perennial vegetative cover with a density of eighty (80) percent over the entire pervious surface has been established; or other equivalent stabilization measures, such as permanent landscape mulches, rock rip-rap or washed/crushed stone have been applied on all disturbed areas that are not covered by permanent structures, concrete or pavement.

**General SPDES permit** - means a SPDES permit issued pursuant to 6 NYCRR Part 750-1.21 and Section 70-0117 of the ECL authorizing a category of discharges.

**Groundwater(s)** - means waters in the saturated zone. The saturated zone is a subsurface zone in which all the interstices are filled with water under pressure greater than that of the atmosphere. Although the zone may contain gas-filled interstices or interstices filled with fluids other than water, it is still considered saturated.

**Historic Property** – means any building, structure, site, object or district that is listed on the State or National Registers of Historic Places or is determined to be eligible for listing on the State or National Registers of Historic Places.

**Impervious Area (Cover)** - means all impermeable surfaces that cannot effectively infiltrate rainfall. This includes paved, concrete and gravel surfaces (i.e. parking lots, driveways, roads, runways and sidewalks); building rooftops and miscellaneous impermeable structures such as patios, pools, and sheds.

**Infeasible** – means not technologically possible, or not economically practicable and achievable in light of best industry practices.



**Larger Common Plan of Development or Sale** - means a contiguous area where multiple separate and distinct *construction activities* are occurring, or will occur, under one plan. The term “plan” in “larger common plan of development or sale” is broadly defined as any announcement or piece of documentation (including a sign, public notice or hearing, marketing plan, advertisement, drawing, permit application, State Environmental Quality Review Act (SEQRA) environmental assessment form or other documents, zoning request, computer design, etc.) or physical demarcation (including boundary signs, lot stakes, surveyor markings, etc.) indicating that *construction activities* may occur on a specific plot.

For discrete construction projects that are located within a larger common plan of development or sale that are at least 1/4 mile apart, each project can be treated as a separate plan of development or sale provided any interconnecting road, pipeline or utility project that is part of the same “common plan” is not concurrently being disturbed.

**Minimize** – means reduce and/or eliminate to the extent achievable using control measures (including best management practices) that are technologically available and economically practicable and achievable in light of best industry practices.

**Municipal Separate Storm Sewer (MS4)** - a conveyance or system of conveyances (including roads with drainage systems, municipal streets, catch basins, curbs, gutters, ditches, man-made channels, or storm drains):

- (i) Owned or operated by a State, city, town, borough, county, parish, district, association, or other public body (created by or pursuant to State law) having jurisdiction over disposal of sewage, industrial wastes, stormwater, or other wastes, including special districts under State law such as a sewer district, flood control district or drainage district, or similar entity, or an Indian tribe or an authorized Indian tribal organization, or a designated and approved management agency under section 208 of the CWA that discharges to surface waters of the State;
- (ii) Designed or used for collecting or conveying stormwater;
- (iii) Which is not a *combined sewer*; and
- (iv) Which is not part of a Publicly Owned Treatment Works (POTW) as defined at 40 CFR 122.2.

**National Pollutant Discharge Elimination System (NPDES)** - means the national system for the issuance of wastewater and stormwater permits under the Federal Water Pollution Control Act (Clean Water Act).

**Natural Buffer** – means an undisturbed area with natural cover running along a surface water (e.g. wetland, stream, river, lake, etc.).

**New Development** – means any land disturbance that does not meet the definition of Redevelopment Activity included in this appendix.



**New York State Erosion and Sediment Control Certificate Program** – a certificate program that establishes and maintains a process to identify and recognize individuals who are capable of developing, designing, inspecting and maintaining erosion and sediment control plans on projects that disturb soils in New York State. The certificate program is administered by the New York State Conservation District Employees Association.

**NOI Acknowledgment Letter** - means the letter that the Department sends to an owner or operator to acknowledge the Department's receipt and acceptance of a complete Notice of Intent. This letter documents the owner's or operator's authorization to discharge in accordance with the general permit for stormwater discharges from *construction activity*.

**Nonpoint Source** - means any source of water pollution or pollutants which is not a discrete conveyance or *point source* permitted pursuant to Title 7 or 8 of Article 17 of the Environmental Conservation Law (see ECL Section 17-1403).

**Overbank** –means flow events that exceed the capacity of the stream channel and spill out into the adjacent floodplain.

**Owner or Operator** - means the person, persons or legal entity which owns or leases the property on which the *construction activity* is occurring; an entity that has operational control over the construction plans and specifications, including the ability to make modifications to the plans and specifications; and/or an entity that has day-to-day operational control of those activities at a project that are necessary to ensure compliance with the permit conditions.

**Performance Criteria** – means the design criteria listed under the “Required Elements” sections in Chapters 5, 6 and 10 of the technical standard, New York State Stormwater Management Design Manual, dated January 2015. It does not include the Sizing Criteria (i.e. WQv, RRv, Cpv, Qp and Qf ) in Part I.C.2. of the permit.

**Point Source** - means any discernible, confined and discrete conveyance, including but not limited to any pipe, ditch, channel, tunnel, conduit, well, discrete fissure, container, rolling stock, concentrated animal feeding operation, vessel or other floating craft, or landfill leachate collection system from which *pollutants* are or may be discharged.

**Pollutant** - means dredged spoil, filter backwash, solid waste, incinerator residue, sewage, garbage, sewage sludge, munitions, chemical wastes, biological materials, radioactive materials, heat, wrecked or discarded equipment, rock, sand and industrial, municipal, agricultural waste and ballast discharged into water; which may cause or might reasonably be expected to cause pollution of the waters of the state in contravention of the standards or guidance values adopted as provided in 6 NYCRR Parts 700 et seq .



**Qualified Inspector** - means a person that is knowledgeable in the principles and practices of erosion and sediment control, such as a licensed Professional Engineer, Certified Professional in Erosion and Sediment Control (CPESC), Registered Landscape Architect, New York State Erosion and Sediment Control Certificate Program holder or other Department endorsed individual(s).

It can also mean someone working under the direct supervision of, and at the same company as, the licensed Professional Engineer or Registered Landscape Architect, provided that person has training in the principles and practices of erosion and sediment control. Training in the principles and practices of erosion and sediment control means that the individual working under the direct supervision of the licensed Professional Engineer or Registered Landscape Architect has received four (4) hours of Department endorsed training in proper erosion and sediment control principles from a Soil and Water Conservation District, or other Department endorsed entity. After receiving the initial training, the individual working under the direct supervision of the licensed Professional Engineer or Registered Landscape Architect shall receive four (4) hours of training every three (3) years.

It can also mean a person that meets the *Qualified Professional* qualifications in addition to the *Qualified Inspector* qualifications.

Note: Inspections of any post-construction stormwater management practices that include structural components, such as a dam for an impoundment, shall be performed by a licensed Professional Engineer.

**Qualified Professional** - means a person that is knowledgeable in the principles and practices of stormwater management and treatment, such as a licensed Professional Engineer, Registered Landscape Architect or other Department endorsed individual(s). Individuals preparing SWPPPs that require the post-construction stormwater management practice component must have an understanding of the principles of hydrology, water quality management practice design, water quantity control design, and, in many cases, the principles of hydraulics. All components of the SWPPP that involve the practice of engineering, as defined by the NYS Education Law (see Article 145), shall be prepared by, or under the direct supervision of, a professional engineer licensed to practice in the State of New York.

**Redevelopment Activity(ies)** – means the disturbance and reconstruction of existing impervious area, including impervious areas that were removed from a project site within five (5) years of preliminary project plan submission to the local government (i.e. site plan, subdivision, etc.).

**Regulated, Traditional Land Use Control MS4** - means a city, town or village with land use control authority that is authorized to discharge under New York State DEC's



SPDES General Permit For Stormwater Discharges from Municipal Separate Stormwater Sewer Systems (MS4s) or the City of New York's Individual SPDES Permit for their Municipal Separate Storm Sewer Systems (NY-0287890).

**Routine Maintenance Activity** - means *construction activity* that is performed to maintain the original line and grade, hydraulic capacity, or original purpose of a facility, including, but not limited to:

- Re-grading of gravel roads or parking lots,
- Cleaning and shaping of existing roadside ditches and culverts that maintains the approximate original line and grade, and hydraulic capacity of the ditch,
- Cleaning and shaping of existing roadside ditches that does not maintain the approximate original grade, hydraulic capacity and purpose of the ditch if the changes to the line and grade, hydraulic capacity or purpose of the ditch are installed to improve water quality and quantity controls (e.g. installing grass lined ditch),
- Placement of aggregate shoulder backing that stabilizes the transition between the road shoulder and the ditch or *embankment*,
- Full depth milling and filling of existing asphalt pavements, replacement of concrete pavement slabs, and similar work that does not expose soil or disturb the bottom six (6) inches of subbase material,
- Long-term use of equipment storage areas at or near highway maintenance facilities,
- Removal of sediment from the edge of the highway to restore a previously existing sheet-flow drainage connection from the highway surface to the highway ditch or *embankment*,
- Existing use of Canal Corp owned upland disposal sites for the canal, and
- Replacement of curbs, gutters, sidewalks and guide rail posts.

**Site limitations** – means site conditions that prevent the use of an infiltration technique and or infiltration of the total WQv. Typical site limitations include: seasonal high groundwater, shallow depth to bedrock, and soils with an infiltration rate less than 0.5 inches/hour. The existence of site limitations shall be confirmed and documented using actual field testing (i.e. test pits, soil borings, and infiltration test) or using information from the most current United States Department of Agriculture (USDA) Soil Survey for the County where the project is located.

**Sizing Criteria** – means the criteria included in Part I.C.2 of the permit that are used to size post-construction stormwater management control practices. The criteria include; Water Quality Volume (WQv), Runoff Reduction Volume (RRv), Channel Protection Volume (Cpv), *Overbank Flood* (Qp), and *Extreme Flood* (Qf).

**State Pollutant Discharge Elimination System (SPDES)** - means the system established pursuant to Article 17 of the ECL and 6 NYCRR Part 750 for issuance of permits authorizing discharges to the waters of the state.



**Steep Slope** – means land area designated on the current United States Department of Agriculture (“USDA”) Soil Survey as Soil Slope Phase “D”, (provided the map unit name is inclusive of slopes greater than 25%) , or Soil Slope Phase E or F, (regardless of the map unit name), or a combination of the three designations.

**Streambank** – as used in this permit, means the terrain alongside the bed of a creek or stream. The bank consists of the sides of the channel, between which the flow is confined.

**Stormwater Pollution Prevention Plan (SWPPP)** – means a project specific report, including construction drawings, that among other things: describes the construction activity(ies), identifies the potential sources of pollution at the *construction site*; describes and shows the stormwater controls that will be used to control the pollutants (i.e. erosion and sediment controls; for many projects, includes post-construction stormwater management controls); and identifies procedures the *owner or operator* will implement to comply with the terms and conditions of the permit. See Part III of the permit for a complete description of the information that must be included in the SWPPP.

**Surface Waters of the State** - shall be construed to include lakes, bays, sounds, ponds, impounding reservoirs, springs, rivers, streams, creeks, estuaries, marshes, inlets, canals, the Atlantic ocean within the territorial seas of the state of New York and all other bodies of surface water, natural or artificial, inland or coastal, fresh or salt, public or private (except those private waters that do not combine or effect a junction with natural surface waters), which are wholly or partially within or bordering the state or within its jurisdiction. Waters of the state are further defined in 6 NYCRR Parts 800 to 941.

**Temporarily Ceased** – means that an existing disturbed area will not be disturbed again within 14 calendar days of the previous soil disturbance.

**Temporary Stabilization** - means that exposed soil has been covered with material(s) as set forth in the technical standard, New York Standards and Specifications for Erosion and Sediment Control, to prevent the exposed soil from eroding. The materials can include, but are not limited to, mulch, seed and mulch, and erosion control mats (e.g. jute twisted yarn, excelsior wood fiber mats).

**Total Maximum Daily Loads (TMDLs)** - A TMDL is the sum of the allowable loads of a single pollutant from all contributing point and *nonpoint sources*. It is a calculation of the maximum amount of a pollutant that a waterbody can receive on a daily basis and still meet *water quality standards*, and an allocation of that amount to the pollutant's sources. A TMDL stipulates wasteload allocations (WLAs) for *point source* discharges, load allocations (LAs) for *nonpoint sources*, and a margin of safety (MOS).

**Trained Contractor** - means an employee from the contracting (construction) company, identified in Part III.A.6., that has received four (4) hours of Department endorsed



training in proper erosion and sediment control principles from a Soil and Water Conservation District, or other Department endorsed entity. After receiving the initial training, the *trained contractor* shall receive four (4) hours of training every three (3) years.

It can also mean an employee from the contracting (construction) company, identified in Part III.A.6., that meets the *qualified inspector* qualifications (e.g. licensed Professional Engineer, Certified Professional in Erosion and Sediment Control (CPESC), Registered Landscape Architect, New York State Erosion and Sediment Control Certificate Program holder, or someone working under the direct supervision of, and at the same company as, the licensed Professional Engineer or Registered Landscape Architect, provided they have received four (4) hours of Department endorsed training in proper erosion and sediment control principles from a Soil and Water Conservation District, or other Department endorsed entity).

The *trained contractor* is responsible for the day to day implementation of the SWPPP.

**Uniform Procedures Act (UPA) Permit** - means a permit required under 6 NYCRR Part 621 of the Environmental Conservation Law (ECL), Article 70.

**Water Quality Standard** - means such measures of purity or quality for any waters in relation to their reasonable and necessary use as promulgated in 6 NYCRR Part 700 et seq.



## APPENDIX B – Required SWPPP Components by Project Type

**Table 1**  
**Construction Activities that Require the Preparation of a SWPPP That Only Includes Erosion and Sediment Controls**

<p><b>The following construction activities that involve soil disturbances of one (1) or more acres of land, but less than five (5) acres:</b></p> <ul style="list-style-type: none"><li>• Single family home <u>not</u> located in one of the watersheds listed in Appendix C or <u>not directly discharging</u> to one of the 303(d) segments listed in Appendix E</li><li>• Single family residential subdivisions with 25% or less impervious cover at total site build-out and <u>not</u> located in one of the watersheds listed in Appendix C and <u>not</u> directly discharging to one of the 303(d) segments listed in Appendix E</li><li>• Construction of a barn or other <i>agricultural building</i>, silo, stock yard or pen.</li></ul>
<p><b>The following construction activities that involve soil disturbances between five thousand (5000) square feet and one (1) acre of land:</b></p> <p>All construction activities located in the watersheds identified in Appendix D that involve soil disturbances between five thousand (5,000) square feet and one (1) acre of land.</p>
<p><b>The following construction activities that involve soil disturbances of one (1) or more acres of land:</b></p> <ul style="list-style-type: none"><li>• Installation of underground, linear utilities; such as gas lines, fiber-optic cable, cable TV, electric, telephone, sewer mains, and water mains</li><li>• Environmental enhancement projects, such as wetland mitigation projects, stormwater retrofits and stream restoration projects</li><li>• Pond construction</li><li>• Linear bike paths running through areas with vegetative cover, including bike paths surfaced with an impervious cover</li><li>• Cross-country ski trails and walking/hiking trails</li><li>• Sidewalk, bike path or walking path projects, surfaced with an impervious cover, that are not part of residential, commercial or institutional development;</li><li>• Sidewalk, bike path or walking path projects, surfaced with an impervious cover, that include incidental shoulder or curb work along an existing highway to support construction of the sidewalk, bike path or walking path.</li><li>• Slope stabilization projects</li><li>• Slope flattening that changes the grade of the site, but does not significantly change the runoff characteristics</li></ul>



**Table 1 (Continued) CONSTRUCTION ACTIVITIES THAT REQUIRE THE PREPARATION OF A SWPPP  
THAT ONLY INCLUDES EROSION AND SEDIMENT CONTROLS**

**The following construction activities that involve soil disturbances of one (1) or more acres of land:**

- Spoil areas that will be covered with vegetation
- Vegetated open space projects (i.e. recreational parks, lawns, meadows, fields, downhill ski trails) excluding projects that *alter hydrology from pre to post development* conditions,
- Athletic fields (natural grass) that do not include the construction or reconstruction of *impervious area* and do not *alter hydrology from pre to post development* conditions
- Demolition project where vegetation will be established, and no redevelopment is planned
- Overhead electric transmission line project that does not include the construction of permanent access roads or parking areas surfaced with *impervious cover*
- Structural practices as identified in Table II in the “Agricultural Management Practices Catalog for Nonpoint Source Pollution in New York State”, excluding projects that involve soil disturbances of greater than five acres and construction activities that include the construction or reconstruction of impervious area
- Temporary access roads, median crossovers, detour roads, lanes, or other temporary impervious areas that will be restored to pre-construction conditions once the construction activity is complete



**Table 2**  
**CONSTRUCTION ACTIVITIES THAT REQUIRE THE PREPARATION OF A SWPPP THAT INCLUDES**  
**POST-CONSTRUCTION STORMWATER MANAGEMENT PRACTICES**

**The following construction activities that involve soil disturbances of one (1) or more acres of land:**

- Single family home located in one of the watersheds listed in Appendix C or *directly discharging* to one of the 303(d) segments listed in Appendix E
- Single family home that disturbs five (5) or more acres of land
- Single family residential subdivisions located in one of the watersheds listed in Appendix C or *directly discharging* to one of the 303(d) segments listed in Appendix E
- Single family residential subdivisions that involve soil disturbances of between one (1) and five (5) acres of land with greater than 25% impervious cover at total site build-out
- Single family residential subdivisions that involve soil disturbances of five (5) or more acres of land, and single family residential subdivisions that involve soil disturbances of less than five (5) acres that are part of a larger common plan of development or sale that will ultimately disturb five or more acres of land
- Multi-family residential developments; includes duplexes, townhomes, condominiums, senior housing complexes, apartment complexes, and mobile home parks
- Airports
- Amusement parks
- Breweries, cideries, and wineries, including establishments constructed on agricultural land
- Campgrounds
- Cemeteries that include the construction or reconstruction of impervious area (>5% of disturbed area) or *alter the hydrology from pre to post development* conditions
- Commercial developments
- Churches and other places of worship
- Construction of a barn or other *agricultural building* (e.g. silo) and structural practices as identified in Table II in the "Agricultural Management Practices Catalog for Nonpoint Source Pollution in New York State" that include the construction or reconstruction of *impervious area*, excluding projects that involve soil disturbances of less than five acres.
- Golf courses
- Institutional development; includes hospitals, prisons, schools and colleges
- Industrial facilities; includes industrial parks
- Landfills
- Municipal facilities; includes highway garages, transfer stations, office buildings, POTW's, water treatment plants, and water storage tanks
- Office complexes
- Playgrounds that include the construction or reconstruction of impervious area
- Sports complexes
- Racetracks; includes racetracks with earthen (dirt) surface
- Road construction or reconstruction, including roads constructed as part of the construction activities listed in Table 1



Table 2 (Continued)

**CONSTRUCTION ACTIVITIES THAT REQUIRE THE PREPARATION OF A SWPPP THAT INCLUDES  
POST-CONSTRUCTION STORMWATER MANAGEMENT PRACTICES**

**The following construction activities that involve soil disturbances of one (1) or more acres of land:**

- Parking lot construction or reconstruction, including parking lots constructed as part of the construction activities listed in Table 1
- Athletic fields (natural grass) that include the construction or reconstruction of impervious area (>5% of disturbed area) or *alter the hydrology from pre to post development* conditions
- Athletic fields with artificial turf
- Permanent access roads, parking areas, substations, compressor stations and well drilling pads, surfaced with *impervious cover*, and constructed as part of an over-head electric transmission line project, wind-power project, cell tower project, oil or gas well drilling project, sewer or water main project or other linear utility project
- Sidewalk, bike path or walking path projects, surfaced with an impervious cover, that are part of a residential, commercial or institutional development
- Sidewalk, bike path or walking path projects, surfaced with an impervious cover, that are part of a highway construction or reconstruction project
- All other construction activities that include the construction or reconstruction of *impervious area* or *alter the hydrology from pre to post development* conditions, and are not listed in Table 1




## APPENDIX C – Watersheds Requiring Enhanced Phosphorus Removal

**Watersheds where *owners or operators* of construction activities identified in Table 2 of Appendix B must prepare a SWPPP that includes post-construction stormwater management practices designed in conformance with the Enhanced Phosphorus Removal Standards included in the technical standard, New York State Stormwater Management Design Manual (“Design Manual”).**

- Entire New York City Watershed located east of the Hudson River - Figure 1
- Onondaga Lake Watershed - Figure 2
- Greenwood Lake Watershed -Figure 3
- Oscawana Lake Watershed – Figure 4
- Kinderhook Lake Watershed – Figure 5



**Figure 1 - New York City Watershed East of the Hudson**



**Figure 2 - Onondaga Lake Watershed**




**Figure 3 - Greenwood Lake Watershed**






**Figure 4 - Oscawana Lake Watershed**





**Figure 5 - Kinderhook Lake Watershed**



## **APPENDIX D – Watersheds with Lower Disturbance Threshold**

**Watersheds where *owners or operators* of construction activities that involve soil disturbances between five thousand (5000) square feet and one (1) acre of land must obtain coverage under this permit.**

Entire New York City Watershed that is located east of the Hudson River - See Figure 1 in Appendix C
--



## APPENDIX E – 303(d) Segments Impaired by Construction Related Pollutant(s)

List of 303(d) segments impaired by pollutants related to *construction activity* (e.g. silt, sediment or nutrients). The list was developed using "The Final New York State 2016 Section 303(d) List of Impaired Waters Requiring a TMDL/Other Strategy" dated November 2016. *Owners or operators* of single family home and single family residential subdivisions with 25% or less total impervious cover at total site build-out that involve soil disturbances of one or more acres of land, but less than 5 acres, and *directly discharge* to one of the listed segments below shall prepare a SWPPP that includes post-construction stormwater management practices designed in conformance with the New York State Stormwater Management Design Manual ("Design Manual"), dated January 2015.

COUNTY	WATERBODY	POLLUTANT
Albany	Ann Lee (Shakers) Pond, Stump Pond	Nutrients
Albany	Basic Creek Reservoir	Nutrients
Allegany	Amity Lake, Saunders Pond	Nutrients
Bronx	Long Island Sound, Bronx	Nutrients
Bronx	Van Cortlandt Lake	Nutrients
Broome	Fly Pond, Deer Lake, Sky Lake	Nutrients
Broome	Minor Tribs to Lower Susquehanna (north)	Nutrients
Broome	Whitney Point Lake/Reservoir	Nutrients
Cattaraugus	Allegheny River/Reservoir	Nutrients
Cattaraugus	Beaver (Alma) Lake	Nutrients
Cattaraugus	Case Lake	Nutrients
Cattaraugus	Linlyco/Club Pond	Nutrients
Cayuga	Duck Lake	Nutrients
Cayuga	Little Sodus Bay	Nutrients
Chautauqua	Bear Lake	Nutrients
Chautauqua	Chadakoin River and tribs	Nutrients
Chautauqua	Chautauqua Lake, North	Nutrients
Chautauqua	Chautauqua Lake, South	Nutrients
Chautauqua	Findley Lake	Nutrients
Chautauqua	Hulburt/Clymer Pond	Nutrients
Clinton	Great Chazy River, Lower, Main Stem	Silt/Sediment
Clinton	Lake Champlain, Main Lake, Middle	Nutrients
Clinton	Lake Champlain, Main Lake, North	Nutrients
Columbia	Kinderhook Lake	Nutrients
Columbia	Robinson Pond	Nutrients
Cortland	Dean Pond	Nutrients



### 303(d) Segments Impaired by Construction Related Pollutant(s)

Dutchess	Fall Kill and tribs	Nutrients
Dutchess	Hillside Lake	Nutrients
Dutchess	Wappingers Lake	Nutrients
Dutchess	Wappingers Lake	Silt/Sediment
Erie	Beeman Creek and tribs	Nutrients
Erie	Ellicott Creek, Lower, and tribs	Silt/Sediment
Erie	Ellicott Creek, Lower, and tribs	Nutrients
Erie	Green Lake	Nutrients
Erie	Little Sister Creek, Lower, and tribs	Nutrients
Erie	Murder Creek, Lower, and tribs	Nutrients
Erie	Rush Creek and tribs	Nutrients
Erie	Scajaquada Creek, Lower, and tribs	Nutrients
Erie	Scajaquada Creek, Middle, and tribs	Nutrients
Erie	Scajaquada Creek, Upper, and tribs	Nutrients
Erie	South Branch Smoke Cr, Lower, and tribs	Silt/Sediment
Erie	South Branch Smoke Cr, Lower, and tribs	Nutrients
Essex	Lake Champlain, Main Lake, South	Nutrients
Essex	Lake Champlain, South Lake	Nutrients
Essex	Willsboro Bay	Nutrients
Genesee	Bigelow Creek and tribs	Nutrients
Genesee	Black Creek, Middle, and minor tribs	Nutrients
Genesee	Black Creek, Upper, and minor tribs	Nutrients
Genesee	Bowen Brook and tribs	Nutrients
Genesee	LeRoy Reservoir	Nutrients
Genesee	Oak Orchard Cr, Upper, and tribs	Nutrients
Genesee	Tonawanda Creek, Middle, Main Stem	Nutrients
Greene	Schoharie Reservoir	Silt/Sediment
Greene	Sleepy Hollow Lake	Silt/Sediment
Herkimer	Steele Creek tribs	Silt/Sediment
Herkimer	Steele Creek tribs	Nutrients
Jefferson	Moon Lake	Nutrients
Kings	Hendrix Creek	Nutrients
Kings	Prospect Park Lake	Nutrients
Lewis	Mill Creek/South Branch, and tribs	Nutrients
Livingston	Christie Creek and tribs	Nutrients
Livingston	Conesus Lake	Nutrients
Livingston	Mill Creek and minor tribs	Silt/Sediment
Monroe	Black Creek, Lower, and minor tribs	Nutrients
Monroe	Buck Pond	Nutrients
Monroe	Cranberry Pond	Nutrients



### 303(d) Segments Impaired by Construction Related Pollutant(s)

Monroe	Lake Ontario Shoreline, Western	Nutrients
Monroe	Long Pond	Nutrients
Monroe	Mill Creek and tribs	Nutrients
Monroe	Mill Creek/Blue Pond Outlet and tribs	Nutrients
Monroe	Minor Tribs to Irondequoit Bay	Nutrients
Monroe	Rochester Embayment - East	Nutrients
Monroe	Rochester Embayment - West	Nutrients
Monroe	Shipbuilders Creek and tribs	Nutrients
Monroe	Thomas Creek/White Brook and tribs	Nutrients
Nassau	Beaver Lake	Nutrients
Nassau	Camaans Pond	Nutrients
Nassau	East Meadow Brook, Upper, and tribs	Silt/Sediment
Nassau	East Rockaway Channel	Nutrients
Nassau	Grant Park Pond	Nutrients
Nassau	Hempstead Bay	Nutrients
Nassau	Hempstead Lake	Nutrients
Nassau	Hewlett Bay	Nutrients
Nassau	Hog Island Channel	Nutrients
Nassau	Long Island Sound, Nassau County Waters	Nutrients
Nassau	Massapequa Creek and tribs	Nutrients
Nassau	Milburn/Parsonage Creeks, Upp, and tribs	Nutrients
Nassau	Reynolds Channel, west	Nutrients
Nassau	Tidal Tribs to Hempstead Bay	Nutrients
Nassau	Tribs (fresh) to East Bay	Nutrients
Nassau	Tribs (fresh) to East Bay	Silt/Sediment
Nassau	Tribs to Smith/Halls Ponds	Nutrients
Nassau	Woodmere Channel	Nutrients
New York	Harlem Meer	Nutrients
New York	The Lake in Central Park	Nutrients
Niagara	Bergholtz Creek and tribs	Nutrients
Niagara	Hyde Park Lake	Nutrients
Niagara	Lake Ontario Shoreline, Western	Nutrients
Niagara	Lake Ontario Shoreline, Western	Nutrients
Oneida	Ballou, Nail Creeks and tribs	Nutrients
Onondaga	Harbor Brook, Lower, and tribs	Nutrients
Onondaga	Ley Creek and tribs	Nutrients
Onondaga	Minor Tribs to Onondaga Lake	Nutrients
Onondaga	Ninemile Creek, Lower, and tribs	Nutrients
Onondaga	Onondaga Creek, Lower, and tribs	Nutrients
Onondaga	Onondaga Creek, Middle, and tribs	Nutrients



### 303(d) Segments Impaired by Construction Related Pollutant(s)

Onondaga	Onondaga Lake, northern end	Nutrients
Onondaga	Onondaga Lake, southern end	Nutrients
Ontario	Great Brook and minor tribs	Silt/Sediment
Ontario	Great Brook and minor tribs	Nutrients
Ontario	Hemlock Lake Outlet and minor tribs	Nutrients
Ontario	Honeoye Lake	Nutrients
Orange	Greenwood Lake	Nutrients
Orange	Monhagen Brook and tribs	Nutrients
Orange	Orange Lake	Nutrients
Orleans	Lake Ontario Shoreline, Western	Nutrients
Orleans	Lake Ontario Shoreline, Western	Nutrients
Oswego	Lake Neatahwanta	Nutrients
Oswego	Pleasant Lake	Nutrients
Putnam	Bog Brook Reservoir	Nutrients
Putnam	Boyd Corners Reservoir	Nutrients
Putnam	Croton Falls Reservoir	Nutrients
Putnam	Diverting Reservoir	Nutrients
Putnam	East Branch Reservoir	Nutrients
Putnam	Lake Carmel	Nutrients
Putnam	Middle Branch Reservoir	Nutrients
Putnam	Oscawana Lake	Nutrients
Putnam	Palmer Lake	Nutrients
Putnam	West Branch Reservoir	Nutrients
Queens	Bergen Basin	Nutrients
Queens	Flushing Creek/Bay	Nutrients
Queens	Jamaica Bay, Eastern, and tribs (Queens)	Nutrients
Queens	Kissena Lake	Nutrients
Queens	Meadow Lake	Nutrients
Queens	Willow Lake	Nutrients
Rensselaer	Nassau Lake	Nutrients
Rensselaer	Snyders Lake	Nutrients
Richmond	Grasmere Lake/Bradys Pond	Nutrients
Rockland	Congers Lake, Swartout Lake	Nutrients
Rockland	Rockland Lake	Nutrients
Saratoga	Ballston Lake	Nutrients
Saratoga	Dwaas Kill and tribs	Silt/Sediment
Saratoga	Dwaas Kill and tribs	Nutrients
Saratoga	Lake Lonely	Nutrients
Saratoga	Round Lake	Nutrients
Saratoga	Tribes to Lake Lonely	Nutrients



### 303(d) Segments Impaired by Construction Related Pollutant(s)

Schenectady	Collins Lake	Nutrients
Schenectady	Duane Lake	Nutrients
Schenectady	Mariaville Lake	Nutrients
Schoharie	Engleville Pond	Nutrients
Schoharie	Summit Lake	Nutrients
Seneca	Reeder Creek and tribs	Nutrients
St.Lawrence	Black Lake Outlet/Black Lake	Nutrients
St.Lawrence	Fish Creek and minor tribs	Nutrients
Steuben	Smith Pond	Nutrients
Suffolk	Agawam Lake	Nutrients
Suffolk	Big/Little Fresh Ponds	Nutrients
Suffolk	Canaan Lake	Silt/Sediment
Suffolk	Canaan Lake	Nutrients
Suffolk	Flanders Bay, West/Lower Sawmill Creek	Nutrients
Suffolk	Fresh Pond	Nutrients
Suffolk	Great South Bay, East	Nutrients
Suffolk	Great South Bay, Middle	Nutrients
Suffolk	Great South Bay, West	Nutrients
Suffolk	Lake Ronkonkoma	Nutrients
Suffolk	Long Island Sound, Suffolk County, West	Nutrients
Suffolk	Mattituck (Marratooka) Pond	Nutrients
Suffolk	Meetinghouse/Terrys Creeks and tribs	Nutrients
Suffolk	Mill and Seven Ponds	Nutrients
Suffolk	Millers Pond	Nutrients
Suffolk	Moriches Bay, East	Nutrients
Suffolk	Moriches Bay, West	Nutrients
Suffolk	Peconic River, Lower, and tidal tribs	Nutrients
Suffolk	Quantuck Bay	Nutrients
Suffolk	Shinnecock Bay and Inlet	Nutrients
Suffolk	Tidal tribs to West Moriches Bay	Nutrients
Sullivan	Bodine, Montgomery Lakes	Nutrients
Sullivan	Davies Lake	Nutrients
Sullivan	Evens Lake	Nutrients
Sullivan	Pleasure Lake	Nutrients
Tompkins	Cayuga Lake, Southern End	Nutrients
Tompkins	Cayuga Lake, Southern End	Silt/Sediment
Tompkins	Owasco Inlet, Upper, and tribs	Nutrients
Ulster	Ashokan Reservoir	Silt/Sediment
Ulster	Esopus Creek, Upper, and minor tribs	Silt/Sediment
Warren	Hague Brook and tribs	Silt/Sediment



### 303(d) Segments Impaired by Construction Related Pollutant(s)

Warren	Huddle/Finkle Brooks and tribs	Silt/Sediment
Warren	Indian Brook and tribs	Silt/Sediment
Warren	Lake George	Silt/Sediment
Warren	Tribs to L.George, Village of L George	Silt/Sediment
Washington	Cossayuna Lake	Nutrients
Washington	Lake Champlain, South Bay	Nutrients
Washington	Tribs to L.George, East Shore	Silt/Sediment
Washington	Wood Cr/Champlain Canal and minor tribs	Nutrients
Wayne	Port Bay	Nutrients
Westchester	Amawalk Reservoir	Nutrients
Westchester	Blind Brook, Upper, and tribs	Silt/Sediment
Westchester	Cross River Reservoir	Nutrients
Westchester	Lake Katonah	Nutrients
Westchester	Lake Lincolndale	Nutrients
Westchester	Lake Meahagh	Nutrients
Westchester	Lake Mohegan	Nutrients
Westchester	Lake Shenorock	Nutrients
Westchester	Long Island Sound, Westchester (East)	Nutrients
Westchester	Mamaroneck River, Lower	Silt/Sediment
Westchester	Mamaroneck River, Upper, and minor tribs	Silt/Sediment
Westchester	Muscoot/Upper New Croton Reservoir	Nutrients
Westchester	New Croton Reservoir	Nutrients
Westchester	Peach Lake	Nutrients
Westchester	Reservoir No.1 (Lake Isle)	Nutrients
Westchester	Saw Mill River, Lower, and tribs	Nutrients
Westchester	Saw Mill River, Middle, and tribs	Nutrients
Westchester	Sheldrake River and tribs	Silt/Sediment
Westchester	Sheldrake River and tribs	Nutrients
Westchester	Silver Lake	Nutrients
Westchester	Teatown Lake	Nutrients
Westchester	Titicus Reservoir	Nutrients
Westchester	Truesdale Lake	Nutrients
Westchester	Wallace Pond	Nutrients
Wyoming	Java Lake	Nutrients
Wyoming	Silver Lake	Nutrients



## APPENDIX F – List of NYS DEC Regional Offices

<u>Region</u>	<u>COVERING THE FOLLOWING COUNTIES:</u>	<u>DIVISION OF ENVIRONMENTAL PERMITS (DEP) PERMIT ADMINISTRATORS</u>	<u>DIVISION OF WATER (DOW) WATER (SPDES) PROGRAM</u>
1	NASSAU AND SUFFOLK	50 CIRCLE ROAD STONY BROOK, NY 11790 TEL. (631) 444-0365	50 CIRCLE ROAD STONY BROOK, NY 11790-3409 TEL. (631) 444-0405
2	BRONX, KINGS, NEW YORK, QUEENS AND RICHMOND	1 HUNTERS POINT PLAZA, 47-40 21ST ST. LONG ISLAND CITY, NY 11101-5407 TEL. (718) 482-4997	1 HUNTERS POINT PLAZA, 47-40 21ST ST. LONG ISLAND CITY, NY 11101-5407 TEL. (718) 482-4933
3	DUTCHESS, ORANGE, PUTNAM, ROCKLAND, SULLIVAN, ULSTER AND WESTCHESTER	21 SOUTH PUTT CORNERS ROAD NEW PALTZ, NY 12561-1696 TEL. (845) 256-3059	100 HILLSIDE AVENUE, SUITE 1W WHITE PLAINS, NY 10603 TEL. (914) 428 - 2505
4	ALBANY, COLUMBIA, DELAWARE, GREENE, MONTGOMERY, OTSEGO, RENSSELAER, SCHENECTADY AND SCHOHARIE	1150 NORTH WESTCOTT ROAD SCHENECTADY, NY 12306-2014 TEL. (518) 357-2069	1130 NORTH WESTCOTT ROAD SCHENECTADY, NY 12306-2014 TEL. (518) 357-2045
5	CLINTON, ESSEX, FRANKLIN, FULTON, HAMILTON, SARATOGA, WARREN AND WASHINGTON	1115 STATE ROUTE 86, Po Box 296 RAY BROOK, NY 12977-0296 TEL. (518) 897-1234	232 GOLF COURSE ROAD WARRENSBURG, NY 12885-1172 TEL. (518) 623-1200
6	HERKIMER, JEFFERSON, LEWIS, ONEIDA AND ST. LAWRENCE	STATE OFFICE BUILDING 317 WASHINGTON STREET WATERTOWN, NY 13601-3787 TEL. (315) 785-2245	STATE OFFICE BUILDING 207 GENESEE STREET UTICA, NY 13501-2885 TEL. (315) 793-2554
7	BROOME, CAYUGA, CHENANGO, CORTLAND, MADISON, ONONDAGA, OSWEGO, TIOGA AND TOMPKINS	615 ERIE BLVD. WEST SYRACUSE, NY 13204-2400 TEL. (315) 426-7438	615 ERIE BLVD. WEST SYRACUSE, NY 13204-2400 TEL. (315) 426-7500
8	CHEMUNG, GENESEE, LIVINGSTON, MONROE, ONTARIO, ORLEANS, SCHUYLER, SENECA, STEUBEN, WAYNE AND YATES	6274 EAST AVON-LIMA ROADAVON, NY 14414-9519 TEL. (585) 226-2466	6274 EAST AVON-LIMA RD. AVON, NY 14414-9519 TEL. (585) 226-2466
9	ALLEGANY, CATTARAUGUS, CHAUTAUQUA, ERIE, NIAGARA AND WYOMING	270 MICHIGAN AVENUE BUFFALO, NY 14203-2999 TEL. (716) 851-7165	270 MICHIGAN AVENUE BUFFALO, NY 14203-2999 TEL. (716) 851-7070



[www.chasolutions.com](http://www.chasolutions.com)





## APPENDIX 8

### Geotechnical Engineering Report – May 2024



THIS PAGE INTENTIONALLY LEFT BLANK.



# Geotechnical Engineering Report

## John Jay Homestead Site and Building Enhancements

Katonah, NY



Prepared for:

**Beyer Blinder Belle  
Architects & Planners LLP**

120 Broadway, 20th Floor  
New York, NY 10271

March 2024, Revised May 2024

CHA Project No.:  
80675




III Winners Circle,  
Albany, NY 12205



---


This report has been prepared and reviewed by the following qualified engineers employed by  
CHA.

Report Prepared By:



Adam J. Bryant, P.E.  
Geotechnical Engineer

Report Reviewed By:



Scott M. Doehla, P.E.  
Senior Geotechnical Engineer





---

## TABLE OF CONTENTS

<b><u>SECTION</u></b>	<b><u>PAGE NUMBER</u></b>
1.0 INTRODUCTION .....	1
2.0 SITE AND PROJECT DESCRIPTION.....	2
3.0 SUBSURFACE EXPLORATION.....	4
3.1 Boring Program.....	4
3.2 Laboratory Analysis.....	6
4.0 SUBSURFACE CONDITIONS .....	7
4.1 Regional Geology .....	7
4.2 Subsurface Stratigraphy .....	7
4.3 Groundwater Observations .....	9
4.4 Infiltration Test Results.....	10
5.0 GEOTECHNICAL RECOMMENDATIONS .....	11
5.1 Shallow Foundations.....	11
5.2 Lateral Earth Pressures .....	12
5.3 Pavement.....	13
5.4 Seismic Site Classification and Design Parameters.....	14
5.5 Site and Subgrade Preparation .....	14
5.6 Structural Fill .....	15
5.7 Groundwater and Control of Water .....	16
6.0 EXCAVATIONS .....	17
7.0 OBSERVATION DURING CONSTRUCTION.....	18
8.0 CLOSURE .....	19

## **TABLES**

Table 1: Groundwater Observation Well Measurements.....	9
Table 2: Infiltration Test Results .....	10
Table 3: Gradation Requirements for Structural Fill .....	15

## **APPENDICES**

APPENDIX A – Figures  
APPENDIX B – Photographs  
APPENDIX C – Boring Logs  
APPENDIX D – Laboratory Test Results



---

## 1.0 INTRODUCTION

CHA was retained by Beyer, Blinder, Belle Architects & Planners, LLP to complete a geotechnical exploration and evaluation for the design of the brick cottage reconstruction at John Jay Homestead State Historic Site located at 400 Jay Street in Katonah, New York. The project site is shown on *Figure 1 - Site Location Map*, included in Appendix A.

The primary objectives of the exploration were to evaluate the subsurface conditions at the site and to provide geotechnical recommendations for the design of the proposed brick cottage reconstruction and paving of the existing access road.



---

## 2.0 SITE AND PROJECT DESCRIPTION

The project site is located in the John Jay Homestead State Historic Site in Katonah, New York. The John Jay Homestead State Historic Site is an approximately 62-acre site comprised of 10 buildings, including the original 1787 John Jay House, with access roads, stone walls, and wooded areas throughout the site. The project site consists of the brick cottage located east of the John Jay House, and an access road and open fields located to the north, east and south of the John Jay House. Wetland areas and a small pond are located to the south and east of the project site. Standing water was observed in the wetland area approximately 100 feet east of the existing access road in April 2024. NYS Route 22 is located to the south, and the Cross River Reservoir is located approximately 3,000 feet northeast of the project site. The ground surface at the project site slopes down from northwest to the southeast from about El. 470 feet to El. 440 feet based on a site survey. The ground surface at the brick cottage slopes down from the northwest to southeast between El. 470 feet to El. 467 feet. The brick cottage has a two-story section with a partially below grade basement of unknown height and a one-story area without a basement. The total approximate footprint of the brick cottage is 3,000 square feet. The brick cottage has a finished floor elevation (FFE) of El. 471.8 feet. An approximately 3-foot-tall stone wall is located to the north of the building. Photographs of the site are included in Appendix B.

The project involves the design of repairs to the existing brick cottage and an existing access road, a new access road, a parking area and stormwater improvements. The repairs to the brick cottage will include partial or full reconstruction of the foundations and basement walls. The existing main access road, proposed access road and parking lot will be paved with asphalt. The existing access road will not include cuts and will be constructed at grades similar to the existing grade. The new access road requires cuts of up to 2 feet and fills of up to 2 feet. The new parking area requires cuts of up to 3 feet and fills of up to 4 feet. The new parking area will have a retaining wall with a north to south orientation, dividing the parking lot in half. The retaining wall will have exposed heights ranging from 2 to 8 feet and a total length of approximately 200 feet. The parking lot area to the east of the retaining wall will have a ground surface elevation of approximately 449 feet and the area to the west will have a ground surface elevation of approximately 459 feet. Stormwater



---

areas will consist of three bioretention ponds located to the east of the proposed new access road and parking area. The bioretention ponds will have footprints of approximately 2,500 to 5,500 square feet. Foundation work was originally being considered at the maintenance garage but was removed from the project scope by the client. Additional park access roads will be paved, the design of which is outside the scope of this report. The existing and proposed site features are shown on *Figure 2 – Subsurface Exploration Plan*, included in Appendix A.



---

### 3.0 SUBSURFACE EXPLORATION

The subsurface explorations and laboratory testing performed for this project are described in the following sections.

#### 3.1 Boring Program

CHA conducted a subsurface exploration program consisting of fourteen total borings designated as B-1 through B-6, B-6A, B-7 through B-10, and B-101 through B-103. Borings B-1 through B-6, B-6A and B-7 through B-10 were completed between January 16 and 19, 2024. Borings B-101 through B-103 were completed on April 15, 2024. CHA retained Underground Surveying, LLC to perform a non-destructive, non-intrusive subsurface utility survey prior to drilling. Borings B-1 and B-2 were performed adjacent to the brick cottage and extended to depths of 20.9 to 22 feet. Boring B-3 was performed adjacent to the maintenance garage and extended to a depth of 22 feet. Borings B-4 and B-5 were performed along the existing access road to depths of 10 feet. Borings B-6, B-6A and B-7 through B-10 were performed for roadway and preliminary stormwater design purposes in the eastern portion of the site to depths of 12 feet. Boring B-7 is located in the vicinity of the parking area site retaining wall, which was added after the completion of the subsurface exploration. Borings B-101 through B-103 were performed for final stormwater design purposes in the eastern portion of the site to depths of 10.5 to 12 feet.

Borings B-1 through B-3 were located onsite by measuring from existing site features. Borings B-4 through B-6, B-6A, B-7 through B-10 and B-101 through B-103 were located onsite using a backpack GPS unit accurate to 1 meter. Ground surface elevations at boring locations were estimated based on interpolation between contours on the site survey and are based on NAVD88. The locations and elevations should be considered accurate only to the degree implied by the method used to determine them. The approximate boring locations are shown on *Figure 2 – Subsurface Exploration Plan*, included in Appendix A.



---

New England Boring Contractors of Glastonbury, Connecticut was retained by CHA to advance the borings. The field exploration was performed under the observation of a CHA geotechnical engineer who confirmed proper drilling and sampling methods were utilized for the exploration, observed and described soil samples, prepared field logs documenting the subsurface conditions, and conducted infiltration testing.

The borings were advanced with a Mobile Drill B53 truck mounted drill rig and Mobile Drill B53 rubber track mounted drill rig using hollow stem augers (HSA) with an inside diameter of 4.25 inches or solid stem augers (SSA) with an inside diameter of 2.25 inches. Continuous split spoon sampling was generally performed to a depth of up to 12 feet below ground surface, and then at standard 5-foot intervals thereafter to the boring termination depths. Standard Penetration Testing (SPT) was utilized during split-spoon sampling in general accordance with ASTM International (ASTM) Standard D-1586 “Standard Test Method for Standard Penetration Test (SPT) and Split-Barrel Sampling of Soils.” The split spoon samples were advanced using an automatic 140 (±) pound hammer falling 30 (±) inches. “Blow counts” recorded on the boring logs indicate the penetration resistance for a 6-inch advancement of the split spoon. Initially, the spoon is driven 6 inches to seat the sampler in undisturbed material. The number of blows required to drive the sampler the next 12 inches is taken as the SPT resistance or N-value. This value is indicative of the soil’s in-place density or consistency. The final 6-inch increment that the spoon is driven is not included in the determination of the N-value. Boreholes B-1 through B-6 were backfilled with soil cuttings upon completion.

Infiltration tests were planned adjacent to borings B-6A, B-7 through B-10 and B-101 through B-103. Infiltration tests were not performed adjacent to B-8 through B-10 and B-101 through B-103 due to shallow groundwater. The infiltration tests conducted adjacent to B-6A and B-7 were designated as IT-6 and IT-7, respectively. Infiltration testing was conducted according to Appendix D of the 2022 New York State Stormwater Management Design Manual. After a presoak was conducted, water was added to the infiltration casing to set it to 24 inches above the bottom of the casing. The distance that the water within the casing dropped in an hour was measured and recorded. Water was added to bring the level back to 24 inches above the bottom of casing for the



---

next testing interval. The test was terminated after five test intervals. Infiltration test holes were backfilled with soil cuttings upon completion. A New York City Department of Environmental Conservation (NYCDEP) representative was onsite to oversee the infiltration testing.

Water level observations were made during and upon completion of drilling. Observation wells were installed in borings B-6A and B-7 through B-10 to depths of 12 feet. Details of the observation well construction are shown on the boring logs included in Appendix C. The water levels within the wells were recorded during the subsurface exploration, and are included in *Section 4.3 – Groundwater Conditions* and on the boring logs in Appendix C.

### **3.2 Laboratory Analysis**

Select soil samples were submitted for laboratory analysis to confirm visual descriptions. Testing included five tests for particle-size analysis (ASTM D422), one test for Atterberg Limits analysis (ASTM D4318) and one test for water content of soil (ASTM D2216). The results of the laboratory testing are included in Appendix D.



---

## 4.0 SUBSURFACE CONDITIONS

Subsurface conditions at the site were assessed based on a review of published geologic maps and the results of the subsurface exploration performed on-site and are summarized below.

### 4.1 Regional Geology

According to the *Surficial Geologic Map of New York – Lower Hudson Sheet*, (Cadwell, D.H. 1991), the surficial soil at the site consists of glacial till.

According to the *Geologic Map of New York – Lower Hudson Sheet*, (Fisher, D.W., Isachsen, Y.W., and Rickard, L.V., 1970), the bedrock underlying the site consists of Fordham Gneiss.

### 4.2 Subsurface Stratigraphy

Subsurface conditions encountered in individual borings are detailed and described on the boring logs included in Appendix C. Subsurface conditions can generally be described as follows, in order of increasing depth:

Topsoil – Topsoil was encountered at the ground surface in borings B-1 through B-3, B-6 through B-10 and B-101 through B-103 and extended to depths ranging from 0.1 to 0.2 feet.

Fill – A layer of existing fill was encountered below the topsoil in borings B-1 and B-2 and at the ground surface in borings B-4 and B-5 and extended to depths ranging from 2 to 4 feet. The layer consisted of varying amounts of fine to coarse sand, silt, fine to coarse gravel, wood and organics. The fill was brown or gray and visually classified as moist, and some near-surface samples appeared frozen. The SPT N-values ranged from 4 to 74, indicating a very loose to very compact density, however, the presence of frost likely affected N-values within the samples taken at shallow depths.



---

Silt/Clayey Silt/Silty Clay – A layer of silt, clayey silt or silty clay was encountered below the topsoil layer in boring B-3, B-6, B-7, and B-101 through B-103, and below the fill in borings B-1 and B-5 and extended to depths ranging from 2 to 6 feet. The layer consisted of silt, clayey silt, or silty clay with varying amounts of fine to coarse sand, fine gravel and organics. The soil was brown and visually classified as moist. The SPT N-values ranged from 2 to 8, indicating a medium stiff consistency for cohesive samples and a very loose to loose density for cohesionless samples.

Glacial Till – Glacial till was encountered below the topsoil layer in borings B-8 through B-10, below the fill in borings B-2 and B-4, below the silt, clayey silt and silty clay layer in borings B-1, B-3, B-5 through B-7 and B-101 through B-103. The glacial till layer extended to depths ranging from 10 to 22 feet. Borings B-2, B-4 through B-10 and B-101 through B-103 terminated within the glacial till layer. The layer generally consisted of various proportions of fine to coarse sand, fine to coarse gravel, silt, clay and organics. The soil was brown and visually classified as moist to wet. The SPT N-values ranged from 5 to split spoon refusal, indicating a very stiff to hard consistency for cohesive samples and a loose to very compact density for cohesionless samples.

Completely Weathered Rock – Completely weathered rock was encountered below the glacial till layer in borings B-1 and B-3 and extended to depths of 20.9 to 22 feet. Borings B-1 and B-3 terminated within the completely weathered rock. The layer consisted of fine to coarse sand with little silt and trace fine gravel. The soil was brown and visually classified as wet. The SPT N-values ranged from 85 to split spoon refusal, indicating a very compact density.



### 4.3 Groundwater Observations

Table 1 summarizes the observation well measurements.

**Table 1: Groundwater Observation Well Measurements**

Boring ID	Surface Elevation (Feet)	Screen Interval Elevation (Feet)	Date	Water Depth (Feet)	Water Elevation (Feet)
B-6A	459.5	447.5 to 452.5	1/17/2024	11.7	447.8
			1/18/2024	11.7	447.8
			1/19/2024	11.7	447.8
			4/15/2024	12.4	447.1
			4/16/2024	12.4	447.1
B-7	451.0	439.0 to 444.0	1/18/2024	7.0	444.0
			1/19/2024	7.3	443.7
			4/15/2024	8.2	442.8
			4/16/2024	7.9	443.1
B-8	451.0	439.0 to 444.0	1/18/2024	9.1	441.9
			1/19/2024	3.5	447.5
			4/15/2024	0.1	450.9
			4/16/2024	0.1	450.9
B-9	449.5	437.5 to 442.5	1/18/2024	1.1	448.4
			1/19/2024	0.8	448.7
			4/15/2024	0.7	448.8
			4/16/2024	0.7	448.8
B-10	448.5	436.5 to 441.5	1/18/2024	4.2	444.3
			1/19/2024	3.0	445.5
			4/15/2024	2.5	446
			4/16/2024	2.8	445.7



Groundwater levels were estimated based upon measurements or observed soil sample moisture content in the remaining boreholes during drilling operations and at the completion of drilling. These estimates are indicated on the boring logs included in Appendix C. Groundwater was estimated at depths ranging from 0.4 to 13.2 feet during drilling. Standing water was observed at the ground surface at boring B-101. The boreholes were only open for a short duration and seasonal factors such as temperature and precipitation affect groundwater levels. For these reasons, long-term groundwater levels may differ from those described in this report.

#### 4.4 Infiltration Test Results

NYCDEP requires two phases of subsurface exploration and testing for stormwater management design. Borings for preliminary design consisted of B-6, B-6A and B-7 through B-10 and borings for final design consisted of B-101 through B-103. Infiltration testing was not performed at the B-8, B-9, B-10, B-101, B-102 and B-103 locations due to shallow groundwater. The results of the testing adjacent to borings B-6A and B-7 are outlined in Table 2.

**Table 2: Infiltration Test Results**

Boring Location	Depth Performed (ft)	Approx. Elevation Performed (ft)	Observed Infiltration Rate (in/hour)				
			Infiltration Test Run No.				
			1	2	3	4	5
IT-6A	2.0	457.5	0.0	0.0	0.0	0.0	0.0
IT-7	2.0	449.0	0.0	0.0	0.0	0.0	0.0



---

## 5.0 GEOTECHNICAL RECOMMENDATIONS

The following sections provide geotechnical recommendations for design of the project. These recommendations are based on our review of the results of the subsurface exploration.

### 5.1 Shallow Foundations

Shallow foundations are recommended for support of the reconstruction of the existing brick cottage and the parking area site retaining wall. The foundations should bear on the natural clayey silt or glacial till soil. Spread footings should be designed based on a maximum net allowable bearing capacity of 3 kips per square foot (ksf). Foundations should be founded at a minimum depth of 4.0 feet below finished grade to provide frost protection. We recommend that isolated footings be a minimum of 3.0 feet wide and continuous strip footings be a minimum of 18 inches wide.

Foundations should be constructed as soon as possible after excavation to minimize the risk of disturbance to the bearing surface by exposure to precipitation or other adverse conditions. Foundation excavations should be backfilled with structural fill in accordance with the placement and compaction procedures included in *Section 5.6 - Structural Fill*.

Footing subgrade shall be protected from freezing during construction. Any disturbed, frozen or softened subgrade should be removed and replaced with structural fill as required to minimize detrimental impacts to foundation performance.

The natural soil is moisture sensitive and prone to disturbance when wet or when exposed to excessive foot traffic. Foundations should be constructed as soon as possible after excavation to minimize the risk of disturbance to the bearing surface by exposure to precipitation or other adverse conditions. To protect the footing subgrade and to provide a stable working surface a minimum of 6-inches of crushed stone over separation geotextile fabric or a 2-inch to 3-inch concrete mud mat should be placed below the footing subgrade. The separation geotextile shall be



---

a non-woven geotextile with an apparent opening size (AOS) equal to or smaller than the U.S. Standard sieve size of 70, such as Mirafi 160N. Crushed stone should consist of a 50:50 mix of NYSDOT size designation No. 1 and No. 2 crushed stone.

A detailed settlement analysis was beyond the scope of this report. However, based on the information obtained during the subsurface exploration and the recommendations outlined in this report, we anticipate that total foundation settlement will be less than 1 inch, with differential settlement of about 1/2 inch across a distance of 20 feet. These estimates are based on the assumption that foundations are constructed as recommended herein and that proper site preparation and construction monitoring is performed.

## 5.2 Lateral Earth Pressures

The new basement walls and the parking area site retaining wall should be designed to resist lateral soil pressure as well as surcharges from adjacent loads. Basement walls restrained against lateral movement should be designed to resist at-rest earth pressures.

New basement walls and the parking area site retaining wall should be backfilled with structural fill meeting the requirements of *Section 5.6 – Structural Fill* for a lateral distance equal to at least one-half of the wall height. Walls backfilled with structural fill should be designed to resist lateral earth pressures based on the following soil properties:

- Total Unit Weight 125 pcf
- Angle of Internal Friction 32 Degrees
- Coefficient of At-Rest Earth Pressure<sup>1</sup> 0.47
- Coefficient of Active Earth Pressure<sup>1</sup> 0.31
- Coefficient of Sliding (Mass concrete on Natural Soil) 0.3



---

Notes:

1. Earth pressure coefficients assume level backfill behind walls and should be adjusted if non-level backfill is proposed.

Design for new basement walls should incorporate drainage measures to prevent hydrostatic build-up and to provide positive drainage. Drainage measures should include a minimum 1-foot-thick horizontal layer of drainage stone from the surrounding soil by a separation geotextile having an AOS equal to or smaller than the U.S. Standard sieve size of 70, such as Mirafi 160N. A prefabricated drainage board may be utilized in lieu of the crushed stone layer. New basement walls that do not include drainage features should be designed for full hydrostatic pressure.

### **5.3 Pavement**

The existing fill, natural clayey silt and silt and glacial till soils anticipated at pavement subgrade elevation are suitable for support of the proposed paved main access road, additional new access road and proposed parking area. The flexible pavement section should be designed using a California Bearing Ratio (CBR) of 5. The anticipated subgrade soils contain a significant amount of fine-grained soil and are poor draining. This soil is considered susceptible to frost heave, particularly if water is available for formation of ice lenses. Subbase course drainage is essential for successful pavement performance and longevity. The subbase course should be maintained in a drained condition at all times. Underdrains should be constructed along portions of the proposed new access road and consist of 4-inch diameter drain, spaced at 15 feet and drained to positive outlet. The underdrains should be a minimum of two feet below the proposed final grade and should be located in the access road areas that have a finished grade of less than or equal to El. 250 feet. Along the existing main access road, drainage may consist of either installing underdrains or sloping the subgrades to planned draining systems or otherwise.

The subgrade should be prepared in accordance with *Section 5.5 – Site and Subgrade Preparation*. The pavement section should include an aggregate subbase course such as NYSDOT Type 2 Subbase. The subbase along the existing access road should be underlain by a woven separation



---

and stabilization geotextile. The geotextile should have an AOS equal to or smaller than the U.S. Standard sieve size of 40, such as Mirafi 600X.

#### 5.4 Seismic Site Classification and Design Parameters

Based on the site location, and in accordance with the 2020 Building Code of New York State (NYSBC) Section 1613, the following spectral response accelerations should be used for seismic design:

- Mapped Spectral Response Acceleration at Short Periods ( $S_s$ ) .....0.27g
- Mapped Spectral Response Acceleration at 1 Second Period ( $S_1$ ) .....0.06g

The location based spectral response accelerations are based on seismic Site Class B and must be adjusted for the project site class based on subsurface conditions. Site class D is recommended based on the subsurface conditions. In accordance with section 1613 of the NYSBC the following seismic design coefficients shall be used:

- Site Coefficient  $F_a$  .....1.6
- Site Coefficient  $F_v$  .....2.4

The potential for earthquake induced soil liquefaction was not required based on the subsurface conditions encountered and seismic design category of B for the project site.

#### 5.5 Site and Subgrade Preparation

The areas within the improvements shall be stripped of any vegetation, topsoil and other deleterious materials. Subsequent to excavating to proposed grades, the exposed subgrade should be proofrolled with a smooth drum roller with a minimum static weight of 10 tons. The roller should operate in its vibratory mode, and complete at least six passes over the subgrade at a speed not exceeding 3 feet per second (fps). Areas which pump or weave during proof rolling shall be



---

undercut by a minimum of 12 inches and stabilized with structural fill meeting the requirements of *Section 5.6 - Structural Fill*. If the vibration roller tends to "bring up" moisture, the subgrade should be proof rolled with the roller operating in the static mode.

## **5.6 Structural Fill**

Structural fill should be used for backfilling foundation excavations, for raising grade behind the site retaining wall, and overexcavations. Structural fill shall consist of sound, durable, non-plastic sand and gravel, free of stumps, roots, organics, and any frozen or deleterious materials.

Structural fill shall be placed in loose lifts not exceeding 8 inches in thickness and should be compacted to at least 95 percent of the maximum laboratory dry density as determined by the modified Proctor test (ASTM D-1557). Structural fill shall conform to the gradation requirements in Table 3.

**Table 3: Gradation Requirements for Structural Fill**

<b>Sieve Size</b>	<b>Percent Passing by Weight</b>
4 inch	100
No. 40	0 to 70
No. 200	0 to 10

**The on-site soil generally does not meet the requirements for Structural Fill.**



---

## 5.7 Groundwater and Control of Water

Groundwater may be encountered when excavating during foundation construction and when excavating to establish roadway subgrades. At the brick cottage, a design groundwater elevation of 465 feet is recommended. At the existing access road, a design groundwater elevation of 448 feet is recommended. At proposed parking area, design groundwater elevations of 448 feet for the western side and 444 feet for the eastern side and site retaining wall are recommended. At the new access road, a design groundwater elevation of 449 feet is recommended. Project specifications should require that groundwater be maintained at a minimum depth of 2.0 feet below the excavation bottom at all times. It is the responsibility of the contractor to determine the most appropriate dewatering methods and to maintain dry conditions so that foundation construction may be completed in the dry.



---

## 6.0 EXCAVATIONS

All excavations should be performed in accordance with the Occupational Safety and Health Administration (OSHA) standards, and applicable state and local codes. Where adequate sloping or benching is not possible, excavation support should be provided. The design of a temporary excavation system shall be performed by a registered Professional Engineer licensed in the State of New York.



---

## 7.0 OBSERVATION DURING CONSTRUCTION

A qualified geotechnical engineer should carefully inspect all excavations, backfilling, and final bearing surfaces for foundations to ascertain that subgrades have been properly prepared. The inspection of soil subgrades should include probing of select areas to confirm density. The materials used as fill should be tested by a qualified soils laboratory to verify they meet the specified gradations and to determine their optimum moisture content and maximum dry density for compaction. In-place density tests should be performed to verify that compaction methods and equipment achieve the required densities.



---

## 8.0 CLOSURE

The geotechnical recommendations presented in this report are based, in part, on project and subsurface information available at the time this report was prepared and in accordance with generally accepted soil and foundation engineering practices. No other warranty, expressed or implied, is made. Some variation of subsurface conditions may occur between locations explored that may not become evident until construction. Depending on the nature and extent of the variations, it may be necessary to re-evaluate the data presented in this report.

This report has been prepared solely for design purposes and shall not be incorporated by reference of other means in the Contract Documents. If this report is included in the Contract Documents, it shall be for information only. Specifications shall take precedence.

CHA does not accept responsibility for designs based upon our recommendations unless we are engaged to review the final plans and specifications to determine whether any changes in the project affect the validity of our recommendations and whether our recommendations have been properly implemented in the design.



THIS PAGE INTENTIONALLY LEFT BLANK.