

## SPECIFICATIONS / SCOPE OF SERVICES

The existing slab, floor drains, and drainpipes in the Engine Bay Room shall be replaced with a new structural slab supported by micro piles,

New drainpipes, and new floor drains.

A portion of the southeast wall and the connecting northeast wall shall be replaced, including the existing precast façade and parapet cap.

The concrete sidewalk, the drop curb, and the adjacent asphalt will be removed and replaced. The existing bollards are to be demolished and replaced.