


| FEEDER SCHEDULE | | | | | | |
|-----------------|--------------|------------|--------------------------------------|--|--|--|
| FEEDER TAG | NUMBER OF | SIZE OF | QUANTITY AND SIZE OF CONDUCTORS | | | |
| <### #₩ | CONDUITS | CONDUITS | PER CONDUIT | | | |
| 200A-4W (HH1) | 1 | 2 1/2" | 4 #250 KCMIL AL. & 1 #4 AWG AL. GND. | | | |
| 200A-4W (HV1) | 1 | 2 1/2" | 4 #250 KCMIL AL. & 1 #4 AWG AL. GND. | | | |
| 200A-SERV | 1 | 2 1/2" | 4 #250 KCMIL AL. | | | |
| 1200A-SERV | 4 | 4" | 4 #500 KCMIL AL. | | | |
| 125 HP FP | 1 | 2 1/2" | 4 #4/0 AWG CU. | | | |



| | | JMMARY | |
|-------------------------------------------------------------------------------------------------------------------|-------------------------------------------------|--------------------|------------------------------------------------|
| DESCRIPTION | CONNECTED LOAD (kVA) | MULTIPLIER | N.E.C. LOAD (kVA) |
| INTERIOR LIGHTING | 18.16 kVA | (NOTE #2) | 59.17 kVA |
| EXTERIOR LIGHTING | 7.57 kVA | 1.25 | 9.47 kVA |
| ELECTRIC HEAT | 8.00 kVA | 1.25 | 10.00 kVA |
| AIR CONDITIONING | 4.78 kVA | 1.00 | 0.00 kVA |
| VENTILATION | 6.10 kVA | 1.00 | 6.10 kVA |
| INSTA HOT - STORAGE WATER HEATER | 0.00 kVA | 1.25 | 0.00 kVA |
| RECEPTACLES | 4.34 kVA | (NOTE #1) | 4.34 kVA |
| ELEVATOR | 0.00 kVA | 1.00 | 0.00 kVA |
| KITCHEN EQUIPMENT | 0.00 kVA | 0.65 | 0.00 kVA |
| REFRIGERATION EQUIPMENT | 0.00 kVA | 1.00 | 0.00 kVA |
| SIGNS | 0.00 kVA | 1.25 | 0.00 kVA |
| SHOW WINDOW (LIGHTING) | 0.00 kVA | 1.25 | 0.00 kVA |
| EV CHARGER | 7.68 kVA | 1.25 | 9.60 kVA |
| FIXED MULTI-OUTLET ASSEMBLIES | 0.00 kVA | 1.00 | 0.00 kVA |
| MISC. LOADS @100% | 5.71 kVA | 1.00 | 5.71 kVA |
| LARGEST MOTOR | 0.00 kVA | 0.25 | 0.00 kVA |
| TOTAL LOAD TOTAL AMPS @480Y/277V, 3-PHASE VA PER FT ² CALCUATION: | 62.34 kVA 75.0 A 88.200 FT ² / | 104386 VA= | 104.39 kVA 125.6 A 1.2 W/FT ² |
| TOTAL LOAD | 62.34 kVA 75.0 A | 0.25 104386 VA= | 104.39 kVA 125.6 A |
| NOTE: CODE LOAD CALCULATED AT 125% FC LOADS EXCEPT AS NOTED BELOW: 1. RECEPT/MISC: 100% OF 10kVA PLUS 50% (| | | ON-CONTINUOUS |

ELECTRICAL ONE LINE DIAGRAM E5.0 / SCALE: NONE

1. ALL SHOWN IS NEW & BY EC UNLESS SPECIFICALLY NOTED OTHERWISE.

PANEL "HV1"

250A MLO

<TX-30P

30kVA; DRY IYPE
TRANSFORMER "T1"
480-208/120V; 3ø

PANEL "LV1" 208/120V, 3ø, 4W 100A MCB

480/277V, 3ø, 4W

30kVA; DRY TYPE

ONE LINE DIAGRAM NOTES:

1. ALL EQUIPMENT & WIRING IS NEW AND BY E.C. UNLESS SPECIFICALLY NOTED OTHERWISE.

BREAKER "ECB-1"

WITH GROUND KIT

PANEL "HL1"

208/120V, 3ø, 4W

100A MCB

2 #8 AWG CU. & 1 #10

AWG CU. GND IN 1" C.—

CHARGEPOINT

STANDARD POWER SHARE EV CHARGER; 240V-1ø 7.68kW/7.68kVA

32 AMP INPUT

SERVICE

GROUNDING


SCHEMATIC

- EXACT LOCATION OF UTILITY TRANSFORMER & METER MUST BE APPROVED BY UTILITY AND GC AND/OR CONSTRUCTION MANAGER AND OWNERS PROJECT MANAGER.
- UTILITY TRANSFORMER ELBOWS AND TERMINATIONS MAY BE FURNISHED & INSTALLED BY E.C (COORDINTE WITH UTILITY). PROVIDE 200A, (15) KV CLASS 3Ø LOADBREAK ELBOW CONNECTOR: ELASTIMOLD OR COOPER POWER SYSTEMS WITH CONCENTRIC NEUTRAL JACKET SEAL & TEST POINT. CONNECTOR MUST BE APPROVED BY UTILITY AND THIS ENGINEER, PROVIDE SECONDARY TERMINATIONS TO UTILITY SPADE TERMINALS USING UTILITY APPROVED DOUBLE BARREL COMPRESSION TYPE LUGS, BURNDY OR EQUAL. LUGS MUST BE APPROVED BY UTILITY.
- 4. VERIFY CUSTOMER VS. UTILITY RESPONSIBILITIES.
- VERIFY NAMEPLATE RATING OF HVAC EQUIPMENT PRIOR TO ORDERING BREAKERS, DISCONNECTS, CABLES, AND PRIOR TO ROUGH-IN.
- A POWER SYSTEMS STUDY (SHORT CIRCUIT, COORDINATION, ARC FLASH) HAS NOT BEEN PERFORMED FOR THIS PROJECT. SHORT CIRCUIT CALCULATIONS HAVE BEEN ESTIMATED BASED ON UTILITY EXPECTED TRANSFORMER SIZE & LOCATION AND BASED ON AN INFINITE PRIMARY BUS AND TYPICAL UTILITY TRANSFORMER IMPEDANCE VALUES (CONSERVATIVE APPROACH).
- CONFIRM SERVICE ENTRANCE CONDUIT AND CONDUCTOR QUANTITIES AND SIZES WITH THE LOCAL UTILITY PRIOR TO START OF WORK. INCREASE QUANTITIES AND SIZES AS REQUIRED TO MEET LOCAL UTILITY SERVICE AND INSTALLATION REGULATIONS.
- CONFIRM COLD SEQUENCE METERING VERSUS HOT SEQUENCE METERING WITH THE LOCAL UTILITY PRIOR TO START OF CONSTRUCTION.
- 9. EACH DISCONNECTING MEANS SHALL BE MARKED TO INDICATE ITS PURPOSE PER 2017 NEC 110.22.
- 10. FIELD MARK SERVICE EQUIPMENT WITH THE MAXIMUM AVAILABLE FAULT CURRENT PER 2017 NEC 110.24. COORDINATE WITH UTILITY COMPANY TO DETERMINE MAXIMUM AVAILABLE FAULT CURRENT AT TRANSFORMER.
- 11. GROUND FAULT CIRCUIT BREAKER(S) SHALL BE PERFORMANCE TESTED IN ACCORDANCE WITH 2017 NEC. SECTION 230.95 (C). THIS TEST SHALL BE CONDUCTED BY A QUALIFIED PERSON(S) USING A TEST PROCESS OF PRIMARY CURRENT INJECTION, IN ACCORDANCE WITH INSTRUCTIONS THAT SHALL BE PROVIDED WITH THE EQUIPMENT. A WRITTEN RECORD OF TESTS MUST BE SENT TO OWNER/ENGINEER AND THE AUTHORITY HAVING JURISDICTION.
- 12. ALL BREAKERS/LUGS/TERMINATIONS SHALL BE RATED FOR COPPER AND ALUMINUM CONDUCTORS.
- 13. ALL SERVICE ENTRANCE CONDUITS SHALL BE SEALED IN ACCORDANCE WITH NEC 230.8 AND NEC 300.5 (G). THE CONTRACTOR SHALL SEAL THE CONDUITS AT THE TRANSFORMER (WHERE PAD MOUNTED IN LIEU OF VAULT MOUNTED) AND AT THE POINT THAT THE SERVICE CONDUITS STUB UP INTO THE BUILDING. UL LISTED SEALING BUSHINGS OR DUCT SEAL SHALL BE USED. ALL SPARE/UNUSED RACEWAYS SHALL ALSO BE PROPERLY SEALED/CAPPED.

NEC TABLE 250.66 GROUNDING ELECTRODE CONDUCTOR FOR AC SYSTEMS SIZE OF LADOEST LINICHOLINIDED

| SIZE OF LARGEST UNGROUNDED SERVICE—ENTRANCE CONDUCTOR (OR EQUIVALENT AREA FOR PARALLEL CONDUCTORS) (AWG/kCMIL) | | SIZE OF GROUNDING ELECTRODE CONDUCTOR (AWG/kCMIL) | | |
|----------------------------------------------------------------------------------------------------------------|---------------------------------------------------|---------------------------------------------------------|----------------------------------------------------|--|
| COPPER (CU) | ALUMINUM (AL) OR COPPER-CLAD ALUMINUM (CCA) | COPPER (CU) | ALUMINUM (AL) OR COPPER-CLAD ALUMINUM (CCA)* | |
| #2 OR SMALLER | #1/0 OR SMALLER | #8 | #6 | |
| #1 OR #1/0 | #2/0 OR #3/0 | #6 | #4 | |
| #2/0 OR #3/0 | #4/0 OR #250 kCMIL | #4 | #2 | |
| OVER #3/0 THRU #350 kCMIL | OVER #250 kCMIL THRU #500 kCMIL | #2 | #1/0 | |
| OVER #350 kCMIL THRU #600 kCMIL | OVER #500 kCMIL THRU #900 kCMIL | #1/0 | #3/0 | |
| OVER #600 kCMIL THRU #1100 kCMIL | OVER #900 kCMIL THRU #1750 kCMIL | #2/0 | #4/0 | |
| OVER #1100 kCMIL | OVER #1750 kCMIL | #3/0 | #250 kCMIL | |


* INSTALLATION RESTRICTIONS APPLY; SEE NEC 250.64(A) MAIN BONDING JUMPER & SYSTEM BONDING JUMPER SIZING [PER 250.28(D)(1)]: MAIN BONDING JUMPERS & SYSTEM BONDING JUMPERS SHALL NOT BE SMALLER THAN THE SIZES SHOWN IN TABLE 250.66. WHERE THE SUPPLY CONDUCTORS ARE LARGER [THAN LISTED], THE BONDING JUMPER SHALL HAVE AN AREA THAT IS NOT LESS THAN 12 ½ PERCENT OF THE AREA OF THE LARGEST PHASE CONDUCTOR.



TRANSFORMER GROUNDING SCHEMATIC SCALE: NONE

NOTES:

- 1. TRANSFORMER GROUNDING MUST COMPLY WITH NEC ARTICLE 250. 2. ALL GROUND CONNECTION AREAS SHALL BE PREPARED BY GRINDING OR
- WIRE BRUSH CLEANING. ALL SURFACES AFFECTED SHALL BE PAINTED WITH RUST INHIBITING PAINT AFTER WELDING IS COMPLETED.
- 3. IF EFFECTIVELY GROUNDED BUILDING STEEL IS NOT PRESENT DUE TO BUILDING CONSTRUCTION, PROVIDE CONNECTION TO EFFECTIVELY GROUNDED METAL WATER PIPE WITHIN 5'-0" OF POINT OF ENTRANCE OF PIPE.
- 4. SYSTEM BONDING JUMPER AND GROUNDING ELECTRODE CONDUCTOR SIZE TABLE IS ONLY APPLICABLE TO TRANSFORMERS WITH A 208/120V; 30
- THIS DETAIL ONLY APPLIES TO DELTA / GROUNDED WYE STEP DOWN DRY TYPE TRANSFORMERS.



GAS PIPING SHALL NOT BE USED AS GROUNDING

ELECTRODE [SEE NEC 250.52(B)(1)]; SEE 250.104(3)(B) FOR FURTHER INSTRUCTIONS

RELATED TO GAS PIPING.

DESIGNER / BUILDER **DESIGN/BUILD**

44 SOUTH BROADWAY, SUITE 1003 WHITE PLAINS, NY 10601 P: 914.821.5535 F: 914.306.6010

ADB | DESIGN SERVICES

PROJECT TITLE **ROCKLAND** LOGISTICS **CENTER BLDG 3**

25 OLD MILL RD. SUFFERN, NY 10901

OWNER BROOKFIELD PROPERTIES 1 MEADOWLANDS PLAZA SUITE 802 EAST RUTHERFORD, NJ 07073

ARCHITECT ADB / DESIGN SERVICES LLC 44 SOUTH BROADWAY, SUITE 1003 WHITE PLAINS, NY 10601

CIVIL ENGINEER DYNAMIC ENGINEERING CONSULTANTS 1904 MAIN STREET

STRUCTURAL ENGINEER ADB STRUCTURAL ENGINEERING 325 S. ALABAMA ST, SUITE 200 INDIANAPOLIS, IN 46204

LAKE COMO, NJ 07719

MECHANICAL ENGINEER NATIONAL DESIGN BUILD SERVICES 11840 BORMAN DRIVE MARYLAND HEIGHTS, MO 63146


ELECTRICAL ENGINEER FXB ENGINEERING 5 CHRISTY DRIVE, SUITE 307 CHADDS FORD, PA 19317

PLUMBING ENGINEER MCCARTHY ENGINEERING 2500 E HIGH STREET, SUITE 630 POTTSTOWN, PA 19464

FIRE PROTECTION ENGINEER S.A. COMUNALE 2900 NEWPARK DRIVE BARBERTON, OH 44203

NY License #: 077635-1 NY License Expiration Date: 04/30/2026





NORTH

SUBMITTALS DESCRIPTION A 11.20.2024 ISSUE FOR REVIEW B 02.02.2024 ISSUE FOR REVIEW 0 02.09.2024 ISSUE FOR PERMIT

DRAWN BY

NGF

SHEET TITLE **ELECTRICAL ONE** LINE DIAGRAM & **SCHEMATICS**

SHEET NO.

PROJECT NO.

AS397-22 | NY154