Wall Indication Legend

EXISTING WALLS TO REMAIN EXISTING TO BE REMOVED

General Demolition Notes

CEASE OPERATION AND NOTIFY ARCHITECT IMMEDIATELY IF SAFETY OF STRUCTURE APPEARS TO BE ENDANGERED. TAKE PRECAUTIONS TO SUPPORT STRUCTURE UNTIL DETERMINATION IS MADE FOR CONTINUING OPERATIONS.

DEMOLITION DRAWINGS DO NOT INCLUDE MECHANICAL/ELECTRICAL DEMOLITION AND ITS AFFECTS ON DEMOLITION OF GENERAL CONSTRUCTION ITEMS.

CONTRACTOR SHALL BE RESPONSIBLE FOR PROTECTION OF ALL EXISTING ELEMENTS TO REMAIN FROM ANY DAMAGE DURING DEMOLITION.

General Demolition Notes

THE CONTRACTOR SHALL PATCH AND REPAIR ALL EXISTING ADJACENT CONSTRUCTION AS MAY BE REQUIRED AFTER DEMOLITION TO PROVIDE A COMPLETE

THE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING AND LEGALLY DISPOSING OF ALL DEBRIS CAUSED BY DEMOLITION. THE CONTRACTOR SHALL NOT ALLOW ANY EXCESSIVE DEBRIS TO ACCUMULATE ON THE SITE AT ANY TIME.

CONTRACTOR TO CEASE WORK AND NOTIFY OWNER SHOULD ANY HAZARDOUS MATERIALS BE ENCOUNTERED AND PERFORM ABATEMENT/ REMEDIATION WORK ACCORDINGLY.

ALL EXIST BASEBOARD HEATERS TO REMAIN.

ELECTRICAL DWGS.

Keyed Demolition Notes # DEMOLITION NOTE SYMBOL

- REMOVE EXIST CEILING TILE OR GWB COMPLETE. REMOVE EXIST LIGHTING FIXTURES, REFER TO
- REMOVE EXIST PLUMBING FIXTURE COMPLETE.
- REMOVE AND REPLACE EXIST PLUMBING FIXTURE. REMOVE ALL EXIST PLUMBING AND ELECTRICAL
- DEFUNCT. REMOVE EXIST DOOR COMPLETE.
- REMOVE AND REPLACE EXIST DOOR, FRAME, AND HARDWARE COMPLETE.
- REMOVE EXIST DOOR, FRAME, AND HARDWARE COMPLETE, INFILL OPENING WITH LIKE
- CONSTRUCTION. REMOVE EXIST DOOR AND FRAME AND INFILL OPENING WITH LIKE MATERIALS.
- 10. REMOVE PORTION OF WALL AND RECONSTRUCT TO PROVIDE NEW DOOR - REFER TO SCHEDULE FOR
- REMOVE AND REPLACE EXIST WINDOW COMPLETE
- 12. REMOVE EXIST AC WINDOW UNIT AND REMOVE EXIST WINDOW COMPLETE, REPLACE WITH NEW

(ADD ALT),

- 14. REMOVE EXIST WALL PARTITION COMPLETE.
- COMPLETE.
- 17. REMOVE EXIST BAR CABINETS COMPLETE. 18. REMOVE TROPHY CASE DISPLAY COMPLETE.
- 19. REMOVE EXIST LOCKER.
- 21. REMOVE EXIST SHELVING.
- 13. REMOVE EXIST WINDOW AND INFILL OPENING WITH TREADS AND RISERS. LIKE CONSTRUCTION.
- 15. REMOVE EXIST FINISH FLOOR AND BASEBOARD
- 16. EXIST PTAC UNIT AND LOUVER TO BE REMOVED. INFILL EXIST M.O. W/ LIKE MATERIALS.

- 20. REMOVE ALL EXIST EQUIPMENT AND WIRING.
- 22. REMOVE AND REPLACE EXIST HANDRAILS. 23. REMOVE AND REPLACE EXIST STAIR FINISH ON
- 24. REMOVE EXIST CLOSET.
- 25. REMOVE AND/OR RELOCATE EXIST ELECTRICAL PANEL,
- 26. REMOVE EXIST KITCHEN EQUIPMENT COMPLETE. 27. REMOVE EXIST TILE WALL AT KITCHEN.
- 28. REMOVE EXIST TREES.
- 29. REMOVE EXIST FLUE.

REMOVED.

REMOVED.

IN KIND WITH NEW (5 1/4x4 AND 5 1/4x10),

32. EXIST OUTDOOR STORAGE CONTAINER TO BE

33. MECHANICAL EQUIPMENT TO BE REMOVED, REFER

TO MECHANICAL DWGS FOR NEW EQUIPMENT.

35. EXIST ASPHALT SHINGLED MANSARD ROOF TO

36. EXIST WALL MOUNTED ROOF ANTENNAE TO BE

34. EXIST ROOF MEMBRANE TO REMAIN.

- 38. REMOVE FAN OR VENT AND INFILL OPENING WITH LIKE CONSTRUCTION. 30. REMOVE EXIST CONCRETE SLAB.
- 39, REMOVE EXISTING LOUVRE AND INFILL OPENING 31. REMOVE AND REPLACE EXIST DAMAGED FASCIA WITH LIKE CONSTRUCTION.

37. EXIST VENT TO REMAIN.

- 40. REMOVE EXIST BATHROOM STALL PARTITIONS.
- 41. REMOVE AND REUSE (IF POSSIBLE) EXIST DOOR AND FRAME, PROVIDE NEW HARDWARE.
- 42. REMOVE AND INFILL EXIST BOILER INTAKE AIR
- 43. UPGRADE DCV BACKFLOW TO RPZ.
- 44. REMOVE PORTION OF MANSARD ROOF TO ACCOMMODATE NEW ADDITION CONSTRUCTION.

45. REMOVE EXIST SUSPENDED AHU AND ASSOCIATED

- DUCTWORK.
- 46. REMOVE EXIST OIL TANK. 47. REMOVE EXIST 4x4 POST.
- 48. REMOVE EXIST ROOFTOP EQUIPMENT, INFILL WITH LIKE CONSTRUCTION AND PATCH ROOFING AS REQUIRED.
- 49, TROUGH DRAIN AND OIL/WATER SEPARATOR
- COVER TO BE REMOVED AND REPLACED IN KIND. 50. EXISTING WAS METER AND SUPPLY LINES TO BE REMOVED AS PART OF NEW SERVICE UPGRADE
- 51. EXISTING PTAC UNIT TO BE REPLACED W/ NEW. ENLARGE M.O. AND PROVIDE NEW LOUVER AS REQ'D PER HYAC DRAWINGS.

WORK- REFER TO PLUMBING DRAWINGS.



Joseph G. Thompson Architect, PLLC 108 N Division Street, Ste 100 Peekskill, New York 10566 PH: (8 4 5) 5 3 2 - 8 1 5 6 EM: joe@jthompsonarch.com


IT IS A VIOLATION OF THE LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A ICENSED ARCHITECT OR ENGINEER O ALTER AN ITEM IN ANY WAY. IF AN ITEM BEARING THE SEAL OF AN ARCHITECT OR ENGINEER IS ALTERED, THE ALTERING ARCHITECT OR ENGINEER SHALL AFFIX TO HIS ITEM THE SEAL AND THE NOTATION "ALTERED BY" FOLLOWED BY HIS SIGNATURE AND THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION

DO NOT SCALE DRAWINGS. WRITTEN DIMENSIONS GOVERN. © JOSEPH G THOMPSON ARCHITECT PLLC. ALL RIGHTS RESERVED



Joseph G. Thompson, RA New York State License #036057

Date: May 7, 2025



2 Existing South Demoliton Elevation
AD2.02 Scale: 3/16" = 1'-0"