| LEG | SEND | | ABBREVIATIONS | | | | |
|--|---|--------------------|-----------------------------------|--|--|--|--|
| SYMBOL | DESCRIPTION | AFF | ABOVE FINISHED FLOOR | | | | |
| <u> </u> | PIPING UP | вти | BRITISH THERMAL UNIT | | | | |
| <u> </u> | PIPING DOWN | втин | BTU PER HOUR | | | | |
| | PIPING RISE OR DROP | CLG | CEILING | | | | |
| | BRANCH-TOP CONNECTION | СО | CLEAN OUT | | | | |
| | BRANCH-BOTTOM CONNECTION | CODP | CLEAN OUT DECK PLATE | | | | |
| | REDUCER | COWP | CLEAN OUT WALL PLATE | | | | |
| CO CO | CLEANOUT | CW | COLD WATER | | | | |
| <u> </u> | FLOOR CLEANOUT | (D) | DEMOLISH | | | | |
| | CAPPED PIPE | DCV | DOUBLE CHECK VALVE DEVICE | | | | |
| <u> </u> | METER | DEG. | ° FAHRENHEIT | | | | |
| | FLOOR DRAIN | DIA | DIAMETER | | | | |
| \Diamond | AQUASTAT | DN | DOWN | | | | |
| | PUMP | (E) | EXISTING | | | | |
| | STRAINER | EA | EACH | | | | |
| <u> </u> | UNION | FAI | FRESH AIR INTAKE | | | | |
| | THERMOSTATIC MIXING VALVE | FD | FLOOR DRAIN | | | | |
| | BALANCING VALVE (BLV) | G | GAS | | | | |
| | | 'GC' | GENERAL CONSTRUCTION CONTRACTOR | | | | |
| —————————————————————————————————————— | GLOBE VALVE (GLV) | GPM | GALLONS PER MINUTE | | | | |
| | CHECK VALVE (CV) | GPH | GALLONS PER HOUR | | | | |
| | GAS COCK, GAS STOP | 'H' | HVAC CONTRACTOR | | | | |
| 151 | BALL VALVE (BV) | НР | HORSEPOWER | | | | |
| - | BUTTERFLY VALVE (BFV) | HW | HOT WATER | | | | |
| S | SOLENOID VALVE | HWR | HOT WATER RETURN | | | | |
| | PRESSURE-REDUCING VALVE (PRV) | IN. | INCHES | | | | |
| | GATE VALVE (GV) | IN. W.C. (W.G.) | INCHES WATER COLUMN (WATER GAUGE) | | | | |
| | PRESSURE-RELIEF VALVE (RV) | KW | KILOWATTS | | | | |
| | BACKFLOW PREVENTER | LBS | POUNDS | | | | |
| *+ | FROST FREE HOSE BIBB | M | METER | | | | |
| | HOSE BIBB | MAX | MAXIMUM | | | | |
| * * * * | RECESSED-BOX HOSE BIBB OR WALL HYDRANT | MIN | MINIMUM | | | | |
| | EXPANSION JOINT | NTS | NOT TO SCALE | | | | |
| <u> </u> | WATER HAMMER ARRESTER | OW | OIL WASTE | | | | |
| HDO | VALVE IN RISER | (P) | PROPOSED | | | | |
| CO T | WALL CLEANOUT (WCO) | 'P' | PLUMBING CONTRACTOR | | | | |
| | PITCH DOWN OR UP IN DIRECTION OF ARROW | PD | PRESSURE DROP | | | | |
| | FLOW IN DIRECTION OF ARROW | RD | ROOF DRAIN | | | | |
| | COLD WATER (CW) | RPM | REVOLUTIONS PER MINUTE | | | | |
| | TEMPERED WATER (TW) | RPZ | REDUCED PRESSURE ZONE | | | | |
| | HOT WATER (HW) | SAN / S | SANITARY | | | | |
| | TEMPERED WATER RETURN (TWR) | ST | STORM DRAIN | | | | |
| | HOT WATER RETURN (HWR) | TEMP | TEMPERATURE | | | | |
| | WASTE PIPING (W,S,OW) | TYP | TYPICAL | | | | |
| | BELOW SLAB WASTE PIPING | TW | TEMPERED WATER (110°F) | | | | |
| | VENT PIPING (V) | TWR | TEMPERED WATER RETURN | | | | |
| | GAS PIPING (G) | V | VENT | | | | |
| | TO BE REMOVED | VTR | VENT THROUGH ROOF | | | | |
| - | POINT OF CONNECTION | W | WASTE | | | | |
| 0 | POINT OF DISCONNECTION | | | | | | |
| | | | | | | | |

GENERAL PLUMBING NOTES

- PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE PLUMBING SYSTEMS AS INDICATED ON THE DRAWINGS. AS SPECIFIED AND AS REQUIRED BY CODE.
- THE CONTRACTOR, BY PRESENTING THEIR BID FOR THE WORK, REPRESENTS THAT HE/SHE HAS INSPECTED THE SITE AND IS COMPLETELY FAMILIAR WITH THE SCOPE OF WORK AND ALL FIELD CONDITIONS RELATED TO, AND AFFECTING THE WORK AND ITS PERFORMANCE. EXCEPTIONS AFFECTING THE WORK AND ITS PERFORMANCE, OR CONFLICTS BETWEEN FIELD CONDITIONS, SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO THE SUBMISSION OF BIDS.
- PERFORM ALL WORK IN ACCORDANCE WITH THE 2020 NEW YORK STATE PLUMBING (NYSPC), FIRE (NYSFC), MECHANICAL (NYSMC), ENERGY CONSERVATION CONSTRUCTION (NYSECC), AND FUEL GAS (NYSFGC) CODE AND THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION.
- COMPLY WITH THE NATIONAL ELECTRIC CODE AND THE REQUIREMENTS OF DIVISION 26 FOR ALL ELECTRICAL
- 5. APPLY FOR AND SECURE ALL REQUIRED PERMITS AND INSPECTIONS AND PAY ALL COSTS FOR THE SAME.
- 6. FIRE STOP ALL OPENINGS IN FIRE RATED CONSTRUCTION FOR PIPING, CONDUIT, ETC.
- DO NOT SCALE DRAWINGS. DRAWINGS FOR PLUMBING WORK ARE DIAGRAMMATIC AND ARE INTENDED TO CONVEY SCOPE AND GENERAL ARRANGEMENT ONLY. THE LOCATIONS OF ALL ITEMS SHOWN ON THE DRAWINGS OR CALLED FOR IN THE SPECIFICATIONS THAT ARE NOT DEFINITELY FIXED BY DIMENSIONS ARE APPROXIMATE.
- COORDINATE CONTRACT DOCUMENTS PROJECT REQUIREMENTS, WORK OF OTHERS, AND EQUIPMENT AND MATERIALS PURCHASED WITH FIELD DIMENSIONS, MANUFACTURERS REQUIREMENTS FOR INSTALLATION, OPERATION, AND MAINTENANCE, CONTRACTORS INTENDED MEANS AND METHODS OF INSTALLATION AND CONTRACTORS FABRICATED ITEMS TO ENSURE A PROPER "FIT" AND INSTALLATION. BRING ANY CONFLICTS TO THE ATTENTION OF THE ARCHITECT/ENGINEER DURING THE SUBMITTAL PHASE FOR RESOLUTION PRIOR TO PURCHASING ANY EQUIPMENT.
- MAINTAIN MAXIMUM HEADROOM AND SPACE CONDITIONS AT ALL POINTS. WHERE HEADROOM AND SPACE CONDITIONS APPEAR INADEQUATE, NOTIFY THE ARCHITECT/ENGINEER PRIOR TO PROCEEDING WITH INSTALLATION. MAINTAIN A MINIMUM OF 6'-8" CLEARANCE FROM FINISHED FLOOR TO UNDERSIDE OF PIPES, CONDUITS, SUSPENDED EQUIPMENT, ETC., THROUGHOUT ACCESS ROUTES IN MECHANICAL ROOMS.
- 10. FIELD VERIFY AND COORDINATE ALL PIPING DIMENSIONS BEFORE FABRICATION. MAKE MODIFICATIONS IN THE LAYOUT AS NEEDED TO PREVENT CONFLICT WITH WORK OF OTHER TRADES OR FOR PROPER EXECUTION OF THE WORK. OBTAIN THE APPROVAL OF THE ARCHITECT/ENGINEER FOR MODIFICATIONS.
- 11. PROVIDE PRODUCTS OF ONE MANUFACTURER WHERE TWO OR MORE ITEMS OF THE SAME TYPE OF MATERIAL OR EQUIPMENT IS REQUIRED.
- 12. INSTALL ALL EQUIPMENT AND APPURTENANCES IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, CONTRACT DOCUMENTS, AND APPLICABLE CODES AND REGULATIONS. REFER TO DETAILS FOR ADDITIONAL PIPING AND **EQUIPMENT INSTALLATION REQUIREMENTS.**
- 13. LOCATE ALL TEMPERATURE, PRESSURE, AND FLOW MEASURING DEVICES IN ACCESSIBLE LOCATIONS WITH STRAIGHT SECTION OF PIPE UP- AND DOWNSTREAM AS RECOMMENDED BY THE MANUFACTURER TO ENSURE MANUFACTURER
- 14. COORDINATE ALL EQUIPMENT CONNECTIONS WITH MANUFACTURER'S CERTIFIED DRAWINGS. COORDINATE AND PROVIDE ALL PIPING TRANSITIONS REQUIRED FOR FINAL CONNECTIONS TO EQUIPMENT.
- 15. COORDINATE LOCATIONS AND SIZES OF ALL FLOOR, WALL, AND ROOF OPENINGS WITH ALL OTHER TRADES. COORDINATE ALL PIPING AND EQUIPMENT SUPPORTED FROM STRUCTURE WITH GENERAL CONSTRUCTION WORK.
- 16. COMPLETE ALL PRESSURE TESTS BEFORE ANY PLUMBING EQUIPMENT, OR PIPING INSULATION IS APPLIED.
- 17. MAKE ALL ATTACHMENTS TO JOISTS, TRUSSES, OR JOIST GIRDERS AT PANEL POINTS. PROVIDE BEAM CLAMPS MEETING MSS STANDARDS. THE USE OF C-CLAMPS IS NOT PERMITTED.
- 18. PROVIDE CONCRETE PADS A MINIMUM OF 4 INCHES HIGH FOR ALL FLOOR MOUNTED EQUIPMENT. EXTEND PAD 4 INCHES BEYOND THE EQUIPMENT ON ALL SIDES.
- 19. INSTALL PIPING, AND CONDUIT CONCEALED IN AREAS HAVING HUNG CEILINGS AND/OR FURRED SPACES UNLESS OTHERWISE INDICATED ON THE DRAWINGS.
- 20. REFER TO ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF ALL ACCESSIBLE FIXTURES. MOUNT ALL SUCH FIXTURES IN ACCORDANCE WITH THE REQUIREMENTS OF THE AUTHORITY HAVING JURISDICTION
- 21. PROVIDE ACCESS DOORS IN WALLS, PARTITIONS, AND CEILINGS AS REQUIRED TO MAKE VALVES, WATER HAMMER
- 22. ARRANGE FOR, COORDINATE, AND MAKE CONNECTION TO ALL SERVICES PROVIDED BY OTHERS. CONFORM TO ALL REQUIREMENTS APPLICABLE TO CONNECTIONS IMPOSED BY UTILITY COMPANIES AND AUTHORITIES HAVING
- 23. INSTALL FIXTURES AND EQUIPMENT WITH VALVES, UNIONS, ETC. TO ALLOW FOR EASE OF SERVICE AND/OR REMOVAL.
- 24. CORE DRILL ALL PENETRATIONS THROUGH CONCRETE FLOORS, WALLS, AND FOOTINGS.
- 25. INSTALL LINK SEAL TYPE PROTECTION FOR WATER RESISTANT SEALS AT ALL SLAB AND BELOW GROUND WALL FOOTING PENETRATIONS.
- 26. PROVIDE A CLEANOUT AT THE BASE OF WASTE AND VENT STACKS WITH FINISHED WALL PLATE IN FINISHED WALLS.
- 27. FURNISH AND INSTALL WATER PRESSURE REDUCING VALVE AND PRESSURE RELIEF VALVE IN ACCORDANCE WITH THE
- NEW YORK STATE PLUMBING CODE ON ALL INCOMING DOMESTIC WATER SYSTEMS IN EXCESS OF 80 P.S.I.G.
- 29. SLOPE ALL VENT PIPING TO DRAIN BACK TO THE DRAINAGE SYSTEM.

28. COVER ALL COPPER PIPING BELOW SLAB WITH "ARMAFLEX" TYPE INSULATION.

ARRESTERS, ETC. READILY ACCESSIBLE

TEMPERATURE OF 110 DEGREES F.

JURISDICTION.

- 30. FLUSH AND DISINFECT ALL DOMESTIC POTABLE WATER PIPING AND TEST THE WATER IN ACCORDANCE WITH THE INTERNATIONAL PLUMBING CODE. PROVIDE CERTIFICATE OF PERFORMANCE AND LABORATORY TEST REPORT TO LOCAL AUTHORITIES HAVING JURISDICTION AND OBTAIN THEIR APPROVAL.
- 31. PROVIDE WATER HAMMER ARRESTORS AT ALL QUICK CLOSING FIXTURE VALVE LOCATIONS.
- 32. ALL PIPING, VALVES AND FITTINGS USED FOR POTABLE WATER SHALL BE NSF 61/372 COMPLIANT AND BE TESTED FOR LOW LEAD.
- 33. ANY PENETRATIONS THROUGH AIR BARRIER SHALL BE SEALED AS PER 2020 NYSECC RESIDENTIAL AND COMMERCIAL PROVISIONS.
- 34. ALL PIPING IN PLENUM SPACES SHALL BE CAST IRON FOR SANITARY, STORM, VENT SYSTEMS, AND COPPER PIPING FOR DOMESTIC SYSTEMS, AND STEEL PIPING FOR GAS SYSTEMS. NO PLASTIC PIPING ALLOWED.
- 35. HOT WATER TEMPERATURE FOR ALL PUBLIC HAND WASHING FIXTURES SHALL BE TEMPERED TO A MAXIMUM
- 36. ALL FIXTURES SHALL MEET THE WATER CONSERVATION REQUIREMENTS LISTED IN THE TABLE 604.4 OF THE 2020 INTERNATIONAL PLUMBING CODE.
- 37. ALL FIXTURES THAT HAS THE ABILITY TO HAVE A HOSE CONNECTED TO IT, OR DIRECT CONNECTED FIXTURES, SHALL HAVE A BACKFLOW PREVENTION DEVICE ON THE FAUCET, VACUUM BREAKER (ASSE 1052 AND ASME A112.21.3).
- 38. ALL SANITARY FITTINGS SHALL BE 'WYE' TYPE AND SHALL FOLLOW THE DIRECTION OF FLOW.
- 39. IN THE EVENT THAT THERE IS A DISCREPANCY BETWEEN DESIGN PLANS, RISER DIAGRAMS, AND/OR SPECIFICATIONS CONCERNING PIPE SIZES, FIXTURES, AND/OR EQUIPMENT, THE MOST STRINGENT REQUIREMENTS SHALL BE APPLIED TO THE PROJECT.

FUEL GAS NOTES

- PERFORM ALL WORK IN ACCORDANCE WITH NFPA 54 NATIONAL FUEL GAS CODE, THE 2020 NEW YORK STATE FUEL GAS CODE (NYSFGC), 2021 CENTRAL HUDSON RED BOOK, AND THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION.
- THE DEPTH OF COVER FOR ALL GAS SERVICE PIPING SHALL BE 24 INCHES. THE WATER SERVICE SHALL BE KEPT A MINIMUM OF 10-FEET FROM THE INCOMING GAS SERVICE MEASURED IN ANY
- DIRECTION. 4. IF ELECTRIC AND GAS SHARE A COMMON TRENCH, THE TRENCH MUST BE WIDE ENOUGH TO MAINTAIN A 6-INCH MINIMUM
- SEPARATION DISTANCE. 5. LOCATION OF PROPOSED GAS METER ON CONTRACT DOCUMENTS ARE SUBJECT TO CHANGE BY THE LOCAL UTILITY
- COMPANY. REFER TO THE LOCAL UTILITY COMPANY HANDBOOKS FOR METER RIG CONSTRUCTION DETAILS, RULES AND REGULATIONS. THIS INCLUDES. BUT NOT LIMITED TO LOCATION OF STEP DOWN REGULATORS. METER SIZE AND SET
- 7. GAS PIPING: 7.1. INDOOR - STEEL PIPE- SCHEDULE 40 WITH WELDED OR THREADED JOINTS. THREADED JOINTS SHALL BE 150 POUND MALLEABLE IRON, FORGED STEEL, BLACK IRON, OR GALVANIZED STEEL.

LENGTHS, VENTING OF REGULATORS, BYPASS PIPING, BOLLARD REQUIREMENTS, CONCRETE PAD, SUPPORTS, AND SHUT

- OUTDOOR ABOVE GROUND GALVANIZED PIPE OR PROPERLY COATED BLACK STEEL PIPE WITH SCREWED OR
- THREADED JOINTS. BELOW GRADE - STEEL PIPE- MILL WRAPPED SCHEDULE 40 WITH WELDED OR THREADED JOINTS
- WELDED JOINTS MUST BE USED FOR GAS PIPING LARGER THAN 4-INCH, OR 3-INCH FOR SCHOOLS. 8. GAS PIPING ENTERING A BUILDING SHALL BE ABOVE GRADE. PENETRATIONS THROUGH BURIED WALLS ARE NOT
- 9. WHERE GAS PIPING IS INSTALLED BELOW GRADE INSIDE A BUILDING, THE GAS PIPING MUST BE INSTALLED IN A CONDUIT AND BE VENTED TO THE EXTERIOR.
- GALVANIZED OR BARE STEEL UP TO 14" W.C. AIR AT 3 PSIG FOR 30 MINUTES

OFF VALVES.

PERMITTED.

10. GAS PRESSURE TEST:

- GALVANIZED OR BARE STEEL GREATER THAN 14" W.C. AIR AT 50 PSIG FOR 30 MINUTES
- COATED OR WRAPPED LESS THAN 2-INCH AIR AT 90 PSIG FOR 1-HOUR 10.3. COATED OR WRAPPED - 2-INCH TO 12-INCH - AIR AT 90 PSIG FOR 4-HOURS
- 11. SUPPLY ALL GAS-FIRED EQUIPMENT WITH GAS PIPING AS PER THE NEW YORK STATE FUEL GAS CODE. PROVIDE EACH PIECE OF EQUIPMENT WITH A DIRT LEG, UNION AND GAS COCK. PROVIDE A VENTED REGULATOR IF EQUIPMENT REQUIRES LOWER THAN LINE GAS PRESSURE.
- 12. PROVIDE VEHICLE IMPACT PROTECTION FOR NEW METER HEADER. BOLLARDS SHALL BE SPACED NO MORE THAN 4-FEET BETWEEN POSTS ON CENTER AND LOCATED NOT LESS THAN 3-FEET FROM THE PROTECTED OBJECT. 13. SHUTOFF VALVES INSTALLED IN TUBING SYSTEMS MUST BE RIGIDLY AND SECURELY SUPPORTED INDEPENDENTLY OF THE
- 14. ALL COOKING APPLIANCE CONNECTIONS MUST BE LISTED AND LABELED.

| | APPLIANCE SHUTOFF | OTHER | VALVE APPLICATION | ONS | | | | | | | |
|--|--|----------------------------|--------------------------|--------------------------|--|--|--|--|--|--|--|
| VALVE STANDARDS | VALVE APPLICATION UP TO 1/2 PSIG PRESSURE | UP TO 1/2 PSIG PRESSURE | UP TO 2 PSIG PRESSURE | UP TO 5 PSIG PRESSURE | | | | | | | |
| ANSI Z21.15/CGA9.1 | X | _ | _ | - | | | | | | | |
| ASME B16.44 | X | X* | X** | _ | | | | | | | |
| ASME B16.33 | X | Х | Х | Х | | | | | | | |
| NOTES: 1. FOR SI: 1 POUND PER SQUARE INCH GAUGE = 6.895 kPa. 2. X* IF LABELED 2G 3. X** IF LABELED 5G | | | | | | | | | | | |

ENERGY NOTES

2020 NEW YORK STATE ENERGY CONSERVATION CODE NOTES: STATEMENT OF COMPLIANCE:


TO THE BEST OF MY KNOWLEDGE, AND PERSONAL JUDGEMENT, THESE PLANS AND SPECIFICATIONS ARE IN COMPLIANCE WITH THE 2020 NEW YORK STATE ENERGY CONSERVATION CODE (NYSECC).

- 1. SERVICE WATER HEATING EQUIPMENT PERFORMANCE EFFICIENCY:
- 1.1. WATER HEATING EQUIPMENT AND HOT WATER STORAGE TANKS SHALL MEET THE REQUIREMENTS OF TABLE C404.2 IN THE 2020 NYSECC. (NYSECC C404.2)
- 1.2. SERVICE WATER HEATING SHALL BE COMMISSIONED AND COMPLETED IN ACCORDANCE WITH SECTION C408.2 OF
- 2. TEMPERATURE CONTROL:
- 2.1. SERVICE WATER HEATING EQUIPMENT SHALL BE PROVIDED WITH CONTROLS ALLOWING A SETPOINT OF 110°F FOR DWELLING UNITS AND 90 °F FOR OTHER OCCUPANCIES. PUBLIC REST ROOM LAVATORIES SHALL HAVE A MAXIMUM **OUTLET TEMPERATURE OF 110°F.**
- 2.2. WHERE WATER HEATING EQUIPMENT SERVING NONCIRCULATING SYSTEMS IS NOT SUPPLIED WITH INTEGRAL HEAT TRAPS, HEAT TRAPS SHALL BE PROVIDED ON THE SUPPLY AND DISCHARGE PIPING. (NYSECC C404.3)
- 3. PIPE INSULATION: 3.1. AUTOMATIC CIRCULATING HOT WATER SYSTEM PIPING SHALL BE INSULATED WITH 1 INCH OF INSULATION WITH A CONDUCTIVITY NOT EXCEEDING 0.27 BTU PER INCH/H X FT X FT X °F, OR THE INSULATION REQUIREMENTS OF SPECIFICATIONS, WHICHEVER IS GREATER. THE FIRST 8 FT OF PIPING IN NONCIRCULATING SYSTEMS WITH EQUIPMENT WITHOUT INTEGRAL HEAT TRAPS SHALL BE INSULATED WITH 0.5 INCH OF MATERIAL HAVING A CONDUCTIVITY NOT EXCEEDING 0.27 BTU PER INCH/H X FT X FT X °F, OR THE INSULATION REQUIREMENTS OF
- SPECIFICATIONS, WHICHEVER IS GREATER. (NYSECC C404.5)
- ALL PIPING TO BE INSULATED WITH 0.21-0.28 CONDUCTIVITY COLD WATER PIPING - ALL SIZES - 1-INCH INSULATION, A.S. JACKET.
- STORM DRAINAGE PIPING ALL HORIZONTAL RUNS AND DRAIN BODY MINIMUM 1-INCH INSULATION, A.S. JACKET.
- HOT WATER PIPING (140°F) AND TEMPERED WATER PIPING (110°F) PIPE SIZE: < 1" INSULATION: 1"
- PIPE SIZE: 1" TO < 1-1/2" INSULATION: 1"
- PIPE SIZE: 1-1/2 TO < 4" INSULATION: 1.5"
- PIPE SIZE: 4" TO < 8" INSULATION: 1.5"
- 4. HOT WATER SYSTEM CONTROLS:
- 4.1. CIRCULATING HOT WATER SYSTEM PUMPS OR HEAT TRACE SHALL BE ARRANGED TO BE TURNED OFF EITHER AUTOMATICALLY OR MANUALLY WHEN THERE IS LIMITED HOT WATER DEMAND. READY ACCESS SHALL BE PROVIDED TO THE OPERATING CONTROLS. (NYSECC C404.6)
- PIPE VOLUME AND MAXIMUM LENGTHS
- 5.1. PER SECTION OF C404.5.1 OF THE 2020 NYSECC, ALL MAXIMUM PIPE LENGTHS FROM FIXTURES SHALL COMPLY WITH THE MAXIMUM PIPE LENGTHS ON THE CHART BELOW. CONTRACTOR TO ENSURE HOT WATER RETURN PIPING IS INSTALLED AS PER PLANS AND THAT THESE LENGTHS ARE MAINTAINED.

| NOMINAL PIPE SIZE | VOLUME (LIQUID OUNCES PER | MAXIMUM PIPINO | G LENGTH (FEET) | | | |
|-------------------|---------------------------|----------------------------|-------------------------------|--|--|--|
| (INCHES) | FOOT LENGTH) | PUBLIC LAVATORY FAUCETS | OTHER FIXTURES AND APPLIANCES | | | |
| 1/4" | 0.33 | 6 | 50 | | | |
| 5/16" | 0.5 | 4 | 50 | | | |
| 3/8" | 0.75 | 3 | 50 | | | |
| 1/2" | 1.5 | 2 | 43 | | | |
| 5/8" | 2 | 1 | 32 | | | |
| 3/4" | 3 | 0.5 | 21 | | | |
| 7/8" | 4 | 0.5 | 16 | | | |
| 1" | 5 | 0.5 | 13 | | | |
| 1-1/4" | 8 | 0.5 | 8 | | | |
| 1-1/2" | 11 | 0.5 | 6 | | | |
| 2" OR LARGER | 18 | 0.5 | 4 | | | |

APPLICABLE CODES

- 2020 NEW YORK STATE RESIDENTIAL CODE (NYSRC) 1ST PRINTING (INCLUDES PLUMBING,
- MECHANICAL, FUEL GAS, AND ENERGY CONSERVATION) 2020 NEW YORK STATE BUILDING CODE (NYSBC) 1ST PRINTING
- 2020 NEW YORK STATE FIRE CODE (NYSFC) 1ST PRINTING
- 2020 NEW YORK STATE PLUMBING CODE (NYSPC) 1ST PRINTING 2020 NEW YORK STATE FUEL GAS CODE (NYSFGC) 1ST PRINTING
- 2020 NEW YORK STATE MECHANICAL CODE (NYSMC) 1ST PRINTING
- 2020 NEW YORK STATE ENERGY CONSERVATION CODE (NYSECC) 1ST PRINTING



538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

| со | NSULTANTS: | | | |
|----|------------|--|--|--|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) **New Fire Station (Phase II)**



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G GENERAL CONSTRUCTION

FINAL BID DOCUMENT

PLUMBING NOTES, LEGEND, AND **ABBREVIATIONS**

P2 001.00

FIXTURE

PLUMBING FIXTURE SCHEDULE

DESCRIPTION

MANUFACTURER

2. MINIMUM CONNECTION SIZES INDICATED ARE EQUIPMENT CONNECTION SIZES OR CODE MINIMUM SIZES, SEE PLANS AND DIAGRAMS FOR ACTUAL SIZES REQUIRED.

3. ALL FLOOR DRAINS SHALL HAVE TRAP SEALS. MANUFACTURER: ZURN; Z1072.

4. INSULATE EXPOSED DRAIN AND SUPPLY PIPING FOR HANDICAPPED FIXTURES WITH TRUEBRO LAV GUARD.

MODEL

| TAG | DESCRIPTION | MANUFACTURER | MODEL | MANUFACTURER | MODEL | TYPE | MOTION SENSOR CONTROL | SIZE | VATER FU | SIZE | WATER FU | SIZE | DFU | VENT | SPECIFICATION REMARKS |
|---------------|---|---------------------------|---------------------------------|-------------------------|------------------------------|-------------------|-----------------------|------|-------------|------|-------------|------------------------|-----|-------|---|
| LAV-1 | LAVATORY - UNDERMOUNT | KOHLER | CAXTON OVAL K-2210 | KOHLER | GEOMETRIC INSIGHT K-13466 | ELECTRONIC | YES | 1/2 | .5 | 1/2 | .5 | 1-1/2 | 1 | 1-1/2 | VITREOUS CHINA UNDER-MOUNT LAVATORY, FRONT OVERFLOW, MOUNTING KIT AND TEMPLATE BY MANUFACTURER. LAVATORY SHALL ADHERE TO ASME A112.19.2 AND ANSI A117.1. FAUCET TO HAVE MAX. FLOW RATE OF 0.5 GPM, VANDAL RESISTANT AERATOR, AND 24" FLEXIBLE SUPPLY HOSES. MIXING FAUCET SHALL ADHERE TO ASME A112.18.1 AND NSF/ANSI 372. |
| LAV-2 | LAVATORY - WALL HUNG - BARRIER FREE | AMERICAN STANDARD | DECORUM 20" X 18" 9024.001EC | KOHLER | GEOMETRIC INSIGHT K-13466 | ELECTRONIC | YES | 1/2 | .5 | 1/2 | .5 | 1-1/2 | 1 | 1-1/2 | 20" X 18" VITREOUS CHINA LAVATORY WITH REAR OVERFLOW. CENTER HOLE ONLY. RECESSED SELF-DRAINING DECK WITH MINIMAL BACKSPLASH. ADA AND TAS COMPLIANT. LAVATORY SHALL ADHERE TO ASME A112.19.2 AND ANSI A117.1. FAUCET TO HAVE MAX. FLOW RATE OF 0.5 GPM, VANDAL RESISTANT AERATOR, AND 24" FLEXIBLE SUPPLY HOSES. MIXING FAUCET SHALL ADHERE TO ASME A112.18.1 AND NSF/ANSI 372. |
| WC-1 | WATER CLOSET - FLUSH VALVE - WALL MOUNT | KOHLER | KINGSTON K-4323 | KOHLER | TRIPOINT K-10956-SV | MANUAL/ELECTRONIC | YES | 1 | 10 | - | - | 3 | 4 | 2 | VITREOUS CHINA, SIPHON JET, ELONGATED BOWL, WALL MOUNTED WITH 1-1/2" REAR SPUD . WATER CLOSET SHALL CONFORM TO ASME A112.19.2 AND ANSI A117.1. FLUSHOMETER SHALL BE FIXTURE MOUNT DESIGN, BRASS CONSTRUCTION, ELECTRONIC INFRARED SENSOR, AND DC STYLE WITH 1.5V AA BATTERIES. PROVIDE ZURN Z1202 NO-HUB WATER CLOSET CARRIER SYSTEM FOR WATER CLOSETS AND P-TRAP. |
| WC-2 | WATER CLOSET - FLUSH VALVE - WALL MOUNT - BARRIER FREE | KOHLER | KINGSTON K-4323 | KOHLER | TRIPOINT K-10956-SV | MANUAL/ELECTRONIC | YES | 1 | 10 | - | - | 3 | 4 | 2 | VITREOUS CHINA, SIPHON JET, ELONGATED BOWL, WALL MOUNTED WITH 1-1/2" REAR SPUD . WATER CLOSET SHALL CONFORM TO ASME A112.19.2 AND ANSI A117.1. FLUSHOMETER SHALL BE FIXTURE MOUNT DESIGN, BRASS CONSTRUCTION, ELECTRONIC INFRARED SENSOR, AND DC STYLE WITH 1.5V AA BATTERIES. PROVIDE ZURN Z1202 NO-HUB WATER CLOSET CARRIER SYSTEM FOR WATER CLOSETS AND P-TRAP. |
| UR-1 | URINAL - FLUSH VALVE - WALL MOUNTED - BARRIER FREE | KOHLER | BARDON K-4991-ER | KOHLER | TRIPOINT K-10949-SV | MANUAL/ELECTRONIC | YES | 3/4 | 5 | - | - | 2 | 2 | 2 | VITREOUS CHINA WASHOUT URINAL, 3/4" REAR SPUD, 14" EXTENDED RIM, CONFORMS TO ASME A112.19.2, ANSI A117.1. FLUSHOMETER SHALL BE FIXTURE MOUNT DESIGN, BRASS CONSTRUCTION, ELECTRONIC INFRARED SENSOR, AND DC STYLE WITH 1.5V AA BATTERIES. PROVIDE ZURN Z1222 URINAL CARRIER SYSTEM FOR WATER CLOSETS AND P-TRAP. |
| SH-1 | SHOWER - VOLUME CONTROL WITH MIXING VALVE AND SHOWER DRAIN | SWAN | STF-3838 SWANSTONE | SYMMONS | TEMPTROL S-96-1-231-X-B | MANUAL | NO | 1/2 | 3 | 1/2 | 3 | 1-1/2 | 2 | 1-1/2 | 38" X 38" COMPRESSION MOLDED SOLID SURFACE SHOWER PAN. 3/4" LOW THRESHOLD ENTRY, WALL-TO-WALL TRENCH DRAIN SYSTEM WITH 304 STAINLESS STEEL GRATE. SLIP-RESISTANT, TEXTURED BOTTOM SURFACE. SHOWER VALVE TO HAVE PRESSURE BALANCING MIXING VALVE WITH INTEGRAL VOLUME CONTROL, ADJUSTABLE STOP SCREW TO LIMIT HANDLE TURN, SHOWER HEAD WITH ARM AND FLANGE, INTEGRAL SERVICE STOPS, AND CHROME BRASS ESCUTCHEON ON VALVE. |
| SH-2 | SHOWER - HANDHELD TRIM WITH MIXING VALVE AND SHOWER DRAIN - BARRIER FREE - ADA | SWAN | STF-3838 SWANSTONE | SYMMONS | TEMPTROL S-96-300-B30-L-V | MANUAL | NO | 1/2 | 3 | 1/2 | 3 | 1-1/2 | 2 | 1-1/2 | 38" X 38" COMPRESSION MOLDED SOLID SURFACE SHOWER PAN. 3/4" LOW THRESHOLD ENTRY, WALL-TO-WALL TRENCH DRAIN SYSTEM WITH 304 STAINLESS STEEL GRATE. SLIP-RESISTANT, TEXTURED BOTTOM SURFACE. SHOWER VALVE TO HAVE HAND SHOWER SYSTEM WITH LEVER HANDLES, PRESSURE BALANCING MIXING VALVE WITH INTEGRAL DIVERTER AND ADJUSTABLE STOP SCREW TO LIMIT HANDLE TURN, 5 FOOT FLEXIBLE METAL HOSE WITH IN-LINE VACUUM BREAKER, WALL CONNECTION AND FLANGE, 30 INCH SLIDE BAR FOR HAND SHOWER MOUNTING, POLISHED CHROME FINISH. |
| LS-1 | LAUNDRY SINK - DROP IN | ADVANCE TABCO | DI-1-2012 | ADVANCE TABCO | K-50 | MANUAL | NO | 1/2 | 2.25 | 1/2 | 2.25 | 1-1/2 | 2 | 1-1/2 | 23" X 21" X 12", 18 GAUGE, ONE PIECE SEAMLESS SINK BOWL. SELF RIMMING DESIGN WITH MOUNTING CLIPS. FAUCET SHALL BE DECK MOUNTED 8" SWING SPOUT, 4" O.C., LEAD FREE. PROVIDE ADDITIONAL ADVANCE TABCO DTA-53 SPLASH MOUNT PRERINSE FAUCET NEXT TO SINK. SEE ARCHITECTURAL SHEETS FOR MORE INFO. PROVIDE SEDIMENT/LINT P-TRAP. |
| SK-1 | PREP SINK - UNDER MOUNT | ADVANCE TABCO | 1620A-12 | ADVANCE TABCO | K-132 | MANUAL | NO | 1/2 | 1 | 1/2 | 1 | 1-1/2 | 2 | 1-1/2 | ONE PIECE 16" X 20" X 12" SEAMLESS STAINLESS STEEL BOWL. 18 GAUGE TYPE 304 STAINLESS STEEL. FAUCET SHALL BE DECK MOUNTED 5-1/2" GOOSENECK SPOUT, 8" O.C., BRASS CHROME PLATED BODY AND SPOUT, CHROME PLATED HANDLES, AND LEAD FREE. ONE PIECE 16" X 20" X 12" SEAMLESS STAINLESS STEEL BOWL. 18 GAUGE TYPE 304 STAINLESS STEEL. |
| SK-2 | HAND SINK - UNDER MOUNT | ADVANCE TABCO | 1620A-10 | ADVANCE TABCO | K-132 | MANUAL | NO | 1/2 | 1 | 1/2 | 1 | 1-1/2 | 2 | 1-1/2 | FAUCET SHALL BE DECK MOUNTED 5-1/2" GOOSENECK SPOUT, 8" O.C., BRASS CHROME PLATED BODY AND SPOUT, CHROME PLATED HANDLES, AND LEAD FREE. PROVIDE P-TRAP, STRAINER, AND DRAIN |
| SK-3 | TWO-COMPARTMENT SINK - KITCHEN | ADVANCE TABCO | FC-2-2424-18RL | ADVANCE TABCO | K-101 | MANUAL | NO | 1/2 | 1 | 1/2 | 1 | 1-1/2 | 2 | 1-1/2 | 16 GAUGE 304 STAINLESS STEEL TWO BASIN SINK WITH ADJUSTABLE HEIGHT, STAINLESS STEEL LEGS, ADJUSTABLE FRONT TO BACK CROSS BRACING, ROLLED RIM EDGE, 8" O.C. FAUCET HOLES. (2) DRAIN BOARDS. FAUCET SHALL BE SPLASH MOUNTED 8" SPOUT, 8" O.C., CHROME PLATED HANDLES, AND LEAD FREE. |
| DF-1 | DRINKING FOUNTAIN - SURFACE MOUNT- BILEVEL - ADA - REFRIGERATED | ELKAY | VRCHDTL8SC | - | - | MANUAL | NO | 1/2 | 0.25 | - | - | 1-1/4" | 1/2 | 1-1/2 | ELKAY WALL MOUNT HEAVY DUTY VANDAL RESISTANT BI-LEVEL ADA COOLER NON-FILTERED REFRIGERATED STAINLESS. FEATURES SHALL INCLUDE HEAVY DUTY VANDAL RESISTANT. FURNISHED WITH VANDAL RESISTANT BUBBLER. MECHANICAL FRONT BUTTON ACTIVATION. UNIT SHALL BE CERTIFIED TO UL 399 AND CSA C22.2 NO 120. LEAD FREE DESIGN CERTIFIED TO NSF/ANSI 61 & 372. |
| DF-2 | DRINKING FOUNTAIN - SURFACE MOUNT - SINGLE - ADA - BOTTLE FILLER - FILTERED - REFRIGERATED | ELKAY | LZS8WSLK | - | - | MANUAL/ELECTRONIC | YES | 1/2 | 0.25 | - | - | 1-1/4" | 1/2 | 1-1/2 | BOTTLE FILLING STATION WITH SINGLE ADA COOLER, FILTERED 8 GPH. FEATURES INCLUDE HANDS FREE, VISUAL FILTER MONITOR, FILTERED, LAMINAR FLOW, ANTI MICROBIAL, DRAIN. ELECTRONIC BOTTLE FILLER SENSOR WITH ELECTRONIC FRONT AND SIDE BUBBLER PUSHBAR ACTIVATION. UNIT SHALL BE CERTIFIED TO UL 399 AND CSA C22.2 NO 120. LEAD FREE DESIGN CERTIFIED TO NSF/ANSI 61 & 372 |
| EM-1 | EMERGENCY EYE/FACE WASH | HAWS | AXION 7360BT -7460BT | - | - | MANUAL | NO | 3/4 | - | 3/4 | - | 1-1/2 | - | - | WALL MOUNTED EYE/FACE WASH SHALL INCLUDE A STAINLESS STEEL 11" ROUND BOWL. AN EYE/FACE WASH HEAD SUPPLIED BY AN INTEGRAL FLOW CONTROL, CHROME-PLATED BRASS STAY-OPEN BALL VALVE EQUIPPED WITH STAINLESS STEEL BALL AND STEM, AND CHROME-PLATED BRASS IN-LINE 50 X 50 MESH WATER STRAINER. UNIT SHALL ALSO INCLUDE CAST-ALUMINUM CHROMATE PROTECTED WALL BRACKET, YELLOW PLASTIC POP-OFF DUST COVER FOR EYEWASH HEAD, TAILPIECE, UNIVERSAL SIGN, 1/2" IPS INLET, AND 1-1/2" IPS WASTE |
| HR-1 | GARDEN HOSE REEL | REELCRAFT | GC83050 OLP | - | - | MANUAL | NO | 3/4 | - | - | - | - | - | - | SPRING RETRACTABLE WATER HOSE REEL. INCLUDES OUTLET HOSE WITH BRASS ON/OFF BALL VALVE, BUMPER, AND INLET HOSE. HOSE END FITTINGS, ADJUSTABLE GUIDE ARM. INDIVIDUALLY POWER-COATED STEEL PARTS. |
| JS-1 | JANITOR SINK - FLOOR MOUNTED | ADVANCE TABCO | 9-OP-40 | ADVANCE TABCO | K-240 | MANUAL | NO | 3/4 | 2.25 | 3/4 | 2.25 | 3 | 2 | 1-1/2 | FLOOR MOUNTED STAINLESS STEEL MOP SINK. 16"X 20"X 12" BOWL SIZE. SERVICE FAUCET SHALL BE WALL MOUNT, 8" OC, 6-1/2" SPOUT, WITH HOSE THREAD OUTLET AND PAIL HOOK, VACUUM BREAKER SPOUT, WALL BRACED, AND CHROME-PLATED BRASS. INCLUDE HOSE BRACKET, HOSE, MOP HOLDER, AND WALL GUARDS. |
| HB-1 | HOSE BIBB - INTERIOR WITH KEY | MURDOCK | 8120-LF | - | - | - | - | 3/4 | - | - | - | - | - | - | HEAVY BRASS BODY, FURNISHED WITH A LOCKSHIELD BONNET AND REMOVABLE LOOSE KEY HANDLE. VACUUM BREAKERS ARE ATMOSPHERIC TYPE AND CONFORM TO ASSE STANDARD 1011. LEAD FREE. |
| HB-2 | WALL HYDRANT - FROST FREE | WATTS | HY-420 | - | - | - | - | 3/4 | - | - | - | • | - | - | NON-FREEZE KEY OPERATED WALL HYDRANT WITH CHROME PLATED FACE, INTEGRAL VACUUM BREAKER, ALL BRONZE HEAD, BRONZE WALL CASING, AND LOOSE KEY. COMPLY WITH ASME B1.20.7 AND ASSE 1019-2004 NON-FREEZE HOT AND COLD FAUCET. SEPERATE HOT AND COLD |
| HB-3 | HOSE BIBB - HOT AND COLD | WOODFORD | MODEL 22 | | | - | - | 3/4 | - | 3/4 | - | - | - | - | INLET TUBES TO ALLOW FOR MANUALLY OPERATED TEMPERATURE CONTROL WITH CROSS CONTAMINATION PROTECTION. PRESSURE RELIEF VALVES AND INTEGRAL BACKFLOW PROTECTION DEVICE. ASSE 1019 LISTED AND CSA, UPC APPROVED. |
| FD-1 | FLOOR DRAIN (CONCRETE FLOORS) - SEE NOTE 3 | ZURN | Z415BL | - | - | - | - | - | - | - | - | 3 | 2 | 2 | FLOOR DRAIN, DURA-COATED CAST IRON BODY, COMBINATION INVERTIBLE MEMBRANE CLAMP AND ADJUSTABLE COLLAR W/ SEEPAGE SLOTS AND TYPE BL D.C.C.I., WIDE FLANGED HEAD AND POLISHED NICKEL BRONZE, LIGHT-DUTY STRAINER. |
| TD-1 | TRENCH DRAIN (APPARATUS BAY) | WATTS | DEAD LEVEL D | | - | - | - | - | - | - | - | 4 | - | 2 | PRE-SLOPED TRENCH DRAIN SYSTEM WITH DUCTILE IRON FRAME, UV STABILIZED TALC-FILLED POLYPROPYLENE CHANNELS WITH INTEGRAL 4" NO HUB BOTTOM OR END OUTLETS. SYSTEM SHALL BE FRAME-ANCHORED, WITH GRATING TO SUIT DIN CLASS LOAD RATING. SYSTEM TO INCLUDE FRAME CONNECTORS, GRATE LOCKDOWNS, AND CONSTRUCTION COVERS. |
| FS-1 | FLOOR SINK | ZURN | Z1900 | - | - | - | - | - | - | - | - | 3 | 2 | 2 | 12" X 12" X 6" DEEP CAST IRON BODY AND SQUARE, LIGHT-DUTY GRATE WITH 1/2" SLOTTED OPENINGS, WHITE ACID RESISTING PORCELAIN ENAMEL INTERIOR AND TOP, COMPLETE WITH WHITE ABS ANTI-SPLASH INTERIOR BOTTOM DOME STRAINER. |
| RD-1 | ROOF DRAIN - COMBINATION | ZURN | Z165 | - | - | - | - | - | - | - | - | SEE PLANS FOR SIZES | - | - | COMBINATION ROOF DRAIN AND OVERFLOW DRAIN, DURA-COATED CAST IRON BODIES WITH COMBINATION MEMBRANE FLASHING CLAMP/GRAVEL GUARDS, DOUBLE DECK PLATE, AND LOW SILHOUETTE CAST IRON DOMES. |
| DS-1 | EMERGENCY DRAIN DOWNSPOUT | ZURN | Z199 | - | - | - | - | - | - | - | - | SEE PLANS FOR SIZES | - | - | DOWNSPOUT NOZZLE. ALL NICKEL BRONZE BODY, DECORATIVE FACE OF WALL FLANGE AND OUTLET NOZZLE. |
| NOTES: | TE ALL DDAIN DIDE CITTINGS IN TRADS AND SUPPLIED THAT ARE S | TYDOSED LOCATED MITHING | ANITIES OF ACCESSIBLE CAD | NETS OD DELIND WATER | CLOSETS | | | | | | | | | | |
| 1. CHROME PLA | TE ALL DRAIN PIPE, FITTINGS, P-TRAPS AND SUPPLY LINES THAT ARE E | EAPUSED, LOCATED WITHIN V | ANTHES OR ACCESSIBLE CAB | ME 19 OK REHIND WATER (| LLU3E13. | | | | | | | | | | |

TRIM

MINIMUM CONNECTION SIZES (IN)

HOT WATER

COLD WATER

MOTION SENSOR

SPECIFICATION

architects

REMARKS

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



JULY 2022 AS SHOWN

VAILS GATE FIRE DISTRICT

New Storage Building (Phase I)

New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G GENERAL CONSTRUCTION

FINAL BID DOCUMENT

PLUMBING FIXTURE SCHEDULE AND SPECIFICATIONS


P2 002.00

| EXPANSIO | N TANKS | | | | | | | | | | | | | | | |
|---------------|----------------------------|--------|----------------------------|--|--|--------------------------------------|-----------|--------------------|---------------------|-------------------------------|--|--|--|--|--|--|
| | | | PERFORMA | ANCE/CONSTRUCTION | REQUIREMENTS | EQUIREMENTS EQUIPMENT SPECIFICATIONS | | | | | | | | | | |
| EQUIPMENT NO. | LOCATION | SYSTEM | | SYSTEM DATA | | | | | | OPERATING WEIGHT (LBS.) | | | | | | |
| · | | SERVED | ESTIMATED VOLUME (GAL.) | MAX. OPERATING PRESS. RANGE (PSIG) | MAX. OPERATING TEMP. RANGE (DEG. F) | MNF | MODEL NO. | DIMENSION DIA. x H | WATER CONNECTION | | | | | | | |
| ET-1 | MECH ROOM BUILDING 4.4 150 | | | 150 | 200 | AMTROL | ST-12 | 11" X 15" | 3/4" | 9 | | | | | | |

| ١ | MIXING VALVE | STATION | | | | | | | | | | | | | |
|---|--------------|-----------|-----------------------------|--------------|--------------|-------------|------------|----------------------------|--|--|--|--|--|--|--|
| ı | EQUIPMENT | | BASIS OF DESIGN INFORMATION | | | | | | | | | | | | |
| | NO. | LOCATION | MAXIMUM PRESSURE RANGE | MINIMUM FLOW | MAXIMUM FLOW | MANUFACTUER | MODEL | NOMINAL DIMENSIONS (W X H) | | | | | | | |
| | MV-1 | MECH ROOM | 200 PSI | 0.25 GPM | 32 GPM | LEONARD | PNV-100-LF | 8-1/2" X 9" | | | | | | | |

| INTERCEP | TORS | | | | | | | | |
|-----------|---------------|------------|---------------|-------------------|--------------------------|---------------|---------|-----------------------------------|---|
| EQUIPMENT | | | | | | | | | |
| NO. | LOCATION | FLUID | FLOW (GPM) | CAPACITY (GAL) | INLET AND OUTLET SIZE | MANUFACTUER | MODEL | NOMINAL DIMENSIONS (L X W X H) | REMARKS |
| GT-1 | PANTRY | GREASE | 35 | 70 | 3" | SCHIER | GB2 | 35" X 23" X 13-3/4" | PROVIDE EXTENSION COLLAR AS REQUIRED DEPENDING ON PIPE INVERTS. |
| OS-1 | APPARATUS BAY | OIL | 35 | 350 | 4" | HIGHLAND TANK | HTC 350 | 72" X 42" DIA. | PROVIDE EXTENSION COLLAR AS REQUIRED DEPENDING ON PIPE INVERTS. |
| LT-1 | LAUNDRY ROOM | LINT WASTE | 70 | 45 | 3" | WATTS | LI-807 | 25" X 25" X 20" | LINT INTERCEPTOR TO BE PLACED WITHIN CONCRETE PIT. SEE STRUCTURAL PLANS FOR MORE DETAIL. |

| ١ | WATER HE | EATER [G | AS] | | | | | | | | | | | | | | | | | | | | | | | | |
|---|---------------|-----------|---------------|---------------|---------------|---------------|--------------------|----------------------|-------------------|--------------------|------------------------------|--|---------------------------------|---------------------|-------------------|-----------|------------------------------|-----------------|---------------------------------|--------------------------|---|---------------|-------------------|---------------|-------------|-------------------------|---------|
| 1 | | | | | | BASI | S OF DESIGN INFORM | IATION | | | | EQUIPMENT SPECIFICATIONS MINIMUM PERFORMANCE OF WATER HEATING (NYSECC TABLE C404.2) | | | | | | | | | | | | | | | |
| | EQUIPMENT NO. | LOCATION | SYSTEM SERVED | SYSTEM SERVED | SYSTEM SERVED | SYSTEM SERVEI |)N SYSTEM SERVED | CATION SYSTEM SERVED | N SYSTEM SERVED G | GAS INPUT (BTU) | GAS INLET PRESS. (IN W.C) | EFFICIENCY | RECOVERY GPH AT 100 DEG RISE | WATER CONNECTION | GAS CONNECTION | FLUE SIZE | MNF | MODEL NO. | NOMINAL DIMENSION DIA x H | CAPACITY (GAL) | NOMINAL OPERATING WEIGHT (LBS.) | VOLTS / PHASE | EQUIPMENT TYPE | SIZE CATEGORY | SUBCATEGORY | PERFORMANCE REQUIRED | REMARKS |
| | WH-1 | MECH ROOM | BUILDING | 199,000 | 3.5 - 14 | 97% | 235 | 1-1/2" | 3/4" | 3" | AO SMITH | BTH-199 | 27-3/4" X 76-1/2" | 100 | 523 | 120/1 | STORAGE WATER HEATER, GAS | > 155,000 BTU/H | < 4,000 BTU/H/GAL | 80 PERCENT FFFICIENCY | HEATERS TO INCLUDE: CONCENTRIC VENT KIT; ALARM BELL; CONDENSATE NEUTRALIZATION KIT. | | | | | | |



| CONSULTANTS: |
|--------------|
| |
| |
| |
| |

| Ш | MARK | DATE | DESCRIPTION |
|-----|------|------|-------------|
| | | | |
| | | | |
| | | | |
| Ш | | | |
| -11 | | | |
| Ш | | | |
| Ш | | | |
| П | | | |
| | | | |
| | | | |
| | | | |
| | | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)




872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G **GENERAL CONSTRUCTION**

FINAL BID DOCUMENT

PLUMBING EQUIPMENT SCHEDULE

P2 003.00



H 2 architengin

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

CONSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553


CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT

SHEET TITLE

PLUMBING SITE PLAN -MAIN FIRE HOUSE

PS2 100.00





H 2 architects + engineers

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 - www.h2m.com

CONSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------------|-------------------------|
| 2 | 12/22/2022 | REVS. PER TOWN COMMENTS |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G
GENERAL CONSTRUCTION

FINAL BID DOCUMENT


PARTIAL DOMESTIC WA


PARTIAL DOMESTIC WATER AND GAS FIRST FLOOR PLAN NEW FIRE HOUSE PHASE 2

P2 120A.02

Domestic Water and Gas First Floor Plan - Area A


SCALE: 3/16" = 1'-0"





CONSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G
GENERAL CONSTRUCTION

FINAL BID DOCUMENT


PARTIAL DOMESTIC WATER AND
GAS FIRST FLOOR PLAN
NEW FIRE HOUSE
PHASE 2

P2 120B.00

AREA OF WORK

PROJECT NORTH

Key Plan




H 2 archit

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

| CONSULTANTS: | | | |
|--------------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT


EET TITLE

PARTIAL DOMESTIC WATER AND GAS SECOND FLOOR PLAN NEW FIRE HOUSE PHASE 2

P2 121A.00







| CONSULT | ANTS: | | | |
|---------|-------|--|--|--|
| | | | | |
| | | | | |
| | | | | |
| | | | | |

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G
GENERAL CONSTRUCTION

FINAL BID DOCUMENT


PARTIAL DOMESTIC WATER AND
GAS SECOND FLOOR PLAN
NEW FIRE HOUSE
PHASE 2


P2 121B.00


AREA OF WORK

PROJECT NORTH

Key Plan







CONSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------------|-------------------------|
| 2 | 12/22/2022 | REVS. PER TOWN COMMENTS |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT


PARTIAL SANITARY, VENT &
STORM UNDERSLAB PLAN
NEW FIRE HOUSE
PHASE 2

P2 130A.02

Sanitary, Vent, and Storm Underslab Part Plan - Area A


SCALE: 3/16" = 1'-0"





CONSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I)

New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553


CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT

AREA OF WORK

PARTIAL SANITARY, VENT &
STORM UNDERSLAB PLAN
NEW FIRE HOUSE
PHASE 2

P2 130B.00





H 2 M

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

ONSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------------|-------------------------|
| 2 | 12/22/2022 | REVS. PER TOWN COMMENTS |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553


CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT

PARTIAL SANITARY, VENT & STORM FIRST FLOOR PLAN NEW FIRE HOUSE PHASE 2

P2 131A.02







CONSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I)

New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553


CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT

AREA OF WORK

PARTIAL SANITARY, VENT &
STORM FIRST FLOOR PLAN
NEW FIRE HOUSE
PHASE 2

P2 131B.00





H 2 ard en

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

| CONSULTANTS: | | | |
|--------------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |

| 1 | MARK | DATE | DESCRIPTION |
|---|------|------|-------------|
| ı | | | |
| ı | | | |
| ı | | | |
| ı | | | |
| ı | | | |
| ı | | | |
| ı | | | |
| ı | | | |
| ı | | | |
| ı | | | |
| ı | | | |
| | | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I)
New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT


PARTIAL SANITARY, VENT, & STORM SECOND FLOOR PLAN NEW FIRE HOUSE PHASE 2

P2 132A.00

Sanitary, Vent and Storm Second Floor Part Plan - Part B

SCALE: 3/16" = 1'-0"





| CONSULTANTS: | | |
|--------------|--|--|
| | | |
| | | |
| ı | | |
| | | |
| ı | | |
| ı | | |
| | | |
| ı | | |
| | | |
| | | |

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G
GENERAL CONSTRUCTION

FINAL BID DOCUMENT


PARTIAL SANITARY, VENT & STORM SECOND FLOOR PLAN NEW FIRE HOUSE PHASE 2


P2 132B.00


AREA OF WORK

PROJECT NORTH

Key Plan








| CONSULTANTS: | | | |
|--------------|--|--|--|
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT


PLUMBING
PARTIAL ROOF PLAN
NEW FIRE HOUSE
PHASE 2

P2 140A.00

Plumbing Roof Plan - Part A


SCALE: 3/16" = 1'-0"





| CONSULTANTS: | | |
|--------------|--|--|
| | | |
| | | |
| | | |
| | | |

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553


CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT

PLUMBING
PARTIAL ROOF PLAN
NEW FIRE HOUSE
PHASE 2


Key Plan

P2 140B.00





| PIPE SIZE | ROD SIZE | PIPE SIZE | ROD SIZE |
|----------------|-----------|------------|-----------|
| UP TO 2" | 3/8" DIA. | 4" THRU 5" | 5/8" DIA. |
| 2 1/2" THRU 3" | 1/2" DIA | | |



Pipe Hanger Detail

GAS PIPE TO BE GALVANIZED INSIDE (BACK) OF WALL **VALVE HOUSING INSIDE** OF INTERIOR WALL

WALL CLAMP (IF USED)

FLANGE LOCKSHIELD

SCREWDRIVER STOP

VALVE BODY ANCHOR

REMOVABLE WHEEL

LOCKSHIELD BONNET

HOSE CONNECTION

WATERTIGHT SEAL

WITH WATERHAMMER

HANDLE WITH

ARRESTERS

LAUNDRY ROOM FINISHED FLOOR

SANITARY MAIN. REFER


TO FLOOR PLANS

OR PAINTED FOR CORROSION PROTECTION **GALVANIZED PIPE GUIDE STRAP** STAINLESS STEEL THREADED ROD TO ADJUST HEIGHT OF PIPE PIPE TO LAY DIRECTLY FIELD VERIFY REQUIRED ABOVE ROLLER ROOF SUPPORT PAD WITH **DOUBLE SIDED TAPE**


| SUPPORT OF GAS PIPING | | |
|-----------------------|---------------------------|--|
| SIZE OF PIPE (IN.) | SPACING OF SUPPORTS (FT.) | |
| 1/2 | 6 | |
| 3/4 OR 1 | 8 | |
| 1-1/4 OR LARGER | 10 | |


Roof Pipe Support Detail

SCALE: NTS




Wall Cleanout - Apparatus Bay Detail





FIRE STOPPING NOTES:



THE FIRE STOPPING SYSTEM AND COMPONENTS SHALL BE AS MANUFACTURED BY 3M. NO SUBSTITUTIONS SHALL BE PERMITTED.

ENSURING THAT PENETRATIONS ARE PROPERLY FIRE

1. CONTRACTOR SHALL BE RESPONSIBLE FOR


STOPPED WITH THE FOLLOWING:

METAL PIPES OR CONDUIT THROUGH BLOCK WALL SHALL USE UL SYSTEM NO. CAJ1044 AND 3M PRODUCT CP25 WB & CAULK

METAL PIPES THROUGH GYPSUM WALLS SHALL USE UL SYSTEM NO. WL 1001 AND 3M PRODUCT CP 25 WB & CAULK


Pipe Penetrations Through Fire Rated Walls

SCALE: NTS



1. FINAL VENT STACK OUTLET LOCATION TO BE 15 FEET (MIN.) AWAY FROM ANY OUTSIDE VENTILATION AIR INTAKE LOCATION, 10 FEET (MIN.) FROM ANY WALL OR STRUCTURE AND 3 (MIN.) FEET ABOVE STRUCTURE.

Vent Through Roof



872 Blooming Grove Turnpike New Windsor, NY 12553

architects

DESCRIPTION

538 Broad Hollow Road, 4th Floor East

Melville, NY 11747

631.756.8000 • www.h2m.com

CONTRACT G GENERAL CONSTRUCTION

FINAL BID DOCUMENT

JRM

VGFD2001

ROJECT No:

KJE

JULY 2022

VAILS GATE FIRE

DISTRICT

New Storage Building (Phase I)

New Fire Station (Phase II)

AS SHOWN

PLUMBING DETAILS

P2 500.00

Washing Machine Supply And Drain Box

SCALE: NTS

FINISHED EXTERIOR WALL

WALL BOX FLANGE

SEE ARCH DWGS FOR WALL
TYPE & DIMENSIONS

Freeze Proof Wall Hydrant Detail

SCALE: NTS


CW IN WALL


2" VENT

IN WALL -

GAS METER RIG SHALL BE CONSTRUCTED IN ACCORDANCE WITH ALL REQUIREMENTS OF CENTRAL HUDSON INCLUDING, BUT NOT LIMITING TO; DIMENSIONS, PIPING, FITTINGS, CONNECTIONS, VALVE, CONCRETE PADS, AND BOLLARDS.


Gas Meter With Gas Fired Emergency Generator Detail






Domestic Hot Water Heater Piping With HWR Detail

SCALE: NTS




Elevator Oil Smart Pump Detail



538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

| | 1 | |
|------|------|-------------|
| MARK | DATE | DESCRIPTION |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I)

New Fire Station (Phase II)




872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT G GENERAL CONSTRUCTION

FINAL BID DOCUMENT


PLUMBING PLUMBING DETAILS II

P2 501.00



Domestic Riser Diagram (1 of 2)

SCALE: NTS



Domestic Riser Diagram (2 of 2)

SCALE: NTS

H 2 architect + engineer

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

DNSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553


CONTRACT G
GENERAL CONSTRUCTION


FINAL BID DOCUMENT

SHEET TITLE

PLUMBING DOMESTIC RISER DIAGRAMS NEW FIRE HOUSE PHASE 2

P2 600.00





Sanitary and Vent Riser Diagram (2 of 2)

SCALE: NTS

H 2 architects + engineers

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

CONSULTANTS:

MARK DATE DESCRIPTION



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)




872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT P
PLUMBING CONSTRUCTION

FINAL BID DOCUMENT

PLUMBING SANITARY AND VENT RISER DIAGRAM BUILDING

P2 601.00




H 2 architects + engineers

538 Broad Hollow Road, 4th Floor East Melville, NY 11747 631.756.8000 • www.h2m.com

ONSULTANTS:

| MARK | DATE | DESCRIPTION |
|------|------|-------------|
| | | |
| | | |
| | | |
| | | |
| | · · | |
| | | |
| | | |
| | | |
| | • | |
| | | |
| | | |
| | | |
| | | |



VAILS GATE FIRE DISTRICT

New Storage Building (Phase I) New Fire Station (Phase II)



872 Blooming Grove Turnpike New Windsor, NY 12553

CONTRACT P
PLUMBING CONSTRUCTION

FINAL BID DOCUMENT

HEET TITLE

GAS AND STORM ISOMETRIC RISER DIAGRAMS NEW FIRE HOUSE PHASE 2

P2 602.00