

Alternates for Tarrytown MRI- Project # 15025

1. Changing room benches in rooms W223 and W267
2. Demolish existing MRI control room counter on existing MRI #1 side, replace with Solid Surface Counter of the same finish with wall hung brackets as the new design shows.
3. Furnish and install Pre-Fabricated Roof Catwalk and stair to crossover ductwork in lieu of the catwalk structure in base bid
4. Furnish and install new circuit breaker for Dynamic sag-corrector, replace 100a with 200a
5. Furnish and Install 75kVA Transformer for the GE provided Chiller. Include rigging. See below sketch. Secondary steel to be added and additional platform grating added to dunnage.
6. Furnish and install screening to match existing on roof around location of new chiller/dunnage. See below sketch.

