

### GENERAL ABBREVIATIONS

<b>A</b>	AC	AIR CONDITIONING	L	LAT	LEAVING AIR TEMPERATURE
	AD	ACCESS DOOR	LB	LB	LINEAR BAR DIFFUSER
	AF	ABOVE FINISHED FLOOR	LBD	LBD	LINEAR BAR GRILLE
	AFS	AIR FLOW MEASURING STATION	LBF	LBF	LINEAR FEET
	AHU	AIR HANDLING UNIT	LFD	LFD	LAMINAR AIRFLOW DIFFUSER
	AL	ACOUSTIC LINING	LLD	LLD	LINEAR LOUVER DIFFUSER
	AP	ACCESS PANEL	LLG	LLG	LINEAR LOUVER GRILLE
	ATC	AUTOMATIC TEMPERATURE CONTROL	LSD	LSD	LINEAR SLOT DIFFUSER
	AVB	AIR VOLUME CONTROL BOX	LSS	LSS	LINEAR SLOT GRILLE
	AWT	AVERAGE WATER TEMPERATURE	LVD	LVD	LINEAR VARIABLE VOLUME DIFFUSER
			LVG	LVG	LINEAR VARIABLE VOLUME GRILLE
			LWT	LWT	LEAVING WATER TEMPERATURE
<b>B</b>			M		
	BD	BAROMETRIC DAMPER	MBH	THOUSAND BTU'S PER HOUR	
	BDD	BACKDRAFT DAMPER	MH	MANHOLE	
	BFP	BACKFLOW PREVENTER	MOD	MOTOR OPERATED DAMPER	
	BHP	BRAKE HORSEPOWER	N		
	BOD	BOTTOM OF DUCT	(N)	NEW	
	BOP	BOTTOM OF PIPE	NC	NORMALLY CLOSED	
	BSC	BIO SAFETY CABINET	NIC	NOT IN CONTRACT	
	BT	BUCKET TRAP	NO	NORMALLY OPEN	
	BTU	BRITISH THERMAL UNITS	NTS	NOT TO SCALE	
	BTUH	BTU'S PER HOUR	O		
<b>C</b>			OA	OUTSIDE AIR	
	CC	COOLING COIL	OBD	OPPOSED BLADE DAMPER	
	CD	CEILING DIFFUSER	P		
	CDR	CEILING DIFFUSER, ROUND	PD	PANEL DIFFUSER	
	CFM	CUBIC FEET PER MINUTE	PF	PERFORATED FACE DIFFUSER	
	CL	CENTERLINE	PFG	PERFORATED FACE GRILLE	
	CUH	CABINET UNIT HEATER	PHC	PREHEAT COIL	
	CVE	CONSTANT VOLUME EXHAUST	PRV	PRESSURE REDUCING VALVE	
	CVR	CONSTANT VOLUME RETURN	PSI	POUNDS PER SQUARE INCH	
	CVS	CONSTANT VOLUME SUPPLY	R		
<b>D</b>			(R)	REMOVE	
	D	DEAERATOR	RA	RETURN AIR	
	DB	DRY BULB	RG	RETURN GRILLE	
	DIA	DIAMETER	RFG	RECTANGULAR FILTER GRILLE	
	DFD	DYNAMIC FIRE DAMPER WITH ACCESS DOOR	RH	RELATIVE HUMIDITY	
	DN	DOWN	RHC	REHEAT COIL	
	DPT	DIFFERENTIAL PRESSURE TRANSMITTER	RHP	RADIANT HEATING PANEL	
	DV	DRAIN VALVE	RPM	REVOLUTIONS PER MINUTE	
<b>E</b>			RR	RETURN REGISTER	
	E	EXHAUST AIR	S		
	EAC	EXHAUST AIR CONTROLLER	SA	SUPPLY AIR	
	EAT	ENTERING AIR TEMPERATURE	SAC	SUPPLY AIR CONTROLLER	
	EF	EXHAUST FAN	SAT	SOUND ATTENUATOR	
	EG	EXHAUST GRILLE	SD	SMOKE DAMPER WITH ACCESS DOOR	
	EJ	EXPANSION JOINT	SD/FD	COMBINATION SMOKE/FIRE DAMPER	
	EJB	EXPANSION JOINT, BELLOWS TYPE	SG	SUPPLY GRILLE	
	EJO	EXPANSION JOINT, OFFSET TYPE	SP	STATIC PRESSURE	
	EL	ELEVATION	SR	STATIC REGISTER	
	ER	EXHAUST REGISTER	SS	STAINLESS STEEL	
	ERV	EXHAUST ROOF VENTILATOR	SV	STEAM VENT	
	ESP	EXTERNAL STATIC PRESSURE	T		
	ET	ELEPHANT TRUNK	TG	TRANSFER GRILLE	
	EWT	ENTERING WATER TEMPERATURE	TOD	TOP OF DUCT	
	EXF	EXFILTRATION	TOP	TOP OF PIPE	
	EXH	EXHAUST	TSP	TOTAL STATIC PRESSURE	
<b>F</b>			TT	THERMOSTATIC TRAP	
	°F	DEGREE FAHRENHEIT	TYP	TYPICAL	
	FC	FLEXIBLE CONNECTION	U		
	FCU	FAN COIL UNIT	UH	UNIT HEATER	
	F.D.	FLOOR DRAIN	UTR	UP THRU ROOF	
	FD	FIRE DAMPER WITH ACCESS DOOR	V		
	FH	FUME HOOD	VAV	VARIABLE AIR VOLUME BOX	
	FHE	FUME HOOD EXHAUST	VD	VOLUME DAMPER	
	FOB	FLAT ON BOTTOM	VI	VIBRATION ISOLATOR	
	FOT	FLAT ON TOP	VVE	VARIABLE VOLUME EXHAUST	
	F&T	FLOAT & THERMOSTATIC TRAP	VVF	VARIABLE VOLUME FAN POWERED	
	FPM	FEET PER MINUTE	VVR	VARIABLE VOLUME RETURN	
	FTR	FINNED TUBE RADIATION	VVS	VARIABLE VOLUME SUPPLY	
	FZP	FREEZE PROTECTION PUMP	W		
<b>G</b>			WB	WET BULB	
	GAL	GALLONS	WG	WATER GAUGE	
	GPH	GALLONS PER HOUR	WMS	WIRE MESH SCREEN	
	GPM	GALLONS PER MINUTE			
	GR	GRILLE			
	GRV	GRAVITY ROOF VENT			
<b>H</b>					
	HC	HEATING COIL			
	HP	HORSEPOWER			
	HX	HEAT EXCHANGER			
<b>I</b>					
	INF	INFILTRATION			

### PIPING SYMBOLS

	AIR OR STEAM VENT WITH MANUAL SERVICE VALVE DIAMETER
	DIRECTION OF FLOW
	EXPANSION JOINT, BELLOWS
	EXPANSION JOINT, OFFSET
	EXPANSION LOOP
	FLEXIBLE CONNECTION
	FLOW METER
	DIFFERENTIAL PRESSURE TRANSMITTER
	PIPE ANCHOR
	PIPE GUIDE
	PITCH OF PIPE, DOWN
	PRESSURE GAUGE AND VALVE
	PRESSURE / TEMPERATURE PLUG
	REDUCER, CONCENTRIC
	REDUCER, ECCENTRIC STRAIGHT CROWN
	REDUCER, ECCENTRIC STRAIGHT INVERT
	RISER OR ELBOW DOWN
	RISER UP AND DOWN ELBOW UP
	STEAM TRAP
	STRAINER
	STRAINER W/GATE VALVE W/NIPPLE & CAP
	THERMOMETER
	THERMOMETER WELL
	THERMOSTAT
	UNION OR FLANGED CONNECTION
	VALVE, AUTOMATIC FLOW CONTROL
	VALVE, BALANCING
	VALVE, CHECK
	VALVE, CHECK NON-SLAM
	VALVE, DRAIN W/NIPPLE & CAP
	VALVE, NEEDLE
	VALVE, PRESSURE REGULATING
	VALVE, RELIEF (SAFETY)
	VALVE, SHUT-OFF
	VALVE, SHUT-OFF LOCK SHIELD
	VALVE, SOLENOID
	VALVE, THROTTLING
	VALVE, THREE-WAY CONTROL
	VALVE, THREE-WAY CONTROL
	VALVE, TRIPLE DUTY
	VALVE, TWO-WAY CONTROL
	VALVE, TWO-WAY CONTROL

### PIPING NOMENCLATURE

— BBD —	BOILER BLOW DOWN
— CHF —	CHEMICAL FEED
— CHWR —	CHILLED WATER RETURN
— CHWS —	CHILLED WATER SUPPLY
— CWR —	CONDENSER WATER RETURN (TO TOWER)
— CWS —	CONDENSER WATER SUPPLY (FROM TOWER)
— CZR —	CONTROLLED ZONE RETURN
— CZS —	CONTROLLED ZONE SUPPLY
— D —	DRAIN LINE
— DTR —	DUAL TEMPERATURE RETURN
— DTS —	DUAL TEMPERATURE SUPPLY
— FOF —	FUEL OIL FILL
— FOG —	FUEL OIL GAUGE
— ECHWR —	EMERGENCY CHILLED WATER RETURN
— ECHWS —	EMERGENCY CHILLED WATER SUPPLY
— FOR —	FUEL OIL RETURN
— FOS —	FUEL OIL SUPPLY
— FOV —	FUEL OIL VENT
— FW —	BOILER FEED WATER
— G —	GAS
— GR —	GLYCOL RETURN
— GS —	GLYCOL SUPPLY
— HPC —	HIGH PRESSURE CONDENSATE
— HPS —	HIGH PRESSURE STEAM
— HRR —	HEAT RECOVERY RETURN
— HRS —	HEAT RECOVERY SUPPLY
— HTWR —	HIGH TEMPERATURE WATER RETURN
— HTWS —	HIGH TEMPERATURE WATER SUPPLY
— HWR —	HEATING WATER RETURN
— HWS —	HEATING WATER SUPPLY
— LCHWR —	LOW TEMPERATURE CHILLED WATER RETURN
— LCHWS —	LOW TEMPERATURE CHILLED WATER SUPPLY
— LPC —	LOW PRESSURE CONDENSATE
— LPS —	LOW PRESSURE STEAM
— LPS* —	LOW PRESSURE STEAM LINE RATED FOR MEDIUM PRESSURE INCLUDING ALL TRAPS AND ACCESSORIES
— MPC —	MEDIUM PRESSURE CONDENSATE
— MPS —	MEDIUM PRESSURE STEAM
— MU —	MAKE-UP WATER (FROM DOMESTIC COLD WATER)
— PCHWR —	PRIMARY CHILLED WATER RETURN
— PCHWS —	PRIMARY CHILLED WATER SUPPLY
— PC —	PUMPED CONDENSATE A/C DRAIN
— PCR —	PUMPED CONDENSATE STEAM CONDENSATE RETURN
— RG —	REFRIGERANT HOT GAS
— RHR —	REHEAT WATER RETURN
— RHS —	REHEAT WATER SUPPLY
— RL —	REFRIGERANT LIQUID
— RS —	REFRIGERANT SUCTION
— V —	VENT, ATMOSPHERIC

### DRAWING INDEX

DRAWINGS		30% SUBMISSION	50% SUBMISSION	80% SUBMISSION	100% SUBMISSION	100% PFA SUBMISSION
M001	HVAC INDEX SHEET	X	X	X	X	X
M002	HVAC INDEX SHEET	X	X	X	X	X
M003	HVAC GENERAL NOTES	X	X	X	X	X
M004	HVAC LOGISTICS AND TEMPORARY SERVICES	X	X	X	X	X
MDH1B3	BASEMENT FLOOR PLAN B3 - DUCTWORK - DEMOLITION	X	X	X	X	X
MDP1B3	BASEMENT FLOOR PLAN B3 - PIPING - DEMOLITION	X	X	X	X	X
MDH1B2	BASEMENT FLOOR PLAN B2 - DUCTWORK - DEMOLITION	X	X	X	X	X
MDP1B2	BASEMENT FLOOR PLAN B2 - PIPING - DEMOLITION	X	X	X	X	X
MDH1B1	BASEMENT FLOOR PLAN B1 - DUCTWORK - DEMOLITION	X	X	X	X	X
MDP1B1	BASEMENT FLOOR PLAN B1 - PIPING - DEMOLITION	X	X	X	X	X
MDH110	FIRST FLOOR PLAN - DUCTWORK - DEMOLITION	X	X	X	X	X
MDP110	FIRST FLOOR PLAN - PIPING - DEMOLITION	X	X	X	X	X
MDH120	SECOND FLOOR PLAN AND ATTIC PARTIAL PLANS - DUCTWORK - DEMOLITION	X	X	X	X	X
MDP120	SECOND FLOOR PLAN - PIPING - DEMOLITION	X	X	X	X	X
MDH130	THIRD FLOOR PLAN - DUCTWORK - DEMOLITION	X	X	X	X	X
MDP130	THIRD FLOOR PLAN - PIPING - DEMOLITION	X	X	X	X	X
MDH140	ATTIC PLAN - DUCTWORK - DEMOLITION	X	X	X	X	X
MDP140	ATTIC PLAN - PIPING - DEMOLITION	X	X	X	X	X
MD401	CULLUM SERVICE YARD PLAN - HVAC - DEMOLITION	X	X	X	X	X
MH1B3	BASEMENT FLOOR PLAN B3 - DUCTWORK	X	X	X	X	X
MP1B3	BASEMENT FLOOR PLAN B3 - PIPING	X	X	X	X	X
MH1B2	BASEMENT FLOOR PLAN B2 - DUCTWORK	X	X	X	X	X
MP1B2	BASEMENT FLOOR PLAN B2 - PIPING	X	X	X	X	X
MH1B1	BASEMENT FLOOR PLAN B1 - DUCTWORK	X	X	X	X	X
MP1B1	BASEMENT FLOOR PLAN B1 - PIPING	X	X	X	X	X
MH110	FIRST FLOOR PLAN - DUCTWORK	X	X	X	X	X
MP110	FIRST FLOOR PLAN - PIPING	X	X	X	X	X
MH120	SECOND FLOOR PLAN - DUCTWORK	X	X	X	X	X
MP120	SECOND FLOOR PLAN - PIPING	X	X	X	X	X
MH130	THIRD FLOOR PLAN - DUCTWORK	X	X	X	X	X
MP130	THIRD FLOOR PLAN - PIPING	X	X	X	X	X
MH140	ATTIC PLAN - DUCTWORK	X	X	X	X	X
MP140	ATTIC PLAN - PIPING	X	X	X	X	X
M301	SECTIONS - HVAC	X	X	X	X	X
M302	SECTIONS - HVAC	X	X	X	X	X
M303	SECTIONS - HVAC	X	X	X	X	X
M304	SECTIONS - HVAC	X	X	X	X	X
M305	SECTIONS - HVAC	X	X	X	X	X
M306	SECTIONS - HVAC	X	X	X	X	X
M401	ENLARGED LOWER MECH ROOM - DUCTWORK	X	X	X	X	X
M402	ENLARGED UPPER MECH ROOM AND NORTH SERVICE YARD - DUCTWORK	X	X	X	X	X
M403	CULLUM SERVICE YARD PLAN - HVAC ABOVE DUNNAGE	X	X	X	X	X
M404	ENLARGED LOWER MECH ROOM - PIPING	X	X	X	X	X
M405	ENLARGED UPPER MECH ROOM AND NORTH SERVICE YARD - PIPING	X	X	X	X	X
M501	DETAILS - HVAC	X	X	X	X	X
M502	DETAILS - HVAC	X	X	X	X	X
M503	DETAILS - HVAC	X	X	X	X	X
M504	DETAILS - HVAC	X	X	X	X	X
M505	DETAILS - HVAC	X	X	X	X	X
M506	DETAILS - HVAC	X	X	X	X	X
M601	SCHEDULES - HVAC	X	X	X	X	X
M602	SCHEDULES - HVAC	X	X	X	X	X
M603	SCHEDULES - HVAC	X	X	X	X	X
M604	SCHEDULES - HVAC	X	X	X	X	X
M605	SCHEDULES - HVAC	X	X	X	X	X
MT01	FLOW DIAGRAMS - HVAC	X	X	X	X	X
MT02	FLOW DIAGRAMS - HVAC	X	X	X	X	X
MT03	FLOW DIAGRAMS - HVAC	X	X	X	X	X
MT04	FLOW DIAGRAMS - HVAC	X	X	X	X	X
MT05	FLOW DIAGRAMS - HVAC	X	X	X	X	X
MT06	FLOW DIAGRAMS - HVAC	X	X	X	X	X
M801	HVAC CONTROLS	X	X	X	X	X
M802	HVAC CONTROLS	X	X	X	X	X
M803	HVAC CONTROLS	X	X	X	X	X
M804	HVAC CONTROLS	X	X	X	X	X
M805	HVAC CONTROLS	X	X	X	X	X
M806	HVAC CONTROLS	X	X	X	X	X
M807	HVAC CONTROLS	X	X	X	X	X
M808	HVAC CONTROLS	X	X	X	X	X
M809	HVAC CONTROLS	X	X	X	X	X
M810	HVAC CONTROLS	X	X	X	X	X
M811	HVAC CONTROLS	X	X	X	X	X
M812	HVAC CONTROLS	X	X	X	X	X
M813	HVAC CONTROLS	X	X	X	X	X
M814	HVAC CONTROLS	X	X	X	X	X
M815	HVAC CONTROLS	X	X	X	X	X
M816	HVAC CONTROLS	X	X	X	X	X
M817	HVAC CONTROLS	X	X	X	X	X

**US Army Corps of Engineers**

DESIGNED BY: [Name] CHECKED BY: [Name] SUBMITTED BY: [Name]	ISSUE DATE: 2/11/2021 CONTRACT NO.: W912DS-19-C-0031 PROJECT NO.: 20190494
---	--

**JACOBS / EWING COLE** A Joint Venture

WEST POINT, NY  
USMA BUILDING 605 CULLUM HALL RENOVATION


HVAC INDEX SHEET

SHEET ID  
**M001**











**B4** BASEMENT B3 FLOOR PLAN - DUCTWORK - DEMOLITION  
SCALE: 1/8" = 1'-0"


**GENERAL DEMOLITION NOTES:**

- REMOVE ALL HVAC DUCTWORK, AIR DEVICES, PIPING, CONTROLS, AND EQUIPMENT NO LONGER REQUIRED DUE TO NEW WORK. PERFORM ALL DEMOLITION REQUIRED TO COORDINATE WITH NEW WORK. REFER TO NEW WORK PLANS.
- OFFER ALL REMOVED EQUIPMENT TO GOVERNMENT AND DELIVER TO A LOCATION AS DIRECTED BY GOVERNMENT.
- REMOVE ALL DEMOLISHED DUCTWORK, PIPING, EQUIPMENT (REFUSED BY GOVERNMENT) AND ACCESSORIES FROM SITE AND PROPERLY DISPOSE OF MATERIALS IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL CODES AND ORDINANCES.
- REMOVE ALL STEAM AND CONDENSATE PIPING THROUGHOUT CULLUM HALL.
- REMOVE ALL STEAM RADIATORS, STEAM CONNECTORS, AND STEAM COILS THROUGHOUT CULLUM HALL. REMOVE ALL ASSOCIATED STEAM TRAPS, ACCESSORIES, AND TRIM.
- REMOVE ALL CONTROL PANELS, CONTROL WIRING, TUBING, AND DEVICES NO LONGER REQUIRED DUE TO EQUIPMENT REMOVALS. PROPERLY SEAL OPENINGS IN CONTROL TUBING SERVING EXISTING AREAS TO REMAIN. REWIRE BAS SERIAL NETWORKS TO MAINTAIN CONTINUITY. T-TAPS & SPLICES ARE NOT PERMITTED IN BAS NETWORKS.
- FOR ALL DUCTWORK SHOWN TO BE REMOVED, REMOVE ALL ASSOCIATED HANGERS, SUPPORTS, INSULATION, VOLUME DAMPERS AND FIRE DAMPERS.
- FOR ALL EQUIPMENT SHOWN TO BE REMOVED, REMOVE ALL ASSOCIATED EQUIPMENT SUPPORTS, CURBS, PADS, AND RAILS.
- REMOVE AND REPLACE EXISTING HANGERS WITH NEW HANGERS AND MISCELLANEOUS HARDWARE AS REQUIRED TO ACCOMMODATE NEW WORK.
- PROVIDE FILTRATION EQUIPMENT, FILTERS, FANS, ETC. REQUIRED TO PREVENT CONSTRUCTION DEBRIS FROM SPREADING TO CLEAN AREAS OR TO BUILDING AIR HANDLING EQUIPMENT.



PLAN NORTH



 US Army Corps of Engineers ©	
	DATE
	MARK DESCRIPTION
DESIGNED BY: WJF DRAWN BY: WJF CHECKED BY: WJF SUBMITTED BY: WJF	ISSUE DATE: 2/11/2021 MODIFICATION NO.: 0 CONTRACT NO.: W912DS-19-C0031 PROJECT NO.: 20190494
US ARMY CORPS OF ENGINEERS  <b>JACOBS / EWING COLE</b> A Joint Venture	
WEST POINT, NY USMA BUILDING 605 CULLUM HALL RENOVATION  BASEMENT FLOOR PLAN B3 - DUCTWORK - DEMOLITION	
SHEET ID <b>MDH1B3</b>	



















1 2 3 4 5 6 7 8 9 10

G  
F  
E  
D  
C  
B  
A



**F9** NORTH ATTIC PARTIAL PLAN  
SCALE: 1/8" = 1'-0"



**B1** SOUTH ATTIC PARTIAL PLAN  
SCALE: 1/8" = 1'-0"




**B4** SECOND FLOOR PLAN - DUCTWORK - DEMOLITION  
SCALE: 1/8" = 1'-0"

**GENERAL DEMOLITION NOTES:**

1. REMOVE ALL HVAC DUCTWORK, AIR DEVICES, PIPING, CONTROLS, AND EQUIPMENT NO LONGER REQUIRED DUE TO NEW WORK. PERFORM ALL DEMOLITION REQUIRED TO COORDINATE WITH NEW WORK. REFER TO NEW WORK PLANS.
2. OFFER ALL REMOVED EQUIPMENT TO GOVERNMENT AND DELIVER TO A LOCATION AS DIRECTED BY GOVERNMENT.
3. REMOVE ALL DEMOLISHED DUCTWORK, PIPING, EQUIPMENT (REFUSED BY GOVERNMENT) AND ACCESSORIES FROM SITE AND PROPERLY DISPOSE OF MATERIALS IN ACCORDANCE WITH ALL FEDERAL, STATE AND LOCAL CODES AND ORDINANCES.
4. REMOVE ALL STEAM AND CONDENSATE PIPING THROUGHOUT CULLUM HALL.
5. REMOVE ALL STEAM RADIATORS, STEAM CONVICTORS, AND STEAM COILS THROUGHOUT CULLUM HALL. REMOVE ALL ASSOCIATED STEAM TRAPS, ACCESSORIES, AND TRIM.
6. REMOVE ALL CONTROL PANELS, CONTROL WIRING, TUBING, AND DEVICES NO LONGER REQUIRED DUE TO EQUIPMENT REMOVALS. PROPERLY SEAL OPENINGS IN CONTROL TUBING SERVING EXISTING AREAS TO REMAIN. REWIRE BAS SERIAL NETWORKS TO MAINTAIN CONTINUITY. T-TAPS & SPLICES ARE NOT PERMITTED IN BAS NETWORKS.
7. FOR ALL DUCTWORK SHOWN TO BE REMOVED, REMOVE ALL ASSOCIATED HANGERS, SUPPORTS, INSULATION, VOLUME DAMPERS AND FIRE DAMPERS.
8. FOR ALL EQUIPMENT SHOWN TO BE REMOVED, REMOVE ALL ASSOCIATED EQUIPMENT SUPPORTS, CURBS, PADS, AND RAILS.
9. REMOVE AND REPLACE EXISTING HANGERS WITH NEW HANGERS AND MISCELLANEOUS HARDWARE AS REQUIRED TO ACCOMMODATE NEW WORK.
10. PROVIDE FILTRATION EQUIPMENT, FILTERS, FANS, ETC. REQUIRED TO PREVENT CONSTRUCTION DEBRIS FROM SPREADING TO CLEAN AREAS OR TO BUILDING AIR HANDLING EQUIPMENT.

**SHEET NOTES:**

- ① REMOVE EXISTING GRILLE, CAP DUCT BEHIND OPENING, PROVIDE FIRE RATED PATCH IN OPENING AND FINISH TO MATCH ADJACENT WALL.
- ② REMOVE ALL DUCTWORK IN THIS AREA.



MARK	DESCRIPTION	DATE

DESIGNED BY: WJF	ISSUE DATE: 2/11/2021
DRAWN BY: WJF	REVISION NO.:
CHECKED BY: WJF	CONTRACT NO.:
SUBMITTED BY: WJF	PROJECT NO.:
SIZE: ANSI D	

US ARMY CORPS OF ENGINEERS

**JACOBS / EWING COLE** A Joint Venture

WEST POINT, NY  
USMA BUILDING 605 CULLUM HALL RENOVATION  
SECOND FLOOR PLAN AND ATTIC PARTIAL PLANS  
- DUCTWORK - DEMOLITION

**SHEET ID**  
**MDH120**





































**B4** THIRD FLOOR PLAN - PIPING  
SCALE: 1/8" = 1'-0"

**GENERAL NOTES:**

- CONDUIT ROUTING FOR SPACE SENSORS MUST BE MINIMIZED TO THE FULLEST EXTENT POSSIBLE IN DESIGNATED HISTORIC AREAS AS INDICATED ON THE ARCHITECTURAL DRAWING A-005. CONDUIT MUST BE ROUTED HORIZONTALLY THROUGH THE LEVEL BELOW HISTORIC AREAS TO SERVE DEVICES WITHIN THOSE SPACES. WHENEVER POSSIBLE, RUN CONDUIT HORIZONTALLY ALONG BASEBOARDS, AND VERTICALLY ALONG ARCHITECTURAL FEATURES LIKE PILASTERS OR DOOR FRAMES. CONDUIT MUST BE CONCEALED AND PAINTED TO MATCH SURROUNDING. CONTRACTOR MUST SUBMIT COORDINATED DRAWINGS AS SPECIFIED IN 013000 FOR APPROVAL PRIOR TO ROUGH-IN. REFER TO ARCHITECTURAL DRAWING A-005 FOR ADDITIONAL CONDUIT ROUTING REQUIREMENTS.
- IT IS NOT PERMITTED TO ANCHOR TO, OR SUPPORT FROM THE EXISTING CLAY TILE ARCH FLOOR CONSTRUCTION UTILITIES, DUCTWORK, PIPING, OR EQUIPMENT, ETC. MUST BE SUPPORTED BY SECONDARY FRAMING, ATTACHED TO THE EXISTING PRIMARY STEEL FLOOR FRAMING. DESIGN OF SECONDARY FRAMING AND CONNECTIONS TO STEEL MUST BE PERFORMED BY THE CONTRACTOR'S LICENSED ENGINEER. REFER TO TYPICAL DETAIL E5/S-504 AND RELATED SPECIFICATIONS.



PLAN NORTH



US Army Corps of Engineers ©

MARK	DESCRIPTION	DATE


DESIGNED BY: WJF	ISSUE DATE: 2/11/2021
DRAWN BY: WJF	REVISION NO: 01
CHECKED BY: WJF	CONTRACT NO: W912DS-19-C0031
SUBMITTED BY: WJF	PROJECT NO: 20190494
SIZE: ANSI D	

USMA BUILDING 605 CULLUM HALL RENOVATION  
THIRD FLOOR PLAN - PIPING


SHEET ID  
**MP130**









**D1** CH-301 SHARED UTILITY NORTH VIEW  
SCALE: 1/4" = 1'-0"




**D4** CH-302 SHARED UTILITY EAST VIEW  
SCALE: 1/4" = 1'-0"




**D7** LINEAR SLOT DIFFUSER COVE  
SCALE: 1/4" = 1'-0"



**A1** CH-301 SHARED UTILITY WEST VIEW  
SCALE: 1/4" = 1'-0"



**A4** CH-302 SHARED UTILITY NORTH VIEW  
SCALE: 1/4" = 1'-0"




**A7** UNDER STAGE WEST VIEW  
SCALE: 1/4" = 1'-0"


<p>US Army Corps of Engineers ©</p>	
	DATE
	DESCRIPTION
	MARK
DESIGNED BY: WJF DRAWN BY: WJF CHECKED BY: WJF SUBMITTED BY: WJF	ISSUE DATE: 2/11/2021 MODIFICATION NO.: 1 CONTRACT NO.: W912DS-19-C0031 PROJECT NO.: 20190494
US ARMY CORPS OF ENGINEERS  <b>JACOBS / EWING COLE</b> A Joint Venture	
WEST POINT, NY USMA BUILDING 605 CULLUM HALL RENOVATION	SECTIONS - HVAC
SHEET ID  <b>M301</b>	




**SHEET NOTES:**  
 ① REFRIGERANT PIPING BY COLDBOX MANUFACTURER. SUGGESTED PIPING PATH INTO BUILDING.  
 ② UNISTRUT MOUNTED BAS PANEL (JACE) INTERFACE.




**D2 MECHANICAL ROOM NORTH VIEW DUCTWORK**  
 SCALE: 1/4" = 1'-0"



**D7 MECHANICAL ROOM WEST VIEW DUCTWORK**  
 SCALE: 1/4" = 1'-0"



**A2 MECHANICAL ROOM NORTH VIEW PIPING**  
 SCALE: 1/4" = 1'-0"



**A7 MECHANICAL ROOM WEST VIEW PIPING**  
 SCALE: 1/4" = 1'-0"

 <b>US Army Corps of Engineers</b> of Engineers ©	
	DATE
	MARK
	DESCRIPTION
DESIGNED BY: WMP DRAWN BY: WMP CHECKED BY: WMP SUBMITTED BY: WMP	ISSUE DATE: 2/11/2021 REVISION NO.: 1 CONTRACT NO.: W912DS-19-C-0031 PROJECT NO.: 20190494
US ARMY CORPS OF ENGINEERS <b>JACOBS / EWING COLE</b> A Joint Venture	
WEST POINT, NY USMA BUILDING 605 CULLUM HALL RENOVATION SECTIONS - HVAC	
SHEET ID <b>M303</b>	














1 2 3 4 5 6 7 8 9 10

G  
F  
E  
D  
C  
B  
A




**SHEET NOTES:**

① SPACE ALLOCATED FOR COLD BOX EQUIPMENT. REFER TO ARCHITECTURAL DRAWINGS.



**GENERAL NOTES:**

1. IT IS NOT PERMITTED TO ANCHOR TO, OR SUPPORT FROM THE EXISTING CLAY TILE ARCH FLOOR CONSTRUCTION. UTILITIES, DUCTWORK, PIPING, OR EQUIPMENT, ETC. MUST BE SUPPORTED BY SECONDARY FRAMING. ATTACHED TO THE EXISTING PRIMARY STEEL FLOOR FRAMING. DESIGN OF SECONDARY FRAMING AND CONNECTIONS TO STEEL MUST BE PERFORMED BY THE CONTRACTOR'S LICENSED ENGINEER. REFER TO TYPICAL DETAIL E5/S-504 AND RELATED SPECIFICATIONS.

**A4** ENLARGED SERVICE YARD HVAC ABOVE DUNNAGE  
SCALE: 1/4" = 1'-0"



PLAN NORTH



MARK	DESCRIPTION	DATE

DESIGNED BY: WJF	ISSUE DATE: 2/11/2021
DRAWN BY: SCA	REVISION NO: 01
CHECKED BY: WJF	CONTRACT NO.:
SUBMITTED BY: BK	PROJECT NO.:
SIZE: ANSI D	

US ARMY CORPS OF ENGINEERS

**JACOBS / EWING COLE** A Joint Venture

WEST POINT, NY  
USMA BUILDING 605 CULLUM HALL RENOVATION

CULLUM SERVICE YARD PLAN - HVAC ABOVE DUNNAGE

**SHEET ID**

**M403**









G  
F  
E  
D  
C  
B  
A

**E1 10 GALLON WATER TREATMENT BYPASS FEEDER PIPING**  
M501 WITH BAG FILTER




- NOTES:**
1. VERTICAL FLOOR MOUNTED TANK SHOWN. PIPING FOR HORIZONTAL TANK SIMILAR.
  2. FOR MULTIPLE TANKS PROVIDE PRESSURE GAUGE W/ NEEDLE VALVE AND LOCK SHIELD SHUTOFF VALVE IN BRANCH CONNECTION TO EACH TANK.

**C1 EXPANSION, PURGE & VENT SYSTEM**  
M501




**A1 DRIP PAN ELBOW AND EXHAUST HEAD**  
M501

**E5 END SUCTION PUMP PIPING**  
M501 WITH ISOLATION BASE




- NOTES:**
1. ALL AUXILIARIES LINE SIZE.
  2. SUCTION DIFFUSER MUST BE BY PUMP MANUFACTURER. MAX PRESSURE DROP 3 PSI (7 FT HD)
  3. BALANCING VALVE MUST BE MANUAL FLOW CONTROL WITH FLOW ORIFICE (VENTURI). USE BUTTERFLY VALVES FOR 3" AND LARGER.



- NOTES:**
1. REFER TO SPECIFICATION 23 05 00 FOR SUPPORT SPACING AND ADDITIONAL REQUIREMENTS


**C5 PIPE SUPPORT DETAILS**  
M501




- NOTES:**
1. PAD DIMENSIONS AND ANCHOR BOLTS TO SUIT EQUIPMENT

**A5 FOUNDATION PAD - TYPE 1**  
M501

**E8 HOT WATER CABINET UNIT HEATER PIPING**  
M501




- NOTES:**
1. VERTICAL UNIT SHOWN. HORIZONTAL UNIT SIMILAR, EXCEPT VALVES OUTSIDE OF ENCLOSURE WHERE LOCATED IN CEILING SPACE OR WHERE PIPING IS EXPOSED.
  2. ALL BRANCH PIPING 3/4" UNLESS OTHERWISE NOTED ON DRAWINGS. PROVIDE FULL LINE SIZE RADIATOR VALVE. PROVIDE 1/2" BALANCING VALVE WHERE FLOW RATE IS 1.3 GPM OR LESS AND FULL LINE SIZE BALANCING VALVE WHERE FLOW RATE IS GREATER.



- NOTES:**
1. ALL TRANSFER DUCT TERMINATIONS MUST HAVE GRILLES ON BOTH ENDS EXCEPT WHERE TERMINATION IS CONCEALED ABOVE A CEILING.
  2. TRANSFER GRILLE SIZE MUST BE EQUIVALENT TO TRANSFER DUCT SIZE.

**C8 NON-ACOUSTICALLY LINED TRANSFER DUCT DETAILS**  
M501



- NOTES:**
1. LENGTH OF SOFT TUBING TO BE SUFFICIENT FOR ACCESS OF PANEL.
  2. PROVIDE FULL LINE SIZE SHUTOFF VALVE AND STRAINER. PROVIDE 1/2" BALANCING VALVE WHERE FLOW RATE IS 1.3 GPM OR LESS AND FULL LINE SIZE BALANCING VALVE WHERE FLOW RATE IS GREATER.
  3. PROVIDE MANUAL AIR VENT AS REQUIRED WHERE HWS/R MAINS ARE INSTALLED AT A LOWER ELEVATION THAN THE RADIANT CEILING PANEL.

**A8 HOT WATER RADIANT CEILING PANELS**  
M501

**US Army Corps of Engineers**

ISSUE DATE: 2/11/2021  
 DESIGN BY: [blank]  
 CHECKED BY: [blank]  
 SUBMITTED BY: [blank]


CONTRACT NO.: W912DS-19-C0031  
 PROJECT NO.: 20190494

WEST POINT, NY  
 USMA BUILDING 605 CULLUM HALL RENOVATION


DETAILS - HVAC

**SHEET ID**  
M501

G  
F  
E  
D  
C  
B  
A




**E1 SINGLE STEAM PRESSURE REDUCING STATION**  
M502




**NOTES:**  
1. WHERE TWO CONTROL VALVES ARE SHOWN, SPECIFIED OR REQUIRED, INSTALL BOTH AT SAME ELEVATION PIPED AS SHOWN FOR SINGLE VALVE WITH COMMON BYPASS FOR BOTH VALVES (SEE DIAGRAM ABOVE). MAKE BYPASS ONE PIPE SIZE LARGER THAN LARGER CONTROL VALVE.  
2. STRAINER IN BYPASS REQUIRED FOR INNER STEAM DISTRIBUTING TUBE COIL ONLY. TURN STRAINER ON ITS SIDE.  
3. PROVIDE STRAINER WITH 3/4" NORMALLY OPEN VALVE AND STEAM TRAP PIPED TO CONDENSATE RETURN WHERE HORIZONTAL DISTANCE BETWEEN STRAINER AND STEAM MAIN IS GREATER THAN 10'-0". WHERE DISTANCE IS LESS THAN 10'-0" TURN STRAINER ON ITS SIDE TO AVOID COLLECTING CONDENSATE IN STRAINER.  
4. THE SYMBOL ON DRAWINGS OR DETAILS INDICATES CONTROL VALVE TO BE INSTALLED AS SHOWN ON THIS DETAIL.

**E5 STEAM CONTROL VALVE ASSEMBLY**  
M502




**NOTES:**  
1. STEAM MAIN DRIP TRAP TO BE 3/4" UNLESS OTHERWISE NOTED.  
2. PROVIDE TEST VALVE AT MAJOR EQUIPMENT ONLY.  
3. PROVIDE ELEVATED SUPPORT LEGS AS REQUIRED FOR FLOOR MOUNTED EQUIPMENT TO OBTAIN MINIMUM TRAP LEG HEIGHT AS SHOWN AND PITCH OF CONDENSATE RETURN TO TERMINATION.  
4. INSTALL TRAP ASSEMBLIES IN PARALLEL WHEN MORE THAN ONE REQUIRED FOR LOAD.  
5. BYPASS ONLY REQUIRED AT MAIN RISERS

**E8 THERMODYNAMIC TRAP ASSEMBLY**  
M502




**NOTES:**  
1. REFER TO SPECIFICATION SECTION 23 52 00 FOR SIZING OF TRAP.  
2. STEAM MAIN DRIP TRAP TO BE 3/4" UNLESS OTHERWISE NOTED.  
3. OMIT CHECK VALVE IF STEAM PRESSURE IS 15 PSIG OR LESS AND CONDENSATE IS NOT LIFTED.  
4. PROVIDE TEST VALVE AT MAJOR EQUIPMENT ONLY.  
5. OMIT INLET SHUTOFF VALVE AND BYPASS FOR UNIT HEATER AND HUMIDIFIER.  
6. FOR PREHEAT COIL ONLY, PROVIDE THERMOSTATIC DRAIN VALVE AHEAD OF BYPASS. PIPE TO F.D.  
7. PROVIDE ELEVATED SUPPORTS/LEGS AS REQUIRED FOR FLOOR MOUNTED EQUIPMENT TO OBTAIN MINIMUM TRAP LEG HEIGHT AS SHOWN AND PITCH OF CONDENSATE RETURN TO TERMINATION.  
8. INSTALL TRAP ASSEMBLIES IN PARALLEL WHEN MORE THAN ONE TRAP REQUIRED FOR LOAD.

**C1 FLOAT AND THERMOSTATIC TRAP ASSEMBLY**  
M502




**NOTES:**  
1. FULL LINE SIZE UP TO 4" MAIN. FOR LARGER MAIN SIZES, 2 TO 3 SIZES SMALLER THAN MAIN SIZE, BUT NOT LESS THAN 4".

**C5 STEAM MAIN DIRT LEG DETAIL**  
M502




**NOTES:**  
1. PORT DESIGNATIONS ARE DIAGRAMMATIC. REVISE PIPING TO SUIT VALVE CONSTRUCTION.

**C8 THREE WAY WATER CONTROL VALVE PIPING**  
M502




**NOTES:**  
1. EQUIPMENT AND MOTOR ON COMMON BED PLATE.

**A1 INERTIA PAD - TYPE 3**  
M502



**A5 PIPING CONNECTION TO EXISTING WORK**  
M502



**NOTES:**  
1. WHERE TWO CONTROL VALVES ARE SHOWN, SPECIFIED OR REQUIRED, INSTALL BOTH AT SAME ELEVATION PIPED AS SHOWN FOR SINGLE VALVE WITH COMMON BYPASS FOR BOTH VALVES (SEE DIAGRAM ABOVE). MAKE BYPASS ONE PIPE SIZE LARGER THAN LARGER CONTROL VALVE.  
2. THE SYMBOL ON DRAWINGS OR DETAILS INDICATES CONTROL VALVE TO BE INSTALLED AS SHOWN ON THIS DETAIL.

**A8 TWO WAY WATER CONTROL VALVE ASSEMBLY**  
M502

**US Army Corps of Engineers**

ISSUE DATE: 2/11/2021  
 REVISION NO.: 1  
 PROJECT NO.: W912DS-19-C0031  
 CONTRACT NO.: W912DS-19-C0031  
 PROJECT NO.: 20190494

DESIGNED BY: [Blank]  
 CHECKED BY: [Blank]  
 SUBMITTED BY: [Blank]

US ARMY CORPS OF ENGINEERS  
**JACOBS / EWING COLE** A Joint Venture

WEST POINT, NY  
 USMA BUILDING 605 CULLUM HALL RENOVATION

DETAILS - HVAC

SHEET ID  
**M502**

G  
F  
E  
D  
C  
B  
A

**US Army Corps of Engineers**

ISSUE DATE: 2/11/2021  
 DESIGNED BY: WJF  
 CHECKED BY: WJF  
 SUBMITTED BY: WJF


PROJECT NO.: W912DS-19-C0031  
 PROJECT NO.: 20190494

US ARMY CORPS OF ENGINEERS  
**JACOBS / EWING COLE** A Joint Venture


WEST POINT, NY  
 USMA BUILDING 605 CULLUM HALL RENOVATION

DETAILS - HVAC


SHEET ID  
**M503**




**E1 SINGLE CHILLED WATER COOLING OR HOT WATER HEATING COIL**  
 M503 TWO-WAY CONTROL VALVE




**E5 REHEAT COIL PIPING**  
 M503 DUCT OR AIR VOLUME CONTROL BOX MOUNTED




**C8 SINGLE HOT WATER HEATING COIL AND INLINE PUMP**  
 M503 TWO-WAY CONTROL VALVE




**C1 STACKED WATER COOLING OR HEATING COIL**  
 M503 TWO-WAY CONTROL VALVE




**C5 STACKED HOT WATER HEATING COIL AND INLINE PUMP**  
 M503 TWO-WAY CONTROL VALVE (SINGLE COIL PIPING SIMILAR)



**A1 SINGLE CHILLED WATER COOLING COIL AND INLINE PUMP**  
 M503 TWO-WAY CONTROL VALVE



**A5 HOT WATER PROPELLER UNIT HEATER PIPING**  
 M503 W/ CONTROL VALVE W/O BYPASS



**A8 IN-LINE PUMP PIPING**  
 M503




































**SHEET NOTES:**  
 ① VALVE AND CAP 8" MAINS FOR FUTURE CONNECTIONS TO SITE CHILLED WATER DISTRIBUTION. VALVES MUST BE LOCKABLE, IN THE OPEN OR CLOSED POSITION.



A5 CHILLED WATER FLOW DIAGRAM  
 M706 NTS




MARK	DESCRIPTION	DATE

DESIGNED BY: WJF	ISSUE DATE: 2/11/2021
DRAWN BY: WJF	REVISION NO: 01
CHECKED BY: WJF	CONTRACT NO.: W912DS-19-C0031
SUBMITTED BY: BK	PROJECT NO.: 20190494
SIZE: ANSI D	

US ARMY CORPS OF ENGINEERS  
 WEST POINT, NY  
 USMA BUILDING 605 CULLUM HALL RENOVATION  
 FLOW DIAGRAMS - HVAC  
 JACOBS / EWING COLE A Joint Venture

SHEET ID  
**M706**



D5 SYSTEM ARCHITECTURE DIAGRAM  
M801

**SHEET NOTES:**  
 ① THE CONTRACTOR MUST PROVIDE A PORTABLE WORKSTATION (LAPTOP) AS SPECIFIED. THE LAPTOP MUST BE STORED IN A SECURE LOCATION, WITHIN THE BUILDING, AS DETERMINED BY THE GOVERNMENT.

**SYMBOLS:**

	DAMPER WITH MOTOR ACTUATOR
	DPDT WHISKER TYPE END SWITCH
	DUCT TEMPERATURE SENSOR
	DUCT HUMIDITY SENSOR
	DUCT HUMIDITY HIGH LIMIT
	DUCT STATIC PRESSURE SENSOR
	IMMERSION TEMPERATURE SENSOR WITH WELL
	SPACE TEMPERATURE SENSOR
	SPACE SENSOR ON EXTERIOR WALL TO BE MOUNTED WITH INSULATED PANEL
	SPACE HUMIDITY SENSOR
	DUCT SMOKE DETECTOR
	CARBON DIOXIDE SENSOR
	SMOKE DAMPER
	SMOKE/FIRE DAMPER
	SMOKE CONTROL DAMPER
	COMPRESSED AIR PIPING
	VOLTAGE SENSOR
	LOW TEMPERATURE LIMIT THERMOSTAT
	STARTER
	VARIABLE FREQUENCY DRIVE
	CURRENT SENSOR
	RELAY
	TWO-WAY VALVE WITH MOTOR ACTUATOR
	TWO-WAY VALVE WITH PNEUMATIC ACTUATOR
	THREE-WAY VALVE WITH MOTOR ACTUATOR
	THREE-WAY VALVE WITH PNEUMATIC ACTUATOR
	AIR FLOW STATION W/ LOCAL DISPLAY
	DIFFERENTIAL PRESSURE TRANSMITTER
	DOOR SWITCH
	FLOW SWITCH
	DX COOLING COIL

**SYMBOLS (CONTINUED):**

	FLOW METER
	ELECTRO-PNEUMATIC RELAY
	PUSHBUTTON
	PUSH TO TEST INDICATING LIGHT X = COLOR
	GAS DETECTION SENSOR
	POSITION SWITCH
	PRESSURE SWITCH
	REHEAT COIL
	1ST TIER CONTROL NETWORK WIRING (ETHERNET)
	2ND TIER CONTROL NETWORK WIRING (SERIAL BUS)

**ABBREVIATIONS:**  
 AHU = AIR HANDLING UNIT  
 BCN = BUILDING CONTROL NETWORK  
 BI = BINARY INPUT (SAME AS DIGITAL INPUT)  
 BO = BINARY OUTPUT (SAME AS DIGITAL OUTPUT)  
 COR = CONTRACTING OFFICER'S REPRESENTATIVE  
 OAT = OUTDOOR AIR TEMPERATURE  
 CH = CHILLER  
 CT = COOLING TOWER  
 CT = COOLING TOWER  
 HMI = HUMAN MACHINE INTERFACE  
 FIA = FIRE ALARM  
 FPFC = FIELD POINT OF CONNECTION  
 GUI = GRAPHICAL USER INTERFACE  
 DDC = DIRECT DIGITAL CONTROL  
 DDCP = DIRECT DIGITAL CONTROL PANEL W/ LOCAL LCD KEYPAD (GPPC)  
 TUC = TERMINAL UNIT CONTROLLER (AGC)  
 VAV = VARIABLE AIR VOLUME BOX  
 NC = NORMALLY CLOSED  
 NO = NORMALLY OPEN  
 AI = ANALOG INPUT  
 AO = ANALOG OUTPUT  
 DI = DIGITAL INPUT (SAME AS BINARY INPUT)  
 DO = DIGITAL OUTPUT (SAME AS BINARY OUTPUT)  
 SD = SMOKE DAMPER  
 BAS = BUILDING AUTOMATION SYSTEM  
 FCU = FAN COIL UNIT  
 AI = ANALOG INPUT (PNEUMATIC)  
 AO = ANALOG OUTPUT (PNEUMATIC)  
 DIP = DIGITAL INPUT (PNEUMATIC)  
 DOP = DIGITAL OUTPUT (PNEUMATIC)  
 NS = LONWORKS NETWORK SERVER (JACE)  
 WSPH = WATER SOURCE HEAT PUMP

**GENERAL NOTES:**

- THE BMS MUST BE A HONEYWELL LON DIRECT DIGITAL CONTROLS (DDC) SYSTEM, OR APPROVED EQUAL. THE NEW INSTALLED SYSTEM MUST BE NIAGARA N4 COMPLIANT. IT MUST BE COMPATIBLE WITH ENERGY MANAGEMENT AND CONTROLS SYSTEM (EMCS) SERVER VIA A JACE INTERFACE.
- ANY INSTALLED HARDWARE FROM OTHER MANUFACTURER OTHER THAN HONEYWELL MUST BE COMPATIBLE WITH HONEYWELL PRODUCTS WHICH MUST NOT AFFECT THE SYSTEM FUNCTIONALITY.
- BMS MUST BE BASED ON THE LONWORKS OPEN PROTOCOL WHICH INCLUDES THE SOFTWARE WITH CAPABILITY FOR SCHEDULING, LOCAL AND REMOTE CONTROL ADJUSTMENT, LOAD SHEDDING, EVENT MANAGEMENT, MONITORING, TRENDDING, LOGGING, MAINTENANCE NOTIFICATION AND ALARMS.
- THE CONTRACTOR MUST HIRE THE SYSTEM INTEGRATOR WITHIN THE BUDGET OF THE PROJECT.
- ALL NEW EQUIPMENT TO BE DDC CONTROLLED THROUGH THE NEW BUILDING AUTOMATION SYSTEM (BAS), UNLESS NOTED OTHERWISE. EQUIPMENT PROVIDED WITH INTEGRAL CONTROLS MUST BE ENABLED, DISABLED, AND ALARMED THRU THE BAS.
- SMOKE DAMPERS MUST BE SUPPLIED, AND INSTALLED BY DIVISION 23 CONTRACTOR, WIRED BY DIVISION 26 CONTRACTOR, AND CONTROLLED BY FIA SYSTEM. ALL WIRING TO FIA SYSTEM BY CONTROLS CONTRACTOR.
- ALL NEW EQUIPMENT MUST BE PROVIDED WITH CONTROL GRAPHICS ON THE EXISTING BAS SYSTEM. THESE GRAPHICS MUST BE ACCESSIBLE FROM ANY EXISTING LOCAL OR REMOTE OPERATORS STATION.
- ALL ABBREVIATIONS AND SYMBOLS MAY NOT APPEAR ON DRAWINGS.
- REFER TO SPECIFICATIONS FOR CONTROL SEQUENCES. PROVIDE ADDITIONAL HARDWARE/SOFTWARE AS REQUIRED TO PERFORM SPECIFIED SEQUENCE. WHERE SPECIFICATIONS AND DRAWINGS CONFLICT, THE MORE STRINGENT MUST APPLY.
- CONTROL DIAGRAMS HAVE NOT BEEN PROVIDED FOR EVERY DEVICE TO BE CONTROLLED BY THE DDC SYSTEM, REFER TO FLOOR PLANS, FLOW DIAGRAMS, DETAILS & SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS.
- ARCHITECTURE SHOWN INDICATES MINIMUM REQUIREMENTS. PROVIDE ADDITIONAL PANELS AS REQUIRED TO ACCOMMODATE CONTROL DIAGRAMS & CONTROL SEQUENCES INDICATED IN SPECIFICATIONS & DRAWINGS.
- CONTROLS CONTRACTOR MUST PROVIDE RELAYS/CONTACTORS NEEDED FOR ALL SINGLE PHASE EQUIPMENT NOT PROVIDED WITH STARTERS.
- CONTROLS CONTRACTOR IS REQUIRED TO PROVIDE APPROPRIATE DEAD BANDS AND ADJUST PROPORTIONAL, INTEGRAL, AND DIFFERENTIAL SETTINGS TO ASSURE NON-CYCLOC OPERATION WITHOUT SACRIFICING SYSTEM ACCURACY.
- FLOATING CONTROL IS NOT PERMITTED. ALL SIGNALS INDICATED AS AO MUST BE 4-20mA OR 0-10V CONTROL SIGNALS.
- CONTROLS CONTRACTOR MUST COORDINATE WITH USACE CONTRACTING OFFICER'S REPRESENTATIVE (COR) TO OBTAIN SECURITY, NETWORK, AND SYSTEM INTEGRATION RULES, PROCEDURES AND CLEARANCES. CONTROLS CONTRACTOR MUST COORDINATE DDC CONTROLLER INTEGRATION TO EXISTING NETWORK WITH USACE COR.
- CONTROLS CONTRACTOR MUST NOTIFY BASE TECHNICIANS PRIOR TO UPLOADING DATA TO EXISTING BAS SERVER.
- CONTROLS CONTRACTOR MUST CHECK THE SYSTEM PROFILE BEFORE AND AFTER CABINET INSTALLATION.
- CONTROLS CONTRACTOR TO MATCH EXISTING CONTROL SYSTEMS UNITS OF MEASUREMENT IN ALL CONTROL SYSTEM PROGRAMMING, DISPLAYS AND GRAPHICS.
- CONTROLS CONTRACTOR MUST PROVIDE AND INSTALL ALL CONTROL NETWORK OUTLETS, WIRING AND CONDUIT.
- CONTROLS CONTRACTOR MUST INSTALL LATEST TECHNOLOGY CONTROLLERS.
- CONTROLS CONTRACTOR MUST USE EXISTING WEST POINT NAMING AND ADDRESS CONVENTIONS FOR NAMING AND ADDRESSING ALL NEW CONTROL HARDWARE.
- CONTROLS CONTRACTOR MUST PROVIDE DDC GRAPHICS FOR ALL NEW SYSTEMS THAT MATCH THE EXISTING GRAPHICS IN CONTENT AND STYLE. OBTAIN USACE COR'S WRITTEN APPROVAL OF GRAPHICS PRIOR TO LOADING ON SYSTEM.
- CONTROLS CONTRACTOR MUST INSTALL AND WIRE ALL CONTROL COMPONENTS SHIPPED LOOSE WITH HVAC EQUIPMENT.
- CONTROLS CONTRACTOR MUST SUBMIT FOR COORDINATION AND A/E APPROVAL, DRAWINGS SHOWING THE PROPOSED LOCATION AND MOUNTING HEIGHT FOR BAS PANELS, SPACE SENSORS, DUCT STATIC PRESSURE SENSORS AND HYDRONIC DIFFERENTIAL PRESSURE SENSORS.
- PROVIDE AN ALARM FOR EVERY MOTOR FAILURE (AS INDICATED BY A CURRENT SENSOR), EQUIPMENT ALARM, AND LISTED SAFETY. ADDITIONALLY, PROVIDE AN ALARM FOR EVERY CONTROLLED VARIABLE WHICH DROPS BELOW OR RISES ABOVE SETPOINT BY MORE THAN 10% (ADJUSTABLE).
- EACH ALARM MUST BE ASSIGNED A PRIORITY LEVEL WHICH WILL BE DISPLAYED WITH THE ALARM DESCRIPTION ON THE OPERATORS CONSOLE AND WHICH MUST TRIGGER AN INDEPENDENTLY PROGRAMMABLE ACTION. AT A MINIMUM THERE MUST BE AT LEAST FOUR LEVELS OF ALARMS - WARNING, MINOR, MAJOR AND CRITICAL.
- COORDINATE ALARM PRIORITY AND APPROPRIATE ACTION WITH USACE COR'S PRIOR TO FINAL ALARM PROGRAMMING. AT A MINIMUM, EVERY ALARM MUST BE GRAPHICALLY CONVEYED AND RECORDED IN A PERMANENT ALARM FILE. AT THE END OF EACH MONTH A NEW ALARM FILE WILL BE CREATED AND THE FILE NAMED BY MONTH AND YEAR.
- REFER TO ARCHITECTURAL DRAWINGS FOR SENSOR MOUNTING HEIGHT REQUIREMENTS. WHERE NOT SHOWN, MOUNT IN ACCORDANCE WITH PROJECT SPECIFICATIONS.
- EACH FAN INLET AIRFLOW MONITOR TO BE PROVIDED WITH A LOCAL DISPLAY INDICATING CURRENT AIRFLOW. LOCATE ADJACENT TO UNIT CONTROL PANEL AND LABEL ACCORDINGLY.
- ALL COIL DISCHARGE AND MIXED AIR TEMPERATURE SENSORS WITHIN AIR HANDLING UNITS MUST BE AVERAGING TYPE.
- REPEATERS MUST NOT BE USED EXCEPT WHERE APPROVED BY USACE COR.
- CONTROLS CONTRACTOR TO PROVIDE ALL POWER AND CONTROL WIRING AND CONDUIT FOR ALL CONTROL COMPONENTS INCLUDING OPERATORS, DAMPERS, CONTROL PANELS, ETC.
- ALL BAS SERIAL NETWORK (FLOOR LEVEL NETWORK-2N BUS) WIRING TO BE CONTINUOUS BETWEEN DEVICES. NO T-TAPS OR SPLICES WILL BE PERMITTED.
- CONTROLS CONTRACTOR MUST SET UP AND PROGRAM PACKAGED EQUIPMENT.
- REVIEW ALL SENSOR LOCATIONS WITH USACE COR PRIOR TO ROUGH-IN.
- PROVIDE STATIC GRAPHICS CONTAINING CONTROL SEQUENCES FOR EVERY CONTROLLED DEVICE. EACH DEVICE IN ACTIVE GRAPHICS MUST CONTAIN A LINK TO THE ASSOCIATED CONTROL SEQUENCE GRAPHIC. PRELIMINARY BUILDING OCCUPANCY SCHEDULE: MON - FRI: 6AM TO 10PM, SAT & SUN: 8AM TO 9PM.
- ALL BAS CONTROL PANELS SERVING EQUIPMENT ON EMERGENCY POWER MUST BE PROVIDED WITH EMERGENCY POWER AND INTEGRAL BATTERY BACKUP TO MAINTAIN POWER UNTIL GENERATOR STARTS.
- PROVIDE A DEDICATED WALL MOUNTED DDC TEMPERATURE SENSOR FOR EACH AVB, FCU, WSPH, AND TF EXCEPT WHERE THE FLOOR PLANS INDICATE THAT A SINGLE SENSOR IS TO SERVE MULTIPLE TERMINAL UNITS.
- UNIT GRAPHICS MUST INDICATE CURRENT OPERATING MODES (E.G. "NORMAL", "CO2 RESET", "UNOCCUPIED", ETC.).
- RETURN AND OUTSIDE AIR DAMPERS IN AHU MIXING BOXES ARE TO BE PARALLEL BLADE TYPE. ALL OTHER CONTROL DAMPERS ARE TO BE OPPOSED BLADE TYPE.
- ALL EQUIPMENT OCCUPANCY SCHEDULES MUST BE SUBMITTED TO AND APPROVED BY THE USACE COR. PROVIDE REPROGRAMMABLE OCCUPANCY SCHEDULES AND PROVIDE UNOCCUPIED MODE SEQUENCES FOR ALL EQUIPMENT. WHERE USACE COR DIRECTS THAT UNITS ARE TO REMAIN IN OCCUPIED MODE (AND NEVER ENTER UNOCCUPIED MODE), SET SCHEDULES FOR 24 HOUR/365 DAY OPERATION.
- ALL CONTROLLERS MUST BE LONWORKS DEVICES CERTIFIED BY THE LONWORKS ASSOCIATION.
- THE ABBREVIATIONS "DI" AND "DO" ARE USED INTERCHANGEABLY WITH BI AND BO THROUGHOUT THE CONTRACT DOCUMENTS.
- PROVIDE AN ALARM FOR HEAT TRACE FAILURE AS INDICATED BY EACH HEAT TRACE CONTROLLER.
- FIELD POINT OF CONNECTION (FPFC) MUST BE N4 COMPATIBLE.
- ALL HARD-WIRED AND VIRTUAL POINTS (CONTROL VARIABLES) MUST BE CAPABLE OF BEING TRENDED BY THE BAS.
- THE SUPERVISORY GATEWAY/FPFC MUST BE A JACE-8XXX (OR OTHER APPROVED MODEL) THAT IS COMPATIBLE WITH THE CURRENT VERSION (v4.7 OR LATER) OF NIAGARA N4.
- CONTROLS CONTRACTOR MUST FULLY INSTALL AND COMPLETE ALL BMS BUILDING CONTROLS INTEGRATION WORK ON WEST POINT EMCS NETWORK. CONTRACTOR MUST COORDINATE ALL BMS CONTROLS INTEGRATION WORK WITH CURRENT WEST POINT EMCS OPERATOR.

**US Army Corps of Engineers**

ISSUE DATE: 2/11/2021  
 DESIGNED BY: [Name]  
 CHECKED BY: [Name]  
 SUBMITTED BY: [Name]

PROJECT NO.: W912DS-19-C0031  
 PROJECT NO.: 20190494

US ARMY CORPS OF ENGINEERS  
 WEST POINT, NY  
 USMA BUILDING 605 CULLUM HALL RENOVATION  
 HVAC CONTROLS

**JACOBS / EWING COLE** A Joint Venture

**SHEET ID**  
**M801**



















**HVAC SYSTEM ISOLATION CONTROL SEQUENCE**

- PROVIDE MANUALLY OPERATED EMERGENCY SHUT-OFF SWITCHES IN LOCATIONS SHOWN ON DRAWINGS. EACH SWITCH MUST BE A TWO POSITION-TWO POLE MUSHROOM RED BUTTON SWITCH.
- THIS SWITCH MUST BE HARDWIRED INTERLOCKED AT EACH OUTSIDE AIR SUPPLY & EXHAUST FAN AND TO EACH EXHAUST, RELIEF & OUTSIDE AIR DAMPER. UPON ACTIVATION OF THE SWITCH, THE RELAY WILL DE-ENERGIZE EACH FAN SYSTEM IN BOTH THE "HAND" AND "AUTOMATIC" MODES OF OPERATION, AND CLOSE ALL OUTSIDE AIR DAMPERS, RELIEF AIR DAMPERS AND EXHAUST AIR DAMPERS.

**E2 HVAC ATFP EMERGENCY SHUTDOWN CONTROL DIAGRAM (TYPICAL)**



**GENERAL**

- SEPARATE OCCUPIED AND UNOCCUPIED TEMPERATURE SET POINTS MUST BE MAINTAINED. EACH FCU MUST HAVE AN INDIVIDUALLY REPROGRAMMABLE OCCUPANCY SCHEDULE.
- THE UNIT FAN MUST RUN CONTINUOUSLY DURING OCCUPIED HOURS AND INTERMITTENTLY DURING UNOCCUPIED MODE (ONLY ON A CALL FOR HEATING OR COOLING).

**OCCUPIED MODE:**

- FAN MUST RUN CONTINUOUSLY DURING OCCUPIED HOURS.
- DDC SPACE SENSOR MUST. ON A FALL IN ROOM AIR TEMPERATURE BELOW OCCUPIED COOLING TEMPERATURE SETPOINT (72°F. ADJUSTABLE), MODULATE CHILLED WATER VALVE CLOSED. ON A CONTINUED FALL BELOW OCCUPIED HEATING TEMPERATURE SETPOINT (68°F. ADJUSTABLE), REHEAT COIL CONTROL VALVE MUST BE MODULATED OPEN.


**UNOCCUPIED MODE:**

- FAN IS DE-ENERGIZED AND CONTROL VALVES ARE CLOSED.
- UPON A RISE IN SPACE TEMPERATURE ABOVE UNOCCUPIED COOLING SETPOINT (80°F. ADJUSTABLE), THE DDC SYSTEM MUST ENERGIZE THE UNIT FAN. UPON A FURTHER RISE IN SPACE TEMPERATURE, THE CHILLED WATER CONTROL VALVE MUST BE MODULATED OPEN.
- UPON A DROP IN SPACE TEMPERATURE BELOW UNOCCUPIED HEATING SETPOINT (60°F. ADJUSTABLE), THE DDC SYSTEM MUST MODULATE THE REHEAT COIL CONTROL VALVE OUTPUT TO MAINTAIN SPACE TEMPERATURE ABOVE THE UNOCCUPIED HEATING SET POINT.

**SAFETY CONTROLS**

- THE LEAK DETECTION CONTROLLER MUST BE HARDWIRED INTO THE FAN SAFETY CIRCUIT.
- THE LEAK DETECTION CONTROLLER MUST ALARM THE BAS. PROVIDE LOCAL ALARM LIGHT.
- THE COIL PAN FLOAT SWITCH MUST ALARM THE BAS. PROVIDE LOCAL ALARM LIGHT.
- THE FILTER DPT MUST ALARM THE BAS. PROVIDE LOCAL ALARM LIGHT.

**A2 DUCTED HORIZONTAL FAN COIL UNIT CONTROL DIAGRAM (TYPICAL)**



**SINGLE DUCT AIR VOLUME CONTROL BOXES (CONSTANT)**


**GENERAL:**

- EACH VAV MUST HAVE AN INDIVIDUALLY REPROGRAMMABLE OCCUPANCY SCHEDULE.
- ALL VAVS MUST HAVE CROSS FLOW AIR FLOW SENSORS, CONTROL TRANSFORMER, DAMPER AND TERMINAL STRIP PROVIDED BY VAV MANUFACTURER.
- CONTROLS CONTRACTOR MUST DELIVER DDC CONTROLLER, DAMPER ACTUATOR, HEATING COIL VALVE OPERATOR (AND VALVE) AND ALL REQUIRED ACCESSORIES TO VAV MANUFACTURER FOR FACTORY INSTALLATION. CONTROLS CONTRACTOR MUST COORDINATE WITH VAV MANUFACTURER AND PROVIDE ALL NECESSARY MATERIALS.
- PROVIDE WALL MOUNTED DDC TEMPERATURE SENSOR.

**OCCUPIED MODE**

- THE VAV DAMPER MUST MODULATE TO MAINTAIN AIRFLOW SETPOINT. THE REHEAT COIL CONTROL VALVE MUST BE MODULATED TO MAINTAIN SPACE TEMPERATURE SETPOINT.

**E5 CONSTANT VOLUME BOX CONTROL DIAGRAM**



**GENERAL**

- SEPARATE OCCUPIED AND UNOCCUPIED TEMPERATURE SET POINTS MUST BE MAINTAINED. EACH FCU MUST HAVE AN INDIVIDUALLY REPROGRAMMABLE OCCUPANCY SCHEDULE.
- THE UNIT FAN MUST RUN CONTINUOUSLY DURING OCCUPIED HOURS AND INTERMITTENTLY DURING UNOCCUPIED MODE (ONLY ON A CALL FOR HEATING OR COOLING).

**OCCUPIED MODE:**

- FAN MUST RUN CONTINUOUSLY DURING OCCUPIED HOURS.
- DDC SPACE SENSOR MUST. ON A FALL IN ROOM AIR TEMPERATURE BELOW OCCUPIED COOLING TEMPERATURE SETPOINT (72°F. ADJUSTABLE), MODULATE CHILLED WATER VALVE CLOSED. ON A CONTINUED FALL BELOW OCCUPIED HEATING TEMPERATURE SETPOINT (68°F. ADJUSTABLE), REHEAT COIL CONTROL VALVE MUST BE MODULATED OPEN.


**UNOCCUPIED MODE:**

- FAN IS DE-ENERGIZED AND CONTROL VALVES ARE CLOSED.
- UPON A RISE IN SPACE TEMPERATURE ABOVE UNOCCUPIED COOLING SETPOINT (80°F. ADJUSTABLE), THE DDC SYSTEM MUST ENERGIZE THE UNIT FAN. UPON A FURTHER RISE IN SPACE TEMPERATURE, THE CHILLED WATER CONTROL VALVE MUST BE MODULATED OPEN.
- UPON A DROP IN SPACE TEMPERATURE BELOW UNOCCUPIED HEATING SETPOINT (60°F. ADJUSTABLE), THE DDC SYSTEM MUST MODULATE THE REHEAT COIL CONTROL VALVE OUTPUT TO MAINTAIN SPACE TEMPERATURE ABOVE THE UNOCCUPIED HEATING SET POINT.

**SAFETY CONTROLS**

- THE LEAK DETECTION CONTROLLER MUST BE HARDWIRED INTO THE FAN SAFETY CIRCUIT.
- THE LEAK DETECTION CONTROLLER MUST ALARM THE BAS. PROVIDE LOCAL ALARM LIGHT.
- THE COIL PAN FLOAT SWITCH MUST ALARM THE BAS. PROVIDE LOCAL ALARM LIGHT.
- THE FILTER DPT MUST ALARM THE BAS. PROVIDE LOCAL ALARM LIGHT.

**A5 NON-DUCTED HORIZONTAL FAN COIL UNIT CONTROL DIAGRAM (VERTICAL UNITS SIMILAR)**



**SINGLE DUCT AIR VOLUME CONTROL BOXES (VARIABLE)**

**GENERAL:**

- SEPARATE OCCUPIED AND UNOCCUPIED TEMPERATURE SET POINTS MUST BE MAINTAINED. EACH VAV MUST HAVE AN INDIVIDUALLY REPROGRAMMABLE OCCUPANCY SCHEDULE.
- ALL VAVS MUST HAVE CROSS FLOW AIR FLOW SENSORS, CONTROL TRANSFORMER, DAMPER AND TERMINAL STRIP PROVIDED BY VAV MANUFACTURER.
- CONTROLS CONTRACTOR MUST DELIVER DDC CONTROLLER, DAMPER ACTUATOR, HEATING COIL VALVE OPERATOR (AND VALVE) AND ALL REQUIRED ACCESSORIES TO VAV MANUFACTURER FOR FACTORY INSTALLATION. CONTROLS CONTRACTOR MUST COORDINATE WITH VAV MANUFACTURER AND PROVIDE ALL NECESSARY MATERIALS.
- PROVIDE WALL MOUNTED DDC TEMPERATURE SENSOR.
- EACH SPACE SENSOR IS TO HAVE AN UNOCCUPIED MODE PUSHBUTTON TO INDEX THE ASSOCIATED AIR HANDLING UNIT INTO OCCUPIED MODE FOR 2 HOURS (REPROGRAMMABLE).

**OCCUPIED MODE**

- ON A FALL IN ROOM AIR TEMPERATURE BELOW OCCUPIED COOLING TEMPERATURE SETPOINT (75°F. ADJUSTABLE), MODULATE VAV TO MINIMUM COOLING AIR FLOW. ON A CONTINUED FALL BELOW OCCUPIED HEATING TEMPERATURE SETPOINT (68°F. ADJUSTABLE), VAV MUST BE SET TO MINIMUM HEATING AIR FLOW & REHEAT COIL CONTROL VALVE MODULATED TO MAINTAIN SPACE TEMPERATURE SETPOINT.


**UNOCCUPIED MODE**

- PRIMARY AIR VALVE IS SET TO MINIMUM COOLING AIR FLOW.
- UPON A RISE IN SPACE TEMPERATURE ABOVE UNOCCUPIED COOLING SETPOINT (80°F. ADJUSTABLE), THE DDC SYSTEM MUST ENERGIZE THE ASSOCIATED AHU IN COOLDOWN MODE AND MODULATE OPEN VAV VALVE TO MAINTAIN SPACE TEMPERATURE 5°F BELOW UNOCCUPIED COOLING SETPOINT.
- UPON A DROP IN SPACE TEMPERATURE BELOW UNOCCUPIED HEATING SETPOINT (60°F. ADJUSTABLE), THE DDC SYSTEM MUST ENERGIZE THE ASSOCIATED AHU. REHEAT COIL WILL BE ENABLED AND THE REHEAT CONTROL VALVE MODULATED TO MAINTAIN SPACE TEMPERATURE 5°F ABOVE UNOCCUPIED HEATING SETPOINT.

**CO2 CONTROL (AHU-3 ONLY)**

- CO2 RESET TO OCCUR ONLY DURING OCCUPIED HOURS.
- UPON A RISE IN SPACE CO2 LEVEL 400 PPM (ADJUSTABLE) ABOVE OUTDOOR LEVEL, THE DDC SYSTEM MUST FIRST MODULATE VAV AIR VALVE OPEN TO MAX COOLING CFM UPON A CONTINUED RISE IN SPACE CO2 LEVEL, MODULATE THE ECONOMIZER DAMPER OPEN (UP TO MAXIMUM SCHEDULED OA) AND MODULATE THE RETURN AIR DAMPERS CLOSED.

**D8 VARIABLE VOLUME BOX CONTROL DIAGRAM**



MARK	DESCRIPTION	DATE

DESIGNED BY:	ISSUE DATE:
CHKD BY:	2/11/2021
APP'D BY:	NO. OF REVISIONS:
CHECKED BY:	CONTRACT NO.:
	W912DS-19-C0031
SUBMITTED BY:	PROJECT NO.:
	20190494

US ARMY CORPS OF ENGINEERS

WEST POINT, NY

USMA BUILDING 605 CULLUM HALL RENOVATION

HVAC CONTROLS

JACOBS / EWING COLE A Joint Venture

SHEET ID

M808





G

F

E

D

C

B

A

AHU-1 SYSTEM POINTS SCHEDULE																				
FUNCTION	POINT NAME	DESCRIPTION	DDC HARDWARE ID	SETTINGS (WITH UNITS) NOTE 4	RANGE (WITH UNITS) NOTE 4	IO TYPE	HOA REQD	CONFIG. TYPE	M&C VIEW AND OVERRIDE	TREND REQD	ALARMING		PRIMARY POINT INFORMATION		OVERRIDES		CONFIGURATION INFORMATION			
											ALARM CONDITION	ALARM PRIORITY	SNVT NAME	SNVT TYPE	NIAGARA ID	SNVT NAME		SNVT TYPE		
PROOFS & SAFETIES	< >	SUPPLY FAN 1&2 VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y		SUPPLY FAN 1 & 2 VFD PROOF FAILED	CRIT	< >	< >	< >	< >	< >		
	< >	SUPPLY FAN 1 STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y		SUPPLY FAN 1 PROOF FAILED	CRIT	< >	< >	< >	< >	< >		
	< >	SUPPLY FAN 2 STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y		SUPPLY FAN 2 PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 3&4 VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y		SUPPLY FAN 3 & 4 VFD PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 3 STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y		SUPPLY FAN 3 PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 4 STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y		SUPPLY FAN 4 PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	RETURN FAN VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y		RETURN FAN PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	LOW LIMIT TEMPERATURE ALARM (FREEZESTAT)	< >	35 DEG F	ALARM/NORMAL	DI	NA	H	V	Y		FREEZESTAT ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	SUPPLY FAN DISCHARGE HIGH PRESSURE SWITCH	< >	4.00 IN-W.C.	ALARM/NORMAL	DI	NA	H	V	Y		SUPPLY AIR HIGH STATIC PRESSURE ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	RETURN FAN INLET LOW PRESSURE SWITCH	< >	-3.00 IN-W.C.	ALARM/NORMAL	DI	NA	H	V	Y		RETURN FAN LOW STATIC PRESSURE ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	SUPPLY AIR SMOKE DETECTOR	< >	-	ALARM/NORMAL	DI	NA	-	V	Y		SUPPLY AIR SMOKE ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	RETURN AIR SMOKE DETECTOR	< >	-	ALARM/NORMAL	DI	NA	-	V	Y		RETURN AIR SMOKE ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	DEHUMIDIFIER STATUS	< >	-	ON/OFF	DI	NA	-	V	Y		DEHUMIDIFIER PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	DEHUMIDIFIER DISCHARGE AIR SMOKE DETECTOR	< >	-	ALARM/NORMAL	DI	NA	-	V	Y		DEHUMIDIFIER DISCHARGE AIR SMOKE ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	SUPPLY FAN 1&2 VFD ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y		SUPPLY FAN 1 & 2 VFD GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	RETURN FAN VFD ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y		RETURN FAN VFD GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	OUTSIDE AIR UNIT ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y		OUTSIDE AIR UNIT GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	OUTSIDE AIR UNIT DISCHARGE AIR SMOKE DETECTOR	< >	-	ALARM/NORMAL	DI	NA	-	V	Y		OUTSIDE AIR UNIT DISCHARGE AIR SMOKE ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	DEHUMIDIFIER ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y		DEHUMIDIFIER GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >
	< >	FILTER DIFFERENTIAL PRESSURE	< >	1.5 IN-W.C.	0 - 2 IN-W.C.	AI	NA	-	VO	Y		DIRTY FILTER ALARM	INFO	< >	< >	< >	< >	< >	< >	< >
SCHEDULING	< >	SYSTEM OCCUPANCY SCHEDULE	-	-	OCCUPIED/UNOCCUPIED	NET-IN	NA	OC	V	-				< >	< >	< >	< >	< >	< >	
	< >	OCCUPANCY COMMAND	-	-	OCCUPIED/UNOCCUPIED	NET-IN	NA	-	VO	-				< >	< >	< >	< >	< >	< >	
START/STOP	< >	SYSTEM OCCUPANCY (ACTUAL)	-	-	OCCUPIED/UNOCCUPIED	NET-OUT	NA	-	V	-				< >	< >	< >	< >	< >	< >	
	< >	ATFP EMERGENCY SHUTDOWN SWITCH STATUS	< >	-	EMERGENCY/NORMAL	NET-OUT	NA	-	V	Y		ATFP EMERGENCY ALARM ACTIVATED	CRIT	< >	< >	< >	< >	< >	< >	< >
SUPPLY FAN CONTROL	< >	SUPPLY FAN 1&2 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y				< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 3&4 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y				< >	< >	< >	< >	< >	< >	
RETURN FAN CONTROL	< >	RETURN FAN VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y				< >	< >	< >	< >	< >	< >	
	< >	DEHUMIDIFIER ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y				< >	< >	< >	< >	< >	< >	
SUPPLY FAN PID LOOP SETTINGS	< >	SUPPLY AIR DUCT STATIC PRESSURE SETPOINT	< >	< 0.65" IN-W.C. >	-	NET-IN	NA	OC	VO	-				< >	< >	< >	< >	< >	< >	
	< >	SUPPLY AIR DUCT STATIC PRESSURE	< >	-	< 0 - 100% >	AI	NA	-	VO	Y				< >	< >	< >	< >	< >	< >	
RETURN FAN PID LOOP SETTINGS	< >	SUPPLY FAN 1&2 VFD SPEED	< >	-	0 - 100%	AO	NA	-	VO	Y				< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 3&4 VFD SPEED	< >	-	0 - 100%	AO	NA	-	VO	Y				< >	< >	< >	< >	< >	< >	
SUPPLY AIR TEMPERATURE CONTROL	< >	SUPPLY FAN DISCHARGE PRESSURE	< >	-	< 0 - 4 IN-W.C. >	AI	NA	-	VO	Y		STATIC PRESSURE RISES ABOVE 3.00 IN-W.C. (ADJ.)	CRIT	< >	< >	< >	< >	< >	< >	
	< >	PROPORTIONAL CONSTANT	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
RETURN FAN CONTROL	< >	INTEGRAL CONSTANT	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
	< >	BIAS	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
SUPPLY AIR TEMPERATURE CONTROL	< >	MAXIMUM OUTPUT	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
	< >	MINIMUM OUTPUT	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
RETURN FAN CONTROL	< >	SUPPLY FAN 1 AIRFLOW	< >	-	< 0 - 100% CFM >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 2 AIRFLOW	< >	-	< 0 - 100% CFM >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
RETURN FAN PID LOOP SETTINGS	< >	SUPPLY FAN 3 AIRFLOW	< >	-	< 0 - 100% CFM >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 4 AIRFLOW	< >	-	< 0 - 100% CFM >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
SUPPLY AIR TEMPERATURE CONTROL	< >	RETURN FAN AIRFLOW	< >	-	< 0 - 100% CFM >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
	< >	AIRFLOW OFFSET VALUE	< >	< 300 CFM >	-	NET-IN	NA	OC	VO	-				< >	< >	< >	< >	< >	< >	
OUTSIDE AIR UNIT CONTROL	< >	RETURN FAN AIRFLOW SETPOINT	< >	-	-	NET-IN	NA	OC	VO	-				< >	< >	< >	< >	< >	< >	
	< >	RETURN FAN VFD SPEED	< >	-	0 - 100%	AO	NA	-	VO	Y				< >	< >	< >	< >	< >	< >	
DEHUMIDIFIER CONTROL	< >	RETURN FAN INLET PRESSURE	< >	-	< -3 - 0 IN-W.C. >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
	< >	PROPORTIONAL CONSTANT	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
SUPPLY AIR TEMPERATURE CONTROL	< >	INTEGRAL CONSTANT	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
	< >	BIAS	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
OUTSIDE AIR UNIT CONTROL	< >	MAXIMUM OUTPUT	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
	< >	MINIMUM OUTPUT	< >	-	-	NA	C	-	-	-				< >	< >	< >	< >	< >	< >	
DEHUMIDIFIER CONTROL	< >	SUPPLY AIR HUMIDITY	< >	-	< 0 - 100% RH >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
	< >	SUPPLY AIR TEMPERATURE SETPOINT	< >	< 55 DEG F >	-	NET-IN	NA	OC	VO	-				< >	< >	< >	< >	< >	< >	
OUTSIDE AIR UNIT CONTROL	< >	SUPPLY AIR TEMPERATURE	< >	-	< 0 - 100% >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
	< >	OUTSIDE AIR UNIT EXHAUST AIR DAMPER COMMAND	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y		TEMPERATURE DEVIATES FROM SETPOINT BY +/- 5 DEG F (ADJ.)	CRIT	< >	< >	< >	< >	< >	< >	
DEHUMIDIFIER CONTROL	< >	OUTSIDE AIR UNIT OUTSIDE AIR DAMPER COMMAND	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y				< >	< >	< >	< >	< >	< >	
	< >	OUTSIDE AIR UNIT INLET DAMPER COMMAND	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y				< >	< >	< >	< >	< >	< >	
OUTSIDE AIR UNIT CONTROL	< >	OUTSIDE AIR UNIT DISCHARGE AIR TEMPERATURE	< >	-	< -10 DEG F - 110 DEG F >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
	< >	OUTSIDE AIR UNIT DISCHARGE AIR DEW POINT	< >	-	< -10 DEG F - 110 DEG F >	AI	NA	-	V	Y				< >	< >	< >	< >	< >	< >	
DEHUMIDIFIER CONTROL	< >	OUTSIDE AIR UNIT DISCHARGE DAMPER COMMAND	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y				< >	< >	< >	< >	< >	< >	
	< >	SPACE RELATIVE HUMIDITY SETPOINT	< >	< 40% RH >	-	NET-IN	NA	OC	VO	-				< >	< >	< >	< >	< >	< >	
DEHUMIDIFIER CONTROL	< >	SPACE HUMIDITY	< >	-	< %RH >	NET-OUT	NA	-	V	-				< >	< >	< >	< >	< >	< >	
	< >	DEHUMIDIFIER BYPASS DAMPER COMMAND	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y		SPACE HUMIDITY RISES ABOVE SETPOINT BY 5% RH (ADJ.)	CRIT	< >	< >	< >	< >	< >	< >	
DEHUMIDIFIER CONTROL	< >	DEHUMIDIFIER INLET DAMPER COMMAND	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y				< >	< >	< >	< >	< >	< >	
	< >	DEHUMIDIFIER REACTIVATION AIR																		

G

F

E

D

C

B

A

AHU-2 SYSTEM POINTS SCHEDULE (CONTINUED)																						
FUNCTION	POINT NAME	DESCRIPTION	DDC HARDWARE ID	SETTINGS (WITH UNITS) NOTE 4	RANGE (WITH UNITS) NOTE 4	IO TYPE	HOA REQ'D	CONFIG. TYPE	M&C VIEW AND OVERRIDE	TENDR RECD	ALARMING				PRIMARY POINT INFORMATION		OVERRIDES		CONFIGURATION INFORMATION			
											ALARM CONDITION	ALARM PRIORITY	SNVT NAME	SNVT TYPE	NIAGARA ID	SNVT NAME	SNVT TYPE					
SCHEDULING	< >	SYSTEM OCCUPANCY SCHEDULE	-	-	MORNING/OCC/UNOCC	NET-IN	NA	OC	V	-	-	-	< >	< >	< >	< >	< >	< >	< >	< >		
	< >	OCCUPANCY COMMAND	-	-	MORNING/OCC/UNOCC	NET-IN	NA	-	VO	-	-	-	< >	< >	< >	< >	< >	< >	< >	< >		
	< >	SYSTEM OCCUPANCY (ACTUAL)	-	-	MORNING/OCC/UNOCC	NET-OUT	NA	-	V	-	-	-	< >	< >	< >	< >	< >	< >	< >	< >		
	< >	ATFP EMERGENCY SHUTDOWN SWITCH STATUS	< >	-	EMERGENCY/NORMAL	NET-OUT	NA	-	V	Y	-	-	ATFP EMERGENCY ALARM ACTIVATED	CRIT	< >	< >	< >	< >	< >	< >	< >	
	< >	OCCUPANCY OVERRIDE PUSH-BUTTON SWITCH STATUS	< >	-	OCCUPIED/NORMAL	NET-OUT	NA	-	V	Y	-	-	UNOCCUPIED MODE OVERRIDE INITIATED	INFO	< >	< >	< >	< >	< >	< >	< >	< >
	< >	SUPPLY FAN 1&2 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 3&4 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	RETURN FAN 1&2 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	RETURN FAN 3&4 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	DAMPER OPERATION TIME DELAY	-	< 30 SEC >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
< >	FAN SPOWDOWN TIME DELAY	-	< 60 SEC >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	SUPPLY AIR ISOLATION DAMPER	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	RETURN AIR ISOLATION DAMPER	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	UNIT HEATER FAN ON/OFF	< >	-	ON/OFF	DO	Y	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	FREEZE PROTECTION PUMP 2A START/STOP	< >	-	ON/OFF	DO	Y	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	FREEZE PROTECTION PUMP 2B START/STOP	< >	-	ON/OFF	DO	Y	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	MODE SWITCH SYSTEM STABILIZE TIME DELAY	-	< 300 SEC >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	SUPPLY AIR DUCT STATIC PRESSURE SETPOINT	< >	< 0.65" IN-W.C. >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	SUPPLY AIR DUCT STATIC PRESSURE	< >	< >	< 0 - ... IN-W.C. >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	SUPPLY FAN 1&2 VFD SPEED	< >	< >	0 - 100%	AO	NA	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	SUPPLY FAN 3&4 VFD SPEED	< >	< >	0 - 100%	AO	NA	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	SUPPLY FAN DISCHARGE PRESSURE	< >	< >	< 0 - 4 IN-W.C. >	AI	NA	-	V	Y	-	-	STATIC PRESSURE RISES ABOVE 3.00 IN-W.C. (ADJ.)	CRIT	< >	< >	< >	< >	< >	< >	< >		
SUPPLY FAN CONTROL	< >	PROPORTIONAL CONSTANT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	INTEGRAL CONSTANT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	BIAS	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	MAXIMUM OUTPUT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	MINIMUM OUTPUT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	SUPPLY FAN 1 AIRFLOW	< >	< >	< 0 - ... CFM >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 2 AIRFLOW	< >	< >	< 0 - ... CFM >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 3 AIRFLOW	< >	< >	< 0 - ... CFM >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY FAN 4 AIRFLOW	< >	< >	< 0 - ... CFM >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	RETURN FAN 1 AIRFLOW	< >	< >	< 0 - ... CFM >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
< >	RETURN FAN 2 AIRFLOW	< >	< >	< 0 - ... CFM >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	RETURN FAN 3 AIRFLOW	< >	< >	< 0 - ... CFM >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	RETURN FAN 4 AIRFLOW	< >	< >	< 0 - ... CFM >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	OCCUPIED AIRFLOW OFFSET VALUE	-	< 1600 CFM >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	OCCUPIED RETURN FAN AIRFLOW SETPOINT	-	< >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	MORNING & UNOCCUPIED AIRFLOW OFFSET VALUE	-	< 0 CFM >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	MORNING & UNOCCUPIED RETURN FAN AIRFLOW SETPOINT	-	< >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	RETURN FAN 1&2 VFD SPEED	< >	< >	0 - 100%	AO	NA	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	RETURN FAN 3&4 VFD SPEED	< >	< >	0 - 100%	AO	NA	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
< >	RETURN FAN INLET PRESSURE	< >	< >	< -3 - 0 IN-W.C. >	AI	NA	-	V	Y	-	-	STATIC PRESSURE FALLS BELOW 2.00 IN-W.C. (ADJ.)	CRIT	< >	< >	< >	< >	< >	< >	< >		
RETURN FAN PID LOOP SETTINGS	< >	PROPORTIONAL CONSTANT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	INTEGRAL CONSTANT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	BIAS	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	MAXIMUM OUTPUT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	MINIMUM OUTPUT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	RETURN AIR HUMIDITY	< >	< >	< 0 - 100% RH >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	RETURN AIR TEMPERATURE	< >	< >	< 0 - ... DEG F >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	MIXED AIR TEMPERATURE	< >	< >	< 0 - ... DEG F >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	PREHEAT COIL CONTROL VALVE COMMAND	< >	< >	0 - 100%	AO	NA	-	VO	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	PREHEAT COIL DISCHARGE TEMPERATURE SETPOINT	-	< 52 DEG F >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
SUPPLY AIR TEMPERATURE CONTROL	< >	PREHEAT COIL DISCHARGE TEMPERATURE	< >	< >	< 0 - ... DEG F >	AI	NA	-	V	Y	-	PREHEAT COIL DISCHARGE TEMP FALLS BELOW SETPOINT BY 5 DEG F (ADJ.)	INFO	< >	< >	< >	< >	< >	< >	< >	< >	
	< >	PROPORTIONAL CONSTANT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	INTEGRAL CONSTANT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	BIAS	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	MAXIMUM OUTPUT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	MINIMUM OUTPUT	-	< >	-	NA	C	-	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >		
	< >	SUPPLY AIR HUMIDITY	< >	< >	< 0 - 100% RH >	AI	NA	-	V	Y	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY AIR TEMPERATURE SETPOINT	-	RESET	< 53 - 65 DEG F >	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
	< >	SUPPLY AIR TEMPERATURE	< >	< >	< 0 - ... DEG F >	AI	NA	-	V	Y	-	-	TEMPERATURE DEVIATES FROM SETPOINT BY +/- 5 DEG F (ADJ.)	CRIT	< >	< >	< >	< >	< >	< >	< >	
	< >	MIXING BOX STATIC PRESSURE SETPOINT	-	< 0.25" IN-W.C. >	-	NET-IN	NA	OC	VO	-	-	-	-	-	< >	< >	< >	< >	< >	< >	< >	
OUTSIDE AIR RETURN AIR, AND RELIEF AIR DAMPER CONTROL	< >	MIXING BOX STATIC PRESSURE	< >	< >	< 0																	



G

F

E

D

C

B

A

HEATING WATER SYSTEM POINTS SCHEDULE													ALARMING				PRIMARY POINT INFORMATION				OVERRIDES		CONFIGURATION INFORMATION
FUNCTION	POINT NAME	DESCRIPTION	DDC HARDWARE ID	SETTINGS (WITH UNITS) NOTE 4	RANGE (WITH UNITS) NOTE 4	IO TYPE	HOA REQ'D	CONFIG. TYPE	M&C VIEW AND OVERRIDE	TREND RECD	ALARM CONDITION	ALARM PRIORITY	SNVT NAME	SNVT TYPE	NIAGARA ID	SNVT NAME	SNVT TYPE	CONFIGURATION INFORMATION					
PROOFS & SAFETIES	< >	BOILER B-1 STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y	BOILER B-1 PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >					
	< >	PUMP P-3 VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y	PUMP P-3 VFD PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >					
	< >	PUMP P-4 VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y	PUMP P-4 VFD PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >	< >				
	< >	BOILER B-1 ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y	BOILER B-1 GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >				
	< >	PUMP P-3 VFD ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y	PUMP P-3 VFD GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >				
	< >	PUMP P-4 VFD ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y	PUMP P-4 VFD GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >	< >			
SCHEDULING	< >	BOILER B-1 EMERGENCY SHUTDOWN SWITCH 1	< >	-	EMERGENCY/NORMAL	DI	NA	-	V	Y	BOILER EMERGENCY ALARM	CRIT	< >	< >	< >	< >	< >	< >					
	< >	BOILER B-1 EMERGENCY SHUTDOWN SWITCH 2	< >	-	EMERGENCY/NORMAL	DI	NA	-	V	Y	BOILER EMERGENCY ALARM	CRIT	< >	< >	< >	< >	< >	< >	< >				
START/STOP	< >	SYSTEM OCCUPANCY SCHEDULE	-	-	OCCUPIED/UNOCCUPIED	NET-IN	NA	OC	V	-	-	< >	< >	< >	< >	< >	< >	< >					
	< >	OCCUPANCY COMMAND	-	-	OCCUPIED/UNOCCUPIED	NET-IN	NA	-	VO	-	-	< >	< >	< >	< >	< >	< >	< >					
	< >	SYSTEM OCCUPANCY (ACTUAL)	-	-	OCCUPIED/UNOCCUPIED	NET-OUT	NA	-	V	-	-	< >	< >	< >	< >	< >	< >	< >					
	< >	SYSTEM MODE	-	-	EMERGENCY/NORMAL	NET-OUT	NA	-	V	-	-	< >	< >	< >	< >	< >	< >	< >					
	< >	OUTDOOR AIR TEMPERATURE	-	< DEG F >	-	NET-OUT	NA	-	V	-	-	< >	< >	< >	< >	< >	< >	< >					
	< >	BOILER COMBUSTION PERMISSIVE	< >	-	EMERGENCY/NORMAL	DO	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	BOILER B-1 ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	PUMP P-3 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	PUMP P-4 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >	< >				
	< >	BOILER ISOLATION VALVE 1	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >	< >				
	< >	BOILER ISOLATION VALVE 2	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >	< >				
	PUMP CONTROL	< >	HEAT EXCHANGER ISOLATION VALVE	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >				
< >		HEATING WATER SYSTEM DIFFERENTIAL PRESSURE SETPOINT	< >	< 10 PSI >	-	NET-IN	NA	OC	VO	-	-	< >	< >	< >	< >	< >	< >	< >					
< >		HEATING WATER SYSTEM DIFFERENTIAL PRESSURE	< >	-	< 0 - PSI >	AI	NA	-	V	Y	-	DIFFERENTIAL PRESSURE DEVIATES FROM SETPOINT BY +/- 20% (ADJ.)	CRIT	< >	< >	< >	< >	< >					
< >		PUMP P-3 VFD SPEED	< >	-	0 - 100%	AO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >					
< >		PUMP P-4 VFD SPEED	< >	-	0 - 100%	AO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >					
< >		MINIMUM FLOW BYPASS VALVE COMMAND	< >	-	0 - 100%	AO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >					
< >		PROPORTIONAL CONSTANT	-	< >	-	NA	C	-	-	-	-	< >	< >	< >	< >	< >	< >	< >					
< >		INTEGRAL CONSTANT	-	< >	-	NA	C	-	-	-	-	< >	< >	< >	< >	< >	< >	< >					
< >		BIAS	-	< >	-	NA	C	-	-	-	-	< >	< >	< >	< >	< >	< >	< >					
< >		MAXIMUM OUTPUT	-	< >	-	NA	C	-	-	-	-	< >	< >	< >	< >	< >	< >	< >					
BOILER & HEAT EXCHANGER CONTROL	< >	MINIMUM OUTPUT	-	< >	-	NA	C	-	-	-	< >	< >	< >	< >	< >	< >	< >	< >					
	< >	BOILER LEAVING WATER TEMPERATURE SETPOINT	< >	< 180 DEG F >	-	NET-IN	NA	OC	VO	-	-	< >	< >	< >	< >	< >	< >	< >					
	< >	BOILER LEAVING WATER TEMPERATURE	< >	< >	-	AO	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	BOILER LEAVING WATER TEMPERATURE	< >	< >	< 0 - 200 DEG F >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	HEAT EXCHANGER LEAVING WATER TEMPERATURE SETPOINT	< >	< 180 DEG F >	-	NET-IN	NA	OC	VO	-	-	< >	< >	< >	< >	< >	< >	< >					
	< >	HEAT EXCHANGER LEAVING WATER TEMPERATURE	< >	< >	< 0 - 200 DEG F >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	BOILER/HEAT EXCHANGER ENTERING WATER TEMPERATURE	< >	< >	< 0 - 200 DEG F >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	HEATING WATER TEMPERATURE SETPOINT	< >	RESET	< 180 - 180 DEG F >	NET-IN	NA	OC	VO	-	-	< >	< >	< >	< >	< >	< >	< >					
	< >	HEATING WATER SUPPLY TEMPERATURE	< >	< >	< 0 - 200 DEG F >	AI	NA	-	V	Y	-	HEATING WATER TEMPERATURE FALLS BELOW SETPOINT BY 5 DEG F (ADJ.)	CRIT	< >	< >	< >	< >	< >					
	< >	HEATING WATER RETURN TEMPERATURE	< >	< >	< 0 - 200 DEG F >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	HEAT EXCHANGER 1/3 CONTROL VALVE COMMAND	< >	-	0 - 100%	AO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	HEAT EXCHANGER 2/3 CONTROL VALVE COMMAND	< >	-	0 - 100%	AO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	INCOMING MEDIUM PRESSURE STEAM PRESSURE	< >	< >	< 0 - PSI >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	CULLUM HALL LOW PRESSURE STEAM PRESSURE	< >	< >	< 0 - PSI >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >					
< >	CULLUM HALL LOW PRESSURE STEAM FLOW	< >	< >	< 0 - LBSHR >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >						
< >	LINCOLN HALL LOW PRESSURE STEAM PRESSURE	< >	< >	< 0 - PSI >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >						
< >	LINCOLN HALL LOW PRESSURE STEAM FLOW	< >	< >	< 0 - LBSHR >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >						
< >	MAKE UP WATER FLOW	< >	< >	< 0 - GPM >	AI	NA	-	V	Y	-	< >	< >	< >	< >	< >	< >	< >						

NOTES:

1. THE CONTRACTOR MUST INCLUDE ALL DATA IN THIS SCHEDULE IN THE POINTS SCHEDULE GENERATED FOR THE CONTROLS SUBMITTAL. ADDITIONAL ROWS, COLUMNS, AND DATA MUST BE ADDED TO THE CONTRACTOR'S POINT SCHEDULE AS REQUIRED BY SPECIFICATION SECTION 23 09 00, PARAGRAPH 3.3.10.
2. THE ABBREVIATIONS "DI" AND "DO" ARE USED INTERCHANGEABLY WITH "BI" AND "BO" THROUGHOUT THE CONSTRUCTION DOCUMENTS.
3. THE SYMBOL "< >" DENOTES FIELDS REQUIRING CONTRACTOR ENTERED DATA. THE SYMBOL "-" DENOTES NO ENTRY REQUIRED. THE SYMBOL "NA" DENOTES NO VALID ENTRY AVAILABLE.
4. ALL SETTINGS AND RANGES MUST BE FULLY ADJUSTABLE. INITIAL VALUES PROVIDED IN THIS SCHEDULE MUST BE ADJUSTED BY THE CONTRACTOR AS REQUIRED FOR SYSTEM BALANCING AND TO PERMIT THE SYSTEMS TO PERFORM THEIR RESPECTIVE SEQUENCES OF OPERATION.

CHILLED WATER SYSTEM POINTS SCHEDULE													ALARMING				PRIMARY POINT INFORMATION				OVERRIDES		CONFIGURATION INFORMATION
FUNCTION	POINT NAME	DESCRIPTION	DDC HARDWARE ID	SETTINGS (WITH UNITS) NOTE 4	RANGE (WITH UNITS) NOTE 4	IO TYPE	HOA REQ'D	CONFIG. TYPE	M&C VIEW AND OVERRIDE	TREND RECD	ALARM CONDITION	ALARM PRIORITY	SNVT NAME	SNVT TYPE	NIAGARA ID	SNVT NAME	SNVT TYPE	CONFIGURATION INFORMATION					
PROOFS & SAFETIES	< >	CHILLER CH-1 STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y	CHILLER CH-1 PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >					
	< >	PUMP P-1 VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y	PUMP P-1 VFD PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >					
	< >	PUMP P-2 VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	NA	-	V	Y	PUMP P-2 VFD PROOF FAILED	CRIT	< >	< >	< >	< >	< >	< >					
	< >	CHILLER CH-1 ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y	CHILLER CH-1 GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >					
	< >	PUMP P-1 VFD ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y	PUMP P-1 VFD GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >					
	< >	PUMP P-2 VFD ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y	PUMP P-2 VFD GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >					
SCHEDULING	< >	GLYCOL FILL SYSTEM ALARM	< >	-	ALARM/NORMAL	DI	NA	-	V	Y	GLYCOL FILL SYSTEM GENERAL ALARM	CRIT	< >	< >	< >	< >	< >	< >					
	< >	HIGH SPACE HUMIDITY	-	-	ALARM/NORMAL	NET-OUT	NA	-	V	-	-	< >	< >	< >	< >	< >	< >						
START/STOP	< >	SYSTEM OCCUPANCY SCHEDULE	-	-	OCCUPIED/UNOCCUPIED	NET-IN	NA	OC	V	-	-	< >	< >	< >	< >	< >	< >						
	< >	OCCUPANCY COMMAND	-	-	OCCUPIED/UNOCCUPIED	NET-IN	NA	-	VO	-	-	< >	< >	< >	< >	< >	< >						
PUMP CONTROL	< >	SYSTEM OCCUPANCY (ACTUAL)	-	-	OCCUPIED/UNOCCUPIED	NET-OUT	NA	-	V	-	-	< >	< >	< >	< >	< >	< >						
	< >	CHILLER CH-1 ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	< >	< >	< >	< >	< >	< >						
	< >	PUMP P-1 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	< >	< >	< >	< >	< >	< >						
	< >	PUMP P-2 VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	< >	< >	< >	< >	< >	< >						
	< >	GLYCOL FILL SYSTEM ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	< >	< >	< >	< >	< >	< >						
	< >	HEAT EXCHANGER BYPASS VALVE	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >						
CHILLER & HEAT EXCHANGER CONTROL	< >	HEAT EXCHANGER ISOLATION VALVE	< >	-	OPEN/CLOSE	DO	NA	-	VO	Y	-	< >	< >	< >	< >	< >	< >	< >					
	< >	CHILLED WATER SYSTEM DIFFERENTIAL PRESSURE SETPOINT	< >																				

G

F

E

D

C

B

A

MISCELLANEOUS SYSTEMS POINTS SCHEDULE																	
FUNCTION	POINT NAME	DESCRIPTION	DDC HARDWARE ID	SETTINGS (WITH UNITS) NOTE 4	RANGE (WITH UNITS) NOTE 4	IO TYPE	HOA REQ'D	CONFIG. TYPE	M&C VIEW AND OVERRIDE	TREND REQ'D	ALARMING			PRIMARY POINT INFORMATION			CONFIGURATION INFORMATION
											ALARM CONDITION	ALARM PRIORITY	SNVT NAME	SNVT TYPE	NIAGARA ID	SNVT NAME	
<b>UNIT HEATERS (TYPICAL)</b>																	
	< >	UNIT HEATER STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	N/A	-	V	Y							
	< >	UNIT HEATER START/STOP	< >	-	ON/OFF	DO	N/A	-	VO	Y							
	< >	HOT WATER VALVE COMMAND	< >	-	0 - 100%	AO	N/A	-	VO	Y							
DETAIL A1/M807	HEATING COIL VALVE PID LOOP SETTINGS	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		BIAS	< >	-	-	N/A	C	-	-	-							
		MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		SPACE TEMPERATURE SETPOINT	< >	< 60 DEG F >	-	-	NET-IN	N/A	OC	VO	-	Y					
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
<b>HUMIDIFIERS DUCT-MOUNTED (TYPICAL)</b>																	
	< >	HUMIDIFIER ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y							
	< >	HUMIDIFIER DRAIN CYCLE STATUS	< >	-	ON/OFF	DI	N/A	-	V	Y							
	< >	HUMIDIFIER ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	N/A	-	VO	Y							
	< >	HUMIDIFIER OUTPUT	< >	-	< 0 - ___ LBS./HR. >	AI	N/A	-	V	Y							
DETAIL A4/M807	SPACE HUMIDITY SETPOINT	SPACE HUMIDITY	< >	< %RH >	-	NET-IN	N/A	OC	VO	-	Y						
		SPACE HUMIDITY	< >	-	< 0 - 100 %RH >	AI	N/A	-	V	Y							
		OUTDOOR AIR TEMPERATURE	< >	-	< -10 - 110 DEG F >	AI	N/A	-	V	Y							
		OUTDOOR AIR RELATIVE HUMIDITY	< >	-	< 0 - 100 %RH >	AI	N/A	-	V	Y							
		SUPPLY AIR DUCT TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
		SUPPLY AIR DUCT DEW POINT	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
	< >	SUPPLY AIR DUCT RELATIVE HUMIDITY HIGH LIMIT	< >	< 90% RH >	< 0 - 100 %RH >	AI	N/A	-	V	Y							
<b>COMPUTER ROOM UNITS WALL MOUNTED (TYPICAL)</b>																	
	< >	COMPUTER ROOM UNIT ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y							
	< >	COMPUTER ROOM UNIT ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	N/A	-	VO	Y							
DETAIL A8/M807	SPACE TEMPERATURE SETPOINT	SPACE TEMPERATURE	< >	< 72 DEG F >	-	NET-IN	N/A	OC	VO	-	Y						
		SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
		SPACE HUMIDITY SETPOINT	< >	< 15 %RH >	-	NET-IN	N/A	OC	VO	-	Y						
	< >	SPACE HUMIDITY	< >	-	< 0 - 100 %RH >	AI	N/A	-	V	Y							
<b>UTILITY METERS (TYPICAL)</b>																	
DETAIL D1/M807	< >	METER PULSE SIGNAL	< >	-	-	DI PULSE	N/A	-	V	Y							
<b>ENERGY METERS (TYPICAL)</b>																	
	< >	SYSTEM FLOW RATE	< >	-	< GPM >	AI	N/A	-	V	Y							
DETAIL D5/M807	< >	TOTAL ENERGY PULSE SIGNAL	< >	-	-	DI PULSE	N/A	-	V	Y							
	< >	ENERGY RATE	< >	-	< BTUH >	AI	N/A	-	V	Y							
<b>SUMP PUMPS (TYPICAL)</b>																	
DETAIL D8/M807	< >	SUMP PUMP ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y							
<b>RADIANT HEATING PANELS (TYPICAL)</b>																	
	< >	HOT WATER VALVE COMMAND	< >	-	OPEN/CLOSE	DO	N/A	-	VO	Y							
DETAIL F1/M807	SPACE TEMPERATURE SETPOINT	SPACE TEMPERATURE	< >	< 72 DEG F >	-	NET-IN	N/A	OC	VO	-	Y						
		SPACE TEMPERATURE	< >	< ___ DEG F >	-	AI	N/A	-	V	Y							
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
<b>HOT WATER HEATERS (TYPICAL)</b>																	
DETAIL F5/M807	< >	HOT WATER HEATER ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y							
<b>FLOOD PROTECTION VALVES (TYPICAL)</b>																	
DETAIL F3/M807	< >	FLOOD PROTECTION VALVE ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y							
<b>FAN COIL UNITS DUCTED (TYPICAL)</b>																	
	< >	FAN STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	N/A	-	V	Y							
	< >	CONDENSATE PAN HIGH LEVEL ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y							
	< >	CONDENSATE PAN HIGH LEVEL INDICATING LIGHT	< >	-	ON/OFF	DO	N/A	-	V	Y							
	< >	LEAK DETECTION ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y							
	< >	LEAK DETECTION INDICATING LIGHT	< >	-	ON/OFF	DO	N/A	-	V	Y							
	< >	FILTER DIFFERENTIAL PRESSURE	< >	< ___ IN-W.C. >	0 - 2 IN-W.C.	AI	N/A	-	VO	Y							
	< >	CHANGE FILTER INDICATING LIGHT	< >	-	ON/OFF	DO	N/A	-	V	Y							
	< >	FAN ON/OFF	< >	-	ON/OFF	DO	Y	-	VO	Y							
	< >	HEATING COIL VALVE COMMAND	< >	-	0 - 100%	AO	N/A	-	VO	Y							
DETAIL A2/M808	HEATING COIL VALVE PID LOOP SETTINGS	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		BIAS	< >	-	-	N/A	C	-	-	-							
		MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		COOLING COIL VALVE COMMAND	< >	-	-	0 - 100%	AO	N/A	-	VO	Y						
DETAIL A2/M808	COOLING COIL VALVE PID LOOP SETTINGS	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		BIAS	< >	-	-	N/A	C	-	-	-							
		MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		RETURN AIR DUCT TEMPERATURE	< >	< ___ DEG F >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y						
	< >	SPACE TEMPERATURE SETPOINT	< >	< 72 DEG F >	-	NET-IN	N/A	OC	VO	-	Y						
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
<b>FAN COIL UNITS NON-DUCTED (TYPICAL)</b>																	
	< >	FAN STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	N/A	-	V	Y							
	< >	CONDENSATE PAN HIGH LEVEL ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y							
	< >	CONDENSATE PAN HIGH LEVEL INDICATING LIGHT	< >	-	ON/OFF	DO	N/A	-	V	Y							
	< >	FILTER DIFFERENTIAL PRESSURE	< >	< ___ IN-W.C. >	0 - 2 IN-W.C.	AI	N/A	-	VO	Y							
	< >	CHANGE FILTER INDICATING LIGHT	< >	-	ON/OFF	DO	N/A	-	V	Y							
	< >	FAN ON/OFF	< >	-	ON/OFF	DO	Y	-	VO	Y							
	< >	HEATING COIL VALVE COMMAND	< >	-	0 - 100%	AO	N/A	-	VO	Y							
DETAIL A5/M808	HEATING COIL VALVE PID LOOP SETTINGS	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		BIAS	< >	-	-	N/A	C	-	-	-							
		MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		COOLING COIL VALVE COMMAND	< >	-	-	0 - 100%	AO	N/A	-	VO	Y						
DETAIL A5/M808	COOLING COIL VALVE PID LOOP SETTINGS	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		BIAS	< >	-	-	N/A	C	-	-	-							
		MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
		SPACE TEMPERATURE SETPOINT	< >	< 72 DEG F >	-	< 0 - 100 DEG F >	NET-IN	N/A	OC	VO	-	Y					
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
<b>VARIABLE VOLUME BOXES (TYPICAL)</b>																	
	< >	VAV BOX AIRFLOW	< >	< ___ CFM >	< 0 - ___ CFM >	AI	N/A	-	V	Y							
	< >	VAV DAMPER POSITION	< >	-	0 - 100%	AO	N/A	-	V	Y							
	< >	VAV DISCHARGE AIR TEMPERATURE	< >	< ___ DEG F >	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
	< >	REHEAT COIL VALVE COMMAND	< >	-	0 - 100%	AO	N/A	-	V	Y							
	< >	SPACE TEMPERATURE SETPOINT	< >	< 72 DEG F >	-	NET-IN	N/A	OC	VO	-	Y						
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
	< >	SPACE TEMPERATURE SETPOINT	< >	-	< 0 - 100 DEG F >	AI	N/A	-	VO	Y							
	< >	UNOCCUPIED MODE OVERRIDE	< >	-	OCCUPIED/NORMAL	DI	N/A	-	V	Y							
	< >	SPACE CO2 LEVEL	< >	-	< 0 - ___ PPM >	AI	N/A	-	V	Y							
DETAIL D8/M808	REHEAT COIL VALVE PID LOOP SETTINGS	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-							
		BIAS	< >	-	-	N/A	C	-	-	-							
		MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-							
	< >	SPACE TEMPERATURE SETPOINT	< >	< 72 DEG F >	-	NET-IN	N/A	OC	VO	-	Y						
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y							
<b>ATFP EMERGENCY SHUTDOWN</b>																	
DETAIL E2/M808	< >																



G

F

E

D

C

B

A

MISCELLANEOUS SYSTEMS POINTS SCHEDULE (CONTINUED)																	
FUNCTION	POINT NAME	DESCRIPTION	DDC HARDWARE ID	SETTINGS (WITH UNITS) NOTE 4	RANGE (WITH UNITS) NOTE 4	IO TYPE	HOA RECD	CONFIG TYPE	MISC-VIEW AND OVERRIDE	TEND RECD	ALARMING		PRIMARY POINT INFORMATION				CONFIGURATION INFORMATION
											ALARM CONDITION	ALARM PRIORITY	SVMT NAME	SVMT TYPE	NIAGARA ID	SVMT NAME	
<b>CONSTANT VOLUME BOXES (TYPICAL)</b>																	
	< >	VAV BOX AIRFLOW	< >	< _ CFM >	< 0 - 100 >	AI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	VAV DAMPER POSITION	< >	-	0 - 100%	AO	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	VAV DISCHARGE AIR TEMPERATURE	< >	< _ DEG F >	< 0 - 100 DEG F >	AI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	REHEAT COIL VALVE COMMAND	< >	-	0 - 100%	AO	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE SETPOINT	< >	< 72 DEG F >	-	NET-IN	N/A	OC	VO	-	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE SETPOINT	< >	-	< 0 - 100 DEG F >	AI	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	SPACE CO2 LEVEL	< >	< _ PPM >	-	AI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	BIAS	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
<b>REHEAT COIL VALVE PID LOOP SETTINGS</b>																	
	< >	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	BIAS	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE SETPOINT	< >	< 60 DEG F >	-	NET-IN	N/A	OC	VO	-	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
<b>CABINET UNIT HEATERS DUCTED (TYPICAL)</b>																	
	< >	FAN STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	FILTER DIFFERENTIAL PRESSURE	< >	< _ IN-W.C. >	0 - 2 IN-W.C.	AI	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	FAN ON/OFF	< >	-	ON/OFF	DO	Y	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	HEATING COIL VALVE COMMAND	< >	-	0 - 100%	AO	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	BIAS	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE SETPOINT	< >	< 60 DEG F >	-	NET-IN	N/A	OC	VO	-	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
<b>CABINET UNIT HEATERS NON-DUCTED (TYPICAL)</b>																	
	< >	FAN STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	FILTER DIFFERENTIAL PRESSURE	< >	< _ IN-W.C. >	0 - 2 IN-W.C.	AI	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	FAN ON/OFF	< >	-	ON/OFF	DO	Y	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	HEATING COIL VALVE COMMAND	< >	-	0 - 100%	AO	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	PROPORTIONAL CONSTANT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	INTEGRAL CONSTANT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	BIAS	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	MAXIMUM OUTPUT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	MINIMUM OUTPUT	< >	-	-	N/A	C	-	-	-	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE SETPOINT	< >	< 60 DEG F >	-	NET-IN	N/A	OC	VO	-	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
<b>EXHAUST FANS IN-LINE (TYPICAL)</b>																	
	< >	FAN STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	FAN INLET LOW PRESSURE SWITCH	< >	< _ IN-W.C. >	ALARM/NORMAL	DI	N/A	H	V	Y	-	-	< >	< >	< >	< >	
	< >	EXHAUST DAMPER STATUS (END SWITCH)	< >	-	OPEN/CLOSE	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	EXHAUST DAMPER COMMAND	< >	-	OPEN/CLOSE	DO	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	FAN START/STOP	< >	-	ON/OFF	DO	Y	-	VO	Y	-	-	< >	< >	< >	< >	
<b>VARIABLE FREQUENCY DRIVES FANS (TYPICAL)</b>																	
	< >	VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	VFD ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	VFD SPEED	< >	-	0 - 100%	AO	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	VFD MODE	< >	-	HAND/AUTO	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	OPEN DAMPERS COMMAND	< >	-	OPEN/CLOSE	DO	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	VFD MODE	< >	-	HAND/AUTO	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD OUTPUT SPEED	< >	-	< _ RPM >	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD OUTPUT FREQUENCY	< >	-	< _ HZ >	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD OUTPUT CURRENT	< >	-	< _ AMPS >	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD OUTPUT POWER	< >	-	< _ KW >	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD ENERGY USAGE	< >	-	< _ KWH >	NET-OUT	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	VFD COMMUNICATION LOSS	< >	-	ALARM/NORMAL	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
<b>VARIABLE FREQUENCY DRIVES PUMPS (TYPICAL)</b>																	
	< >	VFD STATUS (CURRENT SENSOR)	< >	-	ON/OFF	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	VFD ENABLE/DISABLE	< >	-	ENABLE/DISABLE	DO	Y	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	VFD ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	VFD SPEED	< >	-	0 - 100%	AO	N/A	-	VO	Y	-	-	< >	< >	< >	< >	
	< >	VFD MODE	< >	-	HAND/AUTO	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD OUTPUT SPEED	< >	-	< _ RPM >	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD OUTPUT FREQUENCY	< >	-	< _ HZ >	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD OUTPUT CURRENT	< >	-	< _ AMPS >	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD OUTPUT POWER	< >	-	< _ KW >	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	VFD ENERGY USAGE	< >	-	< _ KWH >	NET-OUT	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	VFD COMMUNICATION LOSS	< >	-	ALARM/NORMAL	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
<b>UPS MONITORING (TYPICAL)</b>																	
	< >	UPS ON	< >	-	ON/OFF	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	UPS ONLINE	< >	-	ONLINE/OFFLINE	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	UPS LOAD ON BYPASS	< >	-	BYPASS/NORMAL	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	UPS ALARM	< >	-	ALARM/NORMAL	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	UPS OFF (MAINTENANCE BYPASS)	< >	-	SERVICE/NORMAL	DI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE SETPOINT	< >	< _ DEG F >	-	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	SPACE TEMPERATURE	< >	-	< 0 - 100 DEG F >	AI	N/A	-	V	Y	-	-	< >	< >	< >	< >	
	< >	SPACE RELATIVE HUMIDITY SETPOINT	< >	< _ %RH >	-	NET-OUT	N/A	-	V	-	-	-	< >	< >	< >	< >	
	< >	SPACE RELATIVE HUMIDITY	< >	-	< 0 - 100 %RH >	AI	N/A	-	V	Y	-	-	< >				

