

CONSULTANTS:

MARK	DATE	DESCRIPTION
1	XX-XX-XX	FINAL BID DOCUMENT



DESIGNED BY: CAK	DRAWN BY: CAK	CHECKED BY: BMC	REVIEWED BY: AEH
PROJECT NO: IRSD1903	DATE: OCTOBER 2021	SCALE: AS SHOWN	

CLIENT
Irvington Union Free School District

Facilities Storage Building at Irvington Campus



Irvington Campus
40 N. Broadway
Irvington, NY 10533

SED Number:66-04-02-02-2-022-001

CONTRACT
**CONTRACT G
GENERAL CONSTRUCTION**

STATUS
FINAL BID DOCUMENT

SHEET TITLE
**HVAC
HIGH SCHOOL FACILITIES
STORAGE BUILDING HVAC
CONSTRUCTION**


DRAWING No.
H1.0

GENERAL NOTES

- THESE DRAWINGS SERVE AS A GRAPHICAL REPRESENTATION OF THE INTENDED SCOPE OF WORK AND CONSTITUTE ONE PORTION OF THE CONSTRUCTION DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION BETWEEN THESE DRAWINGS AND THE SPECIFICATIONS.
- ALL WORK SHALL BE IN COMPLIANCE WITH ALL FEDERAL AND NEW YORK STATE APPLICABLE BUILDING CODE.
- REFER TO SEQUENCE OF OPERATIONS FOR DETAILS REGARDING EXHAUST FAN (GX-1) CONTROLS.
- ALL WORK SHALL BE IN COMPLIANCE WITH MANUFACTURER'S CLEARANCE REQUIREMENTS.
- DO NOT SCALE DRAWINGS. LINE WORK IS SHOWN FOR REFERENCE ONLY.
- COORDINATE FINAL LOCATIONS OF SENSORS / SWITCHES WITH OWNER.
- COORDINATE NEW WORK WITH OTHER TRADES.


KEY WORK NOTES

- PROVIDE AND INSTALL NEW ELECTRIC UNIT HEATER EUH-1, 2 WITH APPROPRIATE MOUNTING HARDWARE. MOUNT NEW ELECTRIC UNIT HEATER AS PER MANUFACTURER'S SPECIFICATIONS.
- PROVIDE AND INSTALL NEW SIDEWALL EXHAUST FAN GX-1 WITH APPROPRIATE MOUNTING HARDWARE. MOUNT NEW SIDEWALL EXHAUST FAN AS PER MANUFACTURER'S SPECIFICATIONS. COORDINATE FINAL HEIGHT WITH ARCHITECTURAL / STRUCTURAL PLANS, AND EXISTING SLOPE OF GRADE.
- PROVIDE AND INSTALL NEW SIDEWALL INTAKE LOUVER 'A' WITH APPROPRIATE MOUNTING HARDWARE. MOUNT NEW SIDEWALL INTAKE LOUVER AS PER MANUFACTURER'S SPECIFICATIONS. COORDINATE FINAL HEIGHT WITH ARCHITECTURAL / STRUCTURAL PLANS, AND EXISTING SLOPE OF GRADE.
- NEW MOTORIZED DAMPER SHALL BE INTERLOCKED WITH NEW EXHAUST FAN GX-1. DAMPER SHALL OPEN WHEN GX-1 ACTIVATES (REFER TO SPECIFICATIONS AND ELECTRICAL DRAWINGS FOR DETAILS).



NOTE:
1. MAINTAIN MINIMUM CLEARANCE BETWEEN FAN PROPELLER AND LOUVER AS PER MANUFACTURER'S INSTALLATION MANUAL. PROVIDE SPACERS AS NECESSARY TO MAINTAIN CLEARANCE CALLED FOR IN MANUAL.

2 Sidewall Fan with OSHA Guard
SCALE: NTS (DETAIL #)



1 Facilities Storage Building Plan
SCALE: 1/4"=1'-0"

EQUIPMENT NO.	LOCATION	AREA SERVED	FAN DATA		AIR DATA		HEATING COIL DATA			BASIS OF DESIGN INFORMATION				REMARKS		
			FLOW (CFM)	HP	VOLTS/PHASE	TOTAL CAPACITY (MBH)	TEMP. CHANGE (DEG. F)	THROW (FT.)	ELECTRIC DATA			MNF	MODEL NO.		NOMINAL DIMENSIONS L x W x H	NOMINAL OPERATING WEIGHT (LBS.)
									VOLTS/PHASE	TOTAL KW	AMPS					
EUH-1, 2	SEE PLANS	STORAGE AREA	650	1/30	208/1	25.6	37	18	208/1	7.5	36	QMARK	MUH-07-8	19 x 7.5 x 21.75	38	1-4


- NOTES:
- PROVIDE AND INSTALL MANUFACTURER SPECIFIED MOUNTING BRACKET
 - SINGLE POLE INTERNAL THERMOSTAT ACCESSORY (UHM1)
 - 3-POLE POWER DISCONNECT SWITCH (MPD560)
 - OUTLET MESH (BIRD SCREEN)

EQUIPMENT NO.	LOCATION	SYSTEM SERVED	PERFORMANCE/CONSTRUCTION REQUIREMENTS				BASIS OF DESIGN INFORMATION					REMARKS	
			CFM	EXT S. P. (IN. W.C.)	FAN/MOTOR RPM	BHP	MNF	MODEL NO.	NOMINAL DIMENSION L x W x H	NOMINAL OPERATING WEIGHT (LBS.)	ELECTRICAL DATA		
											VOLTS/PHASE		MOTOR HP
GX-1	SEE PLANS	STORAGE AREA	690	0.3	776	0.18	GREENHECK	SBE-1H20-4	38 x 26.25 x 26.25	152	115/1	1/4	1-4

- NOTES:
- LONG WALL HOUSING WITH OSHA GUARD
 - NEMA 3R POWERED DISCONNECT SWITCH
 - DAMPER MOUNTED WD-320-PB-22X22
 - SINGLE POINT POWER CONNECTION
 - DAMPER ACTUATOR (MP-310)

DESIGNATION	TYPE	BASIS OF DESIGN: MANUFACTURER	BASIS OF DESIGN: MODEL NO.	NOM. DIMENSIONS	FREE AREA (%)	VOLUME (CFM)	FREE AREA VELOCITY (FPM)	PRESSURE DROP (IN. W.G.)	REMARKS
A	INTAKE LOUVER	GREENHECK	ESD-635HP	20 x 20 x 6	42.5	690	566	0.05	1-3

- NOTES:
- (20x20) VCD-23 LOW LEAKAGE 3V BLADE VOLUME CONTROL DAMPER
 - HONEYWELL MS4103F1225 ACTUATOR
 - GREENHECK POC RETAINING ANGLE



Key Plan
SCALE: N.T.S.

IRSD (Irvington U.F.S.D.) 1903 (HVAC Facilities Storage Building) HVAC Construction, High School, Facilities Storage Building HVAC Construction, Oct 18, 2021, 3:03pm, Project on Oct 18, 2021, 4:33pm by caulis