SUNY Orange - Middletown Campus George Shepard Student Center Chiller Replacement, OCCC Project # OCCC-2021-25 FE Project # 20-357

SECTION 01 5000 - TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 SECTION REQUIREMENTS

- A. Use Charges: Contractor shall pay for all use charges except as noted otherwise.
- B. Use water and electric power from Owner's existing system without metering and without payment of use charges.
- C. Standards: Comply with ANSI A10.6, NECA's "Temporary Electrical Facilities," and NFPA 241.
- D. Temporary Utilities: At earliest feasible time, when acceptable to Owner, change over from use of temporary service to use of permanent service.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- A. Heating Equipment: Unless Owner authorizes use of permanent heating system, provide vented, self-contained heaters with thermostatic control when working in new or existing facilities to maintain an indoor temperature of 50 degrees F.
 - 1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
 - 2. Heating Units: Listed and labeled, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use for type of fuel being consumed.

PART 3 - EXECUTION

3.1 TEMPORARY UTILITIES

- A. General: Use owner's facilities where available and as noted. Engage appropriate local utility company to install temporary service or connect to existing service where owner's facilities are insufficient for the use. Where utility company provides only part of the service, provide the remainder.
- B. Sanitary Facilities: Use of Owner's existing facilities will be permitted, as long as facilities are cleaned and maintained in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.



SUNY Orange - Middletown Campus George Shepard Student Center Chiller Replacement, OCCC Project # OCCC-2021-25 FE Project # 20-357

C. Heating and Cooling: Provide temporary heating and cooling required for curing materials or for protecting installed construction from adverse weather. Use equipment that will not have a harmful effect on completed installations or elements being installed.

3.2 TEMPORARY FACILITIES

- A. Provide field offices, storage trailers, and other support facilities as necessary for the Work.
- B. Collect waste daily and, when containers are full, legally dispose of waste off-site.
 - 1. Handle hazardous, dangerous, or unsanitary waste materials in separate closed waste containers. Dispose of material according to applicable laws and regulations.
- C. Provide temporary enclosures for protection of construction and workers from inclement weather and for containment of heat.

3.3 TEMPORARY CONTROLS

- A. Provide temporary environmental controls as required by authorities having jurisdiction including, but not limited to, erosion and sediment control, dust control, noise control, and pollution control.
- B. Provide temporary barricades, warning signs, and lights to protect the public and construction personnel from construction hazards.
 - 1. Enclose construction areas with fences with lockable entrance gates, to prevent unauthorized access.
- C. Provide temporary fire protection until permanent systems supply fire-protection needs. Comply with NFPA 241.

3.4 TERMINATION AND REMOVAL

A. Remove temporary facilities and controls before Substantial Completion. Personnel remaining after Substantial Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

END OF SECTION