

UNIT VENTILATOR SCHEDULE

TAG	LOCATION	TYPE	AIRSIDE PERFORMANCE			HYDRONIC PERFORMANCE							COOLING PERFORMANCE					MANUFACTURER & MODEL NO.	NOTES							
			FAN SPEED SETTING	MIN. O.A. (CFM)	CAPACITY (MBH)	E.A.T. (°F)	L.A.T. (°F)	E.W.T. (°F)	W.T. (°F)	FLOW RATE (GPM)	W.P.D. (FT.)	FLUID	ROWS	TOTAL MBH	SENSIBLE MBH	EAT (DB/WH)	LAT (DB/WH)			REFRIGERANT	VOLT	PHASE	MCA	MAX FUSE		
UV-201	SECOND FL	FLOOR	MED	1250	448	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-202	SECOND FL	FLOOR	MED	1250	448	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-203	SECOND FL	FLOOR	MED	1250	448	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-204	SECOND FL	FLOOR	MED	1250	448	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-208	SECOND FL	FLOOR	MED	1250	448	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-209	SECOND FL	FLOOR	MED	1250	448	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-210	SECOND FL	FLOOR	MED	1250	448	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-211	SECOND FL	FLOOR	MED	1250	448	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-212	SECOND FL	FLOOR	HIGH	1500	797	104	35	100	180	110.4	3	3.5	HW	3	48	34	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-213	SECOND FL	FLOOR	HIGH	1500	770	104	35	100	180	110.4	3	3.5	HW	3	48	34	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-216	SECOND FL	FLOOR	MED	1250	413	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8
UV-304	SECOND FL	FLOOR	MED	1250	403	72	42	100	180	107.3	2	3.5	HW	3	41	26	80/67	55/94	DX	R-410A	208	3	30.1	45	DANKIN – AZD 054	1,2,3,4,5,6,7,8

- REMARKS:
1. PROVIDE MANUFACTURERS DISCONNECT, FACTORY MOUNTED AND WHELED.
 2. PROVIDE UNIT WITH FACTORY MOUNTED THREE SPEED SWITCH SET TO DOWN LOW INDICATED.
 3. PROVIDE UNIT WITH FACE AND BYPASS.
 4. UNIT TO COME WITH FACTORY MOUNTED TECH CONTROLLER.
 5. PROVIDE 1/2" X 1/2" X 1/2" GALV. UNFINISHED ROOM SECTION, PT # 710247460.
 6. PROVIDE SEE DRAMA PANEL.
 7. PROVIDE SEE DRAMA PANEL.
 8. PROVIDE MANUFACTURERS WALL SLEEVES.



Architect:
Hamlin Design Group
915 Broadway, Suite 101A
Albany, New York 12207
Tel: 518.724.5159
Fax: 518.320.8833
Web: hamlindesigngroup.com



Hazardous Material Consultant:
Hazardous Waste Management, Inc.
1000 West 10th Street
Albany, New York 12206
Tel: 518.320.8833
Fax: 518.320.8833
Web: hwmhazmat.com

MEP Engineer:

Engineered Solutions
1000 West 10th Street
Albany, New York 12206
Tel: 518.320.8833
Fax: 518.320.8833
Web: engineered-solutions.net
E: es@engineered-solutions.net
C: es@engineered-solutions.net
F: es@engineered-solutions.net
es@engineered-solutions.net

Client:



Peekskill City School District
1031 Elm St.
Peekskill, NY 10566

Peekskill Reconstruction

SED Project: 66-15-00-01-0-005-020

HOG Project: 201

Peekskill Elementary

201 Elm St.

Peekskill, NY 10566

SED Project: 66-15-00-01-0-007-014

HOG Project: 202

Uriah Hill School

980 Remart Ave.

Peekskill, NY 10566

SED Project: 66-15-00-01-0-008-017

HOG Project: 203

Woodside Elementary

612 Dugan St.

Peekskill, NY 10566

SED Project: 66-15-00-01-0-014-005

HOG Project: 204

Middle School

212 Ringgold St.

Peekskill, NY 10566

DRAWN BY:

MLB

ISSUE: 02/01/2021
REV:



DESCRIPTION

HVAC Schedules

O-M.002.00