GENERAL NOTE:
COORDINATE WITH ELECTRICAL AND MECHANICAL DRAWINGS. OWNER'S AV DRAWINGS CAN BE PROVIDED UPON REQUEST.

CEILING FIXTURE LEGEND

R1 — **RECESSED DIRECTIONAL LIGHT:**
BASIS OF DESIGN: LUMENWERX - VOILA 4" ROUND DOWNLIGHT.
VO4RR-OF-ADJ-UNV-14W-D1-VO4-SW-60-2-80-35-LS-VO4RR-SDL-SR-TMW-TRM-TMW

R8 — **8' LINEAR 4" WIDE RECESSED FIXTURE WITH LOUVERS for INTEGRATION with ARMSTRONG TECHZONE GRID:**
BASIS OF DESIGN: ACUITY BRANDS - MARK ARCHITECTURAL LIGHTING
SLOT 4 LED DESIGN2SHIP - RECESSED LINEAR.
SL4L-QS-LOP-8FT-RLP-TG-80CRI-35K-800LMF-MIN1-ZT

P4 — **8' DIRECT/INDIRECT LINEAR PENDANT**
BASIS OF DESIGN: AXIS SCULPT D/I PENDANT
AXIS SCDI-350-400-80-35-BW-FL-8'-W-UNV-DP-2-CT9(36)

ALTERNATE: MARK ARCHITECTURAL LIGHTING SLOT 1
S1U LLP 8FT MSL8 190CRI 85K 1200LMF BW MIN1
MVOLT WHT WECZT F1/36A RDCY WHTCY WCRD

P5 — **4' DIRECT/INDIRECT LINEAR PENDANT**
BASIS OF DESIGN: AXIS SCULPT D/I PENDANT
AXIS SCDI-350-400-80-35-BW-FL-4'-W-UNV-DP-2-CT9(36)

ALTERNATE: MARK ARCHITECTURAL LIGHTING SLOT 1
S1U LLP 4FT MSL4 190CRI 85K 1200LMF BW MIN1
MVOLT WHT WECZT F1/36A RDCY WHTCY WCRD

P9-W — **ACCENT PENDANT WHITE:**
BROWNLEE LIGHTING - INNIE LED.
2680-20-tbd-45W-tbd-SSM-NT-35K

CEILING FINISHES LEGEND

CEILING MATERIAL

CLG-1 — **2X2 ACOUSTIC CEILING TILE**
ARMSTRONG OPTIMA 2x2 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 3152 - WHITE

CLG-2 — PAINTED GYP BOARD

CEILING TILE PATTERNS
BASIS OF DESIGN: ARMSTRONG DESIGNFLEX - LYRA PB - WITH TECHZONE

CLG-5A — **2X4 ACOUSTIC CEILING TILE**
LYRA PB 2x4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8373PB - TILE PAINT COLOR SW 6716

CLG-5B — **2X2 ACOUSTIC CEILING TILE**
LYRA PB 2x2 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8372PB - TILE PAINT COLOR SW 6716

CLG-5C — **4IN ACOUSTIC CEILING TILE**
TECHZONE PANEL w/ LYRA PB 4INx4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8334PB - TILE PAINT COLOR SW 6716

CLG-6A — **2X4 ACOUSTIC CEILING TILE**
LYRA PB 2x4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8373PB - TILE PAINT COLOR SW 6780

CLG-6B — **2X2 ACOUSTIC CEILING TILE**
LYRA PB 2x2 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8372PB - TILE PAINT COLOR SW 6780

CLG-6C — **4IN ACOUSTIC CEILING TILE**
TECHZONE PANEL w/ LYRA PB 4INx4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8334PB - TILE PAINT COLOR SW 6780

A/V FIXTURES - COORDINATE WITH OWNER'S A/V CONTRACTOR

THIS DRAWING SHOWN FOR ARCHITECTURAL COORDINATION PURPOSES ONLY. SEE ELECTRICAL DRAWINGS. OWNER'S AV DRAWINGS CAN BE PROVIDED UPON REQUEST. ALL POWER, DATA, COPPER WIRE FOR TELECOIL LOOP SYSTEM, AND A/V CONDUIT TO BE BY ELECTRICAL CONTRACTOR.

PROJECTORS AND DISPLAYS

WM — **WALL- MOUNTED PROJECTION SCREEN (BY OWNER):**
BASIS OF DESIGN: DALITE 70199LS TENSIONED CONTOUR ELECTROL, WIDE SCREEN FORMAT, 87"x139".
PROVIDE BLOCKING.

PSE — **CEILING- MOUNTED PROJECTION SCREEN (BY OWNER):**
BASIS OF DESIGN: DALITE DENSIONED ADVANTAGE.
PROVIDE BLOCKING. (SEE INTERIOR ELEVATIONS & RCP)

GS — **CEILING- MOUNTED GREEN SCREEN (BY OWNER):**
BASIS OF DESIGN: DA LITE 70199LS WIDE SCREEN FORMAT, 87"x139". PROVIDE BLOCKING.

VP1 — **CEILING-MOUNTED 6000 LUMEN PROJECTOR (BY OWNER):**
BASIS OF DESIGN: EPSON POWERLITE L615U;
CEILING MOUNTED WUXGA PROJECTOR. PROVIDE BLOCKING.

FP — **WALL-MOUNTED LCD DISPLAY (BY OWNER):**
BASIS OF DESIGN: SHARP, & CHIEF MANUFACTURING. PROVIDE BLOCKING.

SPEAKERS

SP1 — **CEILING-MOUNTED LOUDSPEAKER (BY OWNER):**
BASIS OF DESIGN: FULCRUM ACOUSTIC GX1595 and TQP-48. PROVIDE BLOCKING.

SS — **CEILING-RECESSED AUDIO SPEAKER (BY OWNER):**
BASIS OF DESIGN: COMMUNITY D6 - WHITE. PROVIDE BLOCKING.

L — **CEILING-MOUNTED LINEAR ARRAY SPEAKER (BY OWNER):**
BASIS OF DESIGN: INNOVEX FLEX FOCUS FF-V2.6. PROVIDE BLOCKING.

(ELEV.) (PLAN) — **WALL MOUNTED SPEAKER (BY OWNER):**
BASIS OF DESIGN: INNOVEX MICRO-FOCUS 2.1.
PROVIDE BLOCKING.(SEE INTERIOR ELEVATIONS AND RCP)

ACCESSORIES

(RCP) (PLAN) — **AV EQUIPMENT CEILING RACK (BY OWNER) :**
ADD PRODUCT: BASIS OF DESIGN: ATLAS CR222-NR.
PROVIDE BLOCKING. ATLAS IED CR SERIES CEILING RACK SYSTEMS WITH AmbiTILT EQUIPMENT LOADING (SEE INTERIOR ELEVATIONS AND RCP)

(ELEV.) (PLAN) — **WALL MOUNTED DIGITAL CLOCK: (SEE ELEC. DRAWING)**
WALL MOUNTED, BATTERY POWERED, DIGITAL CLOCK BY GC
PROVIDE BLOCKING. (SEE INTERIOR ELEVATIONS AND COORDINATE w/ POWER PLAN)

(ELEV.) (PLAN) — **IP PHONE: (SEE ELEC. DRAWING)**
BASIS OF DESIGN: CISCO.
PROVIDE BLOCKING. (SEE INTERIOR ELEVATIONS AND COORDINATE w/ POWER PLAN)

(ELEV.) (PLAN) — **TOUCH CONTROL PANEL (BY OWNER)**
EXTRON MLC PLUS 100. (SEE INTERIOR ELEVATIONS AND POWER & TECH PLAN)

TELECOIL LOOP (ALTERNATE A) :
BY ELECTRICAL CONTRACTOR. AUDIO INDUCTION LOOP AIDS ASSISTIVE LISTENING TECHNOLOGY. CONSISTS OF PHYSICAL CABLE LOOPS PLACED AROUND DESIGNATED SPACES. (SEE ELECTRICAL DRAWINGS)

(ELEV.) (PLAN) — **IPAD KIOSK (BY OWNER)**
BASIS OF DESIGN: IPAD. (SEE INTERIOR ELEVATIONS AND POWER & TECH PLAN)

(ELEV.) (PLAN) — **MONITER WITH KETBOARD & MOUSE KIOSK (BY OWNER)**
BASIS OF DESIGN: IMAC. (SEE INTERIOR ELEVATIONS AND POWER & TECH PLAN)

Revision Schedule

No.	Description	Date
A	SED SUBMISSION	10/23/2020
E	ADDITIONS: ISSUED FOR BID	08/10/2021

Geddis Architects
Architecture. Planning. Interiors
71 Old Post Road
P.O. Box 1020
Southport, CT 06890
(203) 256-8700

Fielding International
Transforming Education by Design
259 Water Street Suite 1L
Warren , RI 02885 USA
+1 401-289-2789

BARILE GALLAGHER & ASSOCIATES
CONSULTING ENGINEERS
39 MARBLE AVE PLEASANTVILLE, NY 10570
914.328.6060 GENERAL@BGA-ENG.com www.BGA-ENG.com

Construction Manager
SAVIN ENGINEERS, P.C.
3 Campus Drive
Pleasantville, NY 10570
914-769-3200

Structural Engineer
ODEH ENGINEERS
1223 Mineral Spring Ave
North Providence, RI 02904
401-724-1771

Civil Engineer
WESTON & SAMPSON
1 Winners Circle, Suite 130
Albany, NY 12205
518-463-4400

Roof Consultant
WATSKY ASSOCIATES INC.
20 Madison Ave
Valhalla, NY 10595
914-948-3450

Acoustic Consultant
DP DESIGN
12 Cold Spring Street
Providence, RI
401-861-3218

AV Consultant
CAVANAUGH TOCCI
327 F Boston Post Road
Sudbury, MA 01776-3027
978-443-7871

SED#: 6618-0001-0003-026

PROJECT
Rye City Schools
555 Theodore Fremd Ave, Rye, NY 10580

Midland Elementary School

312 Midland Ave, Rye NY 10580

CEILING FIXTURE AND MATERIAL LEGENDS

Approver

SEAL & SIGNATURE

DATE: 06/29/20
PROJECT No: 9200
DRAWING BY: Author
CHK BY: Checker
DWG No:
A3-400

GENERAL NOTE:
COORDINATE WITH ELECTRICAL AND MECHANICAL DRAWINGS. OWNER'S AV DRAWINGS CAN BE PROVIDED UPON REQUEST.

CEILING FIXTURE LEGEND

R1 — **RECESSED DIRECTIONAL LIGHT:**
BASIS OF DESIGN: LUMENWERX - VOILA 4" ROUND DOWNLIGHT.
VO4RR-OF-ADJ-UNV-14W-D1-VO4-SW-80-2-80-35-LS-VO4RR-SDL-SR-TMW-TRM-TMW

R8 — **8' LINEAR 4" WIDE RECESSED FIXTURE WITH LOUVERS for INTEGRATION with ARMSTRONG TECHZONE GRID:**
BASIS OF DESIGN: ACUITY BRANDS - MARK ARCHITECTURAL LIGHTING
SLOT 4 LED DESIGN2SHIP - RECESSED LINEAR.
SL4L-QS-LOP-8FT-RLP-TG-80CRI-35K-800LMF-MIN1-ZT

P6 — **8' DIRECT/INDIRECT LINEAR PENDANT WITH LOUVERS:**
BASIS OF DESIGN: AXIS STENCIL DI PENDANT
AXIS STLDI-SLI-500-DML-600-8-80-35-W-IJNV

ALTERNATE: MARK ARCHITECTURAL LIGHTING SLOT 1 S4LIDLCB 8FT MSL8 80CRI 35K 800LMF 180CRI 35K 800LMF 8W MIN1 SCT LVRRA SLV F1 36A RDCY SLVCY WCRD

P7 — **6' DIRECT/INDIRECT LINEAR PENDANT WITH LOUVERS:**
BASIS OF DESIGN: AXIS STENCIL DI PENDANT
AXIS STLDI-SLI-500-DML-600-6-80-35-W-IJNV

ALTERNATE: MARK ARCHITECTURAL LIGHTING SLOT 1 S4LIDLCB 6FT MSL8 80CRI 35K 800LMF 180CRI 35K 800LMF 8W MIN1 SCT LVRRA SLV F1 36A RDCY SLVCY WCRD

P9-W — **ACCENT PENDANT WHITE:**
BROWNLEE LIGHTING - INNIE LED.
2680-20-tbd-45W-tbd-SSM-NT-35K

P10 — **GLASS CYLINDER PENDANT:**
ACUITY BRANDS - HEALTHCARE LIGHTING - POPS SINGLE PENDANT
HPP1-9ST-MVOLT-CYL-LRG-35K-ZT-MIN5-INT-BA

CEILING FINISHES LEGEND

CEILING MATERIAL

CLG-1 — **2X2 ACOUSTIC CEILING TILE**
ARMSTRONG OPTIMA 2x2 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 3152 - WHITE

CLG-2 — PAINTED GYP BOARD

CEILING TILE PATTERNS
BASIS OF DESIGN: ARMSTRONG DESIGNFLEX - LYRA PB - WITH TECHZONE

CLG-5A — **2X4 ACOUSTIC CEILING TILE**
LYRA PB 2x4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8373PB - TILE PAINT COLOR SW 6716

CLG-5B — **2X2 ACOUSTIC CEILING TILE**
LYRA PB 2x2 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8372PB - TILE PAINT COLOR SW 6716

CLG-5C — **4IN ACOUSTIC CEILING TILE**
TECHZONE PANEL w/LYRA PB 4INx4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8334PB - TILE PAINT COLOR SW 6716

CLG-6A — **2X4 ACOUSTIC CEILING TILE**
LYRA PB 2x4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8373PB - TILE PAINT COLOR SW 6780

CLG-6B — **2X2 ACOUSTIC CEILING TILE**
LYRA PB 2x2 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8372PB - TILE PAINT COLOR SW 6780

CLG-6C — **4IN ACOUSTIC CEILING TILE**
TECHZONE PANEL w/LYRA PB 4INx4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8334PB - TILE PAINT COLOR SW 6780

CLG-7 — **4IN ACOUSTIC CEILING TILE**
TECHZONE PANEL w/LYRA PB 4INx4 CEILING TILE WITH PRELUDE 15/16" SUSPENSION SYSTEM - 8334PB - WHITE

A/V FIXTURES - COORDINATE WITH OWNER'S A/V CONTRACTOR

THIS DRAWING SHOWN FOR ARCHITECTURAL COORDINATION PURPOSES ONLY. SEE ELECTRICAL DRAWINGS. OWNER'S AV DRAWINGS CAN BE PROVIDED UPON REQUEST. ALL POWER, DATA, COPPER WIRE FOR TELECOIL LOOP SYSTEM, AND A/V CONDUIT TO BE BY ELECTRICAL CONTRACTOR.

PROJECTORS AND DISPLAYS

WM — **WALL - MOUNTED PROJECTION SCREEN (BY OWNER):**
BASIS OF DESIGN: DALITE 70199LS TENSIONED CONTOUR ELECTROL, WIDE SCREEN FORMAT, 87"x139".
PROVIDE BLOCKING.

CM — **CEILING- MOUNTED PROJECTION SCREEN (BY OWNER):**
BASIS OF DESIGN: DALITE TENSIONED ADVANTAGE.
PROVIDE BLOCKING. (SEE INTERIOR ELEVATIONS & RCP)

GS — **CEILING- MOUNTED GREEN SCREEN (BY OWNER):**
BASIS OF DESIGN: DALITE 70199LS
WIDE SCREEN FORMAT, 87"x139". PROVIDE BLOCKING.

VP1 — **CEILING-MOUNTED 6000 LUMEN PROJECTOR (BY OWNER):**
BASIS OF DESIGN: EPSON POWERLITE L615U
CEILING MOUNTED WUXGA PROJECTOR. PROVIDE BLOCKING.

FP — **WALL-MOUNTED LCD DISPLAY (BY OWNER):**
BASIS OF DESIGN: SHARP, CHIEF MANUFACTURING. PROVIDE BLOCKING.

SPEAKERS

SP1 — **CEILING-MOUNTED LOUDSPEAKER (BY OWNER):**
BASIS OF DESIGN: FULCRUM ACOUSTIC GX1595 and TQP-48. PROVIDE BLOCKING.

S2 — **CEILING-RECESSED AUDIO SPEAKER (BY OWNER):**
BASIS OF DESIGN: COMMUNITY D6 - WHITE. PROVIDE BLOCKING.

LA (RCP) (PLAN) — **CEILING-MOUNTED LINEAR ARRAY SPEAKER (BY OWNER):**
BASIS OF DESIGN: INNOVEX FLEC FOCUS FF-V2.6. PROVIDE BLOCKING.

(ELEV.) (PLAN) — **WALL MOUNTED SPEAKER (BY OWNER):**
BASIS OF DESIGN: INNOVEX MICRO - FOCUS 2.1. PROVIDE BLOCKING.(SEE INTERIOR ELEVATIONS AND RCP)

ACCESSORIES

(RCP) (PLAN) — **AV EQUIPMENT CEILING RACK (BY OWNER) :**
BASIS OF DESIGN: ATLAS CR222-NR. PROVIDE BLOCKING.(SEE INTERIOR ELEVATIONS AND RCP)

(ELEV.) (PLAN) — **WALL MOUNTED DIGITAL CLOCK:**
WALL MOUNTED, BATTERY POWERED, DIGITAL CLOCK BY GC
PROVIDE BLOCKING. (SEE INTERIOR ELEVATIONS AND COORDINATE w/ POWER PLAN)

(ELEV.) (PLAN) — **IP PHONE:**
BASIS OF DESIGN: CISCO.
PROVIDE BLOCKING. (SEE INTERIOR ELEVATIONS AND COORDINATE w/ POWER PLAN)

(ELEV.) (PLAN) — **TOUCH CONTROL PANEL (BY OWNER)**
BASIS OF DESIGN: EXTRON MLC PLUS 100. (SEE INTERIOR ELEVATIONS AND POWER & TECH PLAN)

TELECOIL LOOP :
BY ELECTRICAL CONTRACTOR. AUDIO INDUCTION LOOP AIDS ASSISTIVE LISTENING TECHNOLOGY. CONSISTS OF PHYSICAL CABLE LOOPS PLACED AROUND DESIGNATED SPACES. (SEE ELECTRICAL DRAWINGS; SHEET E2-303)

(ELEV.) (PLAN) — **IPAD KIOSK (BY OWNER)**
BASIS OF DESIGN: IPAD. (SEE INTERIOR ELEVATIONS AND POWER & TECH PLAN)

(ELEV.) (PLAN) — **MONITER WITH KETBOARD & MOUSE KIOSK (BY OWNER)**
BASIS OF DESIGN: IMAC. (SEE INTERIOR ELEVATIONS AND POWER & TECH PLAN)

Revision Schedule

No.	Description	Date
A	SED SUBMISSION	10/23/2020
D	ADDITIONS: ISSUED FOR BID	8/10/2021

Geddis Architects
Architecture. Planning. Interiors
71 Old Post Road
P.O. Box 1020
Southport, CT 06890
(203) 256-8700

Fielding International
Transforming Education by Design
259 Water Street Suite 1L
Warren , RI 02885 USA
+1 401-289-2789

BARILE GALLAGHER & ASSOCIATES
CONSULTING ENGINEERS
39 MARBLE AVE PLEASANTVILLE, NY 10570
914.328.6060 GENERAL@BGA-ENG.com www.BGA-ENG.com

Construction Manager
SAVIN ENGINEERS, P.C.
3 Campus Drive
Pleasantville, NY 10570
914-769-3200

Structural Engineer
ODEH ENGINEERS
1223 Mineral Spring Ave
North Providence, RI 02904
401-724-1771

Civil Engineer
WESTON & SAMPSON
1 Winners Circle, Suite 130
Albany, NY 12205
518-463-4400

Roof Consultant
WATSKY ASSOCIATES INC.
20 Madison Ave
Valhalla, NY 10595
914-948-3450

Acoustic Consultant
DP DESIGN
12 Cold Spring Street
Providence, RI
401-861-3218

AV Consultant
CAVANAUGH TOCCI
327 F Boston Post Road
Sudbury, MA 01776-3027
978-443-7871

SED#: 6618-0001-0001-024

PROJECT
Rye City Schools
555 Theodore Fremd Ave, Rye, NY 10580

Osborn Elementary School

10 Osborn Road, Rye NY 10580

CEILING FIXTURE AND MATERIALS LEGEND

Approver

SEAL & SIGNATURE

DATE: 06/29/20
PROJECT No: 9200
DRAWING BY: Author
CHK BY: Checker
DWG No:
A3-400