



D

F**F**

- A. REFER TO IN001 FOR INTERIOR FINISH GENERAL NOTES.
- B. REFER TO SPECIFICATIONS FOR MATERIAL AND INSTALLATION REQUIREMENTS.
- C. REFER TO IN601 FOR FINISH LEGEND AND ROOM FINISH SCHEDULE.
- D. REFER TO A-400 SERIES FOR CASEWORK FINISHES.
- E. REFER TO S-6000 FOR FURNITURE. FURNITURE IS SHOWN FOR REFERENCE ONLY. ALL FURNITURE IS NEW.
- F. REFER TO AW SERIES FOR ALL SIGNAGE.
- G. REFER TO Q SERIES FOR EQUIPMENT INFORMATION.
- H. PAINT ALL WALLS (P-1) UNIFORM.
- I. PAINT ALL EXPOSURES OF INTERIOR CEILING SOFFITS AND GYPSUM WALL BOARD CEILINGS (P-2) UNIFORM.
- J. PAINT ALL HOLLOW METAL DOORS AND HOLLOW METAL FRAMES IN CONTRACT BOUNDARY (P-2) UNIFORM.
- K. UNIFORM GREEN SCREENED BAY FOR CLARITY. REFER TO ARCHITECTURE SERIES FOR WALL CONSTRUCTION INFORMATION.

1 FURNITURE IS HIDDEN FOR CLARITY
2 CONCRETE TO HAVE CLEAR COAT SEALANT
3 BUILDING JOINT LOCATION, JOINT OCCURS AT WALLS AND ROOF ONLY. FLOOR
FINISHES WILL NOT BE AFFECTED; SEE ARCHITECTURAL DRAWINGS FOR MORE
INFORMATION

	MATERIAL FLANGE CHANGE (REFER TO IN501 FOR TRANSITION DETAILS)
	PATTERN CHANGE (REFER TO IN501 FOR TRANSITION DETAILS)
	DIRECTION OF FINISH
	CORNER GUARD LOCATION
	PAINT COLOR / WALL FINISHES
	WALL BASE / FLOOR FINISH TAG
	MILLWORK LOCK LOCATION
	WALL BASE / WALL FINISH TAG

ABBREVIATION	FINISH TYPE
AT	ACOUSTICAL CEILING TILE
AWP	ACOUSTICAL WALL PANEL
C	CONCRETE
CC	CUBICLE CURTAIN TRACK
CG	CORNER GUARD
CHR	CHAIR RAIL
CW	CATWALK
HR	HAND RAIL
LVT	LUXURY VINYL TILE
MB	MEMORY BOX
P	PAINT
PL	PLASTIC LAMINATE
PT	PORCELAIN TILE
RB	RESILIENT BASE
RWC	RIGID WALL COVERING
RWS	ROLLER SHADES
S	SOLID SURFACE
SD	SIDING
ST	STACKED STONE
TR	TRIM
WVC	WYNL WALL COVERING
WD	PLYWOOD
WFT	WALL FINISH TYPE



(DEDUCTIVE ALTERNATES ARE CASCADING AND MUST BE EXERCISED IN THE ORDER PRESENTED FOR A DETAILED DESCRIPTION OF EACH DEDUCTIVE ALTERNATE REFER TO COVER SHEET G1000

DEDUCTIVE ALTERNATE #1: REDUCE WATER AND ICE SHIELD COVERAGE
DEDUCTIVE ALTERNATE #2: ELIMINATE TUNNEL (EAST LEG)

~~DEDUCTIBLE ALTERNATE #1: REDUCE WATER AND ICE SHIELD COVERAGE~~
~~DEDUCTIBLE ALTERNATE #2: ELIMINATE TUNNEL (LAST LEG)~~
~~DEDUCTIBLE ALTERNATE #3: ELIMINATE FAUX WINDOWS AT CLEARSTORY~~
~~DEDUCTIBLE ALTERNATE #4: MINIMIZE WORK AT RE CORRIDOR~~
~~DEDUCTIBLE ALTERNATE #5: ELIMINATE CONCRETE~~
~~DEDUCTIBLE ALTERNATE #6: ELIMINATE LANDSCAPE~~
~~DEDUCTIBLE ALTERNATE #7: REDUCE PLATFORM AT CHILLER~~
~~DEDUCTIBLE ALTERNATE #8: ELIMINATE IVS SECURITY~~
~~DEDUCTIBLE ALTERNATE #9: ELIMINATE LARGE PORCH~~
~~DEDUCTIBLE ALTERNATE #10: ELIMINATE SMALL PORCH A~~
~~DEDUCTIBLE ALTERNATE #11: ELIMINATE SMALL PORCH B~~
~~DEDUCTIBLE ALTERNATE #12: ELIMINATE ENTRANCE CANOPY~~
~~DEDUCTIBLE ALTERNATE #13: ELIMINATE FENCE/Faux ROOFS AT RESIDENT ROOMS~~
~~DEDUCTIBLE ALTERNATE #14: ELIMINATE PATIENT LIFTS TRACK EXPOSITION INTO RESIDENT REAR~~
~~DEDUCTIBLE ALTERNATE #15: ELIMINATE DRIVEWAY/PARKING /PORTION OF DRIVE EN~~
~~DEDUCTIBLE ALTERNATE #16: ELIMINATE EXTERIOR SIGNAGE~~

Project Title NEW COMMUNITY LIVING CENTER		Project Number 620-334
Location 2094 Albany Post Road, Montrose, NY 10548		Building Number CLC
Issue Date 05/09/2022	Checked H.GARDINER	Drawing Number IN101
	Drawn K. MCDERMOTT	