AFF	ABOVE FINISHED FLOOR
BCU	BUILDING CONTROL UNIT
BTU	BRITISH THERMAL UNIT
CFH	CUBIC FEET PER HOUR
CFM	CUBIC FEET PER MINUTE
CLG	CEILING
COMM.	COMMUNICATION
CV	CONTROL VALVE
(D)	DEMOLISH
DB	DRY BULB
DCV	DEMAND CONTROLLED VENTILATION
DEG. F	DEGREES FAHRENHEIT
DIA	DIAMETER
DX 'E'	DIRECT EXPANSION
(E)	ELECTRICAL CONTRACTOR EXISTING
EA	EACH
EAT	ENTERING AIR TEMPERATURE
EER	ENERGY EFFICIENCY RATING
ESP	EXTERNAL STATIC PRESSURE
FAI	FRESH AIR INTAKE
FD	FLOOR DRAIN
FLA	FULL LOAD AMPS
FT. H20	FEET OF WATER
'G'	GENERAL CONSTRUCTION CONTRACTOR
GPM	GALLONS PER MINUTE
GPH	GALLONS PER HOUR
Н	HEIGHT
'H'	HVAC CONTRACTOR
HP	HORSEPOWER
IN.	INCHES
IN. W.C. (W.G.)	INCHES WATER COLUMN (WATER GAUGE
KW	KILOWATTS
L	LENGTH
LAT	LEAVING AIR TEMPERATURE
LBS	POUNDS LIQUID CRYSTAL DISPLAY
LCD	LEAVING DRY BULB TEMPERATURE
LPR	STEAM CONDENSATE RETURN
LPS	LOW PRESSURE STEAM
LWB	LEAVING WET BULB TEMPERATURE
LWT	LEAVING WATER TEMPERATURE
M	METER
MAX	MAXIMUM
MBH	1,000 BTU PER HOUR
MCA	MINIMUM CIRCUIT AMPACITY
MIN	MINIMUM
MNF	MANUFACTURER
N.C.	NORMALLY CLOSED
N.O.	NORMALLY OPEN
NFPA	NATIONAL FIRE PROTECTION ASSOCIATION
NPT	NATIONAL PIPE THREAD
NTS	NOT TO SCALE
OAI	OUTDOOR AIR INTAKE
OED	OPEN ENDED DUCT
OED 'P'	OPEN ENDED DUCT PLUMBING CONTRACTOR
(P)	PROPOSED
PD	PRESSURE DROP
PSIG	LBS / SQUARE INCH (GAUGE PRESSURE)
RD	ROOF DRAIN
RPM	REVOLUTIONS PER MINUTE
RPZ	REDUCED PRESSURE ZONE
SAT	SUPPLY AIR TEMPERATURE
SEER	SEASONAL ENERGY EFFICIENCY RATING
TEMP	TEMPERATURE
TG	TRANSFER GRILLE
TYP	TYPICAL
VFD	VARIABLE FREQUENCY DRIVE
W	WIDTH
WB	WET BULB
WMS	WIRE MESH SCREEN

DUCTWORK LEGEND		
SYMBOL	ABBREV	DESCRIPTION
<u> </u>		DUCTWORK BRANCH CONNECTION
	VD	VOLUME DAMPER
	CD	ROUND FACE SUPPLY DIFFUSER
	SEE AIR DEVICE SCHEDULE	SIDEWALL SUPPLY, RETURN OR EXHAUST GRILLE/REGISTER
	SEE AIR DEVICE SCHEDULE	SQUARE FACE SUPPLY DIFFUSER
K J	SEE AIR DEVICE SCHEDULE	BOTTOM RETURN OR EXHAUST GRILLE/REGISTER
	FC	FLEXIBLE CONNECTION
		TURNING VANES
		RECTANGULAR TO ROUND TRANSITION
	AL	ACOUSTICAL LINING
		END CAP
	SEE AIR DEVICE SCHEDULE	SUPPLY DIFFUSER WITH DIRECTIONAL FLOW (SOLID HATCH INDICATES BLANK OFF PANEL)
		SUPPLY DUCT DROP (TURN DOWN)
		RETURN/EXHAUST DUCT DROP (TURN DOWN)
		SUPPLY DUCT RISE
		RETURN/EXHAUST DUCT RISE
DSD ——	DSD	DUCT SMOKE DETECTOR
M	MD	MOTORIZED DAMPER WITH ACTUATOR
OR OR	AD	ACCESS DOOR
	FD/AD	FIRE DAMPER WITH ACCESS DOOR
	FSD/AD	FIRE SMOKE DAMPER WITH ACCESS DOOR
		FAN
'///// ,		WORK TO BE REMOVED
		POINT OF DISCONNECTION FROM EXISTING
•		POINT OF CONNECTION TO EXISTING
CONTROLS LEGEND		
SYMBOL	ABBREV	DESCRIPTION
©		CARBON MONOXIDE SENSOR
T		THERMOSTAT
<u>S</u>		DIGITAL TEMPERATURE SENSOR

HUMIDITY SENSOR

PRESSURE SENSOR

CARBON DIOXIDE SENSOR

(H)

PIPING LEGEND		
SYMBOL	ABBREV	DESCRIPTION
		NEW WORK
С О		PIPING DOWN/ PIPING UP
— —		BALL VALVE WITH HOSE END CONNECTION
Ф	тн	THERMOMETER
→ ⊢	U	UNION
— 	FPC	FLEXIBLE PIPE CONNECTION
		DIRECTION OF FLOW
	PSR	PRESSURE SAFETY AND RELIEF VALVE
_ \	PRV	PRESSURE REDUCING VALVE
- 5-	BV	BALL VALVE
	ВА	BALANCING VALVE
□	BFV	BUTTERFLY VALVE
_		TEMPERATURE SENSOR WITH THERMOWELL
\longrightarrow	GA	GATE VALVE
₩ ₩	GB	GLOBE VALVE
A	AV	AUTOMATIC AIR VENT
— — ——————————————————————————————————	cv	2-WAY ELECTRONIC CONTROL VALVE
────	cv	3-WAY ELECTRONIC CONTROL VALVE
→ \$ —	cv	2-WAY PNEUMATIC CONTROL VALVE
────	cv	3-WAY PNEUMATIC CONTROL VALVE
	STR	STRAINER WITH BLOW OFF VALVE WITH HOSE END CONNECTION
	FD	FLOOR DRAIN
S		AIR SEPARATOR
——⊗ ^{F&T}		STEAM TRAPS (INDICATE TYPE)
→ →	СН	CHECK VALVE
<u> </u>	PG	PRESSURE GAUGE WITH GAUGE COCK
	RED	REDUCER
ı	со	CLEANOUT END CAP
		PIPE GUIDE
		PIPE ANCHOR
		CAPPED PIPE
		PUMP
· ///// ,		WORK TO BE REMOVED
•		POINT OF DISCONNECTION FROM EXISTING
•		POINT OF CONNECTION TO EXISTING
4/4	TDV	TRIPLE DUTY VALVE

GENERAL ASBESTOS ABATEMENT NOTES:

- 1. ALL ASBESTOS ABATEMENT WORK SHALL CONFORM TO ALL APPLICABLE CODE REQUIREMENTS ALONG WITH SPECIFICATION SECTION 028200 AND INDUSTRIAL CODE RULE 56.
- 2. ALL MATERIALS ASSOCIATED WITH THIS PROJECT HAVE BEEN TESTED FOR THE PRESENCE OF ASBESTOS. SEE SPECIFICATION SECTION 022600 HAZARDOUS MATERIAL ASSESSMENT FOR LOCATIONS OF MATERIALS THAT HAVE BEEN TESTED POSITIVE
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE TO PERFORM PERSONAL AIR MONITORING ON ITS EMPLOYEES IN ACCORDANCE WITH OSHA REGULATIONS.
- 4. THIRD PARTY PROJECT MONITORING AND AIR SAMPLING SHALL BE CONDUCTED BY A CONSULTANT FIRM HIRED DIRECTLY
- BY THE OWNER.
 5. THE CONTRACTOR SHALL BE RESPONSIBLE TO FILE FOR ALL PERMITS AND NOTIFY ALL REGULATORY AGENCIES AS
- 6. UPON COMPLETION OF THE DEMOLITION WORK, THE CONTRACTOR SHALL SUBMIT COPIES OF ALL WASTE MANIFEST AND LANDFILL RECEIPTS TO THE ARCHITECT AS PART OF THE REQUIRED CLOSEOUT DOCUMENTS.
- ALL OPENINGS AND PENETRATIONS INCLUDING BUT NOT LIMITED TO WINDOWS, DOORS, DUCTS, LOUVERS AND GRILLES WITHIN OR OPEN TO THE ROOF AREA SHALL BE COVERED WITH A MINIMUM OF TWO (2) LAYERS OF 6 MIL PLASTIC.
- 8. CONTRACTOR SHALL BE RESPONSIBLE TO PROTECT ALL EXISTING HVAC EQUIPMENT AND ROOF VENTS.

REQUIRED FOR THE WORK AND PAY ALL FEES ASSOCIATED WITH THE AFOREMENTIONED.

GENERAL NOTES

- 1. PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERABLE MECHANICAL SYSTEMS AS INDICATED ON THE DRAWINGS, AS SPECIFIED AND AS REQUIRED BY CODE.
- 2. THE CONTRACTOR, BY PRESENTING THEIR BID FOR THE WORK, REPRESENTS THAT HE/SHE HAS INSPECTED THE SITE AND IS COMPLETELY FAMILIAR WITH THE SCOPE OF WORK AND ALL FIELD CONDITIONS RELATED TO, AND AFFECTING THE WORK AND ITS PERFORMANCE. EXCEPTIONS AFFECTING THE WORK AND ITS PERFORMANCE, OR CONFLICTS BETWEEN FIELD CONDITIONS, SHALL BE BROUGHT TO THE ATTENTION OF THE ARCHITECT PRIOR TO THE SUBMISSION OF BIDS.
- 3. PERFORM ALL WORK IN ACCORDANCE WITH THE PLUMBING CODE, FIRE CODE, MECHANICAL CODE, ENERGY CONSERVATION CONSTRUCTION CODE, AND FUEL GAS CODE OF NEW YORK STATE AND THE REQUIREMENTS OF THE LOCAL AUTHORITIES HAVING JURISDICTION.
- 4. COMPLY WITH THE NATIONAL ELECTRIC CODE AND THE REQUIREMENTS OF DIVISION 26 FOR ALL ELECTRICAL
- 5. FIRE STOP ALL OPENINGS IN FIRE RATED CONSTRUCTION FOR PIPING, DUCTWORK, CONDUIT, ETC. PROVIDE FIRE DAMPERS AND ACCESS DOORS IN ALL OPENINGS IN FIRE RATED FLOORS, PARTITIONS, AND WALLS FOR DUCTWORK AS PER THE MECHANICAL CODE OF NEW YORK STATE. (SEE ARCHITECTURAL DRAWINGS FOR LOCATIONS OF FIRE RATED CONSTRUCTION.)
- 6. DO NOT SCALE DRAWINGS. DRAWINGS FOR HVAC WORK ARE DIAGRAMMATIC AND ARE INTENDED TO CONVEY SCOPE AND GENERAL ARRANGEMENT ONLY. THE LOCATIONS OF ALL ITEMS SHOWN ON THE DRAWINGS OR CALLED FOR IN THE SPECIFICATIONS THAT ARE NOT DEFINITELY FIXED BY DIMENSIONS ARE APPROXIMATE. COORDINATE CONTRACT DOCUMENTS, PROJECT REQUIREMENTS, WORK OF OTHERS, AND EQUIPMENT AND MATERIALS PURCHASED WITH FIELD DIMENSIONS. INSTALL ALL EQUIPMENT AS PER MANUFACTURER'S REQUIREMENTS TO PROVIDE PROPER CLEARANCE FOR INSTALLATION, OPERATION, AND MAINTENANCE. CONTRACTOR'S INTENDED MEANS AND METHODS OF INSTALLATION AND CONTRACTOR'S FABRICATED ITEMS SHALL ENSURE A PROPER "FIT" AND INSTALLATION. BRING ANY CONFLICTS TO THE ATTENTION OF THE ARCHITECT/ENGINEER DURING THE SUBMITTAL PHASE FOR RESOLUTION PRIOR TO PURCHASING ANY
- 7. MAINTAIN MAXIMUM HEADROOM AND SPACE CONDITIONS AT ALL POINTS. WHERE HEADROOM AND SPACE CONDITIONS APPEAR INADEQUATE, NOTIFY THE ARCHITECT/ENGINEER PRIOR TO PROCEEDING WITH INSTALLATION. MAINTAIN A MINIMUM OF 6'-8" CLEARANCE FROM FINISHED FLOOR TO UNDERSIDE OF PIPES, DUCTS, CONDUITS, SUSPENDED EQUIPMENT, ETC., THROUGHOUT ACCESS ROUTES IN MECHANICAL ROOMS.
- 8. FIELD VERIFY AND COORDINATE ALL DUCT AND PIPING DIMENSIONS BEFORE FABRICATION. MAKE MODIFICATIONS IN THE LAYOUT AS NEEDED TO PREVENT CONFLICT WITH WORK OF OTHER TRADES OR FOR PROPER EXECUTION OF THE WORK. OBTAIN THE APPROVAL OF THE ARCHITECT/ENGINEER FOR MODIFICATIONS.
- 9. PROVIDE PRODUCTS OF ONE MANUFACTURER WHERE TWO OR MORE ITEMS OF THE SAME TYPE OF MATERIAL OR EQUIPMENT IS REQUIRED.
- 10. INSTALL ALL EQUIPMENT AND APPURTENANCES IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS, CONTRACT DOCUMENTS, AND APPLICABLE CODES AND REGULATIONS. REFER TO DETAILS FOR ADDITIONAL PIPING AND EQUIPMENT INSTALLATION REQUIREMENTS.
- 11. LOCATE ALL TEMPERATURE, PRESSURE, AND FLOW MEASURING DEVICES IN ACCESSIBLE LOCATIONS WITH STRAIGHT SECTION OF PIPE OR DUCT UP- AND DOWNSTREAM AS RECOMMENDED BY THE MANUFACTURER TO ENSURE MANUFACTURER CERTIFIED ACCURACY.
- 12. COORDINATE ALL EQUIPMENT CONNECTIONS WITH MANUFACTURER'S CERTIFIED DRAWINGS. COORDINATE AND PROVIDE ALL PIPING AND DUCT TRANSITIONS REQUIRED FOR FINAL CONNECTIONS TO EQUIPMENT.
- 13. COORDINATE LOCATIONS AND SIZES OF ALL FLOOR, WALL, AND ROOF OPENINGS WITH ALL OTHER TRADES. COORDINATE ALL PIPING AND EQUIPMENT SUPPORTED FROM STRUCTURE WITH GENERAL CONSTRUCTION
- 14. COORDINATE INSTALLATION OF SUPPLY AND RETURN GRILLES WITH INSTALLATION OF FINISHED CEILINGS.
- 15. COMPLETE ALL PRESSURE TESTS BEFORE ANY MECHANICAL EQUIPMENT, DUCTWORK, OR PIPING INSULATION IS
- 16. TESTING, ADJUSTING, AND BALANCING AGENCY SHALL BE A MEMBER OF THE ASSOCIATED AIR BALANCE COUNCIL (AABC) OR THE NATIONAL ENVIRONMENTAL BALANCING BUREAU (NEBB). PERFORM ALL TESTING, ADJUSTING, AND BALANCING IN ACCORDANCE WITH THE SPECIFICATIONS.
- 17. MAKE ALL ATTACHMENTS TO JOISTS, TRUSSES, OR JOIST GIRDERS AT PANEL POINTS. PROVIDE BEAM CLAMPS MEETING MSS STANDARDS. THE USE OF C-CLAMPS IS NOT PERMITTED.
- 18. PROVIDE CONCRETE PADS A MINIMUM OF 6 INCHES HIGH FOR ALL FLOOR MOUNTED EQUIPMENT. EXTEND PAD 4
- 19. INTERNALLY LINE ALL SUPPLY AND RETURN DUCTWORK WITHIN 20 FEET UPSTREAM AND DOWNSTREAM OF FANS WITH 1" THICK INSULATION. INTERNALLY LINED DUCTWORK MEETING THIS REQUIREMENT SHALL ALSO BE PROVIDED WITH EXTERNALLY APPLIED INSULATION AS REQUIRED BY THE SPECIFICATIONS. SEE SPECIFICATION
- 20. PROVIDE TRAPPED DRAIN PIPING FROM DRAIN PANS OF ALL COOLING COILS, FANS, AND OTHER ACTIVE DRAINS EXPOSED TO SYSTEM AIR STREAM. PROVIDE TRAP AT CONNECTION, WATER SEAL DEPTH 1 INCH GREATER THAN UNIT OPERATING PRESSURE. DIRECT DRAINS TO NEAREST FLOOR DRAIN, MOP SINK, OR OTHER LOCATION APPROVED BY THE ARCHITECT/ENGINEER.
- 21. INSTALL PIPING, DUCTWORK, AND CONDUIT CONCEALED IN AREAS HAVING HUNG CEILINGS AND/OR FURRED SPACES UNLESS OTHERWISE INDICATED ON THE DRAWINGS.

WORK IN EXISTING AREAS

INCHES BEYOND THE EQUIPMENT ON ALL SIDES.

SECTION 230719 FOR ADDITIONAL REQUIREMENTS.

- 1. EXISTING CONDITIONS, INCLUDING EQUIPMENT, DUCT AND PIPE SIZES AND LOCATIONS, INDICATED ON THE DRAWINGS ARE DIAGRAMMATIC. CONFIRM ALL EXISTING CONDITIONS PRIOR TO PROCEEDING WITH THE WORK.
- 2. CUT AND ROUGH PATCH EXISTING CONSTRUCTION AS REQUIRED FOR THE PERFORMANCE OF THE WORK. FINISH PATCHING AND FLASHING REQUIREMENTS ARE SHOWN ON THE ARCHITECTURAL DRAWINGS. PERFORM ALL CUTTING AND PATCHING WORK IN A MANNER SUCH THAT ANY EXISTING WARRANTEES/GUARANTEES ARE NOT VOIDED. USE QUALIFIED PERSONNEL IN PERFORMANCE OF THE WORK.

CONTRACT 'H' SCOPE NOTES

- 1. INSTALL SMOKE DETECTORS IN DUCTWORK FOR AIR HANDLING UNITS RATED AT 2,000 CFM OR GREATER. SMOKE DETECTOR SUPPLY AND WIRING IS PART OF CONTRACT 'E'.
- 2. FURNISH AND INSTALL ALL NECESSARY CONTROL WIRING, CONDUIT, AND ACCESSORIES AS REQUIRED TO PROVIDE FULLY FUNCTIONING SYSTEMS AND SEQUENCES OF OPERATION.
- 3. FURNISH ALL LINTELS FOR DUCT AND PIPE PENETRATIONS IN INTERIOR MASONRY WALLS FOR INSTALLATION BY
- 4. FURNISH ALL SLEEVES FOR PIPE AND CONDUIT FLOOR, WALL, PARTITION, AND ROOF PENETRATIONS FOR
- INSTALLATION BY CONTRACT 'G'.

5. FURNISH ALL CURBS FOR ALL ROOF MOUNTED EQUIPMENT AND DUCT PENETRATIONS FOR INSTALLATION BY

- CONTRACT 'G'.
- 6. REMOVE CHASE ENCLOSURE COVER WHEN PERFORMING WORK IN ANY CHASE, AND REINSTALL THE CHASE ENCLOSURE COVER WHEN WORK IS COMPLETE.
- 7. PERFORM ALL CUTTING AND ROUGH PATCHING AS REQUIRED IN THE EXECUTION OF THE WORK. FINISH PATCHING AND FLASHING IS PART OF CONTRACT 'G'.

LEGENDS/ABBREVIATIONS NOTES

1. ABBREVIATIONS AND SYMBOLS ON THIS SHEET DO NOT DEFINE THE SCOPE OF WORK.



architects + engineers

2700 Westchester Avenue, Suite 415 Purchase, NY 10577 914.358.5623 • www.h2m.com

·		

MARK	DATE	DESCRIPTION
	01-20-2022	FINAL REBID DOCUMENT
	11-18-2021	FINAL BID DOCUMENT



"ALTERATION OF THIS DOCUMENT EXCEPT BY A LICENSED PROFESSIONAL IS ILLEGAL"						
DESIGNED BY:	DRAWN BY:		CHECKED BY:		REVIEWED BY:	
CAK		CAK	BMC		° AEH	
PROJECT No.:	PROJECT No.:		DATE:		:	
IRSD 1910		JANUAI	RY 2022	AS SHOWN		

Irvington Union Free School District

Main Street School Renovations



101 Main Street Irvington, NY 10533

SED Number:66-04-02-02-0-001-016

CONTRACT G
GENERAL CONSTRUCTION


FINAL REBID DOCUMENT

SHEET TITLE

HVAC LEGENDS, SYMBOLS, ABBREVIATIONS, AND GENERAL NOTES

DRAWING No.


H0.0



DUCTWORK MAIN WITH OPENINGS IN THE JOIST.

4 PROVIDE AND INSTALL DUCT SMOKE DETECTORS IN THE SUPPLY AND RETURN DUCT MAINS.

- 4. INSTALL ALL EQUIPMENT IN ACCORDANCE WITH MANUFACTURER'S REQUIRED MAINTENANCE CLEARANCES AND PREVAILING CODE.
- 5. SUBMIT EQUIPMENT / DUCTWORK SHOP DRAWINGS TO ENGINEER FOR REVIEW AND APPROVAL PRIOR TO PURCHASE / RELEASE.
- 6. CONTRACTOR TO COORDINATE THE PLACEMENT OF ALL TEMPERATURE / HUMIDITY / CO2 SENSORS WITH THE OWNER / DISTRICT.
- 7. ALL EXISTING HEATING AND VENTILATION EQUIPMENT, DUCTWORK, DIFFUSERS, ETC. ARE TO REMAIN.



Irvington, NY 10533 SED Number:66-04-02-02-0-001-016

CONTRACT G GENERAL CONSTRUCTION

FINAL REBID DOCUMENT

MAIN STREET

SCHOOL


HVAC UPPER GYMNASIUM CONSTRUCTION PLAN

BUILDING

WALKWAY 🗹

2700 Westchester Avenue, Suite 415 Purchase, NY 10577 914.358.5623 • www.h2m.com

MARK	DATE	DESCRIPTION
	01-20-2022	FINAL REBID DOCUMENT
	11-18-2021	FINAL BID DOCUMENT




Irvington Union Free School District

Main Street School Renovations



101 Main Street

H1.0



GENERAL NOTES:

1. COORDINATE ALL WORK WITH EXISTING CONDITIONS AND OTHER TRADES. LOCATIONS OF EXISTING

2. CONTRACTOR TO INSTALL NEW ROOFTOP UNIT IN COMPLIANCE WITH MANUFACTURER'S REQUIRED MAINTENANCE CLEARANCES, AND APPLICABLE MECHANICAL CODE CLEARANCE REQUIREMENTS.

4. TERMINATE ROOFTOP UNIT CONDENSATE LINES AT THE NEAREST ROOF DRAIN (IF FEASIBLE).

REPRESENTING THE ROOF CURB MANUFACTURER.


3. SUBMIT EQUIPMENT SHOP DRAWINGS TO ENGINEER FOR REVIEW AND APPROVAL PRIOR TO PURCHASE. DO NOT SCALE DRAWINGS. LINE-WORK SHOWN IS SCHEMATIC.

5. CONTRACTOR TO PROVIDE SEISMIC/WIND RATED ROOF CURB MANUFACTURED THYBAR OR APPROVED

6. CONTRACTOR TO PROVIDE PROJECT SPECIFIC ROOF CURB DESIGNED IN ACCORDANCE WITH WIND LOADS PROVIDED ON DRAWINGS, SIGNED AND SEAL BY A LICENSED PROFESSIONAL ENGINEER

ROOFTOP EQUIPMENT HAVE BEEN PROVIDED FOR REFERENCE ONLY. CONTRACTOR IS RESPONSIBLE FOR FIELD VERIFYING LOCATIONS OF ALL EXISTING EQUIPMENT.

WIND LOADS (MC 301.15 & BC 1609)							
ZONE ID	POSITIVE WIND PRESSURE (PSF)	NEGATIVE WIND PRESSURE (PSF)					
ROOF (INT. ZONE)	11.3	-44.1					
ROOF (END ZONE)	11.3	-58.2					
ROOF (CORNER ZONE)	11.3	-79.4					
WALLS (INT. ZONE)	27.7	-30.1					
WALLS (FND ZONF)	27.7	-37 1					



architects
+
engineers

2700 Westchester Avenue, Suite 415
Purchase, NY 10577
914.358.5623 • www.h2m.com

MARK	DATE	DESCRIPTION

FINAL REBID DOCUMENT

FINAL BID DOCUMENT



11-18-2021

Irvington Union Free School District

JANUARY 2022 AS SHOWN

Main Street School Renovations



101 Main Street Irvington, NY 10533

SED Number:66-04-02-02-0-001-016

CONTRACT G
GENERAL CONSTRUCTION

FINAL REBID DOCUMENT

HEET TITLE

HVAC GYMNASIUM ROOF CONSTRUCTION PLAN

H1.1

Key Plan
SCALE: 1/64"=1'-0"

PACKAGED ROOFTOP UNITS													
				PERFORMANCE/CONSTRUCTION REQUIREMENTS									
FOUIDMENT	EQUIPMENT LOCATION AREA SERVED	REQUIRED		SUPPLY FAN(S)				C	OOLING COIL		FILTERS		
		CATION AREA SERVED ENERGY EFFICIENCY				OUTSIDE AIR FLOW (CFM)	TOTAL CAPACITY	U CADACITY DEEDIGEDANT	AIR DATA			\Box	
	RATING (CFM) EXT. S.P. (IN V	EXT. S.P. (IN W.G)	EXT. S.P. (IN W.G) BHP	(OI III)		REFRIGERANT TYPE	ENT. DB/WB (DEG. F)	MAX LVG DB/WB (DEG F)	ТҮРЕ				
RTU-1	ROOF	GYMNASIUM	-	9140	1.5	7.42	3295	292.78	R410A	81.8 / 67.9	59.8 / 57.9	2" MERV-8	\neg
PACKAGI	ED ROOF	TOP UNITS	(CONTIN	IUED)			•		•	•			_

158 / 200

OCCUPANT

Vot = Vou / Ev

OCCUPANTS (CFM/OCCUPANT)

BASED OA RATE OA RATE

4. AN OUTDOOR AIR INTAKE FLOW RATE (Vot) OF 3295 CFM WAS CALCULATED.

AREA BASED

(CFM/SF)

5. ENERGY RECOVERY VENTILATION SYSTEM NOT REQUIRED UNDER EXCEPTION 9, "SYSTEMS EXPECTED TO OPERATE LESS THAN 20 HOURS PER WEEK AT THE OUTDOOR AIR PERCENTAGE COVERED BY TABLE

Ev = SPACE VENTILATION EFFICIENCY FACTOR BASED ON THE LARGEST OA FRACTION.

NON-ADJUSTED

TOTAL OA

REQUIRED (CFM)

PACKAGED ROOFTOP UNITS (CONTINUED)								
			BASIS OF DESIGN	INFORMATION				
					ELECTRICAL DATA			
EQUIPMENT NO.	MNF	MODEL NO.	NOMINAL DIMENSIONS LxWxH	NOMINAL OPERATION WEIGHT (LBS)	VOLTS/PHASE	SUPPLY FAN(S) HP	MCA/MOCP	REMARKS

8. VERTICAL SUPPLY/RETURN

11. NON-FUSED DISCONNECT

SUPPLY AIR

RTU-1	CARRIER	50LC0A26E3M5-1S2C0	158 x 87 x 59	3384	
NOTES:					

1. ROOFTOP UNIT TO BE INSTALLED ON ROOF DUNNAGE

2. RA & SA SMOKE DETECTORS, CO2 SENSORS QNTY. 2

ROOM NAME

GYMNASIUM

SPECTATOR AREA

SPACES WITH DIFFERENT VENTILATION REQUIREMENTS.

 $D = Ps / (\Sigma Pz) = 50 / 176$

 Σ Pz = SUM OF DESIGN ZONE POPULATION.

Ps = PEAK SYSTEM POPULATION

WHERE: D = OCCUPANT DIVERSITY

2. NUMBER OF OCCUPANTS ARE BASED ON OCCUPANCY LOAD REQUIREMENTS.

3. A DIVERSITY FACTOR OF .28 WAS USED TO DETERMINE THE REQUIRED OA RATE

5. SINGLE POINT POWER CONNECTION

ROOM#

NOTES:

HOT GAS MODULATING REHEAT 13. OUTDOOR AIR MONITOR

ECONOMIZER

NUMBER OF

Pz

RTU-1 COMMON VENTILATION INDEX BASED ON 2020 MECHANICAL CODE OF NEW YORK STATE SECTION 403.3.1.1

OCCUPANCY

LOAD

(PERSONS/

1000 SF)

14. LOW SOUND BLANKET 3. DEMAND CONTROLLED VENTILATION 9. VARIABLE FREQUENCY DRIVE 15. BACNET COMPATIBLE 16. POWERED EXHAUST 4. POWERED CONVENIENCE OUTLET 10. COOLING MODE (DX COIL) ONLY

FLOOR

AREA (SF)

6. VARIABLE SPEED COMPRESSOR 12. LOW VOLTAGE CONTROLLER

OCCUPANCY

CLASSIFICATION

AMUSEMENT: GYM

AMUSEMENT: SPECT.

RECIRCULATING SYSTEMS) OF THE 2020 MECHANICAL CODE OF NYS. THIS VENTILATION SYSTEM SERVES

VENTILATION RATE CALCULATED IN ACCORDANCE WITH SECTION 403.3.1.1.2.3 (MULTIPLE ZONE

AIR OUTLETS								
DESIGNATION	SYMBOL	BASIS OF DESIGN: MNF/ MODEL NO.	DESCRIPTION	FACE SIZE (IN)	AIR FLOW RANGE (CFM)		NECK SIZE	REMARKS
					MIN	MAX	DIAMETER (IN.)	KLWAKKS
А		NAILOR/R-UNI	ROUND FACE DUCT MOUNTED DIFFUSER	34" DIA	-	1415	16	1-3
						1750		
NOTES:	_	_	_	_			_	

CORRECTED OA

BASED ON A

COMMON

VENTILATION

SYSTEM (CFM)

2033

1259

SPACE

VENTILATION

EFFICIENCY Ev

- 1. FOR CONSTRUCTION DETAILS AND ACCESSORIES SEE THE SPECIFICATIONS.
- 2. PROVIDE OPPOSED BLADE DAMPER AND EQUALIZING GRID FOR ALL DIFFUSERS.
- 3. PROVIDE ALL REQUIRED MATERIALS TO MOUNT DIFFUSERS TO DUCTWORK.

INSTALL DETECTOR MIN. 6 DUCT

WIDTHS FROM NEAREST INLET OR

-DETECTOR HOUSING

-MOUNTING SCREW(TYP.)

THE VELOCITY RATED SIDE OF LINER MUST FACE THE AIR FLOW
FLOW
DUCT SECTION (TYPICALLY 4 FT. OR 5 FT.)


MAXIMUM SPACING FOR FASTENERS.

LINER ADHERED TO THE DUCT WITH **ADHESIVE**

VELOCITY*	DIMENSIONS				
VELOCITI	Α	В	С	E	
0-1500 FPM	3"	12"	4"	18"	
1501-3500 FPM	3"	6"	4"	16"	


VEL IS


Acoustical Liner Fastening Detail SCALE:NTS (DETAIL #)



TRAPEZE HANGER

1. SIZE ALL SUPPORTS IN ACCORDANCE WITH THE SMACNA DUCT CONSTRUCTION STANDARDS, LATEST EDITION.






- HANDLE INSIDE


1. LATCHES SHALL BE OF THE WEDGE TYPE TO CLOSE DOORS TIGHTLY.

PROVIDE ACCESS PANELS ON ALL EQUIPMENT AND DUCTWORK INSTALLED ABOVE FINISHED CEILINGS WHERE SPACE LIMITATIONS DO NOT ALLOW HINGED DOORS TO OPEN.





ACTUAL INTERVALS ARE APPROXIMATE. 90% MIN. AREA COVERAGE OF

IMEN:	SIONS		* UNLESS A LOWER LEV
В	C E		SET BY MANUFACTURER
12"	4"	18"	LISTING AGENCY
6"	4"	16"	



STRAP HANGER





SECTION "B-B" ACCESS DOOR

2. HINGES ON THE ACCESS DOORS SHALL HAVE NON-CORROSIVE PINS. 3. PROVIDE ACCESS DOORS ON AIR HANDLING UNITS AND DUCTWORK INSTALLED IN EQUIPMENT ROOMS.

Access Door & Panel Details


SCALE: NTS



2700 Westchester Avenue, Suite 415 Purchase, NY 10577 914.358.5623 • www.h2m.com

engineers

MARK	DATE	DESCRIPTION
	01-20-2022	FINAL REBID DOCUMENT
	11-18-2021	FINAL BID DOCUMENT



Irvington Union Free School District

Main Street School Renovations



101 Main Street Irvington, NY 10533


SED Number:66-04-02-02-0-001-016

CONTRACT G GENERAL CONSTRUCTION


FINAL REBID DOCUMENT

HVAC SCHEDULES AND DETAILS

H2.0





SQUARE ELBOW WITH TYPE "A" DOUBLE **THICKNESS VANES**




SQUARE ELBOW WITH TYPE "B" DOUBLE THICKNESS VANES.

USE GALVANIZED STEEL FOR VANES IN EITHER STEEL OR ALUMINUM DUCTWORK.







DUCT ACCESS DOORS

PERPENDICULAR

TO AIR FLOW (IN)

6" - 24"

OVER 48"

PLENUMS AND WALK

IN ACCESS

ZONE

EFFECTIVENESS

FACTOR

ACCESS DOOR

HEIGHT (IN)

DUCT SIZE

2" SMALLER THAN

DUCT SIZE

3'-10"

ZONE OUTDOOR

AIRFLOW

2118

ACCESS DOOR

WIDTH (IN)

8" MINIMUM OR

EQUAL TO ACCESS

DOOR HEIGHT

2'-0"

2'-0"

2'-0"

PRIMARY

OUTDOOR AIR

FRACTION Zp

38.00%

TYPE "A" DOUBLE THICKNESS VANES FOR USE IN DUCTS GREATER THAN 24" x 24" IN SIZE. USE SAME GAUGE GALVANIZED IRON AS DUCT NOT TO EXCEED 20 GAUGE.

SAMPLING TUBE TO EXTEND AT

LEAST 3/4 OF THE TOTAL WIDTH OF THE DUCT AND TO BE LOCATED AT THE CENTER OF THE VERTICAL

DIMENSION OF THE DUCT—

EXHAUST TUBE

DOUBLE THICKNESS VANES FOR USE IN DUCTS 24" x 24" AND UNDER

Duct Mounting Smoke Detector DetailSCALE: NTS

1. INTERFACE OF NEW DUCT SMOKE DETECTORS W/ EXISTING

BUILDING FIRE ALARM SYSTEM BY CONTRACT 'E'.

SEAL MOUNTING WITH FOAM GASKET TO PREVENT AIR LEAKAGE.

Turning Vanes Detail

SCALE: NTS (DETAIL #)