



**DRAWING NOTES:**

- ① REMOVE AND PULL CONDUCTORS FROM EXISTING MECHANICAL EQUIPMENT TO BE DEMOLISHED BACK TO PANEL SERVING THE EQUIPMENT.

**DEMOLITION NOTES:**

- ELECTRICAL CONTRACTOR IS TO VERIFY ALL EXISTING CONDITIONS IN FIELD PRIOR ANY WORK.
- REMOVE ALL OUTLET DEVICES, LIGHTING FIXTURES, LIGHTING CONTROL DEVICES, AND ASSOCIATED WIRING METHODS IN AREAS OF RENOVATION UNLESS NOTED OTHERWISE.
- REMOVE BRANCH CIRCUIT WIRING METHODS BACK TO POWER SOURCE OR TO ITS NEAREST ACTIVE DEVICE. RE-ENERGIZE ALL CIRCUITS INTERRUPTED BY DEMOLITION WORK TO MAINTAIN BRANCH CIRCUIT CONTINUITY.
- TAG ALL OVERCURRENT PROTECTION DEVICES THAT BECOME "SPARE" AS A RESULT OF DEMOLITION WORK. PROVIDE NEW TYPED PANELBOARD DIRECTORIES FOR ALL DISTRIBUTION AND BRANCH CIRCUIT EQUIPMENT AFFECTED BY RENOVATION WORK.
- REMOVE CONDUCTORS, PROVIDE PULL-STRINGS AND CAP OPENINGS AND CONDUITS THAT ARE NOT TO BE RE-USED.
- FIRE ALARM DEVICES ARE TO BE REMOVED AND REPLACE WITH NEW IN NEW LOCATION.
- ALL POWER SHUTDOWNS ARE TO BE SCHEDULED AND COORDINATED WITH OWNER.
- IT IS THE INTENT FOR POWER TO REMAIN ACTIVE IN THE ADJACENT AREAS DURING CONSTRUCTION. CONTRACTOR IS TO MODIFY EXISTING WIRING ARRANGEMENT TO COMPLY.
- IT IS THE INTENT TO REMOVE ALL ELECTRICAL DEVICES WHICH INTERFERES WITH THE NEW CONSTRUCTION WORK OR DEMOLITION WORK, WHETHER SPECIFICALLY IDENTIFIED OR NOT.
- EXISTING BRANCH CIRCUITS THAT ARE FEED FROM THE PANELS TO BE DEMOLISHED AND ARE NOT PART OF THE CIRCUITS IN THE AREA SCOPE OF WORK, SHALL BE REMOVED TO THE NEAREST DEVICE OR EQUIPMENT TO BE RE-ENERGIZE TO NEW PANELS IN NEW LOCATION.

**GROUND FLOOR DEMO PLAN**  
SCALE: 1/8"=1'-0"

THE DELIVERY OF THIS DRAWING SHOULD NOT BE CONSTRUED TO PROVIDE AN EXPRESS WARRANTY OR GUARANTEE TO ANYONE THAT ALL THE DIMENSIONS AND DETAILS ARE EXACT OR TO INDICATE THAT THE USE OF THIS DRAWING IMPLIES THE REVIEW AND APPROVAL BY THE DESIGN PROFESSIONAL OF ANY FUTURE USE. ANY USE OF THIS INFORMATION WITHOUT THE WRITTEN APPROVAL BY THE DESIGN PROFESSIONAL IS AT THE SOLE RISK AND LIABILITY OF THE USER. THE DESIGN PROFESSIONAL RESERVES THE RIGHT TO REMOVE OUR PROFESSIONAL SEAL AND/OR TITLE BLOCK.

**NOTICE**  
THE SCHEDULES AND DRAWINGS REPRESENT ONLY CERTAIN REQUIREMENTS OF THE PROJECT. THERE ARE ADDITIONAL REQUIREMENTS IN THE SPECIFICATIONS BOOKLET WHICH THE CONTRACTOR IS BOUND TO PROVIDE. A SUPPLIER OR CONTRACTOR'S PRICING, WHICH IS BASED ONLY ON DRAWINGS OR SCHEDULES, MAY LEAVE IMPORTANT COSTS UNACCOUNTED FOR WHICH WILL ULTIMATELY BE THE CONTRACTOR OR SUPPLIER'S RESPONSIBILITY TO PROVIDE.

Sheet Name: GROUND FLOOR DEMO  
PLAN - ELECTRICAL

Progress Prints: Revisions:  
Bid Set (08/09/21)

Revisions:  
1  
2  
3  
4

Revisions:  
1  
2  
3  
4

Construction Issue Date:

Drawn By: AFMZ/PR

Checked By:

Scale: AS NOTED

MOUNT SAINT MARY COLLEGE, GUZMAN HALL  
COMMUNITY WELLNESS CENTER

330 POWELL AVE.  
NEWBURGH, NY 12550

**McHUGH**  
ENGINEERING ASSOCIATES INC.

100 Park Street, Suite 200  
Newburgh, NY 12550  
Phone: 845.562.2222  
Fax: 845.562.2223  
www.mchugheng.com

KIMMEL BOGRETTE

Architecture + Site

482 Morrisown Road, Suite 200  
Blue Bell, PA 19422  
Phone: 610.834.7805  
Facsimile: 610.834.7815

© COPYRIGHT 2021 KIMMEL BOGRETTE ARCHITECTURE + SITE, INC. ALL RIGHTS RESERVED

DEI.I