

**888 resorts World Dr
Monticello, NY 12701**

120 HUYSHOPE AVENUE
SUITE 400
HARTFORD, CT 06106
860.247.9226


© 2021 JCJ Architecture

CONSULTANT: _____

VANDERWEIL

R.G. Vanderweil Engineers, LLP : 617.423.7423 TEL
274 Summer Street : 617.423.7401 FAX
Boston, MA 02210 : vanderweil.com

BIDDING &
CONSTRUCTION
07/06/2022



ISSUE	07/06/2022
JOB	30860.00
DRAWN	RD
SCALE	1/8" = 1'-0"
REVISIONS	

THIRD FLOOR

P-7

PLUMBING GENERAL NOTES

1. EXISTING PIPING AND CONDITIONS ARE SHOWN FOR REFERENCE ONLY TO INDICATE NEW TIE-IN LOCATIONS, AND IS NOT INTENDED TO FULLY REPRESENT ALL EXISTING CONDITIONS, PIPING, VALVES, ACCESSORIES, ETC.
2. VERIFY EXACT LOCATIONS OF EXISTING PIPING SYSTEMS, FIXTURES, AND EQUIPMENT IN THE FIELD.

PLUMBING FOOD SERVICE NOTES

1. FOR EXACT ROUGH-IN DIMENSIONS & EQUIPMENT CONNECTIONS REFER TO FOOD SERVICE EQUIPMENT MANUFACTURERS.
2. COORDINATE FINAL LOCATION OF FLOOR DRAINS WITH FOOD SERVICE EQUIPMENT DRAWINGS.
3. ALL FINAL CONNECTIONS TO FOOD SERVICE EQUIPMENT BY PLUMBING CONTRACTOR.
4. PROVIDE INDIRECT WASTE PIPING FROM FOOD SERVICE EQUIPMENT AND TERMINATE AT NEAREST FLOOR SINK OR FURNEL DRAIN WITH AIR GAP.
5. PROVIDE ISOLATION VALVE ON ALL C.W. & H.W. PIPING HANDING SINKS, SINKS, AND FLOOR DRAINS. COORDINATE ISOLATION VALVE LOCATIONS ABOVE THE SINKS AND FLOOR DRAINS. VALVES SHOULD BE LOCATED TO ALLOW THE PROPER ACCESS. VALVES SHOULD BE LOCATED WITHIN 18" ABOVE THE CEILING.
6. REFER TO FOOD SERVICE DRAWINGS FOR ADDITIONAL INSTALLATION REQUIREMENTS.
7. PROVIDE BACKFLOW PREVENTERS CONFORMING TO ASSE 102 FOR OR ALL BEVERIDGE DISPENSERS, INCLUDING COFFEE MACHINES.
8. PROVIDE TEMPERING VALVE LEONARD #270LF [SET AT 110F] ON HOT WATER SUPPLY FOR ALL HANDWASHING SINKS. VALVE SHALL BE PROVIDED BY INTERNAL CHECK VALVES AND SHALL BE MOUNTED ABOVE HAND SINK

① PLUMBING - THIRD FLOOR
1/8" = 1'-0"