AIR COOLED CONDENSING UNIT (HEAT PUMP) SCHEDULE																	
TAG	LOCATION		NOMINAL COOLING NOMINAL COOLING CAPACITY (BTU/H)			SEER	HSPF	ESP		ELECTRICAL DATA			W X H X D	WEIGHT	SOUND DATA	MANUFACTURER AND MODEL	REMARKS
		SERVICE						(IN. WC)	V/P/C	MCA (AMPS)	MOP (AMPS)	RLA (AMPS)	(INCHES)	(LBS)	(DBA)	MANUSCONEIX CARGO MOSEE	
ACCU-1	GRADE – SEE PLANS	FCU-A	54,000	35,500	10.3	18.0	10	0.6	208/1/60	29.1	35.0	19.0	37.0 X 39.0 X 12.6	200	58	DAIKIN RXTQ48TAVJUA	SEE NOTES
NOTES:										•							

FAN COIL UNIT SCHEDULE (INDOOR UNIT)																	
		NOMINAL COOLING CAPACITY (BTU/H)			FRESH AIR (CFM)	COOLING DATA			HEATING DATA		ELECTRICAL DATA		W V II V D				
TAG						EAT LAT		EAT	LAT	V/D/C MC	MCA (AMPS) MOP (AMPS)		WXHXD (INCHES)	WEIGHT (LBS)	MANUFACTURER AND MODEL	REMARKS	
						DB (°F)	DB (°F)	DB (°F)	DB (°F)	DB (°F)	V/P/C	INICA (ANIFS) NIOF (ANIFS	MUP (AMPS)		(== - /		
	AIR CONDITIONING OF CLASSROOMS S139 & S141		17,057	405	0	80.0	67.0	56.1	70.0	108.2	208/1/60	0.4	15	22.6 X 10.2 X 22.6	50	DAIKIN FXZQ15TAVJU	SEE REMARKS

NOTES: FURNISH AND INSTALL UNITS WITH THE FOLLOWING FEATURES AND ACCESSORIES

1. REMOTE CONTROLLER SIMILAR TO DAIKIN MODEL BRC1E73.

2. DECORATION PANEL WHITE SIMILAR TO DAIKIN MODEL BYFQ60C3W1W.

3. REFNET BRANCH PIPING KIT SIMILAR TO DAIKIN MODEL KHRP26A22T9.

4. PROVIDE BACNET CARD FOR TIE IN TO EXISTING BMS.


CONTRACTOR TO THE										
TAG	LOCATION	GPH (10 FT.)	HEAD (FT.)	SUCTION TEMP (°F)	POWER (HP)	VOLTS/PHASE	WEIGHT (LB)	MANUFACTURER AND MODEL	NOTES	
CP-A	SEE PLANS	42	15	45	1/30	115V/1	5.5	LITTLE GIANT VCMX-20UL	1,2	
NOTES: FURNISH UNIT WITH THE FOLLOWING FEATURES AND OPTIONS										

THERMAL OVERLOAD PROTECTOR AND POLYETHYLENE SCREEN.

2. INTEGRAL FLOAT SWITCH, COPPER CHECK VALVE FOR ½" COPPER TUBING. 3. CONDENSATE PUMP TO BE HARD WIRED AND SUITABLE FOR USE IN PLENUMS.



Lothrop Associates LLP Architects
333 Westchester Avenue White Plains, New York 10604 914-741-1115



Westchester Community College State University of New York

	4	7/22/2022	BID ISSUE
	3	6/24/2022	100% PROGRESS ISSUE
	2	6/02/2022	ISSUED FOR ARCH COORDINATION
	1	5/10/2022	ISSUED FOR PROGRESS
	ISSUE NO.	ISSUE DATE	DESCRIPTION

WESTCHESTER COMMUNITY COLLEGE

CYBER SECURITY LABORATORY RENOVATIONS

> 75 GRASSLAND RD VALHALLA, NY 10595

MECHANICAL SCHEDULES

PROJECT NO.: 23095

M200

