

## STO Safety Exhibit Ei

Summary of daily STO safety policies (which are part of STO Safety Program Exhibit E):

- Provide SSSP
  - Include Master JHA list in SSSP
  - PPE mandatory on all projects
    - Hardhat
    - Construction footwear
    - Safety glasses
    - Gloves – Cut resistance type 4
  - All workers must attend STO orientation prior to starting work
  - Identify and complete STO competent person form. This person must be on site full time & have 30hr OSHA Card
  - STO Daily form completed prior to work starting each day
  - JHA/PTP completed prior to work starting each day. Ideal to complete and review day prior, workers to review and sign in the morning prior to work starting
  - Separate JHA's must be submitted for working from heights, cranes/rigging, electrical LOTO, excavations, confined space, or any other high-risk activity
  - Rolled edge studs required on all projects
  - Ladders last program
  - Body harness with retractable lanyard required in all lifts
  - Infrastructure forms to be completed and signed off prior to work starting
    - NFPA 70E for all electrical work (documented training within last 3 years)
    - Utilities tie-ins
  - Complete Site preparedness. Health screening COVID-19 affidavit forms
  - More sites & clients are requiring proof of vaccination for COVID-19. Subcontractor must be required to verify this on such projects
  - Mask requirements per client and site requirements
  - Stilts NOT allowed on STO projects without prior approval
  - All cores/trenches must be covered or protected by contractor performing the work
  - Weekly toolbox talks
  - Site visits by contractor safety representatives
- National
- Arizona
- California
- Colorado
- Connecticut
- Florida
- Georgia
- Hawaii
- Idaho
- Massachusetts
- New Hampshire
- New Jersey
- New York
- Pennsylvania
- Tennessee
- Texas
- Utah
- Washington
- International
- Canada
- England
- Ireland