

CONTRACTOR SHALL PROVIDE A SEPARATE BASE BID PRICE FOR "UN-RELATED LOSS" BID WORK. SEE BID SHEET BSP-1

ALL DUCTWORK AND BALANCING ASSOCIATED WITH EQUIPMENT LABELED GP1 & CH SHALL BE BID AS "UN-RELATED LOSS" BID WORK.

"UN-RELATED LOSS" BID WORK

NOTE: WORK IN ART ROOM 6 IS PART OF FIRE RESTORATION

1 PARTIAL GROUND FLOOR PLAN - NEW WORK

SCALE: 1/16" = 1'-0"

KEYED NOTES - NEW WORK:

- 1 PROVIDE ANEMOSTAT DOOR LOUVER 12x12 MODEL AFEL 6" AFF. COLOR BEIGE
- 2 PROVIDE VOLUME DAMPERS AS SHOWN. REBALANCE AS REQUIRED
- 3 PROVIDE RUSKIN MODEL ELF375XH 80X80(AH-1) 80X80(EF-2) 11"-5x3-0"(EF-1) PROVIDE LOUVER IN UPPER WINDOWS. BLANK OFF UNUSED PORTION AND PAINT TO MATCH ADJACENT SURFACE. SEAL PERIMETER OF LOUVER WATERIGHT. CONTRACTOR TO REMOVE MULLIONS AS NECESSARY FOR INSTALLATION OF NEW GLAZING. DOES NOT CONTAIN PCB'S OR ASBESTOS. THE EXISTING CAULK AROUND PERIMETER OF FRAME CONTAINS PCB'S. DO NOT DISTURB CAULK.
- 4 PROVIDE ELECTRIC UNIT HEATER QUARK MODEL MUHOS-81 WITH THERMOSTAT. PROVIDE ALL SUPPORTS AS REQUIRED. MOUNT 12" BELOW CEILING. (WIRING BY EC)
- 5 PROVIDE GREENECK EXHAUST FAN MODEL BCF-212, 994 RPM, 1.25 STATIC PRESSURE. PROVIDE ALL SUPPORTS, VIBRATION ISOLATORS AND ALL APPURTENANCES. MOUNT HIGH AS POSSIBLE FROM STRUCTURE ABOVE. (WIRING BY EC)
- 6 PROVIDE GREENECK EXHAUST FAN MODEL BCF-212, 1045 RPM, 1.25 STATIC PRESSURE. PROVIDE ALL SUPPORTS, VIBRATION ISOLATORS AND ALL APPURTENANCES. MOUNT HIGH AS POSSIBLE FROM STRUCTURE ABOVE. (WIRING BY EC)
- 7 PROVIDE DAKIN MODEL LAHOOTA AND ALL APPURTENANCES.
- 8 BALANCE ALL NEW EQUIPMENT, DIFFUSERS AND RETURN GRILLES TO CFM'S SHOWN
- 9 PROVIDE NEW LOUVER RUSKIN ELF375XH CUSTOM SIZE 42" 20". SEAL AROUND LOUVER WATERIGHT. CONTRACTOR TO FIELD VERIFY EXACT SIZE BEFORE ORDERING.
- 10 LOUVER L-1 REQUIRES 48x36 FREE AREA. BLANK OFF UNUSED PORTION WITH 4" RIGID INSULATED PANEL AND WITH 22 GAUGE SHEET METAL INTERIOR PANEL. PAINT INTERIOR METAL PANEL TO MATCH ADJACENT SURFACES

NOTE: MECHANICAL CONTRACTOR IS RESPONSIBLE FOR REMOVING CEILINGS AND WALLS FOR THEIR PORTION OF WORK AND TO REINSTALL CEILINGS AND WALLS TO ORIGINAL CONDITIONS.

KEY-PLAN
SCALE NONE

ISSUE FOR ADDENDUM 4

2 PARTIAL GROUND FLOOR PLAN - NEW WORK

SCALE: 3/16" = 1'-0"



CONSULTANT(S)

SWAP



**YONKERS PUBLIC SCHOOLS
FIRE RESTORATIONS
CROSS HILL ACADEMY**
100 BOLLMER AVE. YONKERS N.Y. 10703
S.E.D.# 20-001-004-011

ISSUED FOR BID	NOV 2021
OWNER BY	NY
DESIGNED BY	NY
SHEET SIZE	11x17" x 8"
SCALE	AS NOTED
SHEET TITLE	PARTIAL GROUND FLOOR PLANS - NEW WORK

SHEET NO.
**CHA
MP-100**

1_37_2022