## **CEILING REMOVAL NOTES:**

(COORDINATE REMOVALS W/ ABATEMENT CONTRACTOR)


- CR1) REMOVE EXISTING SUSPENDED CEILING ASSEMBLY (2x4 OR 2x2), SUSPENSION SYSTEM, PANELS, WALL ANGLES, SEISMIC TIES AND ALL RELATED ITEMS. COORDINATE WORK WITH E-CONTRACTOR. PATCH ALL DISTURBED SURFACES TO MATCH EXISTING ADJACENT SURFACES.
- CR2) REMOVE EXISTING ACOUSTICAL SPLINE CEILING PANELS (1'X1') ASSEMBLY INCLUDING ADHESIVE, CLIPS, WALL TRIM, PANELS, WOOD CROWN MOLDING TRIM AND ASSOCIATED ITEMS.
- CR3) EXISTING LIGHT FIXTURES TO BE REMOVED BY E-CONTRACTOR. SEE AE-DWGS & E-DWGS FOR ADDITIONAL INFORMATION.
- CR4) REMOVE & REPLACE EXISTING CEILING MOUNTED DEVICES TO LOCATION SHOWN. BY E-CONTRACTOR SEE AS DWGS & S-DWGS FOR ADDITIONAL INFORMATION
- CR5) RELOCATE EXISTING DIFFUSER AND MODIFY DUCTWORK TO LOCATION SHOWN. BY H-CONTRACTOR
- CR6 RELOCATE EXISTING CEILING MOUNTED DEVICES TO LOCATION SHOWN. BY E-CONTRACTOR. SEE AE-DWGS & E-DWGS FOR ADDITIONAL INFORMATION.

NOTE: ALL CEILING MOUNTED DEVICES IN AREAS INDICATED ON DWG. ASB-102 SHALL BE REMOVED BY ASBESTOS ABATEMENT CONTRACTOR UNDER GENERAL CONSTRUCTION CONTRACT. ALL CEILING MOUNTED DEVICES TO BE RELOCATED ARE TO BE CLEANED AND TURNED OVER TO RESPECTIVE CONTRACTORS AT COMPLETION OF ABATEMENT OPERATIONS.



JOB NAME:

S.E.D. CONTROL NUMBER: 66-23-00-01-0-204-019



YONKERS SCHOOL DISTRICT GORTON HIGH SCHOOL CAPITAL IMPROVEMENT PHASE 3

100 SHONNARD PLACE, YONKERS, N.Y. 10703

DRAWING TITLE:
CEILING REMOVAL NOTES

	04-19-2022	ADDENDUM #3
	DATE	ISSUED TO
	SCALE:	AS NOTED
	FILE NO.	DRAWING NO.
	20373.00	SK-A3.0