



REINFORCEMENT SCHEDULE		
R1	#5 BARS @ 10" O.C. VERT. #4 BARS @ 12" O.C. HORIZ.	
R2	#5 BARS @ 8" O.C. VERT. #4 BARS @ 12" O.C. HORIZ.	
R3	#5 BARS @ 12" O.C. VERT. #4 BARS @ 10" O.C. HORIZ.	
R4	#4 BARS @ 12" O.C. VERT. #4 BARS @ 12" O.C. HORIZ.	
R5	#5 BARS @ 10" O.C. VERT. #4 BARS @ 12" O.C. HORIZ.	
R6	#5 BARS @ 10" O.C. VERT. #4 BARS @ 10" O.C. HORIZ.	
R7	#5 BARS @ 12" O.C. VERT. #4 BARS @ 10" O.C. HORIZ.	

**NORTH ELEVATION (9 1/4" PANEL TYP. U.N.O.)**  
SCALE: 1/8" = 1'-0"  
(LOOKING FROM INSIDE OF BUILDING ALONG COLUMN LINE A)  
NOTES:  
1. VERIFY ALL PANEL AND OPENING DIMENSIONS w/GENERAL CONTRACTOR & ARCHITECT PRIOR TO CUTTING PANELS w/DOORS AND WINDOWS  
2. PROVIDE 1-W/5 E/F. AROUND PERIMETER OF PANEL U.N.O.  
3. CONTINUE REINFORCING THROUGH KNOCK-OUT OPENINGS.  
4. BLOCKING SHALL TO REMAIN AFTER COMPLETION OF ERECTION OF PANELS.  
5. HORIZONTAL STEEL CONTINUES THROUGH PANEL LEGS AT ALL OPENINGS.