DEMOLITION LEGEND

SYMBOL	DESCRIPTION
	GRUB AND REMOVE EXISTING VEGETATION
	STAGING AREA
X	REMOVE TREE STUMP
	TREE PROTECTION FENCE
	TEMPORARY CONSTRUCTION FENCE
	SEDIMENT CONTROL FENCE

EROSION CONTROL NOTES:

1. CONTRACTOR SHALL INSTALL AND MAINTAIN ALL EROSION AND SEDIMENT CONTROL FACILITIES THROUGHOUT THE DURATION OF THE CONTRACT.
2. CONTRACTOR SHALL REMOVE ALL EROSION AND SEDIMENT CONTROL FACILITIES UPON FINAL STABILIZATION OF THE PROJECT SITE.

DEMOLITION NOTES:

THIS DRAWING IS BASED UPON SURVEY MAPS COMPILED BY LABELLA ASSOCIATES, 4 BRITISH AMERICAN BOULEVARD, LATHAM, NY 12110.

1. PRIOR TO COMMENCING WORK THE CONTRACTOR SHALL VERIFY THE LOCATIONS OF ALL UNDERGROUND UTILITIES. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO UTILIZE A LOCATING SERVICE TO VERIFY UNDERGROUND UTILITY LOCATIONS. CALL 1-800-962-7962 OR VISIT *WWW.DIGSAFELYNEWYORK.COM* FOR MORE INFORMATION.
2. THE CONTRACTOR SHALL EXERCISE CARE DURING ALL REMOVAL OPERATIONS TO ENSURE THE PROTECTION OF EXISTING FACILITIES INCLUDING BUT NOT LIMITED TO UTILITIES, PAVEMENTS AND PLANT MATERIAL TO REMAIN. DAMAGED FACILITIES INTENDED TO REMAIN SHALL BE REPAIRED AT CONTRACTOR'S EXPENSE.
3. PROTECT EXISTING TREES TO REMAIN. DO NOT DRIVE BELOW CANOPY OF EXISTING TREES OR STORE MATERIALS OR SPILL LIQUIDS OR CHEMICALS BELOW CANOPY OF EXISTING TREES TO REMAIN. PROVIDE TEMPORARY PROTECTION FENCING PER DETAILS.
4. THE CONTRACTOR SHALL VERIFY WITH THE OWNER ANY ITEMS INDICATED TO BE REMOVED THAT WILL BE SALVAGED. DELIVER SALVAGED MATERIALS TO A STORAGE AREA DESIGNATED BY THE OWNER.
5. THE CONTRACTOR SHALL STRIP, STORE AND REUSE ALL TOPSOIL FROM AREAS TO BE PAVED OR REGRADED.
6. DUST CONTROL MEASURE SHALL BE EMPLOYED THROUGHOUT THE CONSTRUCTION AND THE FREQUENCY OF APPLICATION AND/OR THE APPLICATION RATE MAY NEED TO BE INCREASED IF THE PROBLEM PERSISTS OR INTENSIFIES.
7. ALL DEMOLITION MATERIAL, TREE STUMPS, BUILDING MATERIALS TO BE DISPOSED OF BY CONTRACTOR.

TREE PROTECTION FENCE 3 L500

SEDIMENT CONTROL FENCE 1 L500

TEMPORARY CONSTRUCTION FENCE 5 L500

BENCHMARK
XCUT BED ROCK
ELEV.= 1085.77

CLEAR AND GRUB EXISTING VEGETATION

LIMIT OF DISTURBANCE

STAGING AREA

PROTECT ALL TREES DURING TRENCHING, PLACEMENT AND BACKFILL OF WATER AND SEWER PIPING

N

10' 5' 0 10'

1/18/2023 3:16:00 PM NOT FOR CONSTRUCTION

New York State Parks, Recreation and Historic Preservation

Governor Kathy Hochul — Commissioner Erik Kulleseid

IT IS A VIOLATION OF STATE EDUCATION LAW FOR ANY PERSON, UNLESS UNDER THE DIRECTION OF A LICENSED ARCHITECT/ENGINEER TO ALTER THIS DOCUMENT IN ANYWAY. ALTERATIONS MUST HAVE THE SEAL AFFIXED ALONG WITH A DESCRIPTION OF THE ALTERATIONS, DATE AND ARCHITECT'S/ENGINEER'S SIGNATURE. COPYRIGHT © 2023

Architect:
Saratoga Associates
21 Congress Street, Suite 201
Saratoga Springs, NY 12866

SARATOGA ASSOCIATES
Landscape Architects, Architects, Engineers, and Planners, P.C.

Surveyor/Structural/MEP Engineer:
LaBella Associates
105 N. Tioga Street, Suite 200
Ithaca, NY 14850

LaBella Powered by partnership.

Certificate of Authorization Number:
Professional Engineering: 018281
Land Surveying: 017976
Geological: 018750

Palisades Region
Palisades Interstate Park Commission
Bear Mountain, New York 10911
(845) 786-2701
Executive Director: Joshua Laird

Project Title:
CAMP JUNIOR ON LAKE TIORATI - PHASE 3

Project Location:
HARRIMAN STATE PARK

Key Plan

REVISIONS

Rev No	Description	Date:

Drawn By: APY, JMM
Design By: APY,JMM
Checked By: APY
Approved By: DFM
Date: 3/16/23

Seal and Signature

REGISTERED ARCHITECT DONALD F. MINNERLY 015074 THE STATE OF NEW YORK

Sheet Title:
DEMOLITION PLAN
BATHHOUSE #322
Bid Documents Set

Drawing Number:
L-201

Project Number: 21059.23

Sheet: