



1 SECOND FLOOR DEMOLITION PLAN - AREA 'E'

GENERAL NOTES	
1.	COORDINATE ALL REMOVALS WITH NEW CONSTRUCTION
2.	PATCH AND REPAIR EXISTING AND NEWLY CREATED HOLES IN WALLS (DUPE TO REMOVAL) WITH MATERIALS TO MATCH EXISTING CONSTRUCTION
3.	SALVAGED ITEMS SHALL BE TURNED OVER TO OWNER UNO
4.	ALL KEYED REMOVALS SHALL INCLUDE REMOVAL OF ANY AND ALL ANCHORING SYSTEMS INCLUDING OBJECTS EXTENDING INTO EXISTING WALLS
5.	REFER TO ADDENDUMS AND MEP DRAWINGS FOR ADDITIONAL REMOVAL INFORMATION
6.	PROVIDE TEMPORARY SHORING AS NECESSARY AT ALL AREAS OF WALL REMOVAL AND WALL PENETRATIONS
7.	DELIVER CORNERS OF ALL NEW SAWCUT OPENING PRIOR TO SOUTCUTTING TO PREVENT CUTTING INTO SCHEDULED CONSTRUCTION TO REMAIN.
KEY NOTES - DEMOLITION	
D	DESCRIPTION
D1	REMOVE EXISTING RESIDENTIAL FLOOR, WALL BASE, AND MASONRY IN ITS ENTIRETY COORDINATING WITH HAZARDOUS MATERIALS DIVISION
D7	REMOVE EXISTING MOVABLE DIVIDING PARTITION IN ITS ENTIRETY INCLUDING DOORS, PANELS AND HARDWARE
D10	REMOVE EXISTING DOOR AND HARDWARE IN ITS ENTIRETY

--

