1 FIRST FLOOR NEW WORK PLAN - AREA 'B'
A112 1/8" = 1'-0"

GENERAL NOTES

1. REFER TO SHEET G001 FOR ADDITIONAL GENERAL NOTES.
2. REFER TO A700 SERIES DRAWINGS PARTITION TYPES AND ADDITIONAL NOTES.
3. REFER TO A900 SERIES DRAWINGS FOR DOOR, STOREFRONT, CURTAINWALL, WINDOW AND LOUVER SCHEDULES, DETAILS AND NOTES.
4. ALL NEW LOCKERS ARE 15" WIDE x 10" DEEP & TWO TIER

KEY NOTES - NEW WORK

X	DESCRIPTION
1	PAINT ENTIRE WALL INCLUDING AREA WHERE ACOUSTICAL WALL PANELS WERE PREVIOUSLY REMOVED.
2	PROVIDE NEW 12"x12" VCT FLOORING AND RUBBER WALL BASE OVER EXISTING SUBSTRATE.
3	PROVIDE GYPSUM BOARD PATCHING AND NEW 4" RUBBER WALL BASE AT NEW LOCKERS. NEW LOCKER SYSTEMS TO BE PROVIDED BY LOCKER VENDOR. REFER TO DETAILS FOR ADDITIONAL INFORMATION.

KEYPLAN



COPYRIGHT © ALL RIGHTS RESERVED

19 Front St. Newburgh, New York 12550-7601
845-561-3179 www.csarchpc.com
CSARCH

Consultant

Project Title

HIGHLAND CENTRAL SCHOOL DISTRICT
HIGHLAND HIGH SCHOOL
2022 CAPITAL IMPROVEMENT PROJECT - PHASE 1

REGISTERED ARCHITECT ROBERT RITARDI 023344 STATE OF NEW YORK

Expiration Date: 02/28/2025

No.	DATE	DISCRIPTION

Drawn By:	CSA
Checked By:	CSA
Proj. #:	62-08-03-04-0-009-014
CSArch Proj. #:	197-2201.01
Issued for Bid:	08/18/23

Sheet Title

FIRST FLOOR NEW WORK PLAN - AREA 'B'

Sheet No.

HHS A112

CONSTRUCTION DOCUMENTS

C:\Users\dmiller\Documents\197-2201 - HHS Phase1_ARCH_dmiller3803.rvt