



KEY NOTES - NEW WORK	
(X)	DESCRIPTION
5	PROVIDE NEW ROOF EDGE FLASHINGS AND FASCIAS WHERE PREVIOUSLY REMOVED. TIE-IN NEW FLASHINGS TO EXISTING ROOF USING COMPATIBLE SPRAY FOAM ROOF SYSTEM.
21	REINSTALL EXISTING SCUPPER, DOWNSPOUT, AND LEADER PIPE WHERE PREVIOUSLY REMOVED TO ACCOMMODATE ROOF EDGE REPLACEMENT WORK.

Sheet No.

HHS
A400

CONSTRUCTION DOCUMENT