

LIBERTY CENTRAL SCHOOL DISTRICT MAINTENANCE BUILDING


125 Buckley St., Liberty, NY 12754

Construction Documents: 12/13/22

CSARCH - ARCHITECTS
BLAKE ENGINEERING, PLLC - MEP ENGINEERS
PASSERO ASSOCIATES - SITE/CIVIL & STRUCTURAL ENGINEERS

STATE EDUCATION DEPARTMENT PROJECT CONTROL NUMBER:
MAINTENANCE BUILDING 59-09-01-06-3-016-001
THE DESIGN OF THIS PROJECT CONFORMS TO APPLICABLE PROVISIONS OF THE NEW YORK STATE UNIFORM FIRE PREVENTION AND BUILDING CODE, THE NEW YORK STATE ENERGY CONSERVATION CONSTRUCTION CODE, AND THE MANUAL OF PLANNING STANDARDS OF THE NEW YORK STATE EDUCATION DEPARTMENT.

CSArch PROJECT NO. 203-2201



DRAWING LIST - MAINTENANCE BUILDING (MB)

GENERAL DRAWINGS	
G001	SYMBOLS, ABBREVIATIONS, AND MISC
CIVIL DRAWINGS	
C111	NOTES
C130	EXISTING CONDITIONS, DEMOLITION, EROSION AND SEDIMENT CONTROL PLAN & SITE AND UTILITIES PLAN
C540	DETAILS
ARCHITECTURAL DEMOLITION DRAWINGS	
AD101	DEMOLITION PLAN
LIFE SAFETY DRAWINGS	
LS101	LIFE SAFETY PLANS
STRUCTURAL DRAWINGS	
S001	GENERAL NOTES, DESIGN CRITERIA, AND SCHEDULES
S002	SPECIAL INSPECTIONS
S101	PLANS & SECTIONS
S501	TYPICAL DETAILS
ARCHITECTURAL DRAWINGS	
A111	FIRST FLOOR PLAN
A201	EXTERIOR ELEVATIONS
A251	BUILDING SECTIONS
A301	WALL SECTIONS
A302	WALL SECTIONS
A351	SECTION DETAILS
A352	PLAN DETAILS
A401	ROOF PLAN AND DETAILS
A451	ROOF FRAMING PLAN
A601	ENLARGED PLAN AND ELEVATIONS
A602	ENLARGED PLAN AND ELEVATIONS
A603	ENLARGED PLAN AND ELEVATIONS
A604	TYPICAL EQUIPMENT PLANS, ELEVATIONS, AND DETAILS
A701	PARTITION TYPES
A811	FIRST FLOOR REFLECTED CEILING PLAN AND DETAILS
A901	DOOR SCHEDULE, ELEVATIONS, AND DETAILS
ARCHITECTURAL FINISH DRAWINGS	
AF001	FINISH SCHEDULES AND PLANS
PLUMBING DRAWINGS	
P101	PLUMBING NOTES, SCHEDULE, LEGEND, & DETAILS
P201	WATER & GAS DISTRIBUTION PLAN
P202	SANITARY PLAN
MECHANICAL DRAWINGS	
M101	MECHANICAL NOTES, LEGEND, SCHEDULE, & DETAILS
M102	MECHANICAL SCHEDULES & PIPING DIAGRAM
M201	MECHANICAL PLAN
M202	HYDRONIC PLANS
ELECTRICAL DRAWINGS	
E101	ELECTRICAL NOTES, LEGEND, DETAILS, & SCHEDULES
E102	ELECTRICAL SITE PLAN
E201	LIGHTING PLAN
E301	POWER PLAN



C:\Users\jmliller\OneDrive - CSArch\Documents\2013-2021_Liberty_High_School_Maint Bldg.dmliller2013-CSA303.rvt

ABBREVIATIONS

ABBREVIATION DESCRIPTION

ADD	ADDENDUM
ADMIN	ADMINISTRATIVE
AFF	ABOVE FINISHED FLOOR
ALT	ALTERNATE
APPROX	APPROXIMATE
ARCH	ARCHITECT / ARCHITECTURAL
AV	AUDIO VISUAL
BLDG	BUILDING
BOT OR B/BSMT	BOTTOM OF BASEMENT
CJ	CONTROL / CONSTRUCTION JOINT
CL	CENTERLINE
CLS / CLNS	CLEAR
CLR	CLEAR
CMU	CONCRETE MASONRY UNIT
COL	COLUMN
CONC	CONCRETE
CONF	CONFERENCE
CONT	CONTINUOUS
COORD	COORDINATE
CORR	CORRIDOR
DEMO	DEMOLITION
DET	DETAIL
DIA	DIAMETER
DN	DOWN
DWG	DRAWING
ED	EDUCATION
EPS	EXTERIOR INSULATION FINISH SYSTEM
ELEGT	ELECTRIC / ELECTRICAL
EPDM	ETHYLENE PROPYLENE DIENE MONOMER
EQ	EQUAL
EQUIP	EQUIPMENT
EXST	EXISTING
EJ	EXPANSION JOINT
EXT	EXTERIOR
FIN	FINISH
FIN FL	FINISH FLOOR
FIXT	FIXTURE
FLR	FLOOR
FRT	FIRE-RETARDENT-TREATED MATERIAL
FTG	FOOTING
GA	GAUGE
GAL	GALLON
GALV	GALVANIZED
GC	GENERAL CONTRACT(OR)
GND	GROUND
GWB	GYPSUM WALL BOARD
GWBS	GYPSUM WALL BOARD SOFFIT
HC	HANDICAPPED ACCESSIBLE
HM	HOLLOW METAL
HORIZ	HORIZONTAL
HR	HOOR
HT	HEIGHT
HTG	HEATING
HVAC	HEATING/VENTILATING/AIR CONDITIONING
ID	INSIDE DIMENSION
IN	INCH / INCHES
INT	INTERIOR
JAN	JANITOR
JG	JANITOR'S CLOSET
JST	JOIST
JT	JOINT
LAB	LABORATORY
LB	POUND
LIN	LINEAR
LVL	LEVEL
MAN	MANUAL
MAS	MASONRY
MAX	MAXIMUM
MDF	MEDIUM DENSITY FIBERBOARD
MECH	MECHANICAL
MEZZ	MEZZANINE
MFR	MANUFACTURE(R)
MD	MIDDLE
MIN	MINIMUM
MISC	MISCELLANEOUS
MO	MASONRY OPENING
MTL	METAL
NA	NOT APPLICABLE
NC	NOT IN CONTRACT
NOM	NOMINAL
NTS	NOT TO SCALE
OA	OVERALL
OC	ON CENTER
OD	OUTSIDE DIAMETER
O/HD	OVERHEAD
OPT	OPTIONAL
OZ	OUNCE
PERIM	PERIMETER
PLAM	PLASTIC LAMINATE
PLBS	PLUMBING
PLAS	PLASTER
PLYND	PLYWOOD
PNL	PANEL
PNT	PAINTED
POLYISO	POLYISOCYANURATE
PFT	PRESSURE PRESERVATIVE TREATED
PR	PAIR
PREP	PREPARATORY
PTN	PARTITION
PVC	POLYVINYL CHLORIDE
RAD	RADIUS
RB	RUBBER / RUBBER WALL BASE
REQD	REQUIRED
RM	ROOM
RND	ROUND
RO	ROUGH OPENING
SGH	SCHEDULED
SECT	SECTION
SF	SQUARE FEET
SIM	SIMILAR
SPEC	SPECIFICATION
SQ	SQUARE
SS	STAINLESS STEEL
STC	SOUND TRANSMISSION GLASS
STD	STANDARD
STL	STEEL
STOR	STORAGE
STRUCT	STRUCTURAL / STRUCTURE
SUSP	SUSPENDED
SAC	SUSPENDED ACOUSTICAL CEILING
T&B	TOP AND BOTTOM
T&G	TONGUE AND GROOVE
TECH	TECHNOLOGY
TEMP	TEMPORARY
TMFD	TEMPERED
TOM	TOP OF MASONRY
TOS	TOP OF STEEL
TYP	TYPICAL
UL	UNDERWRITERS LABORATORY
UNO	UNLESS NOTED OTHERWISE
VERT	VERTICAL
VEST	VESTIBULE
VIF	VERIFY IN FIELD
W/	WITH
W/O	WITHOUT
WD	WOOD
WPT	WOOD PRESERVED-TREATED MATERIAL
WT	WEIGHT
YD	YARD

ARCHITECTURAL LEGEND

MATERIAL INDICATIONS

	EARTH
	GRANULAR FILL
	BRICK
	CONCRETE MASONRY UNIT
	CONCRETE
	GROUT
	ROUGH WOOD BLOCKING
	SHIM
	FINISH WOOD
	PLYWOOD
	SHEATHING
	RIGID INSULATION
	BATT INSULATION
	SPRAY FOAM INSULATION
	EPS INSULATION
	STEEL

DIMENSIONING CONVENTIONS

	FACE OF STUD OR CMU
	COLUMN CENTER LINE

SYMBOLS

	CLASSROOM
	ROOM NAME
	ROOM NUMBER
	AREA OF ROOM
	DOOR NUMBER, REFER TO A100 DRAWINGS
	WINDOW TAG, REFER TO A100 DRAWINGS
	BORROWED LIGHT NUMBER, REFER TO A100 DRAWINGS
	STOREFRONT / CURTAIN WALL NUMBER, REFER TO A100 DRAWINGS
	COLUMN GRID DESIGNATION
	PARTITION TAG, REFER TO A100 DRAWINGS
	REVISION NUMBER
	KEY NOTE, NEW WORK
	KEY NOTE, DEMOLITION WORK
	ELEVATION TAG
	HANDICAPPED ACCESSIBLE ELEMENT OR FIXTURE
	INTERIOR FINISH TAG, REFER TO A100 DRAWINGS

DETAIL INDICATOR LEGEND

SECTION INDICATOR

	SECTION NUMBER
	DRAWING SHEET NUMBER
	SECTION IS DRAWN ON
	DIRECTION OF VIEW

DETAIL INDICATOR (SECTION)

	SECTION NUMBER
	DRAWING SHEET NUMBER
	SECTION IS DRAWN ON
	DIRECTION OF VIEW

ENLARGED DETAIL INDICATOR

	DETAIL NUMBER
	DRAWING AREA REQUIRING DETAIL
	DETAIL IS DRAWN ON

DETAIL TITLE

	DETAIL NUMBER
	DETAIL TYPE / NAME
	DRAWING SHEET NUMBER
	SCALE

EXTERIOR ELEVATION INDICATOR

	ELEVATION NUMBER
	DIRECTION OF VIEW
	DRAWING SHEET NUMBER
	DETAIL IS DRAWN ON


INTERIOR ELEVATION INDICATOR

	ELEVATION NUMBER
	BLANK ARROW INDICATES ELEVATIONS NOT DETAILED
	DRAWING SHEET NUMBER
	DETAIL IS DRAWN ON
	DIRECTION OF VIEWS

PLAN GRAPHICS LEGEND

	EXISTING CONSTRUCTION TO REMAIN
	EXISTING CONSTRUCTION TO BE REMOVED
	NEW CONCRETE MASONRY WALL
	NEW METAL STUD WALL
	NEW BRICK VENEER
	EXISTING DOOR TO REMAIN
	EXISTING DOOR TO BE REMOVED
	NEW DOOR

FINISHED DOOR OPENINGS SHALL BE LOCATED AS INDICATED BELOW UNO. DIMENSIONS SHOWN ARE CLEAR DIMENSIONS FROM INSIDE OF FRAME TO WALL FINISH.



GENERAL NOTES

- DIMENSIONS ARE GIVEN THUS (UNLESS NOTED OTHERWISE)
 - TO FACE OF MASONRY WALL
 - TO FACE OF METAL STUD
 - TO COLUMN CENTERLINES
 - TO FINISH FACE OF SOFFIT OR CEILING
 - FACE OF EXISTING CONSTRUCTION
- DO NOT SCALE DRAWINGS. IF A DIMENSION IS NOT SHOWN, BRING IT TO THE ATTENTION OF THE ARCHITECT FOR VERIFICATION BEFORE PROCEEDING WITH THE ASSOCIATED WORK.
- WALLS ON COLUMN LINES ARE CENTERED, UNO.
- ALL DIMENSIONS RELATED TO EXISTING CONDITIONS SHALL BE VERIFIED IN FIELD. CONTRACTOR TO NOTIFY ARCHITECT OF ANY DISCREPANCIES PRIOR TO BEGINNING WORK IN THAT AREA.
- LAYOUT OF TOILET FIXTURES AND ACCESSIBILITY CLEARANCES ARE SHOWN AS CLEAR DIMENSION. CONTRACTORS ARE REQUIRED TO COORDINATE LAYOUTS OF PARTITIONS, UTILITY CONNECTIONS, AND THICKNESS OF FINISHES TO ALLOW THESE CLEAR DIMENSIONS.
- ALL ELEVATIONS (X-X) ARE REFERENCE FROM FIRST FLOOR ELEVATION.
- ALL WOOD BLOCKING WITHIN ROOFING SYSTEM AND WITHIN 2'-0" OF GRADE SHALL BE PRESSURE TREATED.
- ALL FLOOR PENETRATIONS SHALL BE SMOKE-SEALED AND /OR FIRE STOPPED. COORDINATE WITH H DWGSS FOR SMOKE / FIRE DAMPER REQUIREMENTS.
- FOR INTERIOR PARTITION TYPES, REFER TO DRAWING A101.
- FOR DOOR SCHEDULE, REFER TO DRAWING A101.
- FOR FINISH SCHEDULE, REFER TO DRAWING A101.
- ALL EXPOSED SURFACES OF NEW PARTITIONS AND SOFFITS ARE TO BE FINISHED.
- PROVIDE PATCH TO MATCH EXISTING FINISHES AT ALL WALL REMOVAL AREAS, COORDINATE WITH DEMOLITION DRAWINGS AND SPECIFICATIONS.
- FOR ALL MATERIAL TESTING, REFER TO SPECIFICATION DIVISION 000220.
- ALL CONSTRUCTION SHOWN IS NEW UNLESS NOTED OTHERWISE.

19 Front St., Newburgh, New York 12550-7601
845.561.1317 www.csaarch.com

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By:	CSA
Checked By:	CSA
Proj. #:	59-09-01-86-3-016-001
CSArch Proj. #:	203-2201
Construction Documents:	12/13/22


Sheet Title

SYMBOLS,
ABBREVIATIONS,
AND MISC


Sheet No.

MB
G001


CONSTRUCTION DOCUMENTS




1 STANDARD 30"x42" CATCH BASIN DETAIL
N.T.S.




2 OIL-WATER SEPARATOR DETAIL
N.T.S.




3 SANITARY SEWER MANHOLE
N.T.S.




6 ROOF DRAIN DETAIL WITH CLEANOUT
N.T.S.




7 TYPICAL SIDEWALK DETAIL
N.T.S.




9 SINGLE SWING GATE WITH POSTS
N.T.S.




11 TEMPORARY CONSTRUCTION FENCING
N.T.S.




12 SILT FENCE DETAIL
N.T.S.




13 FILTER FABRIC DROP INLET PROTECTION
N.T.S.




16 CONCRETE ENCASEMENT DETAIL
N.T.S.




17 TYPICAL WATER AND SEWER SEPARATION DETAIL
N.T.S.




19 PIPE CONNECTION TO EXISTING STRUCTURE CEMENT GROUT SEAL JOINT
N.T.S.




3A MANHOLE FRAME & COVER
N.T.S.




4 WATERMAIN TRENCH
N.T.S.




8 SITE PAVEMENT SECTION
N.T.S.




5 STORM SEWER/SANITARY SEWER BEDDING DETAILS
N.T.S.




10 6FT HIGH CHAIN-LINK FENCE
N.T.S.




14 WATER VALVE
N.T.S.



15 ANTI-SEEP COLLAR DETAIL
N.T.S.



20 FLARED END SECTION AND STONE RIP-RAP DETAIL
N.T.S.




2 EXISTING CONDITION PHOTOS
AD101 1/2" = 1'-0"

- GENERAL NOTES**
1. CONTRACTOR MUST EMPLOY WORKERS TRAINED, EXPERIENCED, AND KNOWLEDGEABLE IN THIS TYPE OF WORK.
 2. ALL MATERIALS IN THE BUILDING SHALL BE DISPOSED OF AS PART OF THIS WORK. THIS INCLUDES BUT IS NOT LIMITED TO FURNITURE, CABINETS, CEILING TILES, AND CARPETING.
 3. CONTRACTOR IS TO PROVIDE UTILITIES FOR PROJECT MONITOR.
 4. SITE SECURITY IS THE RESPONSIBILITY OF THE CONTRACTOR UNDER CONTROLLED DEMOLITION. CONTRACTOR MUST DEFINE HIS WORK ZONE AND INSTALL 6' HIGH CHAIN LINK CONSTRUCTION FENCING AROUND THE ENTIRE WORK ZONE. THE FENCING SHALL HAVE LOCKABLE GATES FOR EGRESS/INGRESS.
 5. THE CONTRACTOR SHALL COMPLETELY DEMOLISH THE BUILDINGS AND REMOVE ALL FOUNDATIONS AND/OR FOOTER WALLS SPECIFIED.
 6. ANY DAMAGE TO ROADWAYS, SIDEWALKS, CURBS, TREES, UTILITIES OR THEIR STRUCTURES NOT INCLUDED IN THIS WORK SHALL BE REPAIRED TO A CONDITION ACCEPTABLE TO THE OWNER.
 7. REMOVE AND DISPOSE OF ALL MATERIALS IN ACCORDANCE WITH THESE SPECIFICATIONS, THE LATEST REGULATIONS FROM THE ENVIRONMENTAL PROTECTION AGENCY, OSHA, THE U.S. DEPARTMENT OF HEALTH, EDUCATION AND WELFARE, NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION, AND OTHER APPLICABLE FEDERAL, STATE, AND LOCAL GOVERNMENT REGULATIONS. WHENEVER THERE IS A CONFLICT OR OVERLAP OF THE ABOVE REFERENCES, THE MOST STRINGENT PROVISION IS APPLICABLE.
 8. UTILITIES THAT ARE CAPPED ARE TO BE REMOVED FROM THE DISTURBANCE ZONE.
 9. ALL UTILITY DISCONNECTIONS ARE TO BE COORDINATED WITH INDIVIDUAL UTILITY COMPANIES.


KEY NOTES

- DEMOLISH EXISTING 1 STORY STRUCTURAL MASONRY BUILDING, INCLUDING ALL STRUCTURE, FINISHES, EQUIPMENT, ETC.
- DEMOLISH EXISTING ASPHALT AND CONCRETE. REFER TO CIVIL DRAWING FOR ADDITIONAL INFORMATION.




1 DEMOLITION PLAN
AD101 3/16" = 1'-0"

C:\Users\jmliller\OneDrive - CSArch\Documents\2013-2011_Liberty_High_School_Maint_Bldg_dmliller2013-CSA303.rvt



2 SITE PLAN
LS101 1" = 30'-0"



1 LIFE SAFETY FLOOR PLAN
LS101 1/4" = 1'-0"

LIFE SAFETY PLAN LEGEND	
	PRIMARY EXIT
	SECONDARY EXIT
	RESCUE WINDOW (SECONDARY EXIT)
	ACCESSIBLE EXIT
	RESCUE ASSISTANCE STATION / AREA OF REFUGE
	NUMBER OF OCCUPANTS PER TABLE 1004.1.2 (ACTUAL NUMBER OF OCCUPANTS)
	REQUIRED EXIT WIDTH FOR DOOR BASED ON (OCCUPANT * 0.2)
	REQUIRED EXIT WIDTH FOR STAIRS BASED ON (OCCUPANT * 0.3)
	EXIT PATH OF TRAVEL (START - END)
ABBREVIATIONS	
DC	DEFIBRILLATOR CABINET
EWP	EXIT WIDTH PROVIDED
EWK	EXIT WIDTH REQUIRED
FE	FIRE EXTINGUISHER
FEC	FIRE EXTINGUISHER CABINET
OCCS	NUMBER OF OCCUPANTS IN SPACE

FIRE SEPARATION NOTES	
	1 HOUR RATED FIRE PARTITION
	2 HOUR RATED FIRE PARTITION

CODE NARRATIVE:	
NEW CONSTRUCTION:	IIB
CONSTRUCTION TYPE:	3020 SF GROSS
FIRST FLOOR AREA:	51-MODERATE HAZARD STORAGE
CURRENT USE:	

BUILDING AREA:	
PERMITTED FOR TYPE (PER TABLE 506.2)	
REQUIRED CORRIDOR FIRE-RESISTANCE RATING:	
1-HOUR (PER TABLE 1020.1)	

CODE NOTES	
ALL NEW WORK TO BE PERFORMED SHALL BE IN ACCORDANCE WITH THE FOLLOWING:	
1. 2020 INTERNATIONAL BUILDING CODE	
2. 2020 INTERNATIONAL EXISTING BUILDING CODE	
3. NYS BUILDING CODE SUPPLEMENTS	
4. ANSI A117.1-01	
5. 1498 NYSDE MANUAL OF PLANNING STANDARDS	

ALL EXISTING CONDITIONS AND NEW WORK CONDITIONS CONTAIN THE FOLLOWING MAXIMUM TRAVEL DISTANCES:	
1. EXIT ACCESS TRAVEL DISTANCE SHALL NOT EXCEED 200 FEET FOR UNSPRINKLERED BUILDINGS OF OCCUPANCY TYPE 'E'.	
2. ANY POINT IN ANY GROUND FLOOR CORRIDOR MUST BE WITHIN 150 FEET ALONG THE LINE OF TRAVEL TO AN EXTERIOR DOORWAY. ANY POINT IN A CORRIDOR OTHER THAN A GROUND FLOOR CORRIDOR SHALL NOT EXCEED 120 FEET ALONG THE LINE OF TRAVEL TO THE STAIR ENCLOSURE OF AN EXIT STAIRWAY.	

ALL EXISTING CONDITIONS AND NEW WORK CONDITIONS CONTAIN THE FOLLOWING DEAD-END CORRIDOR INFORMATION:	
1. DEAD-END CORRIDOR POCKETS SHALL NOT EXCEED A MAXIMUM DEPTH OF 1 1/2 TIMES THE WIDTH OF THE POCKET, OR 1 1/2 TIMES THE WIDTH OF THE CORRIDOR, WHICHEVER IS LESS. MAX. DEAD-END DISTANCE IS 20'.	

19 Front St., Newburgh, New York 12550-7601
845.561.3379 www.csarchitect.com

CSARCH

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title

DATE	DESCRIPTION

Drawn By:
Checked By:
Proj. #: 59-09-01-86-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

Sheet Title

LIFE SAFETY
PLANS

Sheet No.

MB
LS101

CONSTRUCTION DOCUMENTS

C:\Users\jwelmering\Documents\liberty Maintenance Building_000000.xxxx - STR - RV722_jwelmering.dwt

GENERAL NOTES:

- ALL STRUCTURAL DRAWINGS SHALL BE USED IN CONJUNCTION WITH THE ARCHITECTURAL, MECHANICAL, ELECTRICAL, HVAC, AND PLUMBING DRAWINGS AND SPECIFICATIONS.
- THE CONTRACTOR(S) SHALL VERIFY ALL EXISTING CONDITIONS, DIMENSIONS, ELEVATIONS, ETC., IN THE FIELD AND NOTIFY THE OWNER'S REPRESENTATIVE OF ANY DISCREPANCIES PRIOR TO THE START OF CONSTRUCTION OR SHOP DRAWINGS.
- THE DRAWINGS ARE INTENDED TO REQUIRE AND TO INCLUDE ALL LABOR, MATERIAL AND EQUIPMENT PROPER FOR THE WORK.
- ALL WORK SHALL COMPLY WITH ALL LOCAL, STATE AND NATIONAL CODES AND REQUIREMENTS. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR CONSTRUCTION MEANS, METHODS, TECHNIQUES, SEQUENCES, AND SAFETY PROCEDURES. THE ARCHITECT/ENGINEER SHALL NOT BE RESPONSIBLE FOR THE ACTS OR OMISSIONS OF THE CONTRACTOR, SUBCONTRACTORS OR THEIR AGENTS OR EMPLOYEES OR ANY OTHER PERSONS PERFORMING THE WORK OR ANY PART THEREOF.
- OBSERVE ALL OSHA AND OTHER APPLICABLE SAFETY REQUIREMENTS INCLUDING THE USE OF SAFETY GLASSES, HARD HATS, AND PROTECTION OF AREA WHEN WORKING OVERHEAD. THE CONTRACTOR SHALL ASSUME RESPONSIBILITY FOR CONSTRUCTION SAFETY AT ALL TIMES.
- COORDINATE WORK OF ALL DISCIPLINES (STRUCT., ARCHIT., MECH., ELECT., ETC.) WITH EXISTING CONDITIONS, SPECIAL REQUIREMENTS, CONSTRUCTION SCHEDULE AND OTHER CONTRACTORS PERFORMING WORK AT THE SITE.
- ALL TEMPORARY SHORING SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. THE CONTRACTOR SHALL DESIGN AND PROVIDE ANY TEMPORARY SHORING, BRACING, ETC., AS NEEDED FOR THE WORK SO AS NOT TO ENDANGER THE STRUCTURAL INTEGRITY OF ANY EXISTING FEATURE. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO REPAIR ANY DAMAGE DONE TO EXISTING FEATURES AS A RESULT OF THIS WORK. DAMAGED ITEMS SHALL BE REPLACED IN KIND AND AT NO ADDITIONAL COST TO THE OWNER.
- DO NOT SCALE DRAWINGS. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND LAYOUT PRIOR TO CONSTRUCTION. ALL DIMENSIONS ON STRUCTURAL DRAWINGS SHALL BE CHECKED AGAINST ARCHITECTURAL, MECHANICAL, ELECTRICAL, PLUMBING, AND CIVIL DRAWINGS AND ANY DISCREPANCIES SHALL BE BROUGHT TO THE ATTENTION OF THE OWNER'S REPRESENTATIVE. IMMEDIATELY. SEE THE ARCHITECTURAL DRAWINGS FOR ALL DIMENSIONS NOT SHOWN ON THE STRUCTURAL DRAWINGS. REFER TO MECHANICAL, ELECTRICAL, AND ARCHITECTURAL DRAWINGS FOR OPENINGS NOT SHOWN ON STRUCTURAL DRAWINGS. CHANGES AFFECTING THE LAYOUT SHOWN MUST BE SPECIFIC AND CLEARLY CONVEYED TO THE OWNER'S REPRESENTATIVE IN WRITTEN FORM AS A CHANGE FOR INCLUSION INTO THESE PLANS.
- SHOP DRAWINGS: REPRODUCTION OF DESIGN DRAWINGS SHALL NOT BE PERMITTED FOR SHOP DRAWING SUBMISSIONS. THE GENERAL CONTRACTOR/CONSTRUCTION MANAGER SHALL REVIEW AND PROVIDE REVIEW STAMP ON SHOP DRAWINGS SUBMISSIONS PRIOR TO SUBMITTAL TO ARCHITECT/ENGINEER INDICATING UNDERSTANDING AND ACCEPTANCE OF SUBMITTAL AND CONFIRMING CONFORMANCE TO PROJECT PLANS/SPECIFICATIONS.
- IT IS SOLELY THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE ERECTION PROCEDURE AND SEQUENCE TO INSURE THE SAFETY OF THE BUILDING AND ITS COMPONENT PARTS DURING ERECTION. THIS INCLUDES, BUT IS NOT LIMITED TO, THE ADDITION OF WHATEVER TEMPORARY BRACING, GUYS OR TIE-DOWNS MAY BE NECESSARY.
- EQUIPMENT FRAMING LOADS, OPENINGS AND STRUCTURE IN ANY WAY RELATED TO HVAC, PLUMBING, PROCESS OR ELECTRICAL REQUIREMENTS ARE SHOWN FOR BIDDING PURPOSES ONLY. CONTRACTOR SHALL OBTAIN APPROVAL OF THE PERTINENT TRADES BEFORE PROCEEDING WITH SUCH PORTION OF THE WORK. EXCESS COST RELATED TO VARIATION IN THESE REQUIREMENTS SHALL BE BORNE BY THE APPROPRIATE CONTRACTOR.

FOUNDATION NOTES

- FOOTING ELEVATION SHOWN REPRESENT THE MINIMUM DEPTH TO WHICH FOOTINGS SHALL BE PLACED, BUT SHALL BEAR AT A DEPTH BELOW FINISHED GRADE NO LESS THAN 4'-0". FOOTINGS SHALL BE LOWERED AS REQUIRED TO OBTAIN SUITABLE BEARING. WHERE FOOTINGS ARE REQUIRED TO BE LOWERED MORE THAN 1' FOOT, NOTIFY THE ENGINEER OF RECORD. ALL UNSUITABLE FOUNDATION MATERIAL SHALL BE REMOVED WITH FOOTINGS RESTING ON STRUCTURAL FILL WITH A MINIMUM BEARING CAPACITY OF 1500 PSF, UNLESS OTHERWISE INDICATED.
- A GEOTECHNICAL ENGINEER SHALL VERIFY THE ALLOWABLE BEARING CAPACITY OF THE SOILS PRIOR TO THE START OF CONSTRUCTION, AND NOTIFY THE EOR IF THE ALLOWABLE BEARING CAPACITY IS LOWER THAN 1500 PSF. THE GEOTECHNICAL ENGINEER SHALL PROVIDE RECOMMENDATIONS FOR REMEDIATING POOR BEARING OR PROVIDE ALTERNATE BEARING/FOUNDATION SUPPORT SOLUTIONS.
- A GEOTECHNICAL ENGINEER SHALL OBSERVE THE OPEN EXCAVATION TO DETERMINE THAT THE SOIL TYPE AND CONDITIONS ARE CONSISTENT WITH DESIGN CRITERIA OF THE SOIL REPORT. IF THE SOIL PROPERTIES ARE FOUND TO BE DIFFERENT FROM THIS CRITERIA THE OWNER'S REPRESENTATIVE SHALL BE PROMPTLY NOTIFIED SO THAT THE FOUNDATION DESIGN MAY BE REVIEWED.
- NO FOUNDATION CONCRETE SHALL BE INSTALLED UNTIL ALL FOUNDATION WORK HAS BEEN COORDINATED WITH UNDERGROUNDS UTILITIES. FOOTINGS SHALL BE LOWERED WHERE REQUIRED TO AVOID UTILITIES. WHERE FOOTINGS ARE REQUIRED TO BE LOWERED MORE THAN 1' FOOT, NOTIFY THE ENGINEER OF RECORD.
- TO MINIMIZE WEATHERING, THE LAST 4" CHICES OF EXCAVATION FOR ALL FOOTINGS SHALL BE MADE IMMEDIATELY PRIOR TO PLACEMENT OF FOOTINGS.
- WHERE ROCK OUTCROPPINGS ARE ENCOUNTERED IN ANY FOOTING EXCAVATION, UNDERCUT TO A DEPTH OF NOT LESS THAN 6" INCHES BELOW ELEVATION OF BOTTOM OF FOOTING AND BACKFILL WITH THOROUGHLY COMPACTED #10 FINES.
- UNLESS OTHERWISE SHOWN, THE CENTERLINES OF ALL PIERS AND COLUMN FOOTINGS SHALL BE LOCATED ON COLUMN CENTERLINES.

CONCRETE NOTES

- COMPLY WITH THE FOLLOWING CODES AND STANDARDS:
 - ACI 301 "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDINGS".
 - ACI 305, ACI 306, ACI 318, "BUILDING CODE REQUIREMENTS FOR REINFORCED CONCRETE".
 - ACI DETAILING MANUAL (ACI SP-46-04).
 - ACI 347 "RECOMMENDED PRACTICE FOR CONCRETE FORM WORK".
 - CONCRETE REINFORCING STEEL INSTITUTE (CRSI), "MANUAL OF STANDARD PRACTICE".
 - ACI 304 "RECOMMENDED PRACTICE FOR MEASURING, MIXING, TRANSPORTING AND PLACING CONCRETE".
- MATERIALS:
 - REINFORCING BARS - ASTM A615, GRADE 60, DEFORMED
 - WELDED WIRE FABRIC (WWF) - ASTM A185, FLAT SHEETS
 - PORTLAND CEMENT-ASTM C150, TYPE I OR TYPE II
 - AGGREGATES-ASTM C33
 - AIR ENTRAINING ADMIXTURE-ASTM C260, CERTIFIED BY MANUFACTURER TO BE COMPATIBLE WITH OTHER REQUIRED ADMIXTURES.
 - PROHIBIT ADMIXTURES-CALCIUM CHLORIDE HYOCYANATES OR ADMIXTURES CONTAINING MORE THAN 0.1% CHLORIDE IONS ARE NOT PERMITTED.
 - CONTINUOUS REINFORCING IN WALLS AND SLABS MAY BE SPLICED, AS REQUIRED, PROVIDING BARS ARE OF THE LONGEST PRACTICABLE LENGTH AND SPLICES ARE SHOWN ON REINFORCING SHOP DRAWINGS. WHEREVER POSSIBLE, SPLICES SHALL BE STAGGERED. FIELD CUTTING OF REINFORCEMENT WILL NOT BE PERMITTED.
 - UNLESS OTHERWISE SHOWN, BARS AT WALL AND CONTINUOUS FOOTING CORNERS AND INTERSECTIONS SHALL BE DETAILED AS SHOWN ON FIGURE 15 OF ACI SP-46-04. CORNER BARS SHALL BE DETAILED AS SHOWN FOR OUTSIDE LOADED ONLY CORNERS. INTERSECTIONS SHALL BE DETAILED WITHOUT DIAGONAL BARS. ALL END HOOKS SHALL BE STANDARD 90 DEGREE END HOOKS AND CORNER BARS SHALL BE 48 BAR DIAMETERS X 48 BAR DIAMETERS MINIMUM UNLESS NOTED OTHERWISE.
 - PROVIDE DOWELS TO MATCH REINFORCEMENT SIZE AND SPACING INDICATED FOR ALL STRUCTURAL ELEMENTS, UNLESS OTHERWISE INDICATED. DOWELS MUST BE PLACED AND SECURED PRIOR TO CONCRETE PLACEMENT ("WET STICKING" REINFORCING NOT PERMITTED).
 - MAJOR CONSTRUCTION JOINTS ARE SHOWN ON THE DRAWINGS. INTERMEDIATE JOINTS IN WALLS, SLABS, AND FLOOR FRAMING ARE NOT SHOWN. CONSTRUCTION JOINTS MAY BE ADDED, OMITTED OR RELOCATED IF PROPERLY DETAILED ON SHOP DRAWINGS AND APPROVED BY THE OWNER'S REPRESENTATIVE.
 - SEE ARCHITECTURAL AND MECHANICAL DRAWINGS FOR LOCATIONS OF OPENINGS AND SLEEVES IN CONCRETE WALLS AND SUPPORTED FLOORS. SPREAD REINFORCEMENT AT OPENINGS AND SLEEVES UNLESS OTHERWISE SHOWN. DO NOT CUT REINFORCEMENT. SEE TYPICAL REINFORCEMENT DETAILS FOR OPENINGS IN SLABS AND WALLS FOR ADDITIONAL REQUIREMENTS.
 - PLACING OF REINFORCEMENT: PROVIDE CHAIRS, BOLSTERS, ADDITIONAL REINFORCEMENT, AND ACCESSORIES NECESSARY TO SUPPORT REINFORCEMENT AT POSITION SHOWN ON DRAWINGS. SUPPORT OF REINFORCEMENT ON FORM TIES, WOOD, BRICK, BRICKBAT OR OTHER UNACCEPTABLE MATERIAL, WILL NOT BE PERMITTED.
 - THE CONTRACTOR SHALL REVIEW ALL DRAWINGS FOR SIZE AND LOCATION OF ALL EMBEDDED ITEMS, SLEEVES, SLAB DEPRESSIONS, OPENINGS, ETC. REQUIRED BY OTHER TRADES. RECONCILE THEIR EXACT SIZES AND LOCATIONS BEFORE PROCEEDING WITH THE WORK. ALL ITEMS SHALL BE FURNISHED AND INSTALLED PRIOR TO PLACEMENT OF CONCRETE. SECURE THE APPROVED OWNER'S REPRESENTATIVE PRIOR TO PLACING OPENINGS NOT SHOWN ON THE STRUCTURAL DRAWINGS.
 - IN SLAB-ON-GRADE, PROVIDE 2 #4x4 0" DIAGONAL BARS IN THE MIDDLE OF THE SLAB AT EACH CORNER OF OPENINGS OVER 1' 0" SQUARE AND AT RE-ENTRANT CORNERS.
 - PROVIDE CONTROL JOINTS IN CAST-IN-PLACE CONCRETE SLAB-ON-GRADE AT _____ FEET O.C. MAX. LOCATE CONTROL JOINTS TO FORM APPROXIMATE SQUARE PANELS WITH THE LENGTH OF ONE SIDE NOT EXCEEDING THE ADJACENT SIDE BY A FACTOR OF 1.5. CONTROL JOINTS MAY BE CONSTRUCTION JOINTS, CONSTRUCTION JOINTS, OR EXPANSION JOINTS.
 - WHERE CONSTRUCTION JOINTS ARE REQUIRED BUT ARE NOT INDICATED ON THE DRAWINGS, THEY SHALL BE LOCATED AT THE MID-SPAN OF BEAMS, SLABS AND WALLS AND SHALL BE SUBJECT TO REVIEW BY THE OWNER'S REPRESENTATIVE UNLESS NOTED OTHERWISE OR SHOWN ON THE DRAWINGS. AT CONCRETE SLABS ON STEEL DECK, SUPPORTED BY STEEL BEAMS AND GIRDERS, CONSTRUCTION JOINTS SHALL BE PLACED AT MID-SPAN OF DECK AND MID-WAY BETWEEN GIRDERS
 - CHAMFER EDGES OF PERMANENTLY EXPOSED CONCRETE SURFACES 3/4" INCH. UNO.
 - THE CONTRACTOR IS RESPONSIBLE FOR DETERMINING WHEN IT IS SAFE TO REMOVE FORMS AND/OR SHORING. FORMS AND SHORING MUST NOT BE REMOVED UNTIL THE CONCRETE IS STRONG ENOUGH TO CARRY ITS OWN WEIGHT AND ANY ANTICIPATED SUPERIMPOSED LOADS. WHEN FORMS ARE STRIPPED THERE MUST BE NO EXCESSIVE DEFLECTION, DISTORTION, DISCOLORATION, AND NO EVIDENCE OF DAMAGE TO THE CONCRETE.

MASONRY NOTES:

- MASONRY WORK SHALL CONFORM TO THE LATEST EDITIONS OF ACI 530 AND 530.1.
- MATERIAL:
 - CONCRETE MASONRY UNITS: HOLLOW OR SOLID UNITS ASTM C90. ALL UNITS SHALL BE TYPE I, NORMAL WEIGHT AUTOCLAVED CURVED. MOISTURE CONTENT SHALL NOT EXCEED 30% OF MAXIMUM ABSORPTION, AND SHRINKAGE SHALL BE LESS THAN 0.036% PER ASTM C426.
 - MORTAR: ASTM C270, TYPE S. NO MASONRY CEMENT WILL BE ALLOWED.
 - F_m = 2,000 psi
- REINFORCEMENT BARS: ASTM A615 GRADE 60.
- JOINT REINFORCEMENT: TRUSS TYPE WITH 0.148 INCH DIAMETER FINE GROUT: ASTM C476.
- REINFORCING BARS IN MASONRY SHALL BE FULLY GROUTED FOR THEIR ENTIRE LENGTH AND SHALL BE LAP SPLICED 48 BAR DIAMETERS UNO. VERTICAL REINFORCEMENT SHALL CONFORM TO ASTM A615 GRADE 60.
- UNLESS OTHERWISE NOTED OR SHOWN, PROVIDE CMU UNTELS OVER OPENINGS IN CMU WALLS IN ACCORDANCE WITH TYPICAL CMU UNTEL SCHEDULE.
- UNLESS OTHERWISE SHOWN, PROVIDE SOLID MASONRY BLOCK COURSES, CONSISTING OF SOLID BLOCKS OR GROUT FILLED BLOCKS FOR BEARING UNDER STRUCTURAL MEMBERS IN ACCORDANCE WITH THE FOLLOWING SCHEDULE:
 - THREE COURSES UNDER STEEL BEAMS AND COLUMNS (2' 0" EACH SIDE OF MEMBER)
 - ALL EXPOSED MORTAR JOINTS SHALL BE TOOLED.
 - CMU WALLS SHALL RECEIVE TEMPORARY BRACING. TEMPORARY BRACING SHALL NOT BE REMOVED UNTIL WALL IS PERMANENTLY BRACED BY THE ROOF OR FLOOR.
 - PROJECT MASONRY WORK FROM DAMAGE DUE TO OTHER WORK AND THE WEATHER AS RECOMMENDED BY NCMA. ALL UNITS SHALL BE LAID WITH FULL MORTAR COVERAGE ON HORIZONTAL AND VERTICAL FACE SHELLS. SOLID UNITS SHALL BE LAID WITH FULL HEAD AND BED JOINTS. 3/8" THICK LAY IN FULL RUNNING BOND UNLESS INDICATED OTHERWISE.
 - PLACE HORIZONTAL REINFORCING ON FULL MORTAR BED AT 16" OC MIN OR AS INDICATED ON DRAWINGS. VERTICAL REINFORCING IN MASONRY WHERE SHOWN SHALL BE PLACED IN GROUT FILLED REES AND PROPERLY LOCATED AS INDICATED. SPLICES SHALL BE MINIMUM 36 X BAR DIAMETER.
 - USE LOW-LIFT GROUTING TECHNIQUES TO FILL CORES, UNLESS HIGH-LIFT GROUTING (VERTICAL PLACEMENT >40') IS APPROVED BY THE OWNER'S REPRESENTATIVE IN WRITING.
- PROVIDE DOWELS TO MATCH REINFORCEMENT SIZE AND SPACING INDICATED FOR ALL STRUCTURAL ELEMENTS, UNLESS OTHERWISE INDICATED. DOWELS MUST BE PLACED AND SECURED PRIOR TO CONCRETE PLACEMENT ("WET-STICKING" REINFORCING NOT PERMITTED).

POST-INSTALLED ANCHOR NOTES:

- POST INSTALLED ANCHORS HAVE BEEN DESIGNED WITH MULTI ANCHORS (NOTED BELOW) AS THE BASIS OF DESIGN. INSTALL ANCHORS PER THE MANUFACTURER'S PRINTED INSTALLATION INSTRUCTIONS.
 - EXPANSION ANCHORS: KWIK BOLT (3/8 OR 1/2)
 - SLEEVE ANCHORS: HLC SLEEVE ANCHOR
 - ADHESIVE ANCHORS: HIT HY-200
 - SCREEN TUBE ANCHORS: HIT HY-270
- CONTRACTOR MAY PROVIDE EQUIVALENT ANCHORS WITH SIZE AND FINISH AS NOTED AND EQUIVALENT SHEAR AND TENSION CAPACITIES AFTER MODIFICATION DUE TO EMBEDMENT, SPACING AND EDGE DISTANCES AT THE DISCRETION OF THE OWNER'S REPRESENTATIVE
- ALL ADHESIVE ANCHORS FOR REINFORCING SHALL HAVE BEEN TESTED IN ACCORDANCE WITH ACI 308.4 AND ICC-ES AC308 FOR CRACKED CONCRETE AND SEISMIC APPLICATIONS.
- DESIGN ADHESIVE BOND STRENGTH FOR ADHESIVE ANCHORS IN CONCRETE HAS BEEN BASED ON ACI 308.4, TEMPERATURE CATEGORY B WITH INSTALLATIONS INTO DRY HOLES DRILLED USING A CARBIDE DRILL BIT INTO CRACKED CONCRETE THAT HAS CURED FOR AT LEAST 21 DAYS.
- REQUIRE ANCHORS REQUIRING CERTIFIED INSTALLATIONS SHALL BE INSTALLED BY A CERTIFIED ADHESIVE ANCHOR INSTALLER PER ACI 318 D.9.2.2. INSTALLATIONS REQUIRING CERTIFIED INSTALLERS SHALL BE INSPECTED PER ACI 318 D.9.2.4.

METAL BUILDING SYSTEMS NOTES:

- DESIGN, FABRICATION AND ERECTION OF THE PRE-ENGINEERED METAL BUILDING (PEMB) SYSTEM SHALL BE SUFFICIENT TO WITHSTAND LOADS FROM THERMAL, WIND, GRAVITY, STRUCTURAL MOVEMENT AND SEISMIC ACTION WITHOUT EXCEEDING ALLOWABLE STRESSES AND SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE FOLLOWING:
 - METAL BUILDING MANUFACTURERS ASSOCIATION (MBMA) "METAL BUILDING SYSTEM MANUAL" (LATEST EDITION)
 - AMERICAN INSTITUTE OF STEEL CONSTRUCTION (AISC) "SPECIFICATIONS FOR STRUCTURAL STEEL BUILDINGS AND STEEL DESIGN GUIDE SERIES 3: SERVICEABILITY DESIGN CONSIDERATIONS FOR LOW-RISE BUILDINGS" UNO.
 - IRON AND STEEL INSTITUTE (AISI) "SPECIFICATION FOR THE DESIGN OF COLD FORMED STEEL STRUCTURAL MEMBERS" (LATEST EDITION)
 - AMERICAN WELDING SOCIETY (AWS) "STRUCTURAL WELDING CODE STEEL AWS D1.1/D1.1M"
- DEFORMATIONS OF THE PRE-ENGINEERED BUILDING (INCLUDING BUT NOT LIMITED TO LATERAL DRIFT, RACKING OF FRAMES, AND HORIZONTAL AND OR VERTICAL DEFLECTION OF STRUCTURAL ELEMENTS, CLADDING, OR OTHER SUPPORTED ELEMENTS), IS TO BE LIMITED BY THE RECOMMENDATIONS SET FORTH IN AISC'S STEEL DESIGN GUIDE SERIES 3 "SERVICEABILITY DESIGN CONSIDERATIONS FOR LOW-RISE BUILDINGS" AND AS FOLLOWS:
 - DRIFT OF MAIN FRAMES AT EAVE HEIGHT, UNO: H/100
 - DRIFT OF MAIN FRAMES WITH MASONRY/CONCRETE EXTERIOR WALLS: H/240
 - HORIZONTAL DEFLECTION OF GIRTS SUPPORTING METAL SIDING: L/120
 - VERTICAL DEFLECTION OF MAIN FRAME: L/240 (LIVE) & L/180 (TOTAL)
 - VERTICAL DEFLECTION OF FURLINS: L/240 (LIVE) & L/180 (TOTAL)
 - LATERAL MOVEMENT OF ELEMENTS SUPPORTING DRYWALL PARTITIONS (H=PARTITION HT) H/500
 - HORIZONTAL DEFLECTION OF GIRTS SUPPORTING MASONRY WALLS: L/600
- WIND AND SEISMIC FORCES USED FOR THE COMPUTATION OF MEMBER STRESSES ARE TO BE BASED ON THE LATERAL LOAD DESIGN CRITERIA LISTED IN THE DESIGN CRITERIA ON SHEET S-002.
- CONTRACTOR IS TO ENGAGE AN EXPERIENCED INSTALLER TO ERECT THE PRE-ENGINEERED METAL BUILDING WHO IS EXPERIENCED IN THE ERECTION OF METAL BUILDINGS SIMILAR TO THAT REQUIRED FOR THIS PROJECT AND WHO IS CERTIFIED IN WRITINGS BY THE METAL BUILDING SYSTEM MANUFACTURER AS QUALIFIED FOR THE ERECTION OF THE MANUFACTURER'S PRODUCTS.
- FABRICATE FRAMING COMPONENTS IN THE SHOP TO THE GREATEST EXTENT POSSIBLE. IN GENERAL, SHOP WELD AND FIELD BOLT CONNECTIONS.
- EXERCISE CARE IN DELIVERING, UNLOADING, STORING AND ERECTING BUILDING MEMBERS, WALL AND ROOF COVERING PANELS AND OTHER BUILDING COMPONENTS TO PREVENT BENDING, WARPING, TWISTING AND SURFACE DAMAGE.
- EXERCISE CARE IN DELIVERING, UNLOADING, STORING AND ERECTING BUILDING MEMBERS, WALL AND ROOF COVERING PANELS AND OTHER BUILDING COMPONENTS TO PREVENT BENDING, WARPING, TWISTING AND SURFACE DAMAGE.
- PROVIDE LATERAL LOAD RESISTING SYSTEMS AS REQUIRED TO RESIST THE INDICATED WIND AND SEISMIC LOADS IN ROOF AND SIDE WALLS, WHERE OVERHEAD DOORS INTERFERE WITH DIAGONAL BRACING, PROVIDE STRUCTURAL WIND FRAMES. PROVIDE SAG RODS AS REQUIRED TO MAINTAIN VERTICAL ALIGNMENT OF WALL GIRTS. REFERENCE THE ARCHITECTURAL AND STRUCTURAL PLAN DRAWINGS FOR PERIMETER BRACING AND FRAME LOCATIONS.
- PROVIDE FRAMED DOOR AND WINDOW OPENINGS OF PROPER DESIGN AND SIZE TO ACCOMMODATE FINISHED UNITS AND TO TRANSMIT ALL LOADS TO THE BUILDING STRUCTURE.
- THE FOUNDATION AND ANCHOR ROD DESIGN ON THESE CONTRACT DRAWINGS IS PRELIMINARY AND BASED UPON ASSUMED COLUMN BASE REACTIONS CALCULATED BY A STRUCTURAL ENGINEER. THESE REACTIONS ARE INDICATED IN 'PEMB COLUMN BASE REACTIONS' SCHEDULE ON SHEET S-604. UPON FINAL BUILDING DESIGN, THE ACTUAL COLUMN BASE REACTIONS ARE TO BE COMPARED TO THE PRELIMINARY FOUNDATION AND ANCHOR ROD DESIGN PROVIDED IS VOID AND A REGISTERED PROFESSIONAL ENGINEER MUST BE EMPLOYED BY THE GENERAL CONTRACTOR TO COMPLETE A FOUNDATION DESIGN BASED UPON THE ACTUAL REACTIONS.
- DESIGN THE PRE-ENGINEERED METAL BUILDING TO PROVIDE LATERAL SUPPORT FOR THE TOP OF ALL MASONRY WALLS. LATERAL SUPPORT SHALL BE IN THE FORM OF A GIRT, SPANDREL BEAM OR OTHER APPROVED MEANS. THE TOP OF THE MASONRY WALLS SHALL BE BOLTED TO THE LATERAL SUPPORT. THE LATERAL SUPPORT SHALL BE CLIPPED TO THE MAIN FRAME COLUMNS WITH VERTICALLY SLOTTED CONNECTIONS.
- CONTRACTORS TO COORDINATE WITH THE PEMB MANUFACTURER AND SUBCONTRACTORS TO PROVIDE SUPPORT FOR ALL SUSPENDED EQUIPMENT, PIPING, DUCTWORK AND UTILITIES IDENTIFIED ON THE DRAWINGS OR OTHERWISE NOTED OR REQUIRED.

SPECIAL INSPECTION NOTES:

- SPECIAL INSPECTIONS WILL BE PERFORMED IN ACCORDANCE WITH THE STATEMENT OF SPECIAL INSPECTIONS.
- OWNER, OR ARCHITECT/STRUCTURAL ENGINEER OF RECORD ACTING AS THE OWNER'S AGENT, SHALL DIRECTLY EMPLOY AND PAY FOR SERVICES OF THE SPECIAL INSPECTORS TO PERFORM REQUIRED SPECIAL INSPECTIONS.

STRUCTURAL DESIGN CRITERIA

BUILDING DATA:		DESIGN CRITERIA	
LOCATION	LIBERTY, NY		
BUILDING OCCUPANCY RISK CATEGORY	II		
APPLICABLE BUILDING CODE	2020 BUILDING CODE OF NEW YORK STATE (IBC 2018)		
GEOTECHNICAL INFORMATION:			
ALLOWABLE BEARING PRESSURE	1500 PSF (ASSUMED)		
ROOF DEAD LOADING:			
ROOF	Dlr	BY PEMB	
COLLATERAL	CL	10 PSF	
ROOF LIVE LOADING:			
ROOF	Llr	20 PSF	
SNOW LOADING:			
SNOW IMPORTANCE FACTOR	Is	1.0	
GROUND SNOW LOAD	Pg	63 PSF	
SNOW EXPOSURE FACTOR	Ce	1.0	
ROOF THERMAL FACTOR	Ct	1.2	
FLAT ROOF SNOW LOAD	Pf	49 PSF	
DRIFTING SNOW	BY PEMB MANUF		
WIND LOADING (MAIN WIND FORCE RESISTING SYSTEM):			
ANALYSIS PROCEDURE	DIRECTIONAL PROCEDURE		
ULTIMATE DESIGN WIND SPEED (3-SECOND GUST)	Vult	110 mph	
NOMINAL DESIGN WIND SPEED (3-SECOND GUST)	Vsld	85 mph	
EXPOSURE CATEGORY	B		
ENCLOSURE CLASSIFICATION	ENCLOS2		
INTERNAL PRESSURE COEFFICIENT	GCpi	+0.18/-0.18	
WIND LOADING (COMPONENTS AND CLADDING):			
COMPONENTS AND CLADDING WIND PRESSURE:	BY PEMB MANUF		
SEISMIC LOADING:			
MAPPED SHORT PERIOD SPECTRAL RESPONSE ACCELERATION	Ss	0.148g	
MAPPED 1-SEC PERIOD SPECTRAL RESPONSE ACCELERATION	S1	0.049g	
SHORT PERIOD DESIGN SPECTRAL RESPONSE ACCELERATION	Sds	0.158g	
1-SEC PERIOD DESIGN SPECTRAL RESPONSE ACCELERATION	Sd1	0.078g	
SOIL SITE CLASS	D (DEFAULT)		
SEISMIC DESIGN CATEGORY	B		
SEISMIC FORCE RESISTING SYSTEM	BY PEMB MANUF		
RESPONSE MODIFICATION FACTOR	R	BY PEMB MANUF	
DEFLECTION AMPLIFICATION FACTOR	Cd	BY PEMB MANUF	
SEISMIC RESPONSE COEFFICIENT	Cs	BY PEMB MANUF	
ANALYSIS PROCEDURE	EQUIVALENT LATERAL FORCE		
DESIGN BASE SHEAR	V	BY PEMB MANUF	

FOOTING SCHEDULE

MARK	FOOTING DIMENSIONS			BOTTOM REINFORCING		TOP REINFORCING	REMARKS
	LENGTH	WIDTH	DEPTH	LONGITUDINAL	TRANSVERSE		
F5.0	5'-0"	5'-0"	1'-0"	(6) #5 BARS	(6) #5 BARS	-	-
F6.0	6'-0"	6'-0"	1'-0"	(7) #5 BARS	(7) #5 BARS	-	-
F8.0	8'-0"	8'-0"	1'-0"	(9) #5 BARS	(9) #5 BARS	-	-

WALL FOOTING SCHEDULE

MARK	FOOTING DIMENSIONS		FOOTING REINFORCING		REMARKS
	WIDTH	DEPTH	LONGITUDINAL	TRANSVERSE	
WF2.5	2'-6"	1'-0"	(3) #5 BARS	#5 BARS @ 12" OC	-

PIER SCHEDULE


PIER DIMENSIONS			PIER REINFORCING		REMARKS
TYPE	DEPTH	WIDTH	TIES		
P2.0	2'-0"	2'-0"	(16) #6 BARS	#4 TIES (TOP 2 @ 3' OC, REMIANER @ 12" OC)	SEE PIER DETAIL
P3.1	3'-6"	2'-6"	(16) #8 BARS	#4 TIES (TOP 2 @ 3' OC, REMIANER @ 12" OC)	SEE PIER DETAIL
P3.2	3'-0"	2'-6"	(16) #8 BARS	#4 TIES (TOP 2 @ 3' OC, REMIANER @ 12" OC)	SEE PIER DETAIL

FOUNDATION WALL SCHEDULE

MARK	TYPE	THICKNESS	WALL REINFORCING		REMARKS
			HORIZONTAL	VERTICAL	
CW18	CONC FOUNDATION WALL	1'-6"	#5 BARS @ 12" OC, EF	#5 BARS @ 12" OC, EF	SEE SECTION
CW19.5	CONC FOUNDATION WALL	1'-7 1/2"	#5 BARS @ 12" OC, EF	#5 BARS @ 12" OC, EF	SEE SECTION

SLAB-ON-GRADE SCHEDULE

MARK	TYPE	THICKNESS	SLAB REINFORCING	REMARKS
SOG1	INTERIOR SOG	6"	6X6 - W2.9XW2.9 WWF	-
SOG2	EXTERIOR SOG	8"	#4 BARS @ 12" OC, EW	-



3 TYPICAL ANCHOR ROD DETAIL
N.T.S.

CONCRETE REIN SPICE & DEVELOPMENT LENGTHS SCHEDULE

LAP SPICE LENGTHS (IN.)				DEVELOPMENT LENGTHS (IN.)	
BAR SIZE	TENSION LAP LENGTH		COMP.	TENSION	COMP.
CLASS	A	B	A	B	
#3	19	24	15	19	12
#4	25	33	19	25	15
#5	31	41	24	31	19
#6	37	49	29	37	23
#7	54	71	42	54	27
#8	62	81	48	62	30
#9	70	91	54	70	34
#10	79	102	61	79	39
#11	87	113	67	87	43
LAP SPICE LENGTHS (IN.)				DEVELOPMENT LENGTHS (IN.)	
BAR SIZE	TENSION LAP LENGTH		COMP.	TENSION	COMP.
CLASS	A	B	A	B	
#3	18	23	14	18	12
#4	24	31	18	24	15
#5	30	38	23	30	19
#6	35	46	27	35	23
#7	51	67	40	51	27
#8	59	76	45	59	30
#9	66	86	51	66	34
#10	74	94	57	74	39
#11	82	107	64	82	43
LAP SPICE LENGTHS (IN.)				DEVELOPMENT LENGTHS (IN.)	
BAR SIZE	TENSION LAP LENGTH		COMP.	TENSION	COMP.
CLASS	A	B	A	B	
#3	17	22	13	17	12
#4	23	29	17	23	15
#5	28	36	22	28	19
#6	34	43	26	34	23
#7	49	63	38	49	27
#8	56	72	43	56	30
#9	63	81	48	63	34
#10	70	92	54	70	39
#11	78	102	60	78	43

- NOTES:
- TOP BARS ARE HORIZONTAL BARS, PLACED SO THAT MORE THAN 12 INCHES OF FRESH CONCRETE IS PLACED BELOW THE BAR.
 - ALL LAP SPLICES SHALL BE CLASS "B" UNLESS OTHERWISE NOTED.
 - LENGTHS IN THE TABLE ARE FOR UNCOATED OR ZINC-COATED (GALVANIZED) BARS.
 - CLEAR SPACING OF BARS BEING DEVELOPED OR SPLICED NOT LESS THAN 2DB AND CLEAR COVER NOT LESS THAN DB.
 - VALUES IN TABLE ARE FOR NORMAL WEIGHT CONCRETE.
 - SPACING REQUIREMENTS AND END ANCHORAGE SHALL BE SPACED PER THE REQUIREMENTS OF ACI 318.

REINFORCED CONCRETE COVER SCHEDULE

STRUCTURAL ELEMENT	MIN COVER (IN)
CAST AGAINST EARTH	3"
EXPOSED TO EARTH OR WEATHER	#5 BARS AND SMALLER, WWF 1-1/2"
	#6 BARS AND LARGER 2"
NOT EXPOSED TO EARTH OR WEATHER	#11 BARS AND SMALLER, WWF 3/4"
	#14 BARS AND LARGER 1-1/2"
BEAMS AND COLUMNS	1-1/2"

CONCRETE STRENGTH AND MATERIAL SCHEDULE

STRUCTURAL ELEMENT	MIN COMPRESSIVE STRENGTH AT 28 DAYS (PSI)	MAX WATER/CEMENT RATIO	AIR CONTENT (%)
FOOTINGS, SOG	4,000	0.50	N/A
PIERS, FDN WALLS	4,500	0.45	6 +/- 1.5%
EXT CONC APRON	5,000	0.40	6 +/- 1.5%

- NOTES:
- PREPARE DESIGN MIXES FOR EACH TYPE, AND STRENGTH OF CONCRETE BY EITHER LABORATORY TRIAL BATCH OR FIELD EXPERIENCE METHODS AS SPECIFIED IN ACI 318.
 - CONCRETE SHALL BE READY MIXED PER ASTM C94. JOBSITE MIXING SHALL NOT BE PERMITTED.
 - MAXIMUM NOMINAL AGGREGATE SIZE IS 3/4".

SCHEDULE OF STRUCTURAL SPECIAL INSPECTION & TESTING														
THE FOLLOWING TABLES COMPRISES THE STRUCTURAL SPECIAL INSPECTION REQUIREMENTS FOR THIS PROJECT IN ACCORDANCE WITH CHAPTER 17 OF THE 2018 INTERNATIONAL BUILDING CODE. REFER TO THE PROJECT SPECIFICATIONS FOR REQUIRED QUALIFICATIONS OF ALL PERSONNEL PERFORMING SPECIAL INSPECTION ACTIVITIES AND ADDITIONAL TESTING INFORMATION.														
EARTHWORK - REQUIREMENTS FOR SPECIAL INSPECTION & TESTING				COLD-FORMED STEEL LIGHT-FRAME CONSTRUCTION - REQUIREMENTS FOR SPECIAL INSPECTION & TESTING				STEEL CONSTRUCTION - REQUIREMENTS FOR SPECIAL INSPECTION & TESTING						
AREAS OF INSPECTION & TESTING		FREQUENCY OF INSPECTION OR TESTING	REFERENCE STANDARD	IBC REFERENCE	AREAS OF INSPECTION & TESTING		FREQUENCY OF INSPECTION OR TESTING	REFERENCE STANDARD	IBC REFERENCE	AREAS OF INSPECTION & TESTING		FREQUENCY OF INSPECTION OR TESTING	REFERENCE STANDARD	IBC REFERENCE
1. VERIFY MATERIALS BELOW SHALLOW FOUNDATIONS ARE ADEQUATE TO ACHIEVE DESIGN BEARING CAPACITY.		PERIODIC	-	1705.6	1. FOR WELDING OPERATIONS OF ELEMENTS OF THE SEISMIC FORCE-RESISTING SYSTEM AND FOR SCREW ATTACHMENT, BOLTING, ANCHORINGS AND OTHER FASTENING OF ELEMENTS OF THE SEISMIC FORCE-RESISTING SYSTEM, INCLUDING SHEAR WALLS, BRACES, DIAPHRAGMS, COLLECTORS AND HOLD-DOWNS.		REQUIRED FOR SEISMIC CATEGORY C, D, E OR F.	1705.12.3	-	1. FABRICATOR'S SHOP TESTING AND QUALITY CONTROL PROGRAMS: A. VERIFY FABRICATOR'S CERTIFICATION AND QUALITY CONTROL PROGRAM. B. SPECIAL INSPECTIONS REQUIRED IN FABRICATOR'S SHOP FOR ELEMENTS IDENTIFIED BELOW.		PERIODIC	AISC PLANT CERTIFICATION PROGRAM	1705.2
2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL.		PERIODIC	-	-	2. MATERIAL VERIFICATION OF COLD-FORMED STEEL STRUCTURAL MEMBERS AND CONNECTORS a. PRODUCT IDENTIFICATION TO CONFORM TO AISI STANDARDS AND AS SPECIFIED IN THE CONSTRUCTION DOCUMENTS OR APPROVED SHOP DRAWINGS.		PERIODIC	AISI TABLE DA.5	-	2. INSPECTION TASKS FOR HIGH-STRENGTH BOLTS, NUTS AND WASHERS PRIOR TO BOLTING: A. VERIFY MANUFACTURER'S CERTIFICATIONS AVAILABLE FOR FASTENER MATERIALS. B. FASTENERS MARKED IN ACCORDANCE WITH ASTM REQUIREMENTS. C. PROPER FASTENERS SELECTED FOR JOINT DETAIL (GRADE, TYPE, BOLT LENGTH IF THREADS ARE TO BE EXCLUDED FROM SHEAR PLANE) D. PROPER BOLTING PROCEDURE SELECTED FOR JOINT DETAIL. E. CONNECTING ELEMENTS, INCLUDING THE APPROPRIATE FAYING SURFACE CONDITION AND HOLE PREPARATION, IF SPECIFIED, MEET APPLICABLE REQUIREMENTS. F. PRE-INSTALLATION VERIFICATION AND TESTING BY INSTALLATION PERSONNEL OBSERVED AND DOCUMENTED FOR FASTENER ASSEMBLIES AND METHODS USED. G. PROPER STORAGE PROVIDED FOR BOLTS, NUTS, WASHERS, AND OTHER FASTENERS.		NOT REQUIRED IF FABRICATOR IS AISC CERTIFIED	-	-
3. PERFORM CLASSIFICATION AND TESTING OF COMPACTED FILL MATERIALS		PERIODIC	-	-	3. INSPECTION OF WELDING a. VERIFICATION OF WELDS MEET THE MATERIALS, PROCEDURES, AND WORKMANSHIP ARE IN CONFORMANCE WITH AWS D1.3 AND THE CONSTRUCTION DOCUMENTS OR APPROVED SHOP DRAWINGS.		PERIODIC	AISI TABLE DA.6	-	B. FASTENERS MARKED IN ACCORDANCE WITH ASTM REQUIREMENTS. C. PROPER FASTENERS SELECTED FOR JOINT DETAIL (GRADE, TYPE, BOLT LENGTH IF THREADS ARE TO BE EXCLUDED FROM SHEAR PLANE) D. PROPER BOLTING PROCEDURE SELECTED FOR JOINT DETAIL. E. CONNECTING ELEMENTS, INCLUDING THE APPROPRIATE FAYING SURFACE CONDITION AND HOLE PREPARATION, IF SPECIFIED, MEET APPLICABLE REQUIREMENTS. F. PRE-INSTALLATION VERIFICATION AND TESTING BY INSTALLATION PERSONNEL OBSERVED AND DOCUMENTED FOR FASTENER ASSEMBLIES AND METHODS USED. G. PROPER STORAGE PROVIDED FOR BOLTS, NUTS, WASHERS, AND OTHER FASTENERS.		PERIODIC	-	-
4. VERIFY USE OF PROPER MATERIALS, DENSITIES, AND LIFT THICKNESS DURING PLACEMENT AND COMPACTION OF COMPACTED FILL.		CONTINUOUS	-	-	4. INSPECTION OF MECHANICAL FASTENING a. VERIFICATION OF MECHANICAL FASTENERS MEET THE MATERIALS, PROCEDURES, AND WORKMANSHIP ARE IN CONFORMANCE WITH MANUFACTURERS INSTALLATION INSTRUCTIONS AND THE CONSTRUCTION DOCUMENTS OR APPROVED SHOP DRAWINGS.		PERIODIC	AISI TABLE DA.7	-	D. FASTENERS ARE PRETENSIONED IN ACCORDANCE WITH THE RCSC SPECIFICATION, PROGRESSING SYSTEMATICALLY FROM THE POST RIGID POINT TOWARD THE FREE EDGES.		PERIODIC	-	-
5. PRIOR TO PLACEMENT OF COMPACTED FILL, INSPECT SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY.		PERIODIC	-	-	5. INSPECTION OF COLD-FORMED STEEL LIGHT-FRAME CONSTRUCTION VERIFICATION OF FIELD INSTALLED MEMBERS, COMPONENT ASSEMBLIES AND CONNECTORS ARE IN CONFORMANCE WITH THE CONSTRUCTION DOCUMENTS OR APPROVED SHOP DRAWINGS.		PERIODIC	AISI TABLE DA.8	-	3. INSPECTION TASKS FOR HIGH-STRENGTH BOLTS, NUTS AND WASHERS DURING BOLTING: A. FASTENER ASSEMBLIES, OF SUITABLE CONDITION, PLACED IN ALL HOLES AND WASHERS (IF REQUIRED) ARE POSITIONED AS REQUIRED. B. JOINT BROUGHT TO THE SNUG-TIGHT CONDITION PRIOR TO THE PRETENSIONING OPERATION. C. FASTENER COMPONENT NOT TURNED BY THE WRENCH PREVENTED FROM ROTATING. D. FASTENERS ARE PRETENSIONED IN ACCORDANCE WITH THE RCSC SPECIFICATION, PROGRESSING SYSTEMATICALLY FROM THE POST RIGID POINT TOWARD THE FREE EDGES.		PERIODIC	-	-
CAST-IN-PLACE CONCRETE - REQUIREMENTS FOR SPECIAL INSPECTION & TESTING		FREQUENCY OF INSPECTION OR TESTING	REFERENCE STANDARD	IBC REFERENCE										
1. INSPECT REINFORCEMENT, INCLUDING PRESTRESSING TENDONS, AND VERIFY PLACEMENT.		PERIODIC	ACI 318 CH. 20, 25.2, 25.3, 26.6.1 - 26.6.3	1908.4										
2. REINFORCING BAR WELDING: A. VERIFY WEARABILITY OF REINFORCING BARS OTHER THAN ASTM A706. B. INSPECT SINGLE PASS FILLET WELDS, MAXIMUM 5/16" AND C. INSPECT ALL OTHER WELDS.		PERIODIC	AWS D1.4 ACI 318: 26.6.4	-										
3. INSPECT ANCHORS CAST IN CONCRETE		PERIODIC	ACI 318:17.8.2	-										
4. INSPECT ANCHORS POST-INSTALLED IN HARDENED CONCRETE MEMBERS. A. ADHESIVE ANCHORS INSTALLED IN HORIZONTALLY OR UPWARDLY INCLINED ORIENTATIONS TO RESIST SUSTAINED TENSION LOADS. B. MECHANICAL ANCHORS AND ADHESIVE ANCHORS.		CONTINUOUS	ACI 318: 17.8.2.4	-										
5. VERIFY USE OF REQUIRED DESIGN MIX.		PERIODIC	ACI 318: CH. 19, 26.4.3, 26.4.4	1904.1, 1904.2, 1908.2, 1908.3										
6. PRIOR TO CONCRETE PLACEMENT, FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE.		CONTINUOUS	ASTM C172 ASTM C31 ACI 318: 26.4, 26.12	1908.10										
7. INSPECT CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES.		CONTINUOUS	ACI 318: 26.5	1908.6, 1908.7, 1908.8										
8. VERIFY MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES.		PERIODIC	ACI 318: 26.5.3 - 26.5.5	1908.9										
9. INSPECT PRESTRESSED CONCRETE FOR: A. APPLICATION OF PRESTRESSING FORCES; AND B. GROUTING OF BONDED PRESTRESSING TENDONS.		CONTINUOUS	ACI 318: 26.10	-										
10. INSPECT ERECTION OF PRECAST CONCRETE MEMBERS.		PERIODIC	ACI 318: CH. 26.8	-										
11. VERIFY IN-SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN POST-TENSIONED CONCRETE AND PRIOR TO REMOVAL OF SHORNS AND FORMS FROM BEAMS AND STRUCTURAL SLABS.		PERIODIC	ACI 318: 26.11.2	-										
12. INSPECT FORMWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED.		PERIODIC	ACI 318: 26.11.2 (b)	-										
MASONEY CONSTRUCTION - REQUIREMENTS FOR LEVEL 8 SPECIAL INSPECTION & TESTING		FREQUENCY OF INSPECTION OR TESTING	REFERENCE STANDARD	IBC REFERENCE										
1. VERIFY COMPLIANCE WITH THE APPROVED SUBMITTALS		PERIODIC	-	1705.4										
2. AS MASONEY CONSTRUCTION BEGINS, VERIFY THAT THE FOLLOWING ITEMS ARE IN COMPLIANCE: A. PROPORTIONS OF SITE-PREPARED MORTAR. B. CONSTRUCTION OF MORTAR JOINTS. C. GRADE AND SIZE OF PRESTRESSING TENDONS AND ANCHORAGES. D. LOCATION OF REINFORCEMENT, CONNECTORS, AND PRESTRESSING TENDONS, AND ANCHORAGES. E. PRESTRESSING TECHNIQUE. F. PROPERTIES OF THIN-BED MORTAR FOR AAC MASONRY.		PERIODIC	-	-										
3. PRIOR TO GROUTING, VERIFY THAT THE FOLLOWING ARE IN COMPLIANCE: A. GROUT SPACE B. GRADE, TYPE AND SIZE OF REINFORCEMENT AND ANCHOR BOLTS, AND PRESTRESSING TENDONS AND ANCHORAGES. C. PLACEMENT OF REINFORCEMENT, CONNECTORS, AND PRESTRESSING TENDONS AND ANCHORAGES. D. PROPORTIONS OF SITE-PREPARED GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS. E. CONSTRUCTION OF MORTAR JOINTS.		PERIODIC	TMS 402 SEC. 6.1	-										
4. VERIFY DURING CONSTRUCTION: A. SIZE AND LOCATION OF STRUCTURAL ELEMENTS. B. TYPE, SIZE, AND LOCATION OF ANCHORS, INCLUDING OTHER DETAILS OF ANCHORAGES OF MASONRY TO STRUCTURAL MEMBERS, FRAMES, OR OTHER CONSTRUCTION. C. WELDING OF REINFORCEMENT. D. PREPARATION, CONSTRUCTION, AND PROTECTION OF MASONRY DURING COLE WEATHER (TEMPERATURES BELOW 40) OR HOT WEATHER (TEMPERATURES ABOVE 90). E. APPLICATION AND MEASUREMENT OF PRESTRESSING FORCE. F. PLACEMENT OF GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS IS IN COMPLIANCE G. PLACEMENT OF AAC MASONRY UNITS AND CONSTRUCTION OF THIN-BED MORTAR JOINTS.		PERIODIC	TMS 402 SEC. 6.1, 6.2.2, 6.2.7	-										
5. OBSERVE PREPARATION OF GROUT SPECIMENS, MORTAR SPECIMENS, AND/OR PRESS.		PERIODIC	TMS 402 SEC. 1.2 (E), 6.1.4.3, 6.2.1	-										
		PERIODIC	TMS 402 SEC. 8.1.6.7, 2.3.3.4(C), 11.3.3.4(B)	-										
		CONTINUOUS	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										
		PERIODIC	-	-										

STATEMENT OF SPECIAL INSPECTIONS

LOCATION	Liberty, NY
OWNER	Liberty Central School District
DESIGN PROFESSIONAL IN CHARGE	Patrick J. Williams, PE, SE
The statement of Special Inspections is submitted as a condition for permit issuance in accordance with the Special Inspection and Structural Testing requirements of the applicable building code. It includes a schedule of Special Inspection services applicable to this project as well as the name of the Special Inspection contractor and the identity of other approved agencies to be retained for conducting these inspections and tests. This Statement of Special Inspections encompasses the following disciplines: STRUCTURAL. The Special Inspection Coordinator shall keep records of all inspections and shall furnish inspection reports to the Building Official and the Registered Design Professional in Responsible Charge (RDP). Discovered discrepancies shall be brought to the immediate attention of the contractor for correction. If such discrepancies are not retained, the discrepancies shall be brought to the attention of the Building Official and the RDP. The Special Inspection program does not relieve the contractor of his or her responsibility for quality assurance. Inspection reports shall be submitted to the Building Official and the RDP, monthly. A Final Report of Special Inspections documenting completion of all required Special Inspections, testing, and correction of any discrepancies noted in the inspections shall be submitted by the special inspection Coordinator prior to issuance of a Certificate of Use and Occupancy. Job site safety and means and methods of construction are solely the responsibility of the contractor. In accordance with the applicable building code, the Observations and Inspections listed in the Schedule of Special Inspections are required.	

SCHEDULE OF INSPECTION AND TESTING AGENCIES

SPECIAL INSPECTION AGENCIES	FIRM	ADDRESS	TELEPHONE No.
Special Inspection Coordinator	TBD	TBD	(###) ###-####
Inspector	TBD	TBD	(###) ###-####

Note: The inspectors and testing agencies shall be engaged by the Owner or the Owner's Agent in accordance with the applicable building code, and not by the Contractor or Subcontractor whose work is to be inspected or tested. An approved agency shall be objective, competent and independent from the contractor responsible for the work being inspected. The agency shall also disclose to the building official and the registered design professional in responsible charge possible conflicts of interest so that objectivity can be confirmed.

STATEMENT OF CONTRACTORS RESPONSIBILITY

In accordance with the applicable building code, each contractor responsible for the construction of a main wind or seismic force-resisting system, designated seismic system or a wind or seismic force-resisting component listed in the statement of special inspections above shall submit a written statement of responsibility to the building official and the owner or the owner's authorized agent prior to the commencement of work on the system or component. The contractor's statement of responsibility shall contain acknowledgement of awareness of the special requirements contained in the statement of special inspections.

QUALIFICATIONS OF INSPECTORS AND TESTING TECHNICIANS

The qualifications of all personnel performing Special Inspection and testing activities are subject to the approval of the Building Official. The credentials of all Inspectors and testing technicians shall be provided.

Key for Minimum Qualifications of Inspection Agents

When the Registered Design Professional in Responsible Charge deems it appropriate that the individual performing a stipulated test or inspection have a specific certification or license as indicated below, such designation shall appear below the Agency Number on the Schedule.

PE/SE	Structural Engineer - a licensed PE specializing in the design of building structures
PE/GE	Geotechnical Engineer - a licensed PE specializing in soil mechanics and foundations
ET	Engineer - in - training - a graduate engineer who has passed the Fundamentals of Engineering examination
AMERICAN CONCRETE INSTITUTE (ACI) CERTIFICATION	
ACI-CFTT	Concrete Field Testing Technician - Grade 1
ACI-CCS	Concrete Construction Special Inspector
ACI-LIT	Laboratory Testing Technician - Grade 1 & 2
ACI-STT	Strength Testing Technician
AMERICAN WELDING SOCIETY (AWS) CERTIFICATION	
AWS-CWI	Certified Welding Inspector
AWS/AISC-SSI	Certified Structural Steel Inspector
INTERNATIONAL CODE COUNCIL (ICC) CERTIFICATION	
ICC-SM3I	Structural Masonry Special Inspector
ICC-SWSI	Structural Steel and Welding Special Inspector
ICC-SFSI	Spray-Applied Fireproofing Special Inspector
ICC-PCSI	Prestressed Concrete Special Inspector
ICC-RCSI	Reinforced Concrete Special Inspector
NATIONAL INSTITUTE FOR CERTIFICATION IN ENGINEERING TECHNOLOGIES (NICET)	
NICET-C1	Concrete Technician - Levels I, II, III, & IV
NICET-ST	Soil Technicians - Levels I, II, III & IV
NICET-GET	Geotechnical Engineering Technician - Levels I, II, III, & IV

CS ARCH
19 Front St. - Newburgh - New York 12550-7601
845- 561- 3179 www.csarchpc.com

PA
PASSERO ASSOCIATES
engineering architecture
STRUCTURAL

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING



DATE	DESCRIPTION
Drawn By:	JAMIE WOLMERING, EIT
Checked By:	PATRICK J. WILLIAMS, PE SE
Proj. #:	59-09-01-06-3-016-001
CSArch Proj. #:	203-2201
Construction Documents:	12/13/22


Sheet Title

SPECIAL INSPECTIONS

Sheet No.




S-002

CONSTRUCTION DOCUMENTS



- FOUNDATION PLAN NOTES:**
- SEE SHEET S-001 THROUGH S-002 FOR GENERAL NOTES, DESIGN CRITERIA, SCHEDULES, AND LEGENDS.
 - SEE SHEET S-500 SERIES FOR TYPICAL DETAILS.
 - FINISH FLOOR REFERENCE ELEVATION = 0' - 0".
 - TOP OF FOOTING IS (4' - 0") BELOW FINISH FLOOR REFERENCE ELEVATION, UNLESS OTHERWISE NOTED ON PLAN AS (X' - X") RELATIVE TO TOP OF FINISHED FLOOR REFERENCE ELEVATION.
 - COORDINATE DOOR WIDTHS AND LOCATING DIMENSIONS WITH ARCH.
 - COORDINATE WITH CIVIL, ARCH AND MEP DRAWINGS ON ANY REQUIRED PENETRATIONS THROUGH FOUNDATION WALLS AND FOOTINGS.

FOUNDATION LEGEND	
F# (#' - #'")	F# - DENOTES FOOTING MARK (SEE FOOTING SCHEDULE) (#' - #'") - DENOTES TOP OF FOOTING ELEVATION WITH RESPECT TO DATUM ELEVATION = 0' - 0"
P# (#' - #'")	P# - DENOTES PIER MARK (SEE PIER SCHEDULE) (#' - #'") - DENOTES TOP OF PIER ELEVATION WITH RESPECT TO DATUM ELEVATION = 0' - 0"
CW# (MW#)	CW# - DENOTES CONCRETE WALL MARK (SEE FOUNDATION WALL AND/OR WALL SCHEDULE) MW# - DENOTES MASONRY WALL MARK (SEE MASONRY WALL SCHEDULE)
WF#	WF# - DENOTES WALL FOOTING MARK (SEE WALL FOOTING SCHEDULE)
#' - #'"	#' - #'" - DENOTES TOP OF WALL FOOTING ELEVATION WITH RESPECT TO DATUM ELEVATION = 0' - 0"






1 FOUNDATION PLAN
0' 2' 4' 8' 16'
1/8" = 1'-0"

2 FOUNDATION SECTION
0' 6' 1' 2' 4'
3/4" = 1'-0"

3 FOUNDATION SECTION
0' 6' 1' 2' 4'
3/4" = 1'-0"


4 FOUNDATION SECTION
0' 6' 1' 2' 4'
3/4" = 1'-0"



5 P3.1
0' 6' 1' 2' 4'
3/4" = 1'-0"

6 P3.2
0' 6' 1' 2' 4'
3/4" = 1'-0"


7 P2.0
0' 6' 1' 2' 4'
3/4" = 1'-0"



- NOTES:
- SEE SLAB-ON-GRADE SCHEDULE FOR SLAB THICKNESS.
 - PROVIDE CHAIRS TO SUPPORT SLAB REINFORCING AT SPECIFIED ELEVATION.

1 TYPICAL SLAB-ON-GRADE


N.T.S.



- NOTES:
- SEE ARCH DRAWINGS FOR LOCATION AND DEPTH OF SLAB DEPRESSION.
 - SEE TYPICAL SLAB-ON-GRADE DETAIL THIS SHEET, FOR SLAB DETAILS NOT SHOWN.
 - SEE SLAB-ON-GRADE SCHEDULE FOR SLAB THICKNESS.

2 TYPICAL SLAB-ON-GRADE DEPRESSION

N.T.S.



CONTINUOUS PIPE, TYP.

PROVIDE PIPE SLEEVE THRU FOUNDATION WALL AND WRAP THE CONTINUOUS PIPE WITH 1-1/2\"/>

DO NOT PLACE PIPES THRU FOOTING.


SLEEVE PIPE AND FOOTING TO BOTTOM OF TRENCH (SEE TYPICAL DETAILS).

- NOTE:
- THE PIPE SLEEVE SHALL BE FURNISHED BY OTHERS AND INSTALLED BY THE GENERAL CONTRACTOR. THE COMPRESSIBLE WATERSTOP SHALL BE FURNISHED AND INSTALLED BY THE TRADE REQUIRING THE CONTINUOUS PIPE PENETRATION.
 - WALL AND FOOTING REINFORCING NOT SHOWN FOR CLARITY.

BACKFILL AND COMPACT TRENCH 95%.


8 TYPICAL PIPES AT FOUNDATION

N.T.S.




12 TYPICAL CONCRETE WALL REINFORCING

N.T.S.



CONTROL JOINT (CJ)




CONSTRUCTION JOINT (CNJ)

- NOTES:
- SEE TYPICAL SLAB-ON-GRADE DETAIL FOR INFORMATION NOT SHOWN.
 - IF FORMED JOINT IS USED INSERT 1/8\"/>
 - IF SAWED JOINT IS USED, SEAL IF SLAB IS EXPOSED.
 - SPACE CONTROL JOINTS AS FOLLOWS:
T=4'-0\", 10'-0\"/>

3 TYPICAL SOG CONTROL/CONSTRUCTION JOINT


N.T.S.



NOTE: TYPICAL AT ALL SLAB AND FOUNDATION RE-ENTRANT CORNERS.


4 TYPICAL REENTRANT CORNER REINFORCING

N.T.S.



5 TYPICAL WALL FOOTING STEP


N.T.S.



NOTE: SLEEVE DIAMETER SHALL BE > 2X PIPE DIAMETER

9 TYPICAL PIPE SLEEVE BELOW GRADE

N.T.S.




DETAIL - PIPES < 18\"/>

DETAIL - PIPES > 18\"/>

10 TYPICAL PIPE OPENING IN CONCRETE WALL


N.T.S.



- NOTES:
- SEE FOUNDATION PLAN FOR SLAB THICKNESS.
 - THICKEN SLAB UNDER ALL INTERIOR CMU PARTITIONS EXCEEDING 8'-0\"/>
 - SEE TYPICAL SLAB-ON-GRADE DETAIL THIS SHEET, FOR SLAB DETAILS NOT SHOWN.


14 TYPICAL SLAB DETAIL AT CMU PARTITION WALL

N.T.S.




6 TYPICAL TRENCH DRAIN DETAIL

N.T.S.



7 TYPICAL SLAB AT EXTERIOR DOOR


N.T.S.



- NOTES:
- ALL TOP & BOT. SLAB BARS INTERRUPTED BY THE OPENING SHALL BE REPLACED WITH ADDITIONAL REINF EQUAL TO THAT INTERRUPTED. PLACE HALF OF THE ADDITIONAL REINF ON EACH SIDE OF OPENING AND EXTEND IT A DEVELOPMENT LENGTH BEYOND EDGE OF OPENING.
 - BOXED OUT OPENINGS RECESSED BOXES & PIPE SLEEVE CLUSTERS SHALL BE TREATED AS FOR SLAB OPENINGS.

11 TYPICAL REINF AT OPENING IN SLAB

N.T.S.




CORNER COLUMN / PIER

EXTERIOR COLUMN / PIER

15 TYPICAL SLAB ON GROUND ISOLATION JOINT AT PIER/COLUMN

N.T.S.

C:\Users\jamiler\OneDrive - CSArch\Documents\2013-2021_Liberty_High_School_Maint Bldg.dml (12/13/22) - CSA303.rvt



1 FIRST FLOOR PLAN
A111 1/4" = 1'-0"

GENERAL NOTES

1. REFER TO SHEET 6001 FOR ADDITIONAL GENERAL NOTES.
2. REFER TO A600 SERIES DRAWINGS FOR ADDITIONAL DIMENSIONS AND DETAILED INFORMATION OF CABINETRY.
3. REFER TO A400 SERIES DRAWINGS FOR DOOR, STOREFRONT, CURTAINWALL, WINDOW AND LOUVER SCHEDULES, DETAILS AND NOTES.
4. REFER TO SHEET A101 FOR PARTITION TYPES AND ADDITIONAL NOTES.


19 Front St., Newburgh, New York 12550-7601
845.581.5379 www.csaarch.com

CSARCH

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: _____ Author
Checked By: _____ 59-09-01-86-3-016-001
Proj. #: _____ 203-2201
CSArch Proj. #: _____
Construction Documents: 12/13/22


Sheet Title

FIRST FLOOR
PLAN


Sheet No.

MB
A111


CONSTRUCTION DOCUMENTS




4 WEST ELEVATION
A201 1/4" = 1'-0"



3 SOUTH ELEVATION
A201 1/4" = 1'-0"



2 EAST ELEVATION
A201 1/4" = 1'-0"



1 NORTH ELEVATION
A201 1/4" = 1'-0"

GENERAL NOTES	
1. REFER TO SHEET 6001 FOR ADDITIONAL GENERAL NOTES.	
2. REFER TO A600 SERIES DRAWINGS FOR ADDITIONAL DIMENSIONS AND DETAILED INFORMATION OF CABINETRY.	
3. REFER TO A400 SERIES DRAWINGS FOR DOOR, STOREFRONT, CURTAINWALL, WINDOW AND LOUVER SCHEDULES, DETAILS AND NOTES.	
4. REFER TO SHEET A101 FOR PARTITION TYPES AND ADDITIONAL NOTES.	
KEYNOTES	
#	DESCRIPTION
BD	BOLLARD, TYP. (REFER TO SHEET A600)
BWT	WATERTABLE BLOCK, TYP.
DS	4" x 3" DOWNSPOUT WITH UNDERGROUND CAST IRON BOOT AT ALL LOCATIONS, TYP.
FAS	FASCIA TO MATCH ROOF FINISH, TYP.
GUT	6" x 6" BEVEL GUTTER, TYP.
HD	HOLLOW METAL DOOR
LVR	LOUVER, COORDINATE WITH MC FINAL LOCATION TO BE DETERMINED IN THE FIELD.
MTP	METAL PANELS, TYP.
PC	PRE-CAST CONC. WATERTABLE COPING, TYP.
SNG	SNOWGUARDS
SSR	STANDING SEAM METAL ROOF, TYP.

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING



DATE	DESCRIPTION

Drawn By: Author
Checked By: 59-09-01-86-3-016-001
Proj. #: 203-2201
CSArch Proj. #: 12/13/22
Construction Documents: 12/13/22


Sheet Title

EXTERIOR
ELEVATIONS


Sheet No.

MB
A201


CONSTRUCTION DOCUMENTS



3 BUILDING SECTION
A251 1/4" = 1'-0"



2 BUILDING SECTION
A251 1/4" = 1'-0"



1 BUILDING SECTION
A251 1/4" = 1'-0"


GENERAL NOTES

1. REFER TO SHEET 6001 FOR ADDITIONAL GENERAL NOTES.
2. REFER TO A800 SERIES DRAWINGS FOR ADDITIONAL DIMENSIONS AND DETAILED INFORMATION OF CABINETRY.
3. REFER TO A900 SERIES DRAWINGS FOR DOOR, STOREFRONT, CURTAIN WALL, WINDOW AND LOUVER SCHEDULES, DETAILS AND NOTES.
4. REFER TO SHEET A101 FOR PARTITION TYPES AND ADDITIONAL NOTES.

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: _____ Author
Checked By: _____ 59-09-01-86-3-016-001
Proj. #: _____ 203-2201
CSArch Proj. #: _____
Construction Documents: 12/13/22

Sheet Title

BUILDING
SECTIONS


Sheet No.

MB
A251


CONSTRUCTION DOCUMENTS

COPYRIGHT © ALL RIGHTS RESERVED


C:\Users\jmliller\OneDrive - CSArch\Documents\2013-2021_Liberty_High_School_Maint_Bldg_dmliller2013-CSA303.rvt




4 WALL SECTION
A301 3/4" = 1'-0"



3 WALL SECTION
A301 3/4" = 1'-0"



2 WALL SECTION
A301 3/4" = 1'-0"



1 WALL SECTION
A301 3/4" = 1'-0"

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By:	Author
Checked By:	Checker
Proj. #:	59-09-01-86-3-016-001
CSArch Proj. #:	203-2201
Construction Documents:	12/13/22

Sheet Title


WALL
SECTIONS

Sheet No.


MB
A301

CONSTRUCTION DOCUMENTS


C:\Users\jmliller\OneDrive - CSArch\Documents\2013-2021_Liberty_High_School_Maint Bldg.dmliller2013-CSA303.rvt



3 WALL SECTION
A302 3/4" = 1'-0"



2 WALL SECTION
A302 3/4" = 1'-0"



1 WALL SECTION
A302 3/4" = 1'-0"

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By:	Author
Checked By:	Checker
Proj. #:	59-09-01-86-3-016-001
CSArch Proj. #:	203-2201
Construction Documents:	12/13/22

Sheet Title


WALL
SECTIONS

Sheet No.


MB
A302

CONSTRUCTION DOCUMENTS


C:\Users\jmliller\OneDrive - CSArch\Documents\2013-2021_Liberty_High_School_Maint_Bldg.dmliller2013-CSA303.rvt




4 TYPICAL FOUNDATION WALL COMPOSITION
A351 3" = 1'-0"



3 TYPICAL SLAB ON GRADE
A351 3" = 1'-0"




2 TYPICAL CAST CONCRETE CORNER DETAIL
A351 1 1/2" = 1'-0"




1 TYPICAL CAST CONCRETE COPING DETAIL
A351 6" = 1'-0"


- CAST STONE NOTES**
- ALL DIMENSIONS FOR CAST CONCRETE ARE APPROXIMATE, VERIFY DIMENSIONS WITH ADJACENT CONSTRUCTION BEFORE FABRICATION.
 - LENGTHS OF CAST CONCRETE SECTIONS VARY, BREAK CAST CONCRETE INTO EQUAL SEGMENTS, UNLESS NOTED OTHERWISE.
 - ALL ANCHORS, WIRES, STRAPS, PINS, DOWELS, ETC. USED TO ANCHOR CAST CONCRETE SHALL BE STAINLESS STEEL, UNLESS NOTED OTHERWISE.
 - ALL ANCHORS TO BE SECURED TO STRUCTURE, OR BLOCKING SECURED TO STRUCTURE.
 - ALL EXPOSED 90 DEG. OR LESS EDGES TO BE EASED 1/16" CHAMFER.
 - ALL DIMENSIONS GIVEN ARE BASED ON 3/8" MASONRY JOINTS. PROVIDE 3/8" JOINTS AT CAST CONCRETE SECTIONS IF MASONRY JOINT SIZES ARE CHANGED, ALL DIMENSIONS MUST BE ADJUSTED ACCORDINGLY.




7 WALL SECTION DETAIL
A351 1 1/2" = 1'-0"



6 WALL SECTION DETAIL
A351 1 1/2" = 1'-0"




9 WALL SECTION DETAIL
A351 1 1/2" = 1'-0"





8 WALL SECTION DETAIL
A351 1 1/2" = 1'-0"


TOILET ROOMS
EXTERIOR CLADDING - METAL PANELS
INTERIOR FINISH - GYPSUM WALL BOARD




TOILET ROOMS
EXTERIOR CLADDING - MASONRY
INTERIOR FINISH - GYPSUM WALL BOARD



12 LOUVER HEAD
A351 1 1/2" = 1'-0"



11 LOUVER JAMB
A351 1 1/2" = 1'-0"




10 LOUVER SILL
A351 1 1/2" = 1'-0"

19 Front St., Newburgh - New York 12550-7601
845-561-3379 www.csaarch.com

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: CSA
Checked By: CSA
Proj. #: 59-09-01-86-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

Sheet Title

SECTION
DETAILS









Sheet No.

MB
A351

CONSTRUCTION DOCUMENTS

COPYRIGHT © ALL RIGHTS RESERVED

C:\Users\jmliller\OneDrive - CSArch\Documents\2013-2011_Liberty_High_School_Maint_Bldg_dmliller2013-CSA303.rvt



Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: CSA
Checked By: CSA
Proj. #: 59-09-01-86-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22


Sheet Title

PLAN DETAILS

Sheet No.

MB
A352

CONSTRUCTION DOCUMENTS



DATE	DESCRIPTION

Drawn By: CSA
Checked By: CSA
Proj. #: 59-09-01-86-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

Sheet Title

ROOF PLAN
AND DETAILS

Sheet No.

MB
A401


CONSTRUCTION DOCUMENTS

GENERAL NOTES


1. REFER TO SHEET 6001 FOR ADDITIONAL GENERAL NOTES.
2. REFER TO A600 SERIES DRAWINGS FOR ADDITIONAL DIMENSIONS AND DETAILED INFORMATION OF CABINETRY.
3. REFER TO A400 SERIES DRAWINGS FOR DOOR, STOREFRONT, CURTAINWALL, WINDOW AND LOUVER SCHEDULES, DETAILS AND NOTES.
4. REFER TO SHEET A701 FOR PARTITION TYPES AND ADDITIONAL NOTES.

KEYNOTES


#	DESCRIPTION
GUT	6" x 6" BEVEL GUTTER, TYP.
SNS	SNOWGUARDS
SSR	STANDING SEAM METAL ROOF, TYP.




7 ROOF PIPE PENETRATION
A401 3" = 1'-0"




4 ROOF RIDGE
A401 3" = 1'-0"




5 ROOF EAVE
A401 3" = 1'-0"




6 DOWNSPOUT BOOT DETAIL, TYP.
A401 1 1/2" = 1'-0"



3 ROOF GABLE END RAKE
A401 3" = 1'-0"




2 TYPICAL ROOF COMPOSITION
A401 3" = 1'-0"



1 ROOF PLAN
A401 1/4" = 1'-0"

C:\Users\jmliller\OneDrive - CSArch\Documents\2013-2021_Liberty_High_School_Maint Bldg.dmliller2013-CSA303.rvt



1 ROOF FRAMING PLAN
A451 3/8" = 1'-0"

GENERAL NOTES

1. REFER TO SHEET 6001 FOR ADDITIONAL GENERAL NOTES.
2. REFER TO A600 SERIES DRAWINGS FOR ADDITIONAL DIMENSIONS AND DETAILED INFORMATION OF CABINETRY.
3. REFER TO A400 SERIES DRAWINGS FOR DOOR, STOREFRONT, CURTAINWALL, WINDOW AND LOUVER SCHEDULES, DETAILS AND NOTES.
4. REFER TO SHEET A701 FOR PARTITION TYPES AND ADDITIONAL NOTES.

19 Front St., Newburgh, New York 12550-7601
845.561.1317 www.csaarchitect.com

CSARCH

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



REV.	DATE	DESCRIPTION

Drawn By: CSA
Checked By: CSA
Proj. #: 59-09-01-86-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

Sheet Title

ROOF
FRAMING
PLAN

Sheet No.





MB
A451

CONSTRUCTION DOCUMENTS

C:\Users\jmliller\OneDrive - CSArch\Documents\2013-2021_Liberty_High_School_Maint Bldg.dmliller2013-CSA303.rvt

1 PLUMBING FIXTURE ELEVATIONS

A600 3/8" = 1'-0"




2 BOLLARD DETAIL, TYP.

A600 1" = 1'-0"

NOTES:

- BOLLARDS SHALL NOT PROTRUDE BEYOND DOOR JAMB OR IMPEDE FLOW OF VEHICLES INTO OR FROM BAYS
- BOLLARDS SHALL NOT PROTRUDE BEYOND CORNERS OF BUILDING OR IMPEDE CIRCULATION AROUND SIDES OF BUILDING



3 BOLLARD PLAN, TYP.

A600 1" = 1'-0"

GENERAL NOTES

- ALL CASEWORK SHALL HAVE PLASTIC LAMINATE (PLAN) COUNTERTOPS AND 4" BACK SPLASHES, UNO
- INSTALL MATCHING FILLER PANELS IN LOCATIONS SHOWN. ADD MATCHING FILLER PANELS AS REQUIRED FOR FINAL FIT/FINISH
- PROVIDE BLOCKING IN ALL ADJACENT WALLS AS REQUIRED TO INSTALL ALL CASEWORK
- PROVIDE FINISHED END PANEL AT ALL EXPOSED FACES OF CASEWORK
- PROVIDE WALL BASE AS SCHEDULED ON ALL EXPOSED TOE KICK SPACES AND EXPOSED END PANELS.

CASEWORK NOTES

- HEIGHT OF CASEWORK
- WIDTH OF CASEWORK
- AN DESIGN NUMBER (INDICATES ELEVATION LAYOUT ONLY. REFER TO DETAILS AND SPECIFICATIONS FOR CASEWORK CONSTRUCTION REQUIREMENTS)

KEY NOTES

- EB FLAM BACKSPLASH, 4" HIGH, UNO
- DA DATA OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS
- DP DUPLEX OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS
- EP FINISHED END PANEL
- GP GROUND FAULT INTERRUPT OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS
- LS LIGHT SWITCH, COORDINATE WITH ELECTRICAL DRAWINGS
- MB MARKER BOARD, SIZE AS INDICATED
- CT FLAM COUNTER TOP, CONTINUOUS
- PS PROJECTION SCREEN, SIZE AS INDICATED
- SB SCHEDULED WALL BASE
- TB TACKABLE SURFACE BOARD, LENGTH AS INDICATED (#)
- WB WHITEBOARD, LENGTH AS INDICATED (#)

TOILET ROOM NOTES

- THE HEIGHTS SHOWN ARE TYPICAL AND DO NOT NECESSARILY SHOW ALL EQUIPMENT THAT ARE TO BE LOCATED ON WALLS
- THESE GUIDELINES ESTABLISH LOCATION OF FIXTURES AND EQUIPMENT VERTICALLY AT THE WALL GENERALLY THROUGHOUT THE PROJECT
- THE DIMENSIONS CALLED OUT ARE TO THE TOP OR BOTTOM OF FIXTURES AND EQUIPMENT FACE PLATES/TRIM AS SHOWN, UNO
- THE DIMENSIONS CALLED OUT ARE TO THE CENTERLINE OF FIXTURES AND EQUIPMENT AS SHOWN, UNO
- ALL ACCESSORIES TO BE SURFACE MOUNTED, UNO
- INSTALL PRESSURE TREATED WOOD BLOCKING IN STUD PARTITIONS AT ALL LOCATIONS WHERE TOILET ACCESSORIES ARE MOUNTED TO THE WALL

TOILET ROOM KEY NOTES

- EW ELECTRIC WATER COOLER, COORDINATE WITH PLUMBING DRAWINGS
- GB 36" GRAB BAR
- GB 42" GRAB BAR
- GB 18" VERTICAL GRAB BAR
- LS SINGLE STATION LAVATORY, COORDINATE WITH PLUMBING DRAWINGS
- LS DOUBLE STATION LAVATORY, COORDINATE WITH PLUMBING DRAWINGS
- LS THREE STATION LAVATORY, COORDINATE WITH PLUMBING DRAWINGS
- MR 18"x30" CHANNEL FRAMED GLASS MIRROR
- MR 30"x60" CHANNEL FRAMED GLASS MIRROR
- PD PAPER TOWEL DISPENSER (FURNISHED BY OWNER)
- SD SOAP DISPENSER (FURNISHED BY OWNER)
- SNB SANITARY NAPKIN WASTE RECEPTACLE
- ND SANITARY NAPKIN AND TAMPON DISPENSER
- TD TOILET TISSUE DISPENSER (FURNISHED BY OWNER)
- TP TOILET PARTITION
- UP URINAL PARTITION
- UR URINAL, COORDINATE WITH PLUMBING DRAWINGS
- WC WATER CLOSET, WALL MOUNTED, COORDINATE WITH PLUMBING DRAWINGS

19 Front St., Newburgh - New York 12550-7601
845.561.1317 www.csaarch.com

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION


Drawn By: _____
Checked By: _____
Proj. #: 59-09-01-86-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

Sheet Title
**TYPICAL
EQUIPMENT
PLANS,
ELEVATIONS,
AND DETAILS**


Sheet No.
**MB
A600**

CONSTRUCTION DOCUMENTS


COPYRIGHT © ALL RIGHTS RESERVED




5 INTERIOR ELEVATION - BAY 4
A601 1/4" = 1'-0"




3 INTERIOR ELEVATION - BAY 4
A601 1/4" = 1'-0"



4 INTERIOR ELEVATION - BAY 4
A601 1/4" = 1'-0"



2 INTERIOR ELEVATION - BAY 4
A601 1/4" = 1'-0"



1 ENLARGED FLOOR PLAN
A601 1/4" = 1'-0"

GENERAL NOTES	
1. ALL CASEWORK SHALL HAVE PLASTIC LAMINATE (PLAM) COUNTERTOPS AND 4" BACK SPLASHES, UNO	
2. INSTALL MATCHING FILLER PANELS IN LOCATIONS SHOWN. ADD MATCHING FILLER PANELS AS REQUIRED FOR FINAL FIT/FINISH.	
3. PROVIDE BLOCKING IN ALL ADJACENT WALLS AS REQUIRED TO INSTALL ALL CASEWORK.	
4. PROVIDE FINISHED END PANEL AT ALL EXPOSED FACES OF CASEWORK.	
5. PROVIDE WALL BASE AS SCHEDULED ON ALL EXPOSED TOE KICK SPACES AND EXPOSED END PANELS.	
CASEWORK NOTES	
HEIGHT OF CASEWORK WIDTH OF CASEWORK AXI DESIGN NUMBER (INDICATES ELEVATION LAYOUT ONLY. REFER TO DETAILS AND SPECIFICATIONS FOR CASEWORK CONSTRUCTION REQUIREMENTS)	
KEY NOTES	
(B5) PLAM BACKSPLASH, 4" HIGH, UNO (2A) DATA OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS (2UP) DUPLEX OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS (FEP) FINISHED END PANEL (GFI) GROUND FAULT INTERRUPT OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS (LS) LIGHT SWITCH, COORDINATE WITH ELECTRICAL DRAWINGS (WB) MARKER BOARD, SIZE AS INDICATED (CT) PLAM COUNTER TOP, CONTINUOUS (FS) PROJECTION SCREEN, SIZE AS INDICATED (MB) SCHEDULED WALL BASE (TBS) TACKABLE SURFACE BOARD, LENGTH AS INDICATED (#) (KB) WHITEBOARD, LENGTH AS INDICATED (#)	
KEYNOTES	
#	DESCRIPTION
CMU	CMU WALL, REFER TO DETAILS
FE	FIRE EXTINGUISHER, WALL MOUNT
MTP	METAL PANELS, TYP.

19 Front St., Newburgh, New York 12550-7601
845.561.3379 www.csarch.com

CSARCH

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title

REGISTERED ARCHITECT
JAMES M. RITENBERG
023344
STATE OF NEW YORK

DATE DESCRIPTION

Drawn By: Author
Checked By: 59-09-01-86-3-016-001
Proj. #: 203-2201
CSArch Proj. #: 12/13/22
Construction Documents


Sheet Title
ENLARGED
PLAN AND
ELEVATIONS

Sheet No.
MB
A601
CONSTRUCTION DOCUMENTS




- | KEYNOTES | |
|----------|-------------------------------|
| # | DESCRIPTION |
| CMU | CMU WALL, REFER TO DETAILS' |
| FE | FIRE EXTINGUISHER, WALL MOUNT |
| MTP | METAL PANELS, TYP. |


C:\Users\jdmiller\OneDrive - CSArch\Documents\2013-2011_Liberty_High_School_Maint Bldg.dml:12/13/22 - CSA603.rvt




9 INTERIOR ELEVATION - TOILET T3
A603 1/2" = 1'-0"




8 INTERIOR ELEVATION - TOILET T3
A603 1/2" = 1'-0"




7 INTERIOR ELEVATION - TOILET T3
A603 1/2" = 1'-0"




6 INTERIOR ELEVATION - TOILET T3
A603 1/2" = 1'-0"




5 INTERIOR ELEVATION - TOILET 101A
A603 1/2" = 1'-0"




4 INTERIOR ELEVATION - TOILET 101A
A603 1/2" = 1'-0"



3 INTERIOR ELEVATION - TOILET 101A
A603 1/2" = 1'-0"



2 INTERIOR ELEVATION - TOILET 101A
A603 1/2" = 1'-0"



1 ENLARGED FLOOR PLAN
A603 1/2" = 1'-0"

GENERAL NOTES

1. ALL CASEWORK SHALL HAVE PLASTIC LAMINATE (PLAM) COUNTERTOPS AND 4" BACK SPLASHES, UNO.
2. INSTALL MATCHING FILLER PANELS IN LOCATIONS SHOWN. ADD MATCHING FILLER PANELS AS REQUIRED FOR FINAL FIT/FINISH.
3. PROVIDE BLOCKING IN ALL ADJACENT WALLS AS REQUIRED TO INSTALL ALL CASEWORK.
4. PROVIDE FINISHED END PANEL AT ALL EXPOSED FACES OF CASEWORK.
5. PROVIDE WALL BASE AS SCHEDULED ON ALL EXPOSED TOE KICK SPACES AND EXPOSED END PANELS.

CASEWORK NOTES

- HEIGHT OF CASEWORK
- WIDTH OF CASEWORK
- ANY DESIGN NUMBER INDICATES ELEVATION LAYOUT ONLY. REFER TO DETAILS AND SPECIFICATIONS FOR CASEWORK CONSTRUCTION REQUIREMENTS.)

KEY NOTES

- PLAM BACKSPLASH, 4" HIGH UNO
- DATA OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS
- DUPLEX OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS
- FINISHED END PANEL
- GROUND FAULT INTERRUPT OUTLET, COORDINATE WITH ELECTRICAL DRAWINGS
- LIGHT SWITCH, COORDINATE WITH ELECTRICAL DRAWINGS
- MARKER BOARD, SIZE AS INDICATED
- PLAM COUNTER TOP, CONTINUOUS
- PROJECTION SCREEN, SIZE AS INDICATED
- SCHEDULED WALL BASE
- TACKABLE SURFACE BOARD, LENGTH AS INDICATED (H)
- WHITEBOARD, LENGTH AS INDICATED (H)

TOILET ROOM NOTES

1. THE HEIGHTS SHOWN ARE TYPICAL AND DO NOT NECESSARILY SHOW ALL EQUIPMENT THAT ARE TO BE LOCATED ON WALLS.
2. THESE GUIDELINES ESTABLISH LOCATION OF FIXTURES AND EQUIPMENT VERTICALLY AT THE WALL, GENERALLY THROUGHOUT THE PROJECT.
3. THE DIMENSIONS CALLED OUT ARE TO THE TOP OR BOTTOM OF FIXTURES AND EQUIPMENT FACE PLATES/TRIM AS SHOWN UNO.
4. THE DIMENSIONS CALLED OUT ARE TO THE CENTERLINE OF FIXTURES AND EQUIPMENT AS SHOWN UNO.
5. ALL ACCESSORIES TO BE SURFACE MOUNTED UNO.
6. INSTALL PRESSURE TREATED WOOD BLOCKING IN STUD PARTITIONS AT ALL LOCATIONS WHERE TOILET ACCESSORIES ARE MOUNTED TO THE WALL.

TOILET ROOM KEY NOTES

- ELECTRIC WATER COOLER, COORDINATE WITH PLUMBING DRAWINGS
- 56" GRAB BAR
- 42" GRAB BAR
- 18" VERTICAL GRAB BAR
- SINGLE STATION LAVATORY, COORDINATE WITH PLUMBING DRAWINGS
- DOUBLE STATION LAVATORY, COORDINATE WITH PLUMBING DRAWINGS
- THREE STATION LAVATORY, COORDINATE WITH PLUMBING DRAWINGS
- 18"X30" CHANNEL FRAMED GLASS MIRROR
- 30"X60" CHANNEL FRAMED GLASS MIRROR
- PAPER TOWEL DISPENSER (FURNISHED BY OWNER)
- SOAP DISPENSER (FURNISHED BY OWNER)
- SANITARY NAPKIN WASTE RECEPTACLE
- SANITARY NAPKIN AND TAMPON DISPENSER
- TOILET TISSUE DISPENSER (FURNISHED BY OWNER)
- TOILET PARTITION
- URINAL PARTITION
- URINAL, COORDINATE WITH PLUMBING DRAWINGS
- WATER CLOSET, WALL MOUNTED, COORDINATE WITH PLUMBING DRAWINGS

19 Front St., Newburgh, New York 12550-7601
845.561.1379 www.csaarch.com

CSARCH

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: Author
Checked By: 59-09-01-86-3-016-001
Proj. #: 203-2201
CSArch Proj. #: Construction Documents: 12/13/22

Sheet Title

ENLARGED
PLAN AND
ELEVATIONS



Sheet No.

MB
A603


CONSTRUCTION DOCUMENTS

COPYRIGHT © ALL RIGHTS RESERVED


COPYRIGHT © ALL RIGHTS RESERV



C:\Users\jdmiller\OneDrive - CSArch\Documents\2013-2021_Liberty_High_School_Maint Bldg.dml 2013-CSA303.rvt



1 FIRST FLOOR REFLECTED CEILING PLAN
A811 1/4" = 1'-0"



2 ACT CEILING, TYP.
A811 1 1/2" = 1'-0"

CEILING NOTES

1. INSTALL CEILING GRIDS CENTERED IN THE ROOM. UNO. IN ROOMS OTHER THAN RECTANGULAR SHAPED, INSTALL GRIDS CENTERED ON WALLS OR OTHER BUILT FEATURES AS INDICATED.
2. INSTALLATION HEIGHTS OF THE CEILINGS MAY VARY SLIGHTLY FROM PLANS IN ROOMS WITH EXTERIOR WINDOWS. ACTUAL CEILING HEIGHT TO BE VERIFIED IN THE FIELD.
3. FINAL INSTALLED CEILINGS SHALL HAVE HEIGHTS COORDINATED WITH OTHER CONTRACTORS WITH ABOVE CEILING WORK AND VERIFIED WITH FIELD CONDITIONS. ALL CHANGES IN CONFIGURATION OR HEIGHTS ARE TO BE APPROVED BY THE ARCHITECT.

CEILING LEGEND

- 6MB OR PLASTER CEILING, REFER TO DETAILS AND ROOM FINISH SCHEDULE
- SUSPENDED ACOUSTICAL PANEL CEILING SYSTEM
- CEILING HEIGHT ABOVE FINISHED FLOOR

ELECTRICAL EQUIPMENT, REFER TO ELECTRICAL DRAWINGS FOR ADDITIONAL INFORMATION.

- 2X4 LIGHT FIXTURE
- 2X2 LIGHT FIXTURE
- 1X LIGHT FIXTURE
- PENDANT LIGHT FIXTURE
- RECESSED DOWN LIGHT
- CEILING MOUNTED EXIT SIGN
- CEILING MOUNTED OCCUPANCY SENSOR
- CEILING MOUNTED SMOKE DETECTOR
- CEILING MOUNTED HEAT DETECTOR
- CEILING MOUNTED PA SPEAKER
- CEILING MOUNTED SECURITY J-BOX
- CEILING MOUNTED MOTION SENSOR
- CEILING MOUNTED DATA J-BOX

MECHANICAL EQUIPMENT, REFER TO MECHANICAL DRAWINGS FOR ADDITIONAL INFORMATION.

- HVAC SUPPLY GRILLE
- HVAC RETURN GRILLE

KEYNOTES

#	DESCRIPTION
APC	ACOUSTICAL PANEL CEILING SYSTEM


19 Front St., Newburgh, New York 12550-7601
845.561.1319 www.csaarch.com

CSARCH

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: CSA
Checked By: CSA
Proj. #: 59-09-01-86-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

Sheet Title

FIRST FLOOR
REFLECTED
CEILING PLAN
AND DETAILS

Sheet No.

MB
A811

CONSTRUCTION DOCUMENTS

COPYRIGHT © ALL RIGHTS RESERVED

C:\Users\jamiler\OneDrive - CSArch\Documents\2015-2016_Liberty_High_School_Maint_Bldg.dml 10/15/2015 CSArch3.rvt


FLOOR FINISHES					
EPOXY RESINOUS FLOOR	MANUFACTURER	STYLE	COLOR # /	SIZE	NOTE
ERF-1	DUR-A-FLEX, INC.	HYBRI-FLEX EQ	AS SELECTED BY ARCHITECT FROM FULL RANGE	SEAMLESS	ALL TOILET ROOMS

BASE FINISHES					
EPOXY RESINOUS WALL BASE	MANUFACTURER	STYLE	COLOR # /	SIZE	NOTE
ERB-1	DUR-A-FLEX, INC.	HYBRI-FLEX EQ	AS SELECTED BY ARCHITECT FROM FULL RANGE	SEAMLESS	ALL TOILET ROOMS

WALL FINISHES					
WALL PAINT	MANUFACTURER	STYLE	COLOR # /	SIZE	NOTE
PNT-1	SHERWIN WILLIAMS	EGG-SHELL	AS SELECTED BY ARCHITECT FROM FULL RANGE		BAYS 1 THRU 4 (CMU WALLS)
PNT-2	SHERWIN WILLIAMS	EGG-SHELL	AS SELECTED BY ARCHITECT FROM FULL RANGE		ALL TOILET ROOMS (CMU WALLS)
PNT-3	SHERWIN WILLIAMS	EGG-SHELL	AS SELECTED BY ARCHITECT FROM FULL RANGE		ALL TOILET ROOMS (GWB WALLS)
PNT-4	SHERWIN WILLIAMS	SEMI-GLOSS	AS SELECTED BY ARCHITECT FROM FULL RANGE		HM DOOR FRAMES
PNT-5	SHERWIN WILLIAMS	SEMI-GLOSS	AS SELECTED BY ARCHITECT FROM FULL RANGE		HM DOOR PANELS

CEILING FINISHES					
ACOUSTIC PANEL CEILINGS	MANUFACTURER	STYLE	COLOR # /	SIZE	NOTE
C-1	USG INTERIORS, INC.	MARS, SHADOWLINE	WHITE	24" X 24"	ALL TOILET ROOMS

FINISH SCHEDULE																
ROOM NUMBER	ROOM NAME	FLOOR SUBSTRATE	FLOOR FINISH	BASE SUBSTRATE	BASE FINISH	NORTH WALL SUBSTRATE	NORTH WALL FINISH	EAST WALL SUBSTRATE	EAST WALL FINISH	SOUTH WALL SUBSTRATE	SOUTH WALL FINISH	WEST WALL SUBSTRATE	WEST WALL FINISH	CEILING MATERIAL	CEILING FINISH	COMMENTS
101	BAY 1	CONC	EXP	CONC/CMU	EXP	-	-	MTP	FF	CMU	PNT-1	MTP	FF	EXP	-	
101A	TOILET	CONC	ERF-1	GWB/CMU	ERB-1	CMU	PNT-2	GWB	PNT-3	GWB	PNT-3	CMU	PNT-2	ACT	C-1	
102	BAY 2	CONC	EXP	CONC/CMU	EXP	-	-	MTP	FF	-	-	MTP	FF	EXP	-	
103	BAY 3	CONC	EXP	CONC/CMU	EXP	CMU	PNT-1	MTP	FF	-	-	MTP	FF	EXP	-	
104	BAY 4	CONC	EXP	CONC/CMU	EXP	MTP	FF	MTP	FF	CMU	PNT-1	MTP	FF	EXP	-	
T1	TOILET	CONC	ERF-1	GWB/CMU	ERB-1	CMU	PNT-2	CMU	PNT-2	GWB	PNT-3	GWB	PNT-2	ACT	C-1	
T2	TOILET	CONC	ERF-1	GWB/CMU	ERB-1	CMU	PNT-2	CMU	PNT-2	GWB	PNT-3	CMU	PNT-2	ACT	C-1	
T3	TOILET	CONC	ERF-1	GWB/CMU	ERB-1	CMU	PNT-2	CMU	PNT-2	GWB	PNT-3	CMU	PNT-3	ACT	C-1	



1 FIRST FLOOR FINISH PLAN
AF001 1/4" = 1'-0"

DISCLAIMER NOTE	
MANUFACTURER'S NAMES AND FINISH INFORMATION ARE INDICATED AS REFERENCED TO THE ARCHITECT'S BASIS OF DESIGN SELECTIONS AND HAVE BEEN DETERMINED PRIOR TO BID. THE CONTRACTOR AND OWNER ARE HEREBY NOTIFIED THAT FINISHES INSTALLED IN THE WORK ARE SUBJECT TO CHANGE IN RESPONSE TO SUBMITTALS, CONFIRMED SELECTIONS, PRODUCT AVAILABILITY AND THE SUBSEQUENT COORDINATION OF FINISHES BY ARCHITECT AND MAY DIFFER FROM PRODUCTS LISTED HEREIN.	
ABBREVIATIONS	
ACMU	ARCHITECTURAL CONCRETE MASONRY UNIT
ACT	ACOUSTICAL CEILING TILE
APG	ACOUSTICAL PANEL CEILING
BBT	BIO-BASED TILE
BRK	BRICK
CFT	CERAMIC FLOOR TILE
CMU	CONCRETE MASONRY UNIT
CONC	CONCRETE
CNR	CONCRETE MATER REPELLENT
CPT	CARPET
CTB	CERAMIC TILE BASE
CMT	CERAMIC WALL TILE
ETR	EXISTING TO REMAIN
EXP	EXPOSED
FAC/FF	FACTORY FINISH
GWB/GYP	GYPSON WALL BOARD
LMC	LINEAR METAL CEILING
MBS	MUSIC STORAGE SYSTEM
MVP	METAL WALL PANEL
PCON	POLISHED CONCRETE
FLAM	PLASTIC LAMINATE
PLAS	PLASTER
PNT	PAINT
RAF	RESILIENT ATHLETIC FLOORING
RB	RUBBER BASE
RF	RESINOUS FLOORINGS
RST	RUBBER STAIR TREAD / LANDING
RT	RUBBER TILE FLOORING
SCONC	SEALED CONCRETE
SS	STAINLESS STEEL
STF	SYNTHETIC TURF FLOORING
STL	STEEL
TERR	TERRAZZO
TP	TOILET PARTITIONS
TYP	TYPICAL
VGT	VINYL COMPOSITION TILE
VGTAS	VINYL COMPOSITION TILE ANTI-STATIC
VWG	VINYL WALLCOVERINGS
WAF	WOOD ATHLETIC FLOORING
WOD	WOOD
WOM	WALK-OFF MAT
X-	EXISTING

GENERAL FINISH NOTES	
1.	ALL EXPOSED SURFACES OF NEW PARTITIONS ARE TO BE PAINTED.
2.	WHEN ANY WORK IS PERFORMED ON ANY EXISTING WALL, THE ENTIRE WALL SURFACE IS TO BE PAINTED CORNER TO CORNER, UNLESS NOTED OTHERWISE.
3.	ALL ELECTRIC, MECHANICAL COMPONENTS AND TELEPHONE PANELS EXPOSED IN A ROOM TO MATCH WALL COLOR.
4.	ALL NEW GWB CEILINGS, FASCIAS, AND SOFFITS TO BE PAINTED PNT-2, UNO.
5.	ALL EXPOSED CEILING STRUCTURE, DECK, DUCTWORK, CONDUIT AND PIPING TO BE PAINTED PNT-2, UNO.
6.	ALL STEEL COLUMNS IN AREAS OF WORK ARE TO BE PAINTED.
7.	ALL EXPOSED STEEL ASSOCIATED WITH STAIRS TO BE PAINTED PNT-3, INCLUDING STRINGERS, CHANNELS, RISERS, COLUMNS, PLATES, TUBES, GUARDRAILS, POSTS, UNDERSIDES OF FLOORS, LANDINGS, DECKS, AND STAIR FANS WITH THE EXCEPTION OF SS & FF, UNO.
8.	NEW HM DOORS, DOOR FRAMES AND WINDOW FRAMES AND ETR CORRIDOR DOOR & WINDOW FRAMES AS SCHEDULED ON A600 SERIES DRAWINGS, PNT-1.
9.	ALL EXPOSED GROUND FACE CMU LOCATIONS TO RECEIVE GRAFFITI COATING, TYPICAL FOR INTERIOR LOCATIONS.

FINISH KEYNOTES	
#	DESCRIPTION
F.1	PROVIDE NEW WALL BASE & PAINT AT NEW WORK TO MATCH EXISTING ADJACENT MATERIALS & FINISHES.
F.2	ALIGN FLOOR FINISH TRANSITION TO FACE OF WALL.
F.3	INFILL AREA AFFECTED BY DEMOLITION WITH NEW VGT TO MATCH EXISTING AS REQUIRED.

FINISH KEYS	
Room Name [101]	
Wall Finish [PNT-2]	
Floor Finish [EXP]	
	= FINISH TAG
PNT-1	ACCENT PAINT LOCATION

19 Front St., Newburgh - New York 12550-7601
845-561-1317 www.csarchnyc.com

Consultant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By:	CSA
Checked By:	CSA
Proj. #:	59-09-01-86-3-016-001
CSArch Proj. #:	203-2201
Construction Documents:	12/13/22

Sheet Title

FINISH
SCHEDULES
AND PLANS


Sheet No.

MB
AF001

CONSTRUCTION DOCUMENTS

COPYRIGHT © ALL RIGHTS RESERVED

Plumbing Fixture Schedule											
FIXTURE MARK	DESCRIPTION	PIPING CONNECTION				WATER SUPPLY FIXTURE UNITS	DRAINAGE FIXTURE UNITS	ADA (Y/N)	ELECTRONIC CONTROL (Y/N)	MANUFACTURER/MODEL (OR ACCEPTABLE EQUAL)	REMARKS
		H.W.	C.W.	WASTE	VENT						
1	EXPOSED WALL HYDRANT	-	3/4	-	-	-	-	-	-	EXPOSED WALL HYDRANT TYPICAL OF ZURN ECOLOTROL MODEL #Z1333XL; EXPOSED, LEAD FREE, ANTI SIPHON, AUTO DRAINING	MTD. AT 24" ABOVE FINISHED FLOOR. INSTALL PER MANUFACTURER'S REQUIREMENTS
2	WATER CLOSET	-	1	4	2	10.0	4	Y	Y	WATER CLOSET TYPICAL OF ZURN MODEL #Z5615 HET; WALL HUNG W/ ELONGATED FRONT RIM, 1.28 GPF; FURNISH W/ SEAT MODEL #Z5955SS-EL AND BATTERY SENSOR FLUSH VALVE MODEL# ZER6000AV-HET-CFM	INSTALL PER ADA & MANUFACTURER'S REQUIREMENTS. PROVIDE WALL CARRIER TYPICAL OF ZURN Z1201 OR EQUAL
3	LAVATORY	1/2	1/2	1-1/2	1-1/2	2.0	1	Y	Y	WALL HUNG LAVATORY TYPICAL OF ZURN MODEL #Z5340; VITREOUS CHINA; FURNISH W/ BATTERY SENSOR FAUCET MODEL #Z6955-XL-S-N-L-L, CONCEALED ARM CARRIERS, ADA GRID STRAINER AND ADA TRAP/SUPPLY PROTECTORS	INSTALL PER ADA & MANUFACTURER'S REQUIREMENTS
4	FLOOR DRAIN	-	-	4	2	-	2	-	-	4"Ø FLOOR DRAIN W/ 6" STRAINER TYPICAL OF ZURN MODEL #Z415-BZ1-TSP; FURNISH WITH TRAP SEAL DEVICE	INSTALL PER MANUFACTURER'S REQUIREMENTS
5	TRENCH DRAIN	-	-	4	2	-	2	-	-	12" WIDE PRE-SLOPED HDPE TRENCH DRAIN TYPICAL OF ZURN MODEL #Z882; FURNISH WITH FIBERGLASS CLASS-F GRATE; ASSEMBLE SECTIONS TO HAVE CONTINUOUS SLOPE	INSTALL PER MANUFACTURER'S REQUIREMENTS
6	GAS WATER HEATER	3/4	3/4	-	-	-	-	-	-	GAS WATER HEATER TYPICAL OF BRADFORD WHITE MODEL #L2PV50H763N; 50 GAL. CAPACITY; 81 GPH RECOVERY @ 100F RISE; 89% THERMAL EFFICIENCY; 76 MBH INPUT	INSTALL PER MANUFACTURER'S REQUIREMENTS
7	RECIRC/MIXING STATION	1(110F) 3(140F)	3/4	-	-	-	-	-	-	RECIRCULATION AND MIXING STATION TYPICAL OF BRADLEY MODEL#NRS-4; FURNISH W/ TACO SMARTPLUS MODEL #008-IQSF6-IFC RECIRC PUMP AND AQUASTAT	INSTALL PER MANUFACTURER'S REQUIREMENTS
8	NON-FREEZE WALL HYDRANT	-	3/4	-	-	-	-	-	-	ENCASED WALL HYDRANT TYPICAL OF ZURN ECOLOTROL MODEL #Z1320XL; ENCASED, LEAD FREE, ANTI SIPHON, AUTO DRAINING, NON-FREEZE	MTD. AT 36" ABOVE FINISHED GRADE. INSTALL PER MANUFACTURER'S REQUIREMENTS




NOTES:
1. PIPE 6" AND LARGER SHALL HAVE ROLLER SUPPORTED WITH DUAL RODS.
2. FOR CHW SERVICE OVER 3" REPLACE SADDLE WITH 12" LONG 14 GA SHIELD WITH RIGID INSULATION BETWEEN PIPE AND SHIELD.

PIPE Ø (IN.)	MAX. SPACING BETWEEN HANGERS (FT.)			MIN. ROD SIZE (IN.)
	STEEL PIPE	COPPER PIPE	CPVC	
1/2 THRU 1	7	5	5	3/8
1-1/2 THRU 2	9	8	6	3/8
2-1/2	11	9	7.5	1/2
3	12	10	7.5	1/2
4	14	12	8.5	5/8
6	17	14	9	3/4
8	19	16	10	7/8
10	22	18	10.5	7/8


3 Pipe Hanger Support

N.T.S.




6 Non-Freeze Hose Bibb Detail

N.T.S.




8 Double Cleanout To Grade

N.T.S.




4 Gas Piping Appliance Connection Detail

N.T.S.




7 Accessible Lavatory Detail

Scale: None




9 Typical Water Heater Detail

N.T.S.




2 Pipe Penetrations Detail

N.T.S.



5 Typical Shared Trench Detail

N.T.S.



10 Domestic Water Service Detail

N.T.S.

Plumbing Legend:

---	DOMESTIC COLD WATER SUPPLY
---	110 °F DOMESTIC HOT WATER SUPPLY
---	140 °F DOMESTIC HOT WATER SUPPLY
---	HOT WATER RETURN
---	SANITARY SEWER, ABOVE GRADE
---	SANITARY SEWER, BELOW GRADE
---	GREASE WASTE, BELOW GRADE
---	PLUMBING VENT
---	STORM WATER, ABOVE GRADE
---	STORM WATER, BELOW GRADE
---	NATURAL GAS PIPING
---	DIRECTION OF PIPE SLOPE (DOWN)
---	CONCENTRIC REDUCER OR INCREASER
---	ECCENTRIC REDUCER
---	TOP CONNECTION, 45° OR 90°
---	BOTTOM CONNECTION, 45° OR 90°
---	SIDE CONNECTION
---	CAPPED OUTLET
---	RISE OR DROP IN PIPE
---	UNION
---	PIPE UP
---	PIPE DOWN
---	POINT OF CONNECTION BETWEEN NEW AND EXISTING WORK
---	STRAINER
---	HOSE BIB
---	SOLENOID VALVE
---	GATE VALVE
---	GLOBE VALVE
---	CHECK VALVE
---	BUTTERFLY VALVE
---	FULL PORT BALL VALVE
---	PRESSURE GAUGE
---	PRESSURE REDUCING VALVE (PRV)
---	DRAIN VALVE
---	FLEXIBLE PIPING CONNECTION
---	CLEANOUT
---	WALL CLEANOUT
---	FLOOR CLEANOUT
---	CLEANOUT TO GRADE
---	DOUBLE CLEANOUT TO GRADE
---	PLUMBING FIXTURE MARK

Plumbing Notes:

- ALL MATERIALS AND EQUIPMENT ARE TO BE NEW, UNUSED, AND FREE FROM DEFECTS OF ANY KIND. THE BASIS OF QUALITY SHALL BE THE LATEST REVISION OF ASTM, ANSI, OR OTHER ACCEPTABLE STANDARDS.
- THESE DRAWINGS ARE DIAGRAMMATIC, AND INDICATE GENERAL ARRANGEMENT OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE REVIEWED THE SITE FOR HIS WORK PRIOR TO HAVING SUBMITTED HIS PROPOSAL. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR CONDITIONS FOUND DURING THE COURSE OF THE CONTRACT.
- THE CONTRACTOR SHALL COORDINATE HIS WORK WITH THAT OF ALL OTHER TRADES.
- ALL CUTTING, PATCHING, FIRE-STOPPING, AND SURFACE RESTORATION IN CONNECTION WITH THIS TRADE SHALL BE COMPLETED BY THIS CONTRACTOR.
- THIS CONTRACTOR SHALL PAY ALL FEES, GIVE ALL NOTICES, FILE ALL NECESSARY DRAWINGS, AND OBTAIN ALL PERMITS, INSPECTIONS AND CERTIFICATES OF APPROVAL REQUIRED IN CONNECTION WITH WORK UNDER THIS CONTRACT.
- ALL WORK IN ASSOCIATION WITH THIS CONTRACT SHALL BE COMPLETED IN STRICT COMPLIANCE WITH THE 2020 BUILDING CODE OF NEW YORK STATE, 2020 PLUMBING CODE OF NEW YORK STATE, 2020 FUEL GAS CODE OF NEW YORK STATE & 2020 ENERGY CONSERVATION CONSTRUCTION CODE OF NEW YORK STATE.
- WHERE THE PROJECT INVOLVES A GAS SERVICE, THIS CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COORDINATION, APPLICATIONS AND FEES OF ALL WORK ASSOCIATED WITH THE LOCAL GAS UTILITY COMPANY. ALL WORK INVOLVING THE GAS UTILITY COMPANY SHALL BE COMPLETED IN ACCORDANCE WITH THEIR REGULATIONS AND GUIDELINES.
- ALL DOMESTIC COLD AND HOT WATER PIPING AND FITTINGS ARE TO BE INSULATED WITH 1" THICK RIGID ONE-PIECE MOLDED SECTIONAL FIBERGLASS PIPE COVERING WITH UNIVERSAL JACKET. ALL JOINTS ARE TO BE COMPLETELY SEALED A MINIMUM OF 6" BEYOND JOINT ENDS.
- ALL PIPING SHALL BE PROPERLY SUPPORTED AND ROUTED PARALLEL OR PERPENDICULAR TO BUILDING WALLS. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL SUPPORT HANGERS AND MISCELLANEOUS METALS REQUIRED FOR PROPER INSTALLATION OF WORK.
- ALL EXPOSED PIPING, FITTINGS, TRAPS, ESCUTCHEONS, VALVES, ETC. SHALL BE CHROME PLATED.
- SLOPE SANITARY DRAINAGE PIPING 2" DIAMETER AND SMALLER NOT LESS THAN 1/4" PER FOOT. SLOPE SANITARY DRAINAGE PIPING OVER 2" DIAMETER NOT LESS THAN 1/8" PER FOOT.
- INSTALL A CLEANOUT AT THE BASE OF EACH SOIL STACK, AT EACH CHANGE IN DIRECTION, AT INTERVALS NOT OVER 50 FEET AND ELSEWHERE AS SHOWN ON DRAWINGS OR REQUIRED BY CODE.
- PROVIDE EXPOSED PIPING WITH CHROME PLATED CAST BRASS ESCUTCHEON WITH SET SCREW WHERE PENETRATING FLOORS, CEILINGS, WALLS OR PARTITIONS.
- TEST PIPING AND PROVE TIGHT FOR AT LEAST TWO HOURS IN ACCORDANCE WITH REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION AND/OR AS SPECIFIED. TEST SHALL BE PERFORMED IN THE PRESENCE OF THE ENGINEER AND LOCAL INSPECTOR. TEST SHALL BE REPEATED IF NECESSARY UNTIL FINAL APPROVAL OF SYSTEM IS OBTAINED.
- 14.1. WATER & GAS PIPING TO BE AIR-PRESSURE TESTED TO 1-1/2 TIMES MAXIMUM WORKING PRESSURE.
- 14.2. DRAINAGE, WASTE & VENT PIPING TO BE TESTED BY FILLING THE SYSTEM WITH WATER TO 10-FEET ABOVE HIGHEST POINT.
- SUPPORT HORIZONTAL PIPING UTILIZING A SPACING PER PIPING MANUFACTURER'S REQUIREMENTS.
- INSTALL VALVES ON THE ENTIRE DISTRIBUTION SYSTEM, SO LOCATED AS TO GIVE COMPLETE CONTROL TO ALL FIXTURES AND EQUIPMENT.
- INSTALL DRAIN VALVES AT BASE OF ALL RISERS AND AT LOW POINTS OF PIPING SYSTEM.
- THE CONTRACTOR IS RESPONSIBLE TO TEST ALL EQUIPMENT, PIPING, FIXTURES, AND SYSTEMS INSTALLED UNDER THIS CONTRACT TO ENSURE PROPER OPERATION PRIOR TO FINAL ACCEPTANCE BY THE OWNER AND ENGINEER.
- THE CONTRACTOR IS RESPONSIBLE TO DETERMINE WHETHER SPECIAL LICENSING IS REQUIRED IN ORDER TO PERFORM THE REQUIRED WORK IN THE MUNICIPALITY WHERE THE PROJECT IS LOCATED. IF THE CONTRACTOR CANNOT OBTAIN THE REQUIRED LICENSING TO COMPLETE THE WORK WITHIN THE PROJECT SCHEDULE, THEN THE CONTRACTOR SHALL NOT BE PERMITTED TO BID ON THIS PROJECT.
- CONTRACTOR IS RESPONSIBLE TO CREATE AND SUBMIT RED-LINE "AS-BUILT" PLANS TO THE ENGINEER AT THE END OF THE PROJECT. AS-BUILT PLANS SHALL ACCURATELY REPRESENT THE SYSTEMS AS THEY WERE INSTALLED.

DRAINAGE NOTES:


- DRAINAGE MUST BE PROVIDED TO ACCOMMODATE DISCHARGE DURING TESTING OR RELIEF VALVE DISCHARGE.
- DISCHARGE FROM RELIEF VALVES MUST BE READILY VISIBLE. ADEQUATE LIGHTING MUST BE PROVIDED.
- DISCHARGE PIPING FROM ANY RELIEF VALVE MUST TERMINATE AT LEAST 1" ABOVE GRADE OR RECEIVING RECEPTACLE.

BACKFLOW DEVICE INSTALLATION NOTES:

- STRAINERS ARE RECOMMENDED PRIOR TO EACH BACKFLOW DEVICE ON NON-FIRE FIGHTING LINES ONLY. NO STRAINER IS TO BE USED ON A FIRE LINE WITHOUT INSURANCE UNDERWRITER APPROVAL.
- ASSEMBLIES SHOULD BE SPECIFIED AND INSTALLED WITH MANUFACTURER SUPPLIED VALVES.
- WATER LINES SHOULD BE THOROUGHLY FLUSHED BEFORE INSTALLATION OF DEVICE TO PREVENT DEBRIS FOULING THE DEVICE CHECK VALVES.
- DEVICES MUST BE MOUNTED HORIZONTALLY UNLESS APPROVED FOR VERTICAL INSTALLATION.
- ASSEMBLIES SHOULD NOT BE INSTALLED IN AREAS CONTAINING CORROSIVE OR TOXIC GASES WHICH COULD RENDER THE DEVICE INOPERABLE.
- DUE TO INHERENT DESIGN OF RPZ ASSEMBLIES, FLUCTUATING SUPPLY PRESSURE ON A LOW FLOW CONDITION MAY CAUSE NUISANCE DRIPPING. INSTALLATION OF A SOFT SEATED CHECK VALVE AHEAD OF THE RPZ WILL OFTEN HOLD PRESSURE CONSTANT DURING PERIODS OF LOW FLOW.
- THE INSTALLATION OF A DOUBLE CHECK VALVE DEVICE IS ACCEPTABLE FOR ANY NON-HAZARDOUS TENANT OCCUPANCY. IF A POTENTIALLY HAZARDOUS OCCUPANT (MEDICAL OFFICES, DRY CLEANERS, ETC.) TAKES TENANCY A REDUCED PRESSURE ZONE (RPZ) TYPE BACKFLOW DEVICE NEEDS TO BE INSTALLED IN LIEU OF A DOUBLE CHECK VALVE DEVICE AND ALL ORANGE COUNTY DOH INSTALLATION REQUIREMENTS MUST BE MET. IF AN RPZ IS REQUIRED TO BE INSTALLED, RE-APPROVAL FROM THE ORANGE COUNTY HEALTH DEPARTMENT IS REQUIRED.
- THE INSTALLATION OF THE BACKFLOW PREVENTION DEVICE SHALL MEETING ALL STATE OF NEW YORK DEPARTMENT OF HEALTH (NY DOH) REQUIREMENTS.
- IT IS UNLAWFUL TO REMOVE THIS DEVICE FOR ANY REASON UNLESS NY-DOH IS NOTIFIED. EACH BACKFLOW PREVENTION DEVICE SHALL BE TESTED ANNUALLY BY A STATE OF NEW YORK CERTIFIED TESTER.
- THE ROOM WHERE THE BACKFLOW PREVENTION DEVICE IS TO BE LOCATED HAS HEATING AND LIGHTING.
- STRAINERS ARE RECOMMENDED PRIOR TO EACH BACKFLOW DEVICE ON NON-FIRE FIGHTING LINES ONLY. NO STRAINER IS TO BE USED ON A FIRE LINE WITHOUT INSURANCE UNDERWRITER APPROVAL.
- ASSEMBLIES SHOULD BE SPECIFIED AND INSTALLED WITH MANUFACTURER SUPPLIED VALVES.
- THE DEVICE SHALL BE ADEQUATELY SUPPORTED AND/OR RESTRAINED TO PREVENT MOVEMENT.
- MAINTAIN MIN. 12" CLEAR FROM REAR SIDE OF DEVICE TO ANY WALL OR OBSTRUCTION.
- MAINTAIN MIN. 30" CLEAR FROM FRONT SIDE OF DEVICE TO ANY WALL OR OBSTRUCTION.
- BETWEEN POINT OF ENTRY AND BACKFLOW DEVICE, PIPED MUST BE STENOILED FEED TO BACKFLOW PREVENTER. DO NOT TAP OR CONNECT TO THIS LINE, AT 5' INTERVALS, AND AT WALL PENETRATION.

19 Front St., Newburgh, New York 12550-7601
845-561-3179 www.csarch.com


CSARCH



Constant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: BJK
Checked By: BJK
Proj. #: 59-09-01-06-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22


Sheet Title

PLUMBING
NOTES,
SCHEDULE,
LEGEND &
DETAILS


Sheet No.

MB
P101


CONSTRUCTION DOCUMENTS



ADD ALTERNATE
NO. 03-001




1 Sanitary Plan
P202 Scale: 1/4" = 1'-0"



LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: BJK
Checked By: BJK
Proj. #: 59-09-01-06-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

Sheet Title


SANITARY
PLAN

Sheet No.

MB
P202

CONSTRUCTION DOCUMENTS


THICKNESS & REINFORCING SCHEDULE - * LOW PRESSURE DUCTWORK						
* NOTE: LOW PRESSURE DUCTWORK SHALL BE DUCTWORK IN WHICH THE PRESSURE DOES NOT EXCEED 2" WATER GAUGE.						
GREATEST DUCT DIMENSION	STEEL DUCTS U.S. STANDARD GAUGE	ALUMINUM DUCTS B & S GAUGE	LONGITUDINAL SEAM	TRANSVERSE JOINT SMALLEST DIMENSION	TRANSVERSE JOINT GREATEST DIMENSION	REINFORCING (ALL DUCTS 18" THRU 54" SHALL BE CROSSBROKEN)
12" OR LESS	26	24(0.020")	PITTSBURGH OR ACME LOCK	DRIVE SLIP OR POCKET LOCK OR BAR SLIP	PLAIN "S" SLIP OR POCKET LOCK OR BAR SLIP	NONE REQUIRED
13" THRU 18"	24	22(0.025")	PITTSBURGH OR ACME LOCK	DRIVE SLIP OR POCKET LOCK OR BAR SLIP	PLAIN "S" SLIP OR POCKET LOCK OR BAR SLIP	NONE REQUIRED
19" THRU 30"	24	22(0.025")	PITTSBURGH OR ACME LOCK	HEMMED "S" SLIP OR BAR SLIP OR DRIVE SLIP OR 1" POCKET LOCK	HEMMED "S" SLIP OR BAR SLIP OR 1" POCKET LOCK	IF TRANSVERSE JOINTS ARE LOCATED 4'-0" OR LESS ON CENTER NO REINFORCING IF ON 8'-0" CENTERS REINFORCE WITH 1"x1"x1/8" ANGLES AT 4 FT. O.C. FASTENED ON 8" CENTERS
31" THRU 42"	22	20(0.032")	PITTSBURGH OR ACME LOCK	DRIVE SLIP 18" OR LESS BAR SLIP REINFORCED BAR SLIP OR POCKET LOCK	BAR SLIP OR REINFORCED BAR SLIP OR POCKET LOCK	IF TRANSVERSE JOINTS ARE LOCATED 4'-0" OR LESS ON CENTER NO REINFORCING IF ON 8'-0" CENTERS REINFORCE WITH 1"x1"x1/8" ANGLES AT 4 FT. O.C. FASTENED ON 8" CENTERS
43" THRU 54"	22	20(0.032")	PITTSBURGH LOCK	1 1/4" BAR SLIP, OR REINFORCED BAR SLIP, OR 1 1/2" POCKET LOCK	1 1/4" BAR SLIP, OR REINFORCED BAR SLIP, OR 1 1/2" POCKET LOCK	IF TRANSVERSE JOINTS ARE LOCATED 4'-0" OR LESS ON CENTER NO REINFORCING IF ON 8'-0" CENTERS REINFORCE WITH 1"x1"x1/8" ANGLES AT 4 FT. O.C. FASTENED ON 8" CENTERS
55" THRU 60"	20	18(0.040")	PITTSBURGH LOCK	1 1/4" BAR SLIP, OR REINFORCED BAR SLIP, OR 1 1/2" POCKET LOCK	1 1/4" BAR SLIP, OR REINFORCED BAR SLIP, OR 1 1/2" POCKET LOCK	IF TRANSVERSE JOINTS ARE LOCATED 4'-0" OR LESS ON CENTER NO REINFORCING IF ON 8'-0" CENTERS REINFORCE WITH 1"x1"x1/8" ANGLES AT 4 FT. O.C. FASTENED ON 8" CENTERS
61" THRU 84"	20	18(0.040")	PITTSBURGH LOCK	REINFORCED BAR SLIP, OR ANGLE SLIP, ALTERNATE BAR SLIP, OR ANGLE REINFORCED POCKET LOCK	REINFORCED BAR SLIP, OR ANGLE SLIP, ALTERNATE BAR SLIP, OR ANGLE REINFORCED POCKET LOCK	REINFORCE ALL SIDES OVER 60" WITH 1 1/2"x1 1/2"x3/16" ANGLES ON 2'-0" CENTERS. SIDES 60" OR LESS NEED NO REINFORCING IF JOINTS ARE ON 4'-0" CENTERS. IF JOINTS ARE ON 8'-0" CENTERS REINFORCE WITH 1 1/2"x1 1/2"x1/8" ANGLES ON 4'-0" CENTERS.
85" THRU 96"	18	16(0.051") (LONGITUDINAL SEAM MAY BE STANDING SEAM)	PITTSBURGH LOCK	1 1/2" COMPANION ANGLES, OR ANGLE REINFORCED POCKET LOCK, OR 1 1/2" ANGLE SLIP OR REINFORCED BAR SLIP	1 1/2" COMPANION ANGLES, OR ANGLE REINFORCED POCKET LOCK, OR 1 1/2" ANGLE SLIP OR REINFORCED BAR SLIP	REINFORCE ALL SIDES OVER 84" WITH 1 1/2"x1 1/2"x3/16" ANGLES ON 2'-0" CENTERS. SIDES 81" THRU 84" REINFORCE WITH 1 1/2"x1 1/2"x1/8" ANGLES ON 2'-0" CENTERS. SIDES 80" OR LESS NEED NO REINFORCING IF JOINTS ARE ON 4'-0" CENTERS. IF JOINTS ARE ON 8'-0" CENTERS REINFORCE WITH 1 1/2"x1 1/2"x1/8" ANGLES ON 4'-0" CENTERS.
OVER 96"	18	16(0.051") (LONGITUDINAL SEAM MAY BE STANDING SEAM)	PITTSBURGH LOCK	2" COMPANION ANGLE, OR 2"x2"x1/4" ANGLE SLIP, OR 2"x2"x1/4" ANGLE REINFORCED POCKET LOCK OR REINFORCED BAR SLIP	2" COMPANION ANGLE, OR 2"x2"x1/4" ANGLE SLIP, OR 2"x2"x1/4" ANGLE REINFORCED POCKET LOCK OR REINFORCED BAR SLIP	REINFORCE ALL SIDES OVER 96" WITH 2"x2"x1/4" ANGLES ON 2'-0" CENTERS. REINFORCE ALL SIDES 85" THRU 96" WITH 1 1/2"x1 1/2"x3/16" ANGLES ON 2'-0" CENTERS. SIDES 80" OR LESS NEED NO REINFORCING IF JOINTS ARE ON 4'-0" CENTERS. IF JOINTS ARE ON 8'-0" CENTERS REINFORCE WITH 1 1/2"x1 1/2"x1/8" ANGLES ON 4'-0" CENTERS.



- NOTE:
- ALL VANED ELBOWS SHALL BE CONSTRUCTED AND INSTALLED AS DETAILED BY SMACNA.
 - WHEN W1 IS NOT EQUAL TO W2, VANE SHALL BE SINGLE VANE TYPE REGARDLESS OF W DIMENSION.
 - ALL SINGLE VANES SHALL HAVE A 2" RADIUS, 1-1/2" MAXIMUM SPACE BETWEEN VANES AND A 3/4" TRAILING EDGE.
 - WHEN W EQUALS W2 AND W1 IS GREATER THAN 20" VANES SHALL BE DOUBLE VANE TYPE.


2 Ductwork Squared Elbow Detail

M101 N.T.S.



4 Typical Branch Take-Off Fitting Detail


M101 N.T.S.



- NOTE:
- DELETE INSULATION STAND-OFF ON DUCTWORK WITHOUT EXTERIOR INSULATION.
 - DETAIL SHOWS SINGLE-BLADE DAMPER. DAMPER INSTALLATION SHALL BE SIMILAR FOR MULTI-BLADE DAMPERS & ROUND DAMPERS.

6 Ductwork Volume Damper Detail


M101 N.T.S.



- NOTE:
- AT FIRE RATED PARTITIONS, ADD ADDITIONAL LAYER OF FIRE SAFING INSULATION AROUND PENETRATION SO AS TO FILL CAVITY.
 - DUCT AND PIPE PENETRATIONS THRU CORRIDOR WALLS ABOVE THE CEILING ARE TO BE FIRE STOPPED AROUND THE PENETRATION.

3 Pipe Penetrations Detail


M101 N.T.S.



- NOTE:
- THE INTERIOR SURFACE OF ALL RADIUS ELBOWS SHALL BE MADE ROUND.
 - ALL STANDARD RADIUS ELBOWS CAN BE SUBSTITUTED WITH SHORT RADIUS ELBOWS. ALL SHORT RADIUS ELBOWS SHALL HAVE VANES. VANES SHALL BE CONSTRUCTED, SUPPORTED AND FASTENED AS RECOMMENDED BY SMACNA.

5 Ductwork Radius Elbow Detail


M101 N.T.S.



- NOTE:
- UNLESS OTHERWISE INDICATED ON PLANS, MAXIMUM ANGLES SHOWN SHALL APPLY.

7 Ductwork Transition Detail

M101 N.T.S.




- NOTES:
- PIPE 8" AND LARGER SHALL HAVE ROLLER SUPPORTED WITH DUAL RODS.
 - FOR CHW SERVICE OVER 3' REPLACE SADDLE WITH 12" LONG 14 GA SHIELD WITH RIGID INSULATION BETWEEN PIPE AND SHIELD.

PIPE Ø (IN.)	MAX. SPACING BETWEEN HANGERS (FT.)			MIN. ROD SIZE (IN.)
	STEEL PIPE	COPPER PIPE	CPVC	
1/2 THRU 1	7	5	5	3/8
1-1/2 THRU 2	9	8	6	3/8
2-1/2	11	9	7.5	1/2
3	12	10	7.5	1/2
4	14	12	8.5	5/8
6	17	14	9	3/4
8	19	16	10	7/8
10	22	18	10.5	7/8

1 Pipe Hanger Support

M101 N.T.S.

Mechanical Legend :




Mechanical Notes:

- ALL MATERIALS AND EQUIPMENT ARE TO BE NEW, UNUSED, AND FREE FROM DEFECTS OF ANY KIND. THE BASIS OF QUALITY SHALL BE THE LATEST REVISION OF ASTM, ANSI, OR OTHER ACCEPTABLE STANDARDS.
- THESE DRAWINGS ARE DIAGRAMMATIC, AND INDICATE GENERAL ARRANGEMENT OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE REVIEWED THE SITE FOR HIS WORK PRIOR TO HAVING SUBMITTED HIS PROPOSAL. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR CONDITIONS FOUND DURING THE COURSE OF THE CONTRACT.
- THE CONTRACTOR SHALL COORDINATE HIS WORK WITH THAT OF ALL OTHER TRADES.
- ALL WORK INCLUDING LABOR AND MATERIALS SHALL BE FULLY GUARANTEED FOR ONE (1) YEAR FROM THE DATE OF PAYMENT AND FINAL ACCEPTANCE BY THE OWNER AND ENGINEER.
- ALL CUTTING, PATCHING, FIRE-STOPPING, AND SURFACE RESTORATION IN CONNECTION WITH THIS TRADE SHALL BE COMPLETED BY THIS CONTRACTOR.
- A MINIMUM OF FOUR (4) COPIES OF SHOP DRAWINGS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL PRIOR TO ORDERING AND INSTALLATION OF THE EQUIPMENT AND/OR MATERIALS. BY SUBMITTING SHOP DRAWINGS, THE CONTRACTOR REPRESENTS THAT ACTUAL FIELD CONDITIONS ARE VERIFIED BY HIM AND ARE REFLECTED ON HIS SUBMITTALS.
- THIS CONTRACTOR SHALL PAY ALL FEES, GIVE ALL NOTICES, FILE ALL NECESSARY DRAWINGS, AND OBTAIN ALL PERMITS, INSPECTIONS AND CERTIFICATES OF APPROVAL REQUIRED IN CONNECTION WITH WORK UNDER THIS CONTRACT.
- ALL WORK IN ASSOCIATION WITH THIS CONTRACT SHALL BE COMPLETED IN STRICT COMPLIANCE WITH THE 2020 BUILDING CODE OF NEW YORK STATE, 2020 MECHANICAL CODE OF NEW YORK STATE & 2020 ENERGY CONSERVATION CONSTRUCTION CODE OF NEW YORK STATE.
- ALL HYDRONIC HOT WATER PIPING AND FITTINGS ARE TO BE INSULATED WITH A MINIMUM OF R-5 INSULATION. ALL JOINTS ARE TO BE COMPLETELY SEALED A MINIMUM OF 6" BEYOND JOINT ENDS.
- ALL PIPING SHALL BE PROPERLY SUPPORTED AND ROUTED PARALLEL OR PERPENDICULAR TO BUILDING WALLS. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL SUPPORT HANGERS AND MISCELLANEOUS METALS REQUIRED FOR PROPER INSTALLATION OF WORK.
- ALL PIPING SHALL BE PITCHED SUCH THAT AIR IN THE SYSTEM CAN BE VENTED THROUGH MANUAL AIR VENTS.
- TEST PIPING AND PROVE TIGHT FOR AT LEAST TWO HOURS TO TWICE THE SYSTEM WORKING PRESSURE. TEST SHALL BE PERFORMED IN THE PRESENCE OF THE ENGINEER AND LOCAL INSPECTOR. TEST SHALL BE REPEATED IF NECESSARY UNTIL FINAL APPROVAL OF SYSTEM IS OBTAINED.
- SUPPORT HORIZONTAL PIPING UTILIZING A SPACING PER PIPING MANUFACTURER'S REQUIREMENTS.
- INSTALL VALVES ON THE ENTIRE DISTRIBUTION SYSTEM, SO LOCATED AS TO GIVE COMPLETE CONTROL TO ALL FIXTURES AND EQUIPMENT.
- INSTALL DRAIN VALVES AT BASE OF ALL RISERS AND AT LOW POINTS OF PIPING SYSTEM. INSTALL MANUAL AIR VENT VALVE FACILITIES AT THE TOP OF ALL RISERS AND AT HIGH POINTS OF THE PIPING SYSTEM.
- INSTALL ALL HYDRONIC PIPING AS HIGH AS POSSIBLE PROVIDING RISERS, DROPS AND OFFSETS TO CLEAR STRUCTURAL MEMBERS, LIGHT FIXTURES, OTHER PIPING, AND OTHER OBSTRUCTIONS. WHERE CONFLICTS ARISE, IT SHALL BE BROUGHT TO THE ENGINEER'S ATTENTION PRIOR TO PROCEEDING.
- THE ENTIRE HYDRONIC SYSTEM IS TO BE BALANCED TO WITHIN 10% OF THE SPECIFIED WATER FLOWRATE REQUIREMENTS. A CERTIFIED BALANCING REPORT AND VERIFICATION IS TO BE SUBMITTED TO THE ENGINEER PRIOR TO FINAL ACCEPTANCE.
- ALL DUCTWORK IS TO BE CONSTRUCTED OF GALVANIZED SHEET STEEL (EXCEPT WHERE OTHERWISE SPECIFIED) WITH GAUGES, BRACING AND CONSTRUCTION IN ACCORDANCE WITH THE LATEST SMACNA DUCT MANUAL STANDARDS AND ALL OTHER AUTHORITIES HAVING JURISDICTION.
- PROVIDE MANUAL DAMPERS AT EACH SPLIT OR TAP CONNECTION TO TRUNK DUCTS FOR BALANCING PURPOSES WHETHER OR NOT SPECIFICALLY SHOWN ON DRAWINGS. EACH DAMPER SHALL BE OF THE OPPOSED BLADE DAMPER TYPE INSTALLED WITH AN OPERATOR AND LOCKING DEVICE. ALL DAMPERS LOCATED ABOVE HARD OR INACCESSIBLE CEILINGS SHALL BE INSTALLED WITH REMOTE GEAR OPERATORS.
- FURNISH & INSTALL FUSIBLE LINK FIRE DAMPERS AT ALL LOCATIONS WHERE DUCT PENETRATES FIRE-RATED FLOOR OR CEILING ASSEMBLY WHETHER OR NOT SPECIFICALLY SHOWN. INSTALL DUCTWORK CASING ACCESS DOORS AND FRAMES AHEAD OF EACH FIRE DAMPER FOR INSPECTION AND MAINTENANCE. DOORS SHALL BE A MINIMUM OF 20 GA. DOUBLE PANEL INSULATED TYPE.
- INSTALL TURNING VANES ON ALL RECTANGULAR TURNS. TURNING VANES SHALL BE DOUBLE THICKNESS TYPE CONSTRUCTED IN ACCORDANCE WITH SMACNA MANUAL.
- ROUND SHEET STEEL ELBOWS ARE TO BE INSTALLED AT THE DUCT CONNECTION TO ALL SUPPLY AIR DIFFUSERS. SHEET STEEL PLENUM BOXES ARE TO BE INSTALLED AT THE DUCT CONNECTION TO ALL RETURN AND EXHAUST AIR GRILLES. THE CONTRACTOR IS TO PAINT THE INSIDE OF THE SHEET STEEL PLENUM BOXES FLAT BLACK.
- ALL SUPPLY AND RETURN DUCTWORK LOCATED IN UNCONDITIONED SPACES OR ABOVE CEILINGS SHALL BE INSULATED WITH A MINIMUM OF R-5 INSULATION. ALL DUCTWORK LOCATED OUTSIDE THE BUILDING ENVELOPE SHALL BE INSULATED WITH A MINIMUM OF R-8 INSULATION. INSULATION SHALL BE FIBERGLASS DUCT WRAP WITH VAPOR SEAL SECURELY TAPED AROUND DUCT. IF DUCT LINING IS TO BE USED, ALL DUCT SIZES SHOWN SHALL BE CONSIDERED TO BE INSIDE CLEAR DIMENSIONS.
- INSTALL ALL DUCTWORK AS HIGH AS POSSIBLE PROVIDING RISERS, DROPS AND OFFSETS TO CLEAR STRUCTURAL MEMBERS, LIGHT FIXTURES, OTHER PIPING, AND OTHER OBSTRUCTIONS. WHERE CONFLICTS ARISE, IT SHALL BE BROUGHT TO THE ENGINEER'S ATTENTION PRIOR TO PROCEEDING.
- THE ENTIRE AIR DISTRIBUTION SYSTEM IS TO BE BALANCED TO WITHIN 10% OF THE SPECIFIED AIRFLOW REQUIREMENTS.
- THE CONTRACTOR IS RESPONSIBLE TO TEST ALL EQUIPMENT, PIPING, FIXTURES, AND SYSTEMS INSTALLED UNDER THIS CONTRACT TO ENSURE PROPER OPERATION PRIOR TO FINAL ACCEPTANCE BY THE OWNER AND ENGINEER.
- THE CONTRACTOR IS RESPONSIBLE TO DETERMINE WHETHER SPECIAL LICENSING IS REQUIRED IN ORDER TO PERFORM THE REQUIRED WORK IN THE MUNICIPALITY WHERE THE PROJECT IS LOCATED. IF THE CONTRACTOR CANNOT OBTAIN THE REQUIRED LICENSING TO COMPLETE THE WORK WITHIN THE PROJECT SCHEDULE, THEN THE CONTRACTOR SHALL NOT BE PERMITTED TO BID ON THIS PROJECT.
- CONTRACTOR IS RESPONSIBLE TO CREATE AND SUBMIT RED-LINE "AS-BUILT" PLANS TO THE ENGINEER AT THE END OF THE PROJECT. AS-BUILT PLANS SHALL ACCURATELY REPRESENT THE SYSTEMS AS THEY WERE INSTALLED.

Mechanical Equipment:

- R PROGRAMMABLE THERMOSTAT TYPICAL OF WATTS RADIANT THERMOSTAT MODEL 519; PROVIDE W/ SLAB SENSOR 079; MTD. @ 5'-0" A.F.F.
- H PROGRAMMABLE THERMOSTAT TYPICAL OF HONEYWELL MODEL TH4321R1001; 7 DAY PROGRAMMABLE; MTD. @ 5'-0" A.F.F.




8 Coil Piping Connection Detail

M101 Scale: None

19 Front St., Newburgh, New York 12550-7601
845-551-3179 www.csarch.com

CSARCH



Constant

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Project Title



DATE	DESCRIPTION

Drawn By: BK
Checked By: BK
Proj. #: 59-09-01-06-3-016-001
CSArch Proj. #: 203-2001
Construction Documents: 12/13/22

Sheet Title

MECHANICAL
NOTES, LEGEND,
SCHEDULE &
DETAILS

Sheet No.

MB
M101

CONSTRUCTION DOCUMENTS

ENERGY RECOVERY VENTILATOR SCHEDULE																													
EQUIPMENT TAG	MANUFACTURER (OR ACCEPT. EQUAL)	MODEL	FRESH AIR FLOW RATE (CFM)	EXHAUST AIR FLOW RATE (CFM)	ROOM EXH. AIR (°F)				OUTSIDE AIR (°F)				SUPPLY AIR (°F)				RECOVERY EFFECTIVENESS				ELECTRICAL DATA						WEIGHT (LB)	NOTES	
					WINTER		SUMMER		WINTER		SUMMER		WINTER		SUMMER		SENSIBLE		TOTAL		MOTOR		VOLT.	PHASE	Hz.	MCA			MOCP
					DB	WB	DB	WB	DB	WB	DB	WB	DB	WB	DB	WB	DB	WB	WINTER	SUMMER	WINTER	SUMMER							
ERV-1	RENEWAIRE	HE15XINH	650	650	70	25	75	50	0.0	-1.5	86	71	53.9	41.6	77.5	65.4	77.2%	77.2%	75.9%	62.7%	1	4.4 x 2	208	1	60	9.9	15	504	FURNISH W/ MERV 3 FILTERS, 12" BACKDRAFT DAMPERS, LOUVERED WALL VENTS, DIGITAL TIME CLOCK & 4 k w ELECTRIC DUCT HEATER (208V, 3 PH., SCR, 12"x12")

AIR GRILLE/DIFFUSER SCHEDULE													
EQUIPMENT TAG	MANUFACTURER (OR ACCEPT. EQUAL)	MODEL	AIR DEVICE TYPE	AIRFLOW (CFM)		MAX AIR PRESS. DROP (IN. W.C.)	MOUNTING	PANEL/FRAME SIZE	NECK SIZE (IN.)	MAX NC	DAMPER	FINISH	NOTES
				MIN.	MAX.								
D-1	KRUEGER	PLQ-6-F22-12x12-00-00-44	SQUARE PLAUQUE FACE DIFFUSER	50	175	0.10	SURFACE MOUNT	12"x12"	6"Ø	20	OBD	WHITE	-
D-2	KRUEGER	5DMGDR-H-10-6-10-01-81	DUCT MOUNTED SUPPLY GRILLE	0	200	0.10	DUCT MTD.	12"x8"	10"x6"	20	OBD	CLEAR ANOD.	-
EG-1	KRUEGER	S80H-6x6-F22-NONE-00-00-00-44	35° DEFLECTION RETURN GRILLE	0	125	0.08	SURFACE MTD.	8"x8"	6"x6"	20	-	WHITE	FURNISH & INSTALL FULL-SIZE INSULATED SHEET METAL BOX ON REAR OF GRILLE, PAINT INSIDE OF BOX FLAT BLACK
EG-2	KRUEGER	5DMGPR-H-10-6-10-01-81	DUCT MOUNTED EXHAUST GRILLE	0	200	0.10	DUCT MTD.	12"x8"	10"x6"	20	OBD	CLEAR ANOD.	-

LOUVER SCHEDULE														
EQUIPMENT TAG	QTY.	MANUFACTURER (OR ACCEPT. EQUAL)	MODEL	AIR DEVICE TYPE	LOUVER SIZE			FREE AREA (SQ. FT.)	AIRFLOW (CFM)	VELOCITY (FT./MIN.)	MOUNTING	SCREEN	FINISH	NOTES
					WIDE	HIGH	DEPTH							
SL-1	1	RUSKIN	ELF6875DAX	STATIONARY LOUVER	36"	30"	6"	3.17	2,000	630.9	METAL WALL	YES	TBD	1, 2, & 3
CL-1	1	RUSKIN	ELC6875DAX	COMBINATION LOUVER	36"	30"	6"	3.17	2,000	630.9	METAL WALL	YES	TBD	1, 2, 3 & 4

1. COLOR TO BE COORDINATED WITH OWNER BEFORE ORDERING
2. FURNISH WITH INSECT-SCREEN OPTION.

3. FURNISH W/ PROPER MOUNTING HARDWARE.
4. FURNISH W/ 120VAC ACTUATOR.

EXHAUST FAN SCHEDULE											
EQUIPMENT TAG	MANUFACTURER	MODEL	SERVICE	FAN C.F.M.	R.P.M.	EXTERNAL STATIC PRESSURE INCH H ₂ O	MOTOR				REMARKS
							POWER	VOLT.	PHASE	HZ.	
EF-1	LOREN COOK	150SQ17D	GARAGE EXHAUST	2,000	1,298	0.30	1.0 HP	208	3	60	FURNISH W/ BACKDRAFT DAMPER & VFD

VENTILATION SCHEDULE													
SYSTEM	SPACE SERVED	SPACE TYPE	SPACE AREA (SQ. FT.)	OCCUPANTS PER 1000 SQ. FT.	# OF OCCUPANTS (NOTE 1)	CFM PER PERSON	CFM PER SQ. FT.	CALCULATED VENTILATION RATE (CFM)	PROVIDED VENTILATION RATE (CFM)	EA CFM PER FIXTURE	EA CFM PER SQ. FT.	MIN. EA RATE (CFM)	EA PROVIDED (CFM)
ERV-1	BAY 1-3	STORAGE/ GARAGE	1,885	-	-	-	0.12	226.2	250	-	0.75	1413.8	1450
	BAY 4	STORAGE/ GARAGE	710	-	-	-	0.12	85.2	100	-	0.75	532.5	550
	TOILET T1	BATHROOM	85	-	-	-	-	-	75	75	-	75	75
	TOILET T2	BATHROOM	65	-	-	-	-	-	75	75	-	75	75
	TOILET T3	BATHROOM	65	-	-	-	-	-	75	75	-	75	75
	TOILET 101A	BATHROOM	85	-	-	-	-	-	75	75	-	75	75

GAS UNIT HEATER SCHEDULE																NOTES	
EQUIPMENT TAG	MANUFACTURER (OR ACCEPT. EQUAL)	MODEL	AREA OF BUILDING SERVED	TOTAL AIRFLOW (CFM)	HEATING CAPACITY					ELECTRICAL DATA							TOTAL WEIGHT (LB)
					GAS INPUT (MBH)	OUTPUT (MBH)	E.A.T. Db (°F)	L.A.T. Db (°F)	AFUE (%)	BLOWER FAN MOTOR HP	UNIT POWER CONNECTION						
											VOLT.	PHASE	Hc	FLA	MOCp		
UH-1	REZNOR	UBZ60	BAYS	1012	60.0	49.2	50.0	125.0	82	1/3	120	1	60	7.1	15	103	FURNISH W/ HEATING THERMOSTAT & PROPANE CONVERSION KIT; MOUNT UNIT @ 10'-0" A.F.F.

HOT WATER UNIT HEATER SCHEDULE																	
EQUIPMENT TAG	MANUFACTURER (OR ACCEPT. EQUAL)	MODEL	AIRFLOW (CFM)	EFT (°F)	LFT (°F)	CAPACITY (MBH)	E.A.T. DB (°F)	L.A.T. DB (°F)	FPD (FT)	FLOW RATE (GPM)	MOTOR						NOTES
											NOM. H.P.	VOLT.	PHASE	HZ	RPM	FLA	
UH-2	STERLING	HS-60	900	160	140	31.2	60	105	0.17	4.4	1/20	120	1	60	-	1.4	PROPERLY SUPPORT FROM STRUCTURE ABOVE; PROVIDE W/ CONTROL TRANSFORMER, FAN GUARD & DISCONNECT SWITCH

HOT WATER PUMP SCHEDULE																
EQUIPMENT TAG	MANUFACTURER (OR ACCEPT. EQUAL)	MODEL	LOCATION	AREA SERVED	PUMP TYPE	CIRCULATING FLUID				MOTOR					NOTES	
						FLUID	G.P.M.	HEAD (FT.)	TEMP. (°F)	NOM. H.P.	VOLT.	PHASE	HZ.	RPM		FLA
CP-1	GRUNDFOS	UPMXL	MECHANICAL ROOM	BOILER PUMP	IN-LINE	HOT WATER	14.7	15.0	160	-	120	1	60	1160	1.4	FURNISHED W/ BOILER
CP-2	GRUNDFOS	UPMXL	MECHANICAL ROOM	BOILER PUMP	IN-LINE	HOT WATER	14.7	15.0	160	-	120	1	60	1160	1.4	FURNISHED W/ BOILER
CP-3	GRUNDFOS	MAGNA3 32-60F	MECHANICAL ROOM	UNIT HEATERS	IN-LINE	HOT WATER	13.2	18.0	160	-	120	1	60	VARI.	1.0	VARIABLE SPEED ECM
CP-4	GRUNDFOS	MAGNA3 32-60F	MECHANICAL ROOM	INJECTION PUMP	IN-LINE	HOT WATER	3.8	5.0	160	-	120	1	60	VARI.	1.0	VARIABLE SPEED ECM
CP-5	GRUNDFOS	ALPHA1 26-99F	MECHANICAL ROOM	RADIANT ZONE RM-1	IN-LINE	HOT WATER	1.0	3.1	125	-	120	1	60	VARI.	1.7	VARIABLE SPEED ECM
CP-6	GRUNDFOS	MAGNA3 32-60F	MECHANICAL ROOM	RADIANT ZONE RM-2	IN-LINE	HOT WATER	5.5	6.2	125	-	120	1	60	VARI.	1.0	VARIABLE SPEED ECM
CP-7	GRUNDFOS	ALPHA1 15-55FR	MECHANICAL ROOM	RADIANT ZONE RM-3	IN-LINE	HOT WATER	2.1	5.6	125	-	120	1	60	VARI.	0.65	VARIABLE SPEED ECM

CONDENSING BOILER SCHEDULE									
EQUIPMENT TAG	MANUFACTURER	MODEL	INPUT (MBH)		THERMAL EFFICIENCY	OUTPUT (MBH)	NET AHRI RATING (MBH)	TURNDOWN RATIO	REMARKS
			MIN.	MAX.					
CB-1 & CB-2	LOCHINVAR	WHB155N	15.5	155	95%	144	125	10:1	FURNISH W/ ADD'L HIGH LIMIT & LOW WATER CUTOFF



N.T.S.

MAINTENANCE BUILDING

[illegible]

Drawn By:	
Checked By:	
Proj. #:	59-09-01-06-3-0
Arch Proj. #:	20
Construction Documents:	12


Sheet Title

MECHANICAL
PLAN


Sheet No. _____

MB
M201


CONSTRUCTION DOCUMENT



1 Mechanical Plan
M201 Scale: 1/4" = 1'-0"



1 Radiant Heating Plan
M201 Scale: 1/4" = 1'-0"




2 Hydronic Plan
M201 Scale: 1/4" = 1'-0"

Infloor Radiant Heating Notes:

1. RADIANT FLOOR TUBING LAYOUT IS PROVIDED FOR BIDDING PURPOSES & BASIS OF DESIGN ONLY. CONTRACTOR IS REQUIRED TO PROVIDE DETAILED SHOP DRAWING OF RADIANT FLOOR LAYOUT TO THE ENGINEER FOR REVIEW.
2. ALL TUBING IS TO BE TYPICAL OF WATTS RADIANTPEX+ BARRIER TUBING OR ACCEPTABLE EQUAL. ALL TUBING IS TO BE 5/8" IN SIZE.
3. ALL RADIANT MANIFOLD SETS ARE TO BE TYPICAL OF WATTS STAINLESS MANIFOLDS W/ SHUT OFF, BALANCING VALVES & FLOW METERS FOR EACH CIRCUIT.
4. EACH CIRCUIT SERVING INDIVIDUAL ROOMS IS TO BE EQUIPPED WITH A 24V POWERHEAD FOR ADDITIONAL ZONE CONTROL. FURNISH & INSTALL A HEATING THERMOSTAT TYPICAL OF WATTS DIGITAL THERMOSTAT OR ACCEPTABLE EQUAL IN EACH ROOM TO CONTROL THE INDIVIDUAL POWERHEADS. FURNISH THERMOSTAT WITH SLAB TEMPERATURE SENSOR.
5. MECHANICAL CONTRACTOR IS TO FURNISH & INSTALL UNDER-CONCRETE INSULATION UNDER THE ENTIRE RADIANT FLOORING SYSTEM. UNDERSLAB INSULATION SHALL HAVE A MINIMUM RATING OF R-10. SUBMIT PRODUCT DATA TO ENGINEER & ARCHITECT FOR DESIGN CONFORMANCE REVIEW PRIOR TO ANY WORK. PROPERLY OVERLAP & SEAL ALL JOINTS PER MANUFACTURER'S REQUIREMENTS. COORDINATE INSTALLATION W/ GENERAL CONSTRUCTION CONTRACTOR.
6. PROPERLY SECURE ALL RADIANT TUBING TO THE WELDED WIRE MESH OR REBAR IN CONCRETE FLOOR.
7. RIGID PVC TUBING ELBOWS TO BE USED AS SLEEVES FOR THE PEX TUBING WHEREVER IT PENETRATES THE CONCRETE FLOOR.
8. MECHANICAL CONTRACTOR IS TO PRESSURE TEST THE ENTIRE SYSTEM WITH AIR TO 1.5 TIMES OPERATING PRESSURE, AND THE SYSTEM IS TO REMAIN PRESSURIZED DURING THE CONCRETE POUR.
9. MECHANICAL CONTRACTOR IS TO COORDINATE THE ROUTING OF ALL RADIANT TUBING WITH THE GENERAL CONSTRUCTION CONTRACTOR TO ENSURE THAT THE TUBING DOES NOT INCUR DAMAGE DURING THE INSTALLATION OF THE WALL FRAMING.

ADD ALTERNATE
NO. 02-001

ADD ALTERNATE
NO. 02-001




DATE	DESCRIPTION

Drawn By: BJK
Checked By: BJK
Proj. #: 59-09-01-06-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

LIGHTING FIXTURE SCHEDULE										
TAG	SYMBOL	MANUFACTURER & MODEL	TYPE	VOLTAGE	# OF LAMPS	LAMP WATTS	FIXTURE WATTS	MOUNTING	SIZE	NOTES
A		HE WILLIAMS HIGH BAY LED GLN-4-L150/84-DRV-UNV	LED	120	1	101.2	101.2	SUSPENDED	48"x8 1/2"	4000K COLOR TEMPERATURE; FURNISH W/ CABLE SUSPENSION KIT; SUSPEND 18'-6" A.F.F.
B		HE WILLIAMS HIGH BAY LED GLN-4-L63/84-DRV-UNV	LED	120	1	42.3	42.3	SUSPENDED	48"x8 1/2"	4000K COLOR TEMPERATURE; FURNISH W/ CABLE SUSPENSION KIT; SUSPEND 8'-6" ABOVE MEZZ. FLOOR
C		HE WILLIAMS LED WRAP 17-4-L55/840-AF-DRV-UNV	LED	120	1	42.3	42.3	SURFACE MTD.	48"x10 1/2"	4000K COLOR TEMPERATURE
D		HE WILLIAMS LED WALLPACK WPCL-L44/840-SZ-PC-DIM-UNV	LED	120	1	42	42	SURFACE MTD.	8 1/2"x5 1/2"x11"	4000K COLOR TEMP; MOUNT 15'-6" A.F.G.
F		HUBBELL LIGHTING LED EMERGENCY WALL PACK CUSO4DB-H-ND	LED	120	1	3.4	3.4	SURFACE MTD.	-9"x6"x3"	4000K COLOR TEMP.; FURNISH W/ PHOTO- SENSOR, HEATER & EMERGENCY BATTERY; MOUNT 8'-6" A.F.G.
-		HE WILLIAMS LED EMERGENCY LIGHT EMER/LED-WHT-SOT-D	LED	120	2	1.0	2.0	UNIVERSAL	-	90-MINUTE BATTERY BACKUP
-		HE WILLIAMS LED EXIT & EMERGENCY LIGHT EXIT/EM/LED-R-WHT-RC-SOT-D	LED	120	2	3	6	UNIVERSAL	-	90-MINUTE BATTERY BACKUP; PROVIDE W/ REMOTE HEAD MODEL WETRL-T-WHT-HL-MV

2
E101
Typical Conduit Trench Detail
N.T.S.




120/208V 3Ø 4W+G, 22 kA/C										
BUS RATING: 225A										
225A MAIN CIRCUIT BREAKER										
CONNECTED LOAD	CONDUCTORS	CBT BREAKER AMPS	POSITION	L1 KVA	L2 KVA	L3 KVA	POSITION	CBT BREAKER AMPS	CONDUCTORS	CONNECTED LOAD
ERV	(2) #12 CU & (1) #12 GND.	15	1	1.03	0.98	0.98	2	15	(2) #12 CU & (1) #12 GND.	EF-1
WATER HEATER	(2) #12 CU & (1) #12 GND.	20	5	0.50	0.50	0.50	6	20	(2) #12 CU & (1) #12 GND.	
OVERHEAD DOOR	(2) #12 CU & (1) #12 GND.	15	7	0.50	0.50	0.50	8	15	(2) #12 CU & (1) #12 GND.	OVERHEAD DOOR
OVERHEAD DOOR	(2) #12 CU & (1) #12 GND.	15	9	0.50	0.50	0.50	10	15	(2) #12 CU & (1) #12 GND.	OVERHEAD DOOR
BOILER CB-1	(2) #12 CU & (1) #12 GND.	20	11	0.50	0.50	0.50	12	20	(2) #12 CU & (1) #12 GND.	BOILER CB-2
MIXING STATION	(2) #12 CU & (1) #12 GND.	20	13	0.50	0.50	0.50	14	20	(2) #12 CU & (1) #12 GND.	HVAC CTRLS & PUMPS
GAS DETECTION SYSTEM	(2) #12 CU & (1) #12 GND.	15	15	0.18	0.17	0.17	16	15	(2) #12 CU & (1) #12 GND.	LIGHTS
LIGHTS	(2) #12 CU & (1) #12 GND.	20	17	0.91	0.91	0.91	18	20	(2) #12 CU & (1) #12 GND.	RECEPTACLES
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	19	0.36	0.36	0.36	20	20	(2) #12 CU & (1) #12 GND.	RECEPTACLES
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	21	0.36	0.36	0.36	21	20	(2) #12 CU & (1) #12 GND.	RECEPTACLES
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	23	0.54	0.54	0.54	22	20	(2) #12 CU & (1) #12 GND.	RECEPTACLES
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	25	0.18	0.18	0.18	23	20	(2) #12 CU & (1) #12 GND.	RECEPTACLES
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	27	0.92	0.92	0.92	24	20	(2) #12 CU & (1) #12 GND.	UNIT HEATER
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	29	1.33	1.33	1.33	25	20	(2) #12 CU & (1) #12 GND.	UNIT HEATER
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	31	0.54	0.54	0.54	26	20	(2) #12 CU & (1) #12 GND.	ELECTRIC WALL HEATER
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	33	0.18	0.18	0.18	27	20	(2) #12 CU & (1) #12 GND.	ELECTRIC WALL HEATER
RECEPTACLES	(2) #12 CU & (1) #12 GND.	20	35	0.92	0.92	0.92	28	20	(2) #12 CU & (1) #12 GND.	ELECTRIC DUCT HEATER
UNIT HEATER	(2) #12 CU & (1) #12 GND.	15	37	1.33	1.33	1.33	29	15	(3) #12 CU & (1) #12 GND.	
ELECTRIC WALL HEATER	(2) #12 CU & (1) #12 GND.	20	39	0.54	0.54	0.54	30	20		
ELECTRIC WALL HEATER	(2) #12 CU & (1) #12 GND.	20	41	0.18	0.18	0.18	31	20		
ELECTRIC DUCT HEATER	(3) #12 CU & (1) #12 GND.	15	43	0.92	0.92	0.92	32	15		
SPARE	-	20	45	1.33	1.33	1.33	33	20		
SPARE	-	20	47	0.54	0.54	0.54	34	20		
SPARE	-	20	49	0.18	0.18	0.18	35	20		
SPARE	-	20	51	0.92	0.92	0.92	36	20		
SPARE	-	20	53	1.33	1.33	1.33	37	20		
SQUARE 'D' NQ PANELBOARD W/ BOLT ON BREAKERS				6.75	10.24	10.48	29.48 KVA TOTAL			

1
E101
New Panelboard PP-1
Scale: None



4
E101
Heating System Control Schematic
Scale: None



5
E101
Radiant Loop Actuator Control Schematic
Scale: None

ELECTRICAL LEGEND:

- MOTOR
- EARTH GROUND
- JUNCTION BOX
- PULL BOX
- FUSE WITH RATING
- MOLDED CASE CIRCUIT BREAKER
- DISCONNECT SWITCH, FUSED
- DISCONNECT SWITCH, UNFUSED
- STARTER, COMBINATION WITH DISCONNECT SWITCH
- STARTER OR MOTOR CONTROLLER
- METER
- 20A 120V DUPLEX CEILING MOUNTED RECEPTACLE
- 20A 120V DUPLEX WALL MOUNTED RECEPTACLE; 18" A.F.F. UNLESS OTHERWISE NOTED
- 20A 120V DUPLEX WALL MOUNTED RECEPTACLE WITH GROUND FAULT CIRCUIT INTERRUPTER
- 20A 120V QUADRAPLEX RECEPTACLE
- WALL MOUNTED SPECIAL PURPOSE RECEPTACLE
- 20A 120V WALL MOUNTED USB CHARGER RECEPTACLE TYPICAL OF HUBBELL USB20X OR ACCEPTABLE EQUAL
- FLOOR BOX WITH STAINLESS COVER TYPICAL OF LEW ELECTRIC #WB-1-SP OR ACCEPTABLE EQUAL. PUSH BUTTON OPEN; FULLY IP66 RATED WATER PROOF (WHEN IN CLOSED POSITION); W/ 20A 125V E01020 GFCI RECEPTACLE (UNLESS OTHERWISE NOTED)
- WALL PHONE OUTLET MTD. 48" A.F.F.; 3/4" EMT CDT. IN WALL TO ABOVE CEILING W/ PULL CORD
- WALL BOX FOR TELEVISION CONNECTION; 1-1/4" EMT CDT. IN WALL TO ABOVE CEILING W/ PULL CORD
- TELEPHONE/DATA COMMUNICATION BOX W/ (2) 3/4" EMT CDT. IN WALL TO ABOVE CEILING W/ PULL CORD; NO FACE PLATE
- BRANCH CIRCUIT HOMERUN: LINES INDICATE NUMBER OF CIRCUITS, NEUTRAL, AND SWITCH LEG CONDUCTORS; ONE SEPARATE GROUNDING CONDUCTOR SHALL BE PROVIDED FOR EACH HOMERUN; NOT SHOWN
- SWITCH
BLANK = SINGLE POLE
3 = THREE-WAY
D = DIMMER
P = WITH PILOT LIGHT
T = TIMER OPERATED
X = EXPLOSION PROOF
- 2 = DOUBLE POLE
4 = FOUR-WAY
K = KEY OPERATED
PB = PUSH BUTTON
WP = WEATHER PROOF
OC = OCCUPANCY SENSOR
- DUAL TECHNOLOGY OCCUPANCY SENSOR
- DAYLIGHT SENSOR
- HORN/STROBE DEVICE, ONE ASSEMBLY; MTD. 80" A.F.F. UNLESS OTHERWISE NOTED; 15 CANDELA UNLESS OTHERWISE NOTED
- STROBE DEVICE, MTD. 80" A.F.F. UNLESS OTHERWISE NOTED; 15 CANDELA UNLESS OTHERWISE NOTED
- MANUAL PULL STATION; MTD. 48" A.F.F.
- WATER FLOW SWITCH
- VALVE TAMPER SWITCH
- DETECTOR: LETTER INDICATES AS FOLLOWS:
BLANK = SMOKE DETECTOR
P = PHOTOELECTRIC SMOKE
M = MULTIPLE STATION SMOKE ALARM
D = PHOTOELECTRIC DUCT SMOKE DETECTOR
FSD = DUCT SMOKE DETECTOR FOR FIRE SMOKE DAMPER
- RATE OF RISE HEAT DETECTOR, 135°F
- CARBON MONOXIDE DETECTOR
- ADDRESSABLE FIRE ALARM CONTROL PANEL
- FIRE ALARM ANNUNCIATOR PANEL
- REMOTE TEST SWITCH & LED FOR DUCT SMOKE DETECTORS
- FIRE ALARM RELAY

ELECTRICAL NOTES:

- ALL MATERIALS AND EQUIPMENT ARE TO BE NEW, UNUSED, AND FREE FROM DEFECTS OF ANY KIND. THE BASIS OF QUALITY SHALL BE THE LATEST REVISION OF ASTM, ANSI, OR OTHER ACCEPTABLE STANDARDS.
- THESE DRAWINGS ARE DIAGRAMMATIC, AND INDICATE GENERAL ARRANGEMENT OF WORK. THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE REVIEWED THE SITE FOR HIS WORK PRIOR TO HAVING SUBMITTED HIS PROPOSAL. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR CONDITIONS FOUND DURING THE COURSE OF THE CONTRACT.
- THE CONTRACTOR SHALL COORDINATE HIS WORK WITH THAT OF ALL OTHER TRADES.
- ALL WORK INCLUDING LABOR AND MATERIALS SHALL BE FULLY GUARANTEED FOR ONE (1) YEAR FROM THE DATE OF PAYMENT AND FINAL ACCEPTANCE BY THE OWNER AND ENGINEER.
- ALL CUTTING, PATCHING, FIRE-STOPPING, AND SURFACE RESTORATION IN CONNECTION WITH THIS TRADE SHALL BE COMPLETED BY THIS CONTRACTOR.
- A MINIMUM OF FOUR (4) COPIES OF SHOP DRAWINGS SHALL BE SUBMITTED TO THE ARCHITECT FOR APPROVAL PRIOR TO ORDERING AND INSTALLATION OF THE EQUIPMENT AND/OR MATERIALS. BY SUBMITTING SHOP DRAWINGS, THE CONTRACTOR REPRESENTS THAT ACTUAL FIELD CONDITIONS ARE VERIFIED BY HIM AND ARE REFLECTED ON HIS SUBMITTALS.
- THIS CONTRACTOR SHALL PAY ALL FEES, GIVE ALL NOTICES, FILE ALL NECESSARY DRAWINGS, AND OBTAIN ALL PERMITS, INSPECTIONS AND CERTIFICATES OF APPROVAL REQUIRED IN CONNECTION WITH WORK UNDER THIS CONTRACT.
- EQUIPMENT AND MATERIALS FOR WHICH UNDERWRITERS LABORATORIES, INC. (UL) PROVIDES PRODUCT LISTING SERVICE SHALL BE LISTED AND BEAR THE LISTING MARK.
- ALL WORK IN ASSOCIATION WITH THIS CONTRACT SHALL BE COMPLETED IN STRICT COMPLIANCE WITH THE 2015 NATIONAL ELECTRIC CODE, 2020 BUILDING CODE OF NEW YORK STATE, 2020 FIRE CODE OF NEW YORK STATE & 2020 ENERGY CONSERVATION CONSTRUCTION CODE OF NEW YORK STATE.
- ALL NEW LIGHTING FIXTURES SHALL BE INSTALLED FULLY LAMPED AND OPERABLE. THE CONTRACTOR SHALL TURN OVER TO THE OWNER SPARE LAMPS OF EVERY TYPE ON THE PROJECT IN AN AMOUNT NOT LESS THAN 20% OF THE TOTAL NUMBER OF EACH TYPE (MINIMUM 1 PER TYPE).
- THIS CONTRACTOR SHALL BE RESPONSIBLE FOR ALL COORDINATION, APPLICATIONS AND FEES OF ALL WORK ASSOCIATED WITH THE LOCAL UTILITY COMPANY AND/OR THE TELEPHONE COMPANY. ALL WORK INVOLVING THE UTILITY COMPANY SHALL BE COMPLETED IN ACCORDANCE WITH THEIR REGULATIONS AND GUIDELINES.
- ALL CONDUCTORS SHALL BE COPPER, SHALL NOT BE LESS THAN #12 AWG, AND SHALL NOT EXCEED 70 FEET FROM PANEL BOARD TO FURTHEST CONNECTION UNLESS OTHERWISE NOTED ON PLANS.
- LIGHTING LOADS SHALL NOT BE COMBINED ON THE SAME CIRCUIT AS ANY OTHER ELECTRICAL LOADS.
- CONTRACTOR SHALL BE RESPONSIBLE TO FURNISH & INSTALL ALL SMALL DETAILS AND INCIDENTAL WORK NOT SHOWN OR SPECIFIED, BUT WHICH CAN BE REASONABLY INFERRED AS REQUIRED FOR A COMPLETE AND OPERATING SYSTEM OF HIGH QUALITY MEETING ALL APPLICABLE CODES AND REGULATIONS.
- FOR EACH NEW OR MODIFIED ELECTRICAL PANEL, THE CONTRACTOR SHALL PROVIDE A TYPE WRITTEN DIRECTORY CARD TO REFLECT ALL CIRCUITING. ADDITIONALLY, THE CONTRACTOR SHALL LABEL (WITH A PERMANENT MARKER OR LABEL) EACH RECEPTACLE ON THE INSIDE OF EACH FACE PLATE WITH PANEL AND CIRCUIT NUMBER DESIGNATION.
- MINIMUM REQUIREMENT FOR EQUIPMENT GROUNDING SHALL BE GOVERNED BY THE NEC. ALL GROUNDS, BONDING, ETC. SHALL MEET THESE REQUIREMENTS. THE CONTRACTOR SHALL FURNISH AND INSTALL ANY AND ALL ITEMS NECESSARY TO MEET THESE REQUIREMENTS AT NO EXTRA COST, EVEN IF SUCH ITEMS ARE NOT DETAILED ON THE DRAWINGS.
- ALL CONDUIT AND CABLE SHALL BE PROPERLY SUPPORTED AND ROUTED PARALLEL OR PERPENDICULAR TO BUILDING WALLS. THE CONTRACTOR SHALL FURNISH AND INSTALL ALL SUPPORT HANGERS AND MISCELLANEOUS METALS REQUIRED FOR PROPER INSTALLATION OF WORK.
- THE CONTRACTOR IS RESPONSIBLE TO TEST ALL EQUIPMENT, WIRING, DEVICES, AND SYSTEMS INSTALLED UNDER THIS CONTRACT TO ENSURE PROPER OPERATION PRIOR TO FINAL ACCEPTANCE BY THE OWNER AND ENGINEER.
- THE CONTRACTOR IS RESPONSIBLE TO DETERMINE WHETHER SPECIAL LICENSING IS REQUIRED IN ORDER TO PERFORM THE REQUIRED WORK IN THE MUNICIPALITY WHERE THE PROJECT IS LOCATED. IF THE CONTRACTOR CANNOT OBTAIN THE REQUIRED LICENSING TO COMPLETE THE WORK WITHIN THE PROJECT SCHEDULE, THEN THE CONTRACTOR SHALL NOT BE PERMITTED TO BID ON THIS PROJECT.

WIRE COLOR CODING TABLE						
PHASE	WIRES	VOLTAGE	L1	L2	L3	NEUTRAL GROUND
1	2 (1)	120	BLACK	-	-	WHITE
1	2 (1)	208	BLACK	RED	-	WHITE
1	3	120	BLACK	-	-	WHITE
1	3	208	BLACK	RED	-	WHITE
3	4	208	BLACK	RED	BLUE	-
3	5	208	BLACK	RED	BLUE	WHITE
1	3	277	BROWN	-	-	GRAY
1	3	480	BROWN	ORANGE	-	-
3	4	480	BROWN	ORANGE	YELLOW	-
3	5	480	BROWN	ORANGE	YELLOW	GRAY

NOTES:
1. FOR DOUBLE INSULATED EQUIPMENT ONLY.
2. GREEN/YELLOW MAY BE USED:
- GREEN/YELLOW SHALL BE GREEN WITH ONE OR MORE YELLOW STRIPES.
- GREEN = 50 TO 70%, YELLOW = 50 TO 30%.
- GREEN/YELLOW IS THE ONLY COLOR INTERNATIONALLY ACCEPTED FOR USE AS AN EQUIPMENT GROUNDING CONDUCTOR.
- GREEN OR GREEN/YELLOW MUST ONLY BE USED FOR GROUNDING CONDUCTORS.

DEVICE MOUNTING HEIGHTS	
POWER RECEPTACLES (INTERIOR)	18" A.F.F.
POWER RECEPTACLES (EXTERIOR)	36" A.F.F.
POWER RECEPTACLES (@ COUNTER)	44" A.F.F.
LIGHT SWITCHES	44" A.F.F. TO TOP OF DEVICE
DISCONNECT SWITCHES	SEE NEC 404.8(A)
TELEPHONE/DATA RECEPTACLES	18" A.F.F.
TELEPHONE/DATA RECEPTACLES (@ COUNTER)	44" A.F.F.
WALL TELEPHONE RECEPTACLES	48" A.F.F. TO TOP OF DEVICE
FIRE ALARM PULL STATIONS	42" A.F.F. MIN./44" A.F.F. MAX.
FIRE ALARM AUDIO/VISUAL DEVICES	80" A.F.F. MIN./96" A.F.F. MAX.
EXIT LIGHTS (WALL MOUNTED)	12" ABOVE DOOR
EMERGENCY LIGHTS (WALL MOUNTED)	90" A.F.F.
TV & AV OUTLETS	18" A.F.F.

NOTE: ALL DIMENSIONS ARE TO CENTER OF DEVICE UNLESS OTHERWISE NOTED

19 Front St. · Newburgh · New York 12550-7601
845-561-3179 · www.csarch.com


Project Title
LIBERTY CENTRAL SCHOOL DISTRICT
MAINTENANCE BUILDING

Drawn By: BJK
Checked By: BJK
Proj. #: 59-09-01-06-3-016-001
CSArch Proj. #: 203-2201
Construction Documents: 12/13/22

Sheet Title
ELECTRICAL
NOTES, LEGEND,
DETAILS &
SCHEDULES

Sheet No.
MB
E101

CONSTRUCTION DOCUMENTS



1 Lighting Plan
E201 Scale: 1/4" = 1'-0"

