WATER HEATER SCHEDULE

NO.	SERVICE	TYPE	BTUH INPUT	GALLONS/ HOUR...	TEMP RISE DEG F	FUEL TYPE	VENT IN INCHES	ELECTRIC	DESIGN MAKE
DWH-1									

FIXTURE AND EQUIPMENT CONNECTION SCHEDULE

DESIGNATION	DESCRIPTION	COLD WATER	HOT WATER	WASTE OR SANITARY	VENT	REMARKS
WC	WATER CLOSET	1/2"	-	4"	2"	
UR	URINAL	1"	-	2"	1-1/2"	
LAV	LAVATORY	1/2"	1/2"	1-1/2"	1-1/2"	
SK	SINK	1/2"	1/2"	1-1/2"	1-1/2"	
FD	FLOOR DRAIN	-	-	3" OR 4"	2"	PROVIDE TRAP PRIMER
MB	MOP BASIN	3/4"	3/4"	3"	2"	

PLUMBING SYMBOL LIST

SYMBOL	DESCRIPTION
	NEW PIPING LOCATED ABOVE FLOOR/SLAB
	NEW PIPING LOCATED BELOW FLOOR/SLAB
— • —	COLD WATER PIPING (CW)
— • • —	HOT WATER PIPING (HW)
— • • • —	HOT WATER RECIRCULATING PIPING (HWR)
— W —	WATER SERVICE - EXTERIOR
— SAN —	SANITARY SEWER PIPING
	VENT PIPING
— G —	NATURAL GAS PIPING (G)
	ELBOW DOWN
	ELBOW UP
	BOTTOM/TEE CONNECTION
	TOP TEE CONNECTION
	"P" TRAP
	PIPE CONTINUATION
	CAP OR PLUG
	DECK PLATE CLEANOUT (DPCO)
	WALL PLATE CLEANOUT (WPCO)
	FLOOR DRAIN (FD) / FLOOR SINK (FS)
	WALL HYDRANT (WH)
	SHUT OFF VALVE
	BALANCING VALVE
	CHECK VALVE
	BACKFLOW PREVENTER (BFP)
X	DRAWING KEYNOTE

PLUMBING GENERAL NOTES:

A. COORDINATE PLUMBING WORK WITH ALL OTHER TRADES TO AVOID INTERFERENCE IN FIELD.
B. RUN ALL NEW HORIZONTAL PIPING AS HIGH AS POSSIBLE ABOVE CEILINGS OR BELOW FLOOR.
C. REFER TO ARCHITECTURAL DRAWINGS FOR ADDITIONAL INFORMATION REGARDING NEW BUILDING WORK.
D. COORDINATE AND SCHEDULE WORK AND SHUTDOWNS WITH THE OWNER AND ALL OTHER TRADES PRIOR TO CONSTRUCTION.
E. MAINTAIN SERVICE CLEARANCES FOR ALL EQUIPMENT AS RECOMMENDED BY THE MANUFACTURER. ADVISE OTHER TRADES OF THE REQUIRED SERVICE CLEARANCES.
F. PROVIDE FOR THE DRAINING AND REFILLING OF PIPING SYSTEMS, INCLUDING AIR REMOVAL, READJUSTING FLUSH VALVES, FLUSHING SYSTEMS OF DIRT AND SCALE CAUSED BY SHUT DOWNS AND STARTUPS.
G. REFER TO PLUMBING FIXTURE AND EQUIPMENT CONNECTION SCHEDULE ON THIS DRAWING FOR FINAL CONNECTION SIZES.
H. ALL PLUMBING EQUIPMENT SHALL BE INSTALLED AT LOCATIONS SHOWN ON THE ARCHITECTURAL DRAWINGS.
I. FLUSH VALVES ON ACCESSIBLE WATER CLOSETS SHALL BE ROUGHED SO THE HANDLE IS ON THE WIDE SIDE OF THE ROOM OR STALL.

RW Monster Golf Clubhouse Building

84 CHALET ROAD
KIAMESHA LAKE, NY 12751

JCJARCHITECTURE
120 HUYSHOPE AVENUE
SUITE 400
HARTFORD, CT 06106
860.247.9226

© 2019 JCJ Architecture

CONSULTANTS:

NOT FOR CONSTRUCTION

P.I.C. _____ L.D. _____
P.M. _____ P.A. _____

ISSUE 11/08/2019
JOB H18064.00 PHASE 14
DRAWN EAS
SCALE 1/8" = 1'-0"

REVISIONS:

DETAILS, SCHEDULES AND SYMBOL LIST - PLUMBING

P-001