PIPE SCHEDULE	
PIPE SIZE	# OF HEADS
1"	1
1-1/4"	2-3
1-1/2"	4-5
2"	6-10

THE SIZES INDICATED ABOVE ARE BASED ON PRELIMINARY HYDRAULIC CALCULATIONS. THE FIRE PROTECTION CONTRACTOR SHALL PERFORM FINAL CALCULATIONS ON THE COORDINATED SYSTEM DESIGN TO VERIFY SIZES PRIOR TO COMMENCING WORK.

FIRE PROTECTION SYMBOL LIST	
SYMBOL	DESCRIPTION
FC	FLUSHING CONNECTION
	NEW PIPING
FP	FIRE PROTECTION SERVICE (FP)
B	SPRINKLER MAIN/BRANCH PIPING (B)
D	SPRINKLER DRAIN PIPING (D)
	ELBOW DOWN
	ELBOW UP
	BOTTOM TEE CONNECTION
	TOP TEE CONNECTION
	PIPE CONTINUATION
	FLANGED CONNECTION
	PENDENT SPRINKLER
	CONCEALED PENDENT SPRINKLER
	UPRIGHT SPRINKLER
	DRAIN VALVE
	CHECK VALVE
	PRESSURE REDUCING VALVE
	RELIEF VALVE
	BACK-FLOW PREVENTER (BFP)
	SHUTOFF VALVE WITH TAMPER SWITCH (TS)
FS	FLOW SWITCH (FS)
	ALARM CHECK VALVE WET-TRIM (ACV)
	FIRE DEPARTMENT VALVE (FDV)
	WATER MOTOR GONG
	FIRE DEPARTMENT CONNECTION (FDC)
	INSPECTOR'S TEST CONNECTION (ITC)
	FIRE HYDRANT (FH)
X	DRAWING KEYNOTE

RW Monster Golf Clubhouse Building

94 CHALET ROAD
KAMILSHA LAKE, NY 12751

JCJARCHITECTURE
120 HUYSHOPE AVENUE
SUITE 400
HARTFORD, CT 06106
860.247.6223

©2019 JCJ Architecture

CONSULTANTS:

NOT FOR CONSTRUCTION

P.I.C. _____ L.D. _____
P.M. _____ P.A. _____

ISSUE 11/08/2019
JOB H18084.00 PHASE 14
DRAWN EAS
SCALE NOT TO SCALE

REVISION #:

DETAILS, SCHEDULES AND SYMBOL LIST - FIRE PROTECTION

FP-001