PIPE SCHEDULE	
PIPE SIZE	# OF HEADS
1"	1
1-1/4"	2-3
1-1/2"	4-5
2"	6-10

THE SIZES INDICATED ABOVE ARE BASED ON PRELIMINARY HYDRAULIC CALCULATIONS. THE FIRE PROTECTION CONTRACTOR SHALL PERFORM FINAL CALCULATIONS ON THE COORDINATED SYSTEM DESIGN TO VERIFY SIZES PRIOR TO COMMENCING WORK.

FIRE PROTECTION SYMBOL LIST	
SYMBOL	DESCRIPTION
FC	FLUSHING CONNECTION
	NEW PIPING
FP	FIRE PROTECTION SERVICE (FP)
Z	SPRINKLER MAIN DRAIN PIPING (Z)
D	SPRINKLER DRAIN PIPING (D)
	ELBOW DOWN
	BOTTOM TEE CONNECTION
	TOP TEE CONNECTION
	FIRE PROTECTION
	FLUSHING CONNECTION
	PENDENT SPRINKLER
	CONCEALED PENDENT SPRINKLER
	UPRIGHT SPRINKLER
	DRAIN VALVE
	CHECK VALVE
	RELIEF VALVE
	BACKFLOW PREVENTER (BFP)
	SHUT-OFF VALVE WITH TAMPER SWITCH (TS)
TS	FLOW SWITCH (FS)
	ALARM CHECK VALVE WITH TRIM (ACV)
	WATER MOTOR GONG
	FIRE DEPARTMENT CONNECTION (FDC)
	INSPECTOR'S TEST CONNECTION (ITC)
X	DRAWING KEYNOTE

RW Monster Golf Maintenance Building

94 CHALET ROAD
KAMILSHA LAKE, NY 12751

JCJARCHITECTURE
120 HUYSHOPE AVENUE
SUITE 400
HARTFORD, CT 06106
860.247.6228

©2019 JCJ Architecture

CONSULTANTS:

NOT FOR CONSTRUCTION

P.I.C. _____ L.D. _____
P.M. _____ P.A. _____

ISSUE 11/08/2019
JOB H18084-09 PHASE 14
DRAWN DMS2
SCALE NOT TO SCALE

REVISION #:

DETAILS, SCHEDULES AND SYMBOL LISTS - FIRE PROTECTION

FP-002