
Space Requirements

The printing system requires a floor space / working area of at least 1710 mm x 1470 mm (67.3 inch x 57.9 inches).



Environmental Conditions

| Temperature and relative Humidity | Temperature | R.H. | |
|-----------------------------------|-------------|------|----|
| | C | F | % |
| Guaranteed performance area | 20 | 68 | 30 |
| | 27 | 81 | 30 |
| | 27 | 81 | 60 |
| | 20 | 68 | 60 |
| Reasonable performance area | 17 | 63 | 20 |
| | 30 | 86 | 20 |
| | 30 | 86 | 80 |
| | 17 | 63 | 80 |

| Room volume and ventilation | | | System | | |
|-----------------------------|----------|-------------|----------|-------------------|--|
| minimum ro | om volun | ne | - | 25 m ³ | |
| minimum ventilation) | room | ventilation | (natural | 12,5 m³/hour | |

Electrical Requirements

Customer is responsible for providing the electrical power as outlined below prior to the machine installation. Electrical receptacle (as shown below) is required.

- 115 Volt
- 20 Amps for Plotwave
- 3 Wire Ground
- Electrical Supply must be a dedicated line



NEMA 5-20R for Printer

The electrical service will be available on:

upon delivery

Please note 31.5" machine depth, and be sure to check door widths.

| Ship | pina | Informat | ior |
|------|------|----------|-----|
| | | | |

| Machine dimensions unpacked | De | Depth | | Width | | without elivery nd User face | Height with Top Delivery Tray and User Interface | |
|---|------|-------|------|-------|------|---------------------------------------|---|------|
| | (mm) | (C) | (mm | (") | (mm) | (") | (mm) | (") |
| Océ PlotWave 300 to 360 | 800 | 31.5 | 1527 | 60.1 | 1052 | 41.4 | 1495 | 58.9 |
| Océ PlotWave 300 to 360 multifunction Express | 800 | 31.5 | 1527 | 60.1 | 1110 | 43.7 | 1495 | 58.9 |

| Machine dimensions | Depth | | Width | | Height | |
|-------------------------|-------|------|-------|------|--------|------|
| Packed on pallet | (cm) | (") | (cm) | (") | (cm) | (") |
| Océ PlotWave 300 to 360 | 145 | 57.1 | 85 | 33.5 | 126 | 49.6 |

| Machine weight | Ün | packed | Packed | | |
|--|-----|--------|--------------------------|--------------------------|--|
| | Kg | lbs | Kg | lbs | |
| Océ PlotWave 300 to 360 | 180 | 397 | 285 | 629 | |
| Océ PlotWave 300 to 360 multifunction Express (includes PW and Scanner Express) | 200 | 441 | Not available Packed. | Not available Packed. | |
| Scanner Express | 20 | 44 | 47 | 104 | |

| | 1.50 | | Key Operator | | | |
|---------------------------------|-----------------------|--|---|-------------------------------|---------------------|----------|
| Key Operator (s |) will be tra | ined upon completion of | install: | #W | | |
| Key Operator | Name: | Ron Lombardo | | Phone/Ext; | 140 | |
| | Name: | | | Phone/Ext: | | |
| | | | Field Service | | | |
| Installation Tech | inician: | | | Number: | | |
| Primary Technic | ian: | | | Number: | | |
| Back Up Technic | cian: | | | Number: | | |
| EINMELL | | Please ei | nsure that all signature | s are present | | |
| Océ Represen | tative: | | Date: | | | |
| Customer: | | | Date: | | | |
| Field Service M | fanager: — | | Date: | | | |
| Please return if any changes | complete s occur p | rior to installation da Return to: 1 | ch Administrator. No nte. R. S. Knapp Attn: Bob I 200 Wall Str wndhurst. N | Co., Inc Loppe eet West | Administrator and (| COF (HQ) |

201-438-1500