

DEPARTMENT OF GENERAL SERVICES

Samantha Sweikata Acting Commissioner

Steven M. Neuhaus County Executive 255-275 Main St., P.O. Box 218 Goshen, New York 10924 TEL: (845) 291-2792 FAX: (845) 378-2365 www.orangecountygov.com

January 12, 2023

RFB-OC177-22 Orange County Medical Examiner's Office

Addendum D

This amendment is to address questions for the above mentioned RFB:

1. Q: Please provide the schedule for spec 010110

A: Please refer to Section 00 70000A Table 1-1. Substantial completion date shall be 411 days from issuance of Notice to Proceed. Final completion shall be 60 days from Substantial Completion.

2. Q: [Are there] any thresholds that would deem us exempt from [the PLA requirements]?

A: No

3. Q: Please provide a spec for generator. Also drawing E001 calls for a 500kw generator while drawing E700 calls for a 300kw on the one line. Please clarify.

A: A generator spec has been added, see attached. The generator is a 500KW SD500 diesel generator with level two sound enclosure and 28 hour base tank. Generator shall be placed on an 8" high reinforced concrete pad extending out 6" wider than the generator on all sides. Pad shall have #4 rebar 12" O.C. in each direction on top and bottom of pad.

4. Q: Please provide a spec for the fire alarm system.

A: A fire alarm spec has been added, see attached.

- 5. Q: Geotech report is missing from the project manual.
 - A: See attached
- Q: Section 311000, page 6, 3.9 B Burning of brush and trees permitted on site?
 A: Remove 3.9 B Burning
- 7. Q: Section 312000, page 5, 3.4 B, blasting of rock is permitted on site?
 A: Remove (blasting) 312000 3.4 (B) 1 (A)
- 8. Q: Section 312000, pages 8 & 9, "dimensions insert" marked in red. Who fills in these dimensions?

A: Remove <insert dimension> all location in this section

9. Q: Section 312000, page 9, 3.14 A & B. Where is this method of back fill being used on the site? Is there a place that requires Geofoam?
A: Remove section 3.14

- 10.Q: Section 312000, page 10, 3.15, who is performing the soil moisture testing? **A: By others.**
- 11.Q: Section 017419 page 5& 6, 3.4, Rock, asphalt, and concrete from site to be crushed to 1 ½", washed and stockpiled? Please advise. Can this material be used for back fill operations? If so where can it be used?
 A: This material can be use if it mosts the criteria of the requirement set

A: This material can be use if it meets the criteria of the requirement set forth in these specifications. Use of material would be determined by the structural engineer.

- 12.Q: Section 017419, page 6, 3.4 D., E. is it your intent to reused the pipe and conduits removed for new work installation?
 - A: No: The intent is not to re-use. The above section is incorrect
- 13.Q: Specification 084243 section 2.2-c.9 calls for "miniblinds", however there is no information regarding the miniblind glazing in this specification or 088000. at the request of the basis of design, please provide further information so it can be quoted as desired.

A: Provide "miniblind" glass in window BL-2 and all glass panels in automatic sliding door 147 into Special Autopsy Room 147 as follows:

Miniblind Glazing: ASTM E 2190.

- 1. Basis of Design Manufacturer: Unicel, Vision Control Mini, Thumbwheel control.
- 2. Glass: ASTM C 1036, Type 1, Class 1, q3.
 - a. Tint: Clear.
 - b. Kind: 5/32" Fully tempered.
- 3. Integral Miniblinds: Manufacturer's standard, horizontal louver blinds with aluminum slats and polyester-fiber cords; located in space between glass lites and operated by hardware located on face of glass panel.
 - a. Operation: Tilt only. Thumbwheel operator.
 - b. Color: As selected by Architect from manufacturer's full range.
- 4. Factory Glazing: Install miniblind glazing at the factory.
- 5. Test and adjust miniblinds to operate properly.
- 14. Q: Is there an electrical budget amount for this project? If so, can you please release it, we need it for bonding purposes.

A: No budget. Bonding amounts dependent on total bid price.

15.Q: Please have the site designer clearly indicate the limits of proposed concrete curbing and proposed concrete sidewalks.

A: The limits of the proposed curbs and sidewalks have been clarified, see revised drawing attached.

16.Q: There are details for both segmental block walls and gabion walls. Please advise which detail applies to which walls.

A: Gabion walls have been eliminated from the project please disregard the detail.

17.Q: Both the Utility Plan and Site Plan show blacked out areas at the smart car charging spaces. What does this represent?

A: The smart car striping did not print correctly, see revised drawings attached.

18.Q: Please provide rim and inverts on sanitary sewer.

A: Existing rims and inverts previously provided on sanitary manholes, please see sheet ESCP attached.

19. Q: Please provide a soils report or boring report.

A: See attached

20.Q: Sheet C-102 shows DMH 1&2 having identical Rim Elev. As OCS-#1 (479.65). These elevations are significantly above finished grade in the immediate vicinity. Please provide correct Rim Elev. For both structures.

A: The rim elevations have been corrected, see revised drawing attached.

21. Q: Detail sheets D101, 102, & 103 contain no detail for a DMH, which is called out. Please provide a construction detail.

A: See revised drawing with detail attached.

22.Q: The relocation of existing watermain (8"+12") has little detail. Can these lines be shutdown during the connections? Or will live wet tapping be required? If new valves are required, provide a detail and spec for their installation, and any required thrust blocks.

A: Wet tap and valve details have been provided, see revised drawing attached.

23.Q: Floor plan A-101, exterior wall details A700/7, A607/7 on rooms 134 Elec/Mech, 142 Storage, and 143 Chem. Stor. do not show spray foam at exterior walls; however, building section A202/2, and exterior elevation A201/2 do. Is spray foam required at these exterior wall rooms?

A: Yes, spray foam is to be provided in all of these exterior wall locations instead of batt insulation.

24. Q: Floor plan A-101, details A507/1, A700/10 and A506/1 along line B.9, between columns 7 & 9 show spray foam at wall. Please confirm if spray foam is required along this interior wall.

A: Yes, spray foam is to be provided as shown in those locations.

25.Q: Please clarify which catch basins shall be new Catch Basins denoted on Drawing C-102, and which detail on Drawing D102 shall be utilized for the new catch basin (there are two different details). Same goes for the Manhole and Sanitary Lines (which are new and which to remain); which are the new MH's and new sanitary lines?

A: The new catch basins will be 30X48, the 30X30 detail provided is for the raising the rim of the existing catch basins in the parking lot as required. All sewer manholes and the sewer main are existing. There is a new 6" sewer lateral to tie into the existing main as shown, clarification has been provided. See sheet ESCP attached.

26.Q: A detail for light pole bases is also missing. Please provide one.

A: Existing light pole bases to be utilized, no new light poles are proposed.

27. Q: There is no information regarding how the connection to the existing sewer main shall be completed. Please provide instruction and the size of the existing main.

A: See detail provided on sheet D-102, see sheet ESCP attached.

28.Q: Sheet ES101 shows Generator at a different location than C101. Please clarify the location.

A: Contractor to reference electrical drawings for generator location.

29.Q: On the fixture schedule, type D is an 8ft linear fixture. The symbol shown on the fixture schedule & plans is the typical downlight symbol. Can you confirm if this is supposed to be a downlight or a linear fixture?

A: The fixture schedule has been revised. See attached drawing.

30.Q: Type F – model number HTG-3P is for a pendant mount, but description says recessed. Which is correct?

A: The fixture schedule has been revised. See attached drawing.

31.Q: Type H – is unspecified – Please provide a make and model for this fixture.

A: The fixture schedule has been revised. See attached drawing.

32.Q: Type I – cannot identify a J4 series, I believe this is actually the Juno L4 series. Can you confirm?

A: The fixture schedule has been revised. See attached drawing.

33.Q: Type J – model number HTG-1P is for a pendant mount, but description says wall mounted. Which is correct? It does not appear to be wall mounted on the plans for type J.

A: The fixture schedule has been revised. See attached drawing.

34.Q: On the fixture schedule, the model numbers are mostly for 35k, or 3k, but descriptions state 4000k. Please clarify which color we should go by.

A: The facility lighting should be 3500K with exception of the two autopsy rooms which shall be 4000K.

35.Q: We have contacted the suppliers for the "Radiation Protection" materials listed in section 134900. To provide the correct shielding, we need the Radiologist Shielding Report. This is the information that the suppliers use to determine what thickness lead shielding will be required.

A: Provide 1/16" lead shielding as shown in the documents. See Section 134900, 2.2, C and D. A radiologist's report will be available to the contractor after bid and modifications made at that time if required.

36.Q: Cuts and fills in the building footprint; do footings and piers have to be on virgin soil? Or structural fill?

A: See note 8 on Drawing S002 and Foundation Construction Considerations in the Geotechnical Report.

37.Q: Drawing C-102, Excess material is indicated to go hear as shown by an arrow. After reviewing the existing site there is no access to this area for stock piling material. Please clarify.

A: Location of stockpile has been modified. See drawing attached.

38.Q: If Contract 2 is awarded, who is responsible for the removal of the slurry from the Geo well drilling operation?

A: The General Contractor.

39.Q: What is the finish material between the building and block retaining wall? Appears to connect to asphalt at the southeast corner of the building (+-) EL 509?

A: 6" of $\frac{3}{4}$ " red aggregate to be provided in this area as shown on sheet L101.

- 40.Q: Drawing H801 under the pump schedule, Pumps P-A, B: The scheduled model numbers are split-coupled end suction pumps, however, written specs 232123 only discusses close-coupled end suction pumps. Which is required?
 A: The scheduled pumps are required.
- 41.Q: Drawing P200 shows a water control box (WB-1) in Room 149. Is this water control box necessary?

A: Yes.

42.Q: Drawing H703, detail 2 shows a water meter with remote reader on the coldwater fill line for the hydronic system. Is this water meter to be provided by the water utility? If not, please provide a manufacturer and model number for the water meter.

A: Disregard the water meter.

43.Q: Is an Errors and Omissions coverage being requested; or an OCP with the Construction manager as the named insured?

A: If the GC is doing the professional work, then they need it. If they are contracting that out, then their subs need it.

- 44.Q: Please clarify and define the request for a Construction project Management Liability Policy. Or, is this defined by a General Liability insurance coverage?
 A: Owners and Contractors Protective (OCP) Liability Coverage a standalone policy that covers the named insured's liability for bodily injury (BI) and property damage (PD) caused, in whole or in part, by an independent contractor's work for the insured. The contractor purchases the policy to provide coverage for vicarious liability the client (project owner) incurs as a result of the contractor's acts or omissions on the project. The OCP policy also responds to liability arising out of the insured's own acts or omissions in connection with its general supervision of the contractor's operations.
- 45.Q: Pollution coverage is requested, however, there are no ACM removals listed in in scope of work. Please provide a breakdown of the abatement being performed.

A: Pollution coverage is needed.

46.Q: Will the local utility be responsible for pole- mounted transformers and medium voltage cabling between the poles?

A: No the electrical contractor is responsible for this equipment and work.

47.Q: The H fixture in the lighting legend (E001) does not have a description/type, will one be provided?

A: The fixture schedule has been updated. See attached drawing.

48. Q: On E- 200 room 149, the light fixtures do not have a type of fixture designated to them. What type should they be?

A: They are type 'A'.

49.Q: Who will be responsible for running communication lines between temporary utility poles, Fiber, Cat#6, ETC?

A: The electrical contractor is responsible for this equipment and work.

50.Q: Will a fire alarm Riser diagram be provided?

A: Yes

51.Q: Will a spec or model # be provided for the FLR receptacles on E- 200 in the conference room?

A: Yes refer to details on attached drawings.

52.Q: There is not a Fire A arm Control Panel indicated in the drawings, will a spec and location be provided? This will be needed.

A: Yes refer to drawings and attached spec. The new panel shall be a "Fire-lite" model ES-200X, addressable fire alarm control panel located on the south wall of room 108.

53.Q: Can a location for Cir's 73- 84 in panel PP1- 2 on E- 800 be provided on the power plan? They are not shown.

A: They are now home runs for CH 1, 2, 3 & 4 located in mech room 121. The home runs shown on the plans were for the pumps only.

- 54.Q: Please provide additional information on the characteristics of the fabric, openness, and color of the Flexshade by Draper in Spec section 12 49 00-'Manually Operated Window Treatments'.
 - A: 1. Characteristics of the fabric: Duplex basketweave fabric. 36% Fiberglass, 64% Vinyl. Approximately 99% UV Blockage, .027 inches thick. 14.6 oz/square yard.
 - 2. Openness: 1 percent open.
 - 3. Color: SW 2701 Oyster.
- 55.Q: P001-Note 4,14-Speaks to existing work-Slab removal, replacement and such. New building?

A: Disregard

56.Q: E701-detail 10, Note 2-Calls for rods above and below duct bank-Need rebar detail for #4 bar as to how many, spacing, distance past roadway, Etc.

A: Place #4 rebar in the concrete ductbank 2" from top and bottom, 8"O.C. in each direction. Extend 8' past roadway.

57.Q: ES 101-Note 5-Provide 2" conduit for future car chargers-It was answered in previous question Electric Cont. to supply chargers. Are there more chargers in the future not shown?

A: Provide a spare two inch conduit for future car chargers.

58.Q: Note 31-Building steel to be grounded -Exothermic Welded -Foundation rebar within concrete as well?

A: No not required.

59. Q: Note 29-Paint and rustproof conduit as directed by General Contractor? A: Paint emt light grey with Rustoleum or equal. 60.Q: E001-Note 12-Certificates to be delivered to General Contractor before final payment?.

A: For electrical inspections

61.Q: Radiation Protection-134900-1/1.2-B-1-Section 033000-Cast in Place Concrete, For Concrete topping over lead shielding in concrete slabs-Not finding lead shield within slabs, is this spec to be used and if so where?

A: There will be no shielding in concrete slabs. Disregard reference.

62.Q: There is no specific contract for the SPRINKLER WORK. What contract will this scope of work fall under?

A: Plumbing.

63.Q: Regarding your response in addendum #1 to the "Radiation Protection" materials listed in specification 134900, no thickness of the lead is called out. A radiation shielding report is a federal requirement, as per Ray-Bar. Please see the attached Ray-Bar document for a shielding report needed. No one will quote the lead shield material without a report or lead thickness. Please provide.

A: See response to question 35.

64. What is the finish for all hardware-on-hardware sets 1 / 1.5 /2 / and 15? Only note we see is in the door spec, says for standard hardware finish to match doors. Doors are all painted and that is not a standard finish for door hardware.

A: Door hardware finish is to be selected from manufacturers standard finishes. They will not be painted.

65. Storefront type B is located at the exterior of the security vestibule but only has normal glazing (IG1). All windows in this room have security glazing. Should this glazing be BR-1? Please confirm.

A: Yes. Glazing in storefront type B is to be BR-1.

66. Drawing D101, please indicate the extent of the new timber railing and the new steel railing. The site plan is not clear on the footage for these railings.

A: Detail has been clarified, there are no steel railings on the project.

67. Drawing H102 shows existing and new grades. Can you provide a new top or bottom of curb to determine the new top of replacement pavement?

A: Contractor to maintain a 6" reveal, grade tolerances may vary and are not depicted.

68. Drawing H102, in the building footprint, what does abbreviation LSE (508.0) stand for? There is no description for this abbreviation.

A: It's a carrier over from the architectural or civil plan set. It has no HVAC meaning.

69. Plans call for the milling of 56,000sf of existing asphalt complete to subbase. Specification section 321216, page 4, 3.3 calls to mill 2 inches of existing asphalt. Also, the specification 017419 calls to dispose of millings on site. Can this material be used for back fill? If so, in what areas can it be used?

A: 56,000 S.F. of existing asphalt to be demolished, milling is subject to the contractor's discretion. Millings cannot be used for backfill.

- 70. Specification section 312000, page 11, 3.19 B calls for fabric under the new subbase. The detail on drawing D101 does not call for fabric. Please clarify.A: No fabric is required.
- 71. Specification section 321713 calls for "Wheel stops / Bumpers" however there are not shown on the drawings. Please clarify.
 - A: No wheel stops are to be provided.
 - 72. Remove Drawing Cover Sheet and Replace with attached Cover sheet showing revised Drawing List.
 - 73. Remove Drawing C101 and Replace with attached Drawing C101.
 - 74. Remove Drawing C102 and Replace with attached Drawing C102.
 - 75. Remove Drawing E101 Electrical Site Plan and Replace with attached Drawing CE101 Electrical Site Plan.
 - 76. Remove Drawing ESCP and Replace with attached Drawing ESCP.
 - 77. Remove Drawing D101 and Replace with attached Drawing D101.
 - 78. Remove Drawing D102 and Replace with attached Drawing D102.
 - 79. Remove Drawing H100 and Replace with attached Drawing H100.
 - 80. Remove Drawing H101 and Replace with attached Drawing H101.
 - 81. Remove Drawing H801 and Replace with attached Drawing H801.
 - 82. Remove Drawing E001 and Replace with attached Drawing E001.
 - 83. Remove Drawing E100 and Replace with attached Drawing E100.
 - 84. Remove Drawing E101 Electrical Power Floor Plan and Replace with attached Drawing E101 Electrical Power Floor Plan.
 - 85. Remove Drawing E200 and Replace with attached Drawing E200.
 - 86. Remove Drawing E800 and Replace with attached Drawing E800.
 - 87. Add attached Drawing E801, Electrical Schedules & Details.

Regards,

Samantha Sweikata Acting Commissioner

SECTION 263213 - ENGINE GENERATORS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes packaged engine-generator sets for emergency power supply with the following features:
 - 1. Diesel engine.
 - 2. Unit-mounted cooling system.
 - 3. Unit-mounted control and monitoring.
 - 4. Performance requirements for sensitive loads.
 - 5. Load banks.
 - 6. Outdoor enclosure.

1.3 DEFINITIONS

A. Operational Bandwidth: The total variation from the lowest to highest value of a parameter over the range of conditions indicated, expressed as a percentage of the nominal value of the parameter.

1.4 SUBMITTALS

- A. Shop Drawings: Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
 - 1. Dimensioned outline plan and elevation drawings of engine-generator set and other components specified.
 - 2. Design Calculations: Signed and sealed by a qualified professional engineer. Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.
 - 3. Vibration Isolation Base Details: Signed and sealed by a qualified professional engineer. Detail fabrication, including anchorages and attachments to structure and to supported equipment. Include base weights.
 - 4. Wiring Diagrams: Power, signal, and control wiring.

- B. Qualification Data: For manufacturer.
- C. Source quality-control test reports.
 - 1. Certified summary of prototype-unit test report.
 - 2. Certified Test Reports: For components and accessories that are equivalent, but not identical, to those tested on prototype unit.
 - 3. Certified Summary of Performance Tests: Certify compliance with specified requirement to meet performance criteria for sensitive loads.
 - 4. Report of factory test on units to be shipped for this Project, showing evidence of compliance with specified requirements.
 - 5. Report of sound generation.
 - 6. Report of exhaust emissions showing compliance with applicable regulations.
 - 7. Certified Torsional Vibration Compatibility: Comply with NFPA 110.
- D. Field quality-control test reports.
- E. Operation and Maintenance Data: For packaged engine generators to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
 - 1. List of tools and replacement items recommended to be stored at Project for ready access. Include part and drawing numbers, current unit prices, and source of supply.
- F. Warranty: Special warranty specified in this Section.

1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
 - 1. Maintenance Proximity: Not more than two hours' normal travel time from Installer's place of business to Project site.
 - 2. Engineering Responsibility: Preparation of data for vibration isolators and seismic restraints of engine skid mounts, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.
- B. Manufacturer Qualifications: A qualified manufacturer. Maintain, within 100 miles of Project site, a service center capable of providing training, parts, and emergency maintenance repairs.
- C. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a member company of the InterNational Electrical Testing Association or is a nationally recognized testing laboratory (NRTL), and that is acceptable to authorities having jurisdiction.

- 1. Testing Agency's Field Supervisor: Person currently certified by the InterNational Electrical Testing Association or the National Institute for Certification in Engineering Technologies to supervise on-site testing specified in Part 3.
- D. Source Limitations: Obtain packaged generator sets and auxiliary components through one source from a single manufacturer.
- E. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- F. Comply with ASME B15.1.
- G. Comply with NFPA 37.
- H. Comply with NFPA 70.
- I. Comply with NFPA 99.
- J. Comply with NFPA 110 requirements for Level 1 emergency power supply system.
- K. Comply with UL 2200.
- L. Engine Exhaust Emissions: Comply with applicable state and local government requirements.

1.6 PROJECT CONDITIONS

- A. Interruption of Existing Electrical Service: Do not interrupt electrical service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electrical service according to requirements indicated:
 - 1. Notify Owner no fewer than two days in advance of proposed interruption of electrical service.
 - 2. Do not proceed with interruption of electrical service without Owner's written permission.
- B. Environmental Conditions: Engine-generator system shall withstand the following environmental conditions without mechanical or electrical damage or degradation of performance capability:
 - 1. Ambient Temperature: Minus 15 to plus 40 deg C.
 - 2. Relative Humidity: 0 to 95 percent.
 - 3. Altitude: Sea level to 1000 feet.

1.7 COORDINATION

A. Coordinate size and location of concrete bases for package engine generators. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.

1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of packaged engine generators and associated auxiliary components that fail in materials or workmanship within specified warranty period.
 - 1. Warranty Period: 5 years from date of Substantial Completion.

1.9 MAINTENANCE SERVICE

A. Initial Maintenance Service: Beginning at Substantial Completion, provide 12 months' full maintenance by skilled employees of manufacturer's designated service organization. Include quarterly exercising to check for proper starting, load transfer, and running under load. Include routine preventive maintenance as recommended by manufacturer and adjusting as required for proper operation. Provide parts and supplies same as those used in the manufacture and installation of original equipment.

1.10 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Fuses: One for every 10 of each type and rating, but no fewer than one of each.
 - 2. Indicator Lamps: Two for every six of each type used, but no fewer than two of each.
 - 3. Filters: One set each of lubricating oil, fuel, and combustion-air filters.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- C. Basis-of-Design Product: Subject to compliance with requirements, provide Generac SD500 with level 2 enclosure or a comparable product by one of the following:

- 1. Caterpillar; Engine Div.
- 2. Generac Power Systems, Inc.
- 3. Onan/Cummins Power Generation; Industrial Business Group.

2.2 ENGINE-GENERATOR SET

- A. Factory-assembled and -tested, engine-generator set.
- B. Mounting Frame: Maintain alignment of mounted components without depending on concrete foundation; and have lifting attachments.
 - 1. Rigging Diagram: Inscribed on metal plate permanently attached to mounting frame to indicate location and lifting capacity of each lifting attachment and generator-set center of gravity.
- C. Capacities and Characteristics:
 - 1. Power Output Ratings: Nominal ratings as indicated.
 - 2. Output Connections: Three-phase, four wire.
 - 3. Nameplates: For each major system component to identify manufacturer's name and address, and model and serial number of component.
- D. Generator-Set Performance:
 - 1. Steady-State Voltage Operational Bandwidth: 3 percent of rated output voltage from no load to full load.
 - 2. Transient Voltage Performance: Not more than 20 percent variation for 50 percent stepload increase or decrease. Voltage shall recover and remain within the steady-state operating band within three seconds.
 - 3. Steady-State Frequency Operational Bandwidth: 0.5 percent of rated frequency from no load to full load.
 - 4. Steady-State Frequency Stability: When system is operating at any constant load within the rated load, there shall be no random speed variations outside the steady-state operational band and no hunting or surging of speed.
 - 5. Transient Frequency Performance: Less than 5 percent variation for 50 percent step-load increase or decrease. Frequency shall recover and remain within the steady-state operating band within five seconds.
 - 6. Output Waveform: At no load, harmonic content measured line to line or line to neutral shall not exceed 5 percent total and 3 percent for single harmonics. Telephone influence factor, determined according to NEMA MG 1, shall not exceed 50 percent.
 - 7. Sustained Short-Circuit Current: For a 3-phase, bolted short circuit at system output terminals, system shall supply a minimum of 250 percent of rated full-load current for not less than 10 seconds and then clear the fault automatically, without damage to generator system components.
 - 8. Start Time: Comply with NFPA 110, Type 10, system requirements.
- E. Generator-Set Performance for Sensitive Loads:

- 1. Steady-State Voltage Operational Bandwidth: 1 percent of rated output voltage from no load to full load.
- 2. Transient Voltage Performance: Not more than 10 percent variation for 50 percent stepload increase or decrease. Voltage shall recover and remain within the steady-state operating band within 0.5 second.
- 3. Steady-State Frequency Operational Bandwidth: Plus or minus 0.25 percent of rated frequency from no load to full load.
- 4. Steady-State Frequency Stability: When system is operating at any constant load within the rated load, there shall be no random speed variations outside the steady-state operational band and no hunting or surging of speed.
- 5. Transient Frequency Performance: Less than 2-Hz variation for 50 percent step-load increase or decrease. Frequency shall recover and remain within the steady-state operating band within three seconds.
- 6. Output Waveform: At no load, harmonic content measured line to neutral shall not exceed 2 percent total with no slot ripple. Telephone influence factor, determined according to NEMA MG 1, shall not exceed 50 percent.
- 7. Sustained Short-Circuit Current: For a 3-phase, bolted short circuit at system output terminals, system shall supply a minimum of 300 percent of rated full-load current for not less than 10 seconds and then clear the fault automatically, without damage to winding insulation or other generator system components.
- 8. Excitation System: Performance shall be unaffected by voltage distortion caused by nonlinear load.
 - a. Provide permanent magnet excitation for power source to voltage regulator.
- 9. Start Time: Comply with NFPA 110, Type 10, system requirements.

2.3 ENGINE

- A. Fuel: Fuel oil, Grade DF-2.
- B. Rated Engine Speed: 1800 rpm.
- C. Maximum Piston Speed for Four-Cycle Engines: 2250 fpm (11.4 m/s).
- D. Lubrication System: The following items are mounted on engine or skid:
 - 1. Filter and Strainer: Rated to remove 90 percent of particles 5 micrometers and smaller while passing full flow.
 - 2. Thermostatic Control Valve: Control flow in system to maintain optimum oil temperature. Unit shall be capable of full flow and is designed to be fail-safe.
 - 3. Crankcase Drain: Arranged for complete gravity drainage to an easily removable container with no disassembly and without use of pumps, siphons, special tools, or appliances.
- E. Engine Fuel System:

- 1. Main Fuel Pump: Mounted on engine. Pump ensures adequate primary fuel flow under starting and load conditions.
- 2. Relief-Bypass Valve: Automatically regulates pressure in fuel line and returns excess fuel to source.
- 3. Dual Natural Gas with LP-Gas Backup (Vapor-Withdrawal) System:
 - a. Carburetor.
 - b. Fuel-Shutoff Solenoid Valves: One for each fuel source.
 - c. Flexible Fuel Connectors: One for each fuel source.
- F. Coolant Jacket Heater: Electric-immersion type, factory installed in coolant jacket system. Comply with NFPA 110 requirements for Level 1 equipment for heater capacity.
- G. Cooling System: Closed loop, liquid cooled, with radiator factory mounted on enginegenerator-set mounting frame and integral engine-driven coolant pump.
 - 1. Coolant: Solution of 50 percent ethylene-glycol-based antifreeze and 50 percent water, with anticorrosion additives as recommended by engine manufacturer.
 - 2. Size of Radiator: Adequate to contain expansion of total system coolant from cold start to 110 percent load condition.
 - 3. Expansion Tank: Constructed of welded steel plate and rated to withstand maximum closed-loop coolant system pressure for engine used. Equip with gage glass and petcock.
 - 4. Temperature Control: Self-contained, thermostatic-control valve modulates coolant flow automatically to maintain optimum constant coolant temperature as recommended by engine manufacturer.
 - 5. Coolant Hose: Flexible assembly with inside surface of nonporous rubber and outer covering of aging-, ultraviolet-, and abrasion-resistant fabric.
 - a. Rating: 50-psig (345-kPa) maximum working pressure with coolant at 180 deg F (82 deg C), and noncollapsible under vacuum.
 - b. End Fittings: Flanges or steel pipe nipples with clamps to suit piping and equipment connections.
- H. Muffler/Silencer: Critical type, sized as recommended by engine manufacturer and selected with exhaust piping system to not exceed engine manufacturer's engine backpressure requirements.
 - 1. Minimum sound attenuation of 25 dB at 500 Hz.
 - 2. Sound level measured at a distance of 10 feet (3 m) from exhaust discharge after installation is complete shall be 85 dBA or less.
- I. Muffler/Silencer: Industrial type, sized as recommended by engine manufacturer and selected with exhaust piping system to not exceed engine manufacturer's engine backpressure requirements.
 - 1. Minimum sound attenuation of 12 dB at 500 Hz.
 - 2. Sound level measured at a distance of 25 feet (8 m) from exhaust discharge after installation is complete shall be 87 dBA or less.

- J. Air-Intake Filter: Standard-duty, engine-mounted air cleaner with replaceable dry-filter element and "blocked filter" indicator.
- K. Starting System: 12-V electric, with negative ground.
 - 1. Components: Sized so they will not be damaged during a full engine-cranking cycle with ambient temperature at maximum specified in Part 1 "Project Conditions" Article.
 - 2. Cranking Motor: Heavy-duty unit that automatically engages and releases from engine flywheel without binding.
 - 3. Cranking Cycle: As required by NFPA 110 for system level specified.
 - 4. Battery: Adequate capacity within ambient temperature range specified in Part 1 "Project Conditions" Article to provide specified cranking cycle at least three times without recharging.
 - 5. Battery Cable: Size as recommended by engine manufacturer for cable length indicated. Include required interconnecting conductors and connection accessories.
 - 6. Battery Compartment: Factory fabricated of metal with acid-resistant finish and thermal insulation. Thermostatically controlled heater shall be arranged to maintain battery above 10 deg C regardless of external ambient temperature within range specified in Part 1 "Project Conditions" Article. Include accessories required to support and fasten batteries in place.
 - 7. Battery-Charging Alternator: Factory mounted on engine with solid-state voltage regulation and 35-A minimum continuous rating.
 - 8. Battery Charger: Current-limiting, automatic-equalizing and float-charging type. Unit shall comply with UL 1236 and include the following features:
 - a. Operation: Equalizing-charging rate of 10 A shall be initiated automatically after battery has lost charge until an adjustable equalizing voltage is achieved at battery terminals. Unit shall then be automatically switched to a lower float-charging mode and shall continue to operate in that mode until battery is discharged again.
 - b. Automatic Temperature Compensation: Adjust float and equalize voltages for variations in ambient temperature from minus 40 deg C to plus 60 deg C to prevent overcharging at high temperatures and undercharging at low temperatures.
 - c. Automatic Voltage Regulation: Maintain constant output voltage regardless of input voltage variations up to plus or minus 10 percent.
 - d. Ammeter and Voltmeter: Flush mounted in door. Meters shall indicate charging rates.
 - e. Safety Functions: Sense abnormally low battery voltage and close contacts providing low battery voltage indication on control and monitoring panel. Sense high battery voltage and loss of ac input or dc output of battery charger. Either condition shall close contacts that provide a battery-charger malfunction indication at system control and monitoring panel.
 - f. Enclosure and Mounting: NEMA 250, Type 3, wall-mounted cabinet.

2.4 FUEL OIL STORAGE

A. Comply with NFPA 30.

- B. Base-Mounted Fuel Oil Tank: Factory installed and piped, complying with UL 142 fuel oil tank. Features include the following:
 - 1. Tank level indicator.
 - 2. Capacity: Fuel for 28 hours' continuous operation at 100 percent rated power output.
 - 3. Vandal-resistant fill cap.
 - 4. Containment Provisions: Comply with requirements of authorities having jurisdiction.

2.5 CONTROL AND MONITORING

- A. Automatic Starting System Sequence of Operation: When mode-selector switch on the control and monitoring panel is in the automatic position, remote-control contacts in one or more separate automatic transfer switches initiate starting and stopping of generator set. When modeselector switch is switched to the on position, generator set starts. The off position of same switch initiates generator-set shutdown. When generator set is running, specified system or equipment failures or derangements automatically shut down generator set and initiate alarms. Operation of a remote emergency-stop switch also shuts down generator set.
- B. Manual Starting System Sequence of Operation: Switching on-off switch on the generator control panel to the on position starts generator set. The off position of same switch initiates generator-set shutdown. When generator set is running, specified system or equipment failures or derangements automatically shut down generator set and initiate alarms. Operation of a remote emergency-stop switch also shuts down generator set.
- C. Configuration: Operating and safety indications, protective devices, basic system controls, and engine gages shall be grouped in a common control and monitoring panel mounted on the generator set. Mounting method shall isolate the control panel from generator-set vibration.
- D. Configuration: Operating and safety indications, protective devices, basic system controls, and engine gages shall be grouped in a common wall-mounted control and monitoring panel.
- E. Configuration: Operating and safety indications, protective devices, basic system controls, engine gages, instrument transformers, generator disconnect switch or circuit breaker, and other indicated components shall be grouped in a combination control and power panel. Control and monitoring section of panel shall be isolated from power sections by steel barriers. Panel features shall include the following:
 - 1. Wall-Mounting Cabinet Construction: Rigid, self-supporting steel unit complying with NEMA ICS 6. Power bus shall be copper. Bus, bus supports, control wiring, and temperature rise shall comply with UL 891.
 - 2. Switchboard Construction: Freestanding unit complying with Division 26 Section "Switchboards."
 - 3. Switchgear Construction: Freestanding unit complying with Division 26 Section "Low-Voltage Switchgear."
 - 4. Current and Potential Transformers: Instrument accuracy class.
- F. Indicating and Protective Devices and Controls: As required by NFPA 110 for Level 2 system, and the following:

- 1. AC voltmeter.
- 2. AC ammeter.
- 3. AC frequency meter.
- 4. DC voltmeter (alternator battery charging).
- 5. Engine-coolant temperature gage.
- 6. Engine lubricating-oil pressure gage.
- 7. Running-time meter.
- 8. Ammeter-voltmeter, phase-selector switch(es).
- 9. Generator-voltage adjusting rheostat.
- 10. Fuel tank derangement alarm.
- 11. Fuel tank high-level shutdown of fuel supply alarm.
- 12. Generator overload.
- G. Supporting Items: Include sensors, transducers, terminals, relays, and other devices and include wiring required to support specified items. Locate sensors and other supporting items on engine or generator, unless otherwise indicated.
- H. Connection to Data Link: A separate terminal block, factory wired to Form C dry contacts, for each alarm and status indication is reserved for connections for data-link transmission of indications to remote data terminals. Data system connections to terminals are covered in Division 26 Section "Electrical Power Monitoring and Control."
- I. Common Remote Audible Alarm: Comply with NFPA 110 requirements for Level 1 systems. Include necessary contacts and terminals in control and monitoring panel.
 - 1. Overcrank shutdown.
 - 2. Coolant low-temperature alarm.
 - 3. Control switch not in auto position.
 - 4. Battery-charger malfunction alarm.
 - 5. Battery low-voltage alarm.
- J. Common Remote Audible Alarm: Signal the occurrence of any events listed below without differentiating between event types. Connect so that after an alarm is silenced, clearing of initiating condition will reactivate alarm until silencing switch is reset.
 - 1. Engine high-temperature shutdown.
 - 2. Lube-oil, low-pressure shutdown.
 - 3. Overspeed shutdown.
 - 4. Remote emergency-stop shutdown.
 - 5. Engine high-temperature prealarm.
 - 6. Lube-oil, low-pressure prealarm.
 - 7. Fuel tank, low-fuel level.
 - 8. Low coolant level.
- K. Remote Alarm Annunciator: Comply with NFPA 99. An LED labeled with proper alarm conditions shall identify each alarm event and a common audible signal shall sound for each alarm condition. Silencing switch in face of panel shall silence signal without altering visual indication. Connect so that after an alarm is silenced, clearing of initiating condition will

reactivate alarm until silencing switch is reset. Cabinet and faceplate are surface- or flushmounting type to suit mounting conditions indicated.

L. Remote Emergency-Stop Switch: Flush; wall mounted, unless otherwise indicated; and labeled. Push button shall be protected from accidental operation.

2.6 GENERATOR OVERCURRENT AND FAULT PROTECTION

- A. Generator Circuit Breaker: Molded-case, thermal-magnetic type; 100 percent rated; complying with NEMA AB 1 and UL 489.
 - 1. Tripping Characteristic: Designed specifically for generator protection.
 - 2. Trip Rating: Matched to generator rating.
 - 3. Shunt Trip: Connected to trip breaker when generator set is shut down by other protective devices.
 - 4. Mounting: Adjacent to or integrated with control and monitoring panel.
- B. Generator Disconnect Switch: Molded-case type, 100 percent rated.
 - 1. Rating: Matched to generator output rating.
 - 2. Shunt Trip: Connected to trip switch when signaled by generator protector or by other protective devices.
- C. Generator Protector: Microprocessor-based unit shall continuously monitor current level in each phase of generator output, integrate generator heating effect over time, and predict when thermal damage of alternator will occur. When signaled by generator protector or other generator-set protective devices, a shunt-trip device in the generator disconnect switch shall open the switch to disconnect the generator from load circuits. Protector shall perform the following functions:
 - 1. Initiates a generator overload alarm when generator has operated at an overload equivalent to 110 percent of full-rated load for 60 seconds. Indication for this alarm is integrated with other generator-set malfunction alarms.
 - 2. Under single or three-phase fault conditions, regulates generator to 300 percent of rated full-load current for up to 10 seconds.
 - 3. As overcurrent heating effect on the generator approaches the thermal damage point of the unit, protector switches the excitation system off, opens the generator disconnect device, and shuts down the generator set.
 - 4. Senses clearing of a fault by other overcurrent devices and controls recovery of rated voltage to avoid overshoot.
- D. Ground-Fault Indication: Comply with NFPA 70, "Emergency System" signals for ground-fault. Integrate ground-fault alarm indication with other generator-set alarm indications.

2.7 GENERATOR, EXCITER, AND VOLTAGE REGULATOR

A. Comply with NEMA MG 1.

ENGINE GENERATORS

- B. Drive: Generator shaft shall be directly connected to engine shaft. Exciter shall be rotated integrally with generator rotor.
- C. Electrical Insulation: Class H or Class F.
- D. Stator-Winding Leads: Brought out to terminal box to permit future reconnection for other voltages if required.
- E. Construction shall prevent mechanical, electrical, and thermal damage due to vibration, overspeed up to 125 percent of rating, and heat during operation at 110 percent of rated capacity.
- F. Enclosure: Dripproof.
- G. Instrument Transformers: Mounted within generator enclosure.
- H. Voltage Regulator: Solid-state type, separate from exciter, providing performance as specified.
 - 1. Adjusting rheostat on control and monitoring panel shall provide plus or minus 5 percent adjustment of output-voltage operating band.
- I. Strip Heater: Thermostatically controlled unit arranged to maintain stator windings above dew point.
- J. Windings: Two-thirds pitch stator winding and fully linked amortisseur winding.
- K. Subtransient Reactance: 12 percent, maximum.

2.8 LOAD BANK

- A. Description: Permanent, outdoor, weatherproof, remote-controlled, forced-air-cooled, resistive and reactive unit capable of providing a balanced 3-phase, delta-connected load to generator set at 50 percent rated-system capacity, at 80 percent power factor, lagging. Unit may be composed of separate resistive and reactive load banks controlled by a common control panel. Unit shall be capable of selective control of load in 25 percent steps and with minimum step changes of approximately 5 and 10 percent available.
- B. Resistive Load Elements: Corrosion-resistant chromium alloy with ceramic and steel supports. Elements shall be double insulated and designed for repetitive on-off cycling. Elements shall be mounted in removable aluminized-steel heater cases.
- C. Reactive Load Elements: Epoxy-encapsulated reactor coils.
- D. Load-Bank Heat Dissipation: Integral fan with totally enclosed motor shall provide uniform cooling airflow through load elements. Airflow and coil operating current shall be such that, at maximum load, with ambient temperature at the upper end of specified range, load-bank elements operate at not more than 50 percent of maximum continuous temperature rating of resistance elements.

- E. Load Element Switching: Remote-controlled contactors switch groups of load elements. Contactor coils are rated 120 V. Contactors shall be located in a separate NEMA 250, Type 3R enclosure within load-bank enclosure, accessible from exterior through hinged doors with tumbler locks.
- F. Contactor Enclosures: Heated by thermostatically controlled strip heaters to prevent condensation.
- G. Load-Bank Enclosures: NEMA 250, Type 3R, complying with NEMA ICS 6. Louvers at cooling-air intake and discharge openings shall prevent entry of rain and snow. Openings for airflow shall be screened with 1/2-inch- (13-mm-) square, galvanized-steel mesh. Reactive load bank shall include automatic shutters at air intake and discharge.
- H. Protective Devices: Power input circuits to load banks shall be fused, and fuses shall be selected to coordinate with generator circuit breaker. Fuse blocks shall be located in contactor enclosure. Cooling airflow and overtemperature sensors shall automatically shut down and lock out load bank until manually reset. Safety interlocks on access panels and doors shall disconnect load power, control, and heater circuits. Fan motor shall be separately protected by overload and short-circuit devices. Short-circuit devices shall be noninterchangeable fuses with 200,000-A interrupting capacity.
- I. Remote-Control Panel: Separate from load bank in NEMA 250, Type 1 enclosure with a control power switch and pilot light, and switches controlling groups of load elements.
- J. Control Sequence: Control panel may be preset for adjustable single-step loading of generator during automatic exercising.

2.9 OUTDOOR GENERATOR-SET ENCLOSURE

- A. Description: Vandal-resistant, weatherproof steel housing, wind resistant up to 100 mph (160 km/h). Multiple panels shall be lockable and provide adequate access to components requiring maintenance. Panels shall be removable by one person without tools. Instruments and control shall be mounted within enclosure.
- B. Engine Cooling Airflow through Enclosure: Maintain temperature rise of system components within required limits when unit operates at 110 percent of rated load for 2 hours with ambient temperature at top of range specified in system service conditions.
 - 1. Louvers: Fixed-engine, cooling-air inlet and discharge. Storm-proof and drainable louvers prevent entry of rain and snow.
 - 2. Automatic Dampers: At engine cooling-air inlet and discharge. Dampers shall be closed to reduce enclosure heat loss in cold weather when unit is not operating.
- C. Interior Lights with Switch: Factory-wired, vaporproof-type fixtures within housing; arranged to illuminate controls and accessible interior. Arrange for external electrical connection.
 - 1. AC lighting system and connection point for operation when remote source is available.

D. Convenience Outlets: Factory wired, GFCI. Arrange for external electrical connection.

2.10 MOTORS

- A. General requirements for motors are specified in Division 23 Section "Common Motor Requirements for HVAC Equipment."
 - 1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.
 - 2. Controllers, Electrical Devices, and Wiring: Electrical devices and connections are specified in Division 26 Sections.

2.11 VIBRATION ISOLATION DEVICES

- A. Elastomeric Isolator Pads: Oil- and water-resistant elastomer or natural rubber, arranged in single or multiple layers, molded with a nonslip pattern and galvanized-steel baseplates of sufficient stiffness for uniform loading over pad area, and factory cut to sizes that match requirements of supported equipment.
 - 1. Material: Standard neoprene.
 - 2. Durometer Rating: 50.
 - 3. Number of Layers: Two.
- B. Restrained Spring Isolators: Freestanding, steel, open-spring isolators with seismic restraint.
 - 1. Housing: Steel with resilient vertical-limit stops to prevent spring extension due to wind loads or if weight is removed; factory-drilled baseplate bonded to 1/4-inch- (6-mm-) thick, elastomeric isolator pad attached to baseplate underside; and adjustable equipment mounting and leveling bolt that acts as blocking during installation.
 - 2. Outside Spring Diameter: Not less than 80 percent of compressed height of the spring at rated load.
 - 3. Minimum Additional Travel: 50 percent of required deflection at rated load.
 - 4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
 - 5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.

2.12 FINISHES

A. Indoor and Outdoor Enclosures and Components: Manufacturer's standard finish over corrosion-resistant pretreatment and compatible primer.

2.13 SOURCE QUALITY CONTROL

A. Prototype Testing: Factory test engine-generator set using same engine model, constructed of identical or equivalent components and equipped with identical or equivalent accessories.

- 1. Tests: Comply with NFPA 110, Level 1 Energy Converters and with IEEE 115.
- B. Project-Specific Equipment Tests: Before shipment, factory test engine-generator set and other system components and accessories manufactured specifically for this Project. Perform tests at rated load and power factor. Include the following tests:
 - 1. Test components and accessories furnished with installed unit that are not identical to those on tested prototype to demonstrate compatibility and reliability.
 - 2. Full load run.
 - 3. Maximum power.
 - 4. Voltage regulation.
 - 5. Transient and steady-state governing.
 - 6. Single-step load pickup.
 - 7. Safety shutdown.
 - 8. Provide 14 days' advance notice of tests and opportunity for observation of tests by Owner's representative.
 - 9. Report factory test results within 10 days of completion of test.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine areas, equipment bases, and conditions, with Installer present, for compliance with requirements for installation and other conditions affecting packaged engine-generator performance.
- B. Examine roughing-in of piping systems and electrical connections. Verify actual locations of connections before packaged engine-generator installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

3.2 INSTALLATION

- A. Comply with packaged engine-generator manufacturers' written installation and alignment instructions and with NFPA 110.
- B. Install packaged engine generator to provide access, without removing connections or accessories, for periodic maintenance.
- C. Install packaged engine generator with restrained spring isolators having a minimum deflection of 1 inch 8-inch- high concrete base. Secure sets to anchor bolts installed in concrete bases.
- D. Electrical Wiring: Install electrical devices furnished by equipment manufacturers but not specified to be factory mounted.

3.3 CONNECTIONS

- A. Piping installation requirements are specified in Division 23 Sections. Drawings indicate general arrangement of piping and specialties.
- B. Connect fuel, cooling-system, and exhaust-system piping adjacent to packaged engine generator to allow service and maintenance.
- C. Connect engine exhaust pipe to engine with flexible connector.
- D. Connect fuel piping to engines with a gate valve and union and flexible connector.
 - 1. Diesel storage tanks, tank accessories, piping, valves, and specialties for fuel systems.
- E. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- F. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

3.4 IDENTIFICATION

A. Identify system components according to Division 23 Section "Identification for HVAC Piping and Equipment" and Division 26 Section "Identification for Electrical Systems."

3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections and prepare test reports.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections. Report results in writing.
- C. Perform tests and inspections and prepare test reports.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- D. Tests and Inspections:
 - 1. Perform tests recommended by manufacturer and each electrical test and visual and mechanical inspection (except those indicated to be optional) for "AC Generators and for Emergency Systems" specified in NETA Acceptance Testing Specification. Certify compliance with test parameters.

- 2. NFPA 110 Acceptance Tests: Perform tests required by NFPA 110 that are additional to those specified here including, but not limited to, single-step full-load pickup test.
- 3. Battery Tests: Equalize charging of battery cells according to manufacturer's written instructions. Record individual cell voltages.
 - a. Measure charging voltage and voltages between available battery terminals for full-charging and float-charging conditions. Check electrolyte level and specific gravity under both conditions.
 - b. Test for contact integrity of all connectors. Perform an integrity load test and a capacity load test for the battery.
 - c. Verify acceptance of charge for each element of the battery after discharge.
 - d. Verify that measurements are within manufacturer's specifications.
- 4. Battery-Charger Tests: Verify specified rates of charge for both equalizing and floatcharging conditions.
- 5. System Integrity Tests: Methodically verify proper installation, connection, and integrity of each element of engine-generator system before and during system operation. Check for air, exhaust, and fluid leaks.
- 6. Exhaust-System Back-Pressure Test: Use a manometer with a scale exceeding 40-inch wg (120 kPa). Connect to exhaust line close to engine exhaust manifold. Verify that back pressure at full-rated load is within manufacturer's written allowable limits for the engine.
- 7. Exhaust Emissions Test: Comply with applicable government test criteria.
- 8. Voltage and Frequency Transient Stability Tests: Use recording oscilloscope to measure voltage and frequency transients for 50 and 100 percent step-load increases and decreases, and verify that performance is as specified.
- 9. Harmonic-Content Tests: Measure harmonic content of output voltage under 25 percent and at 100 percent of rated linear load. Verify that harmonic content is within specified limits.
- 10. Noise Level Tests: Measure A-weighted level of noise emanating from generator-set installation, including engine exhaust and cooling-air intake and discharge, at two locations, and compare measured levels with required values.
- E. Coordinate tests with tests for transfer switches and run them concurrently.
- F. Test instruments shall have been calibrated within the last 12 months, traceable to standards of NIST, and adequate for making positive observation of test results. Make calibration records available for examination on request.
- G. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
- H. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
- I. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- J. Remove and replace malfunctioning units and retest as specified above.

- K. Retest: Correct deficiencies identified by tests and observations and retest until specified requirements are met.
- L. Report results of tests and inspections in writing. Record adjustable relay settings and measured insulation resistances, time delays, and other values and observations. Attach a label or tag to each tested component indicating satisfactory completion of tests.
- M. Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each power wiring termination and each bus connection. Remove all access panels so terminations and connections are accessible to portable scanner.
 - 1. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan 11 months after date of Substantial Completion.
 - 2. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
 - 3. Record of Infrared Scanning: Prepare a certified report that identifies terminations and connections checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

3.6 DEMONSTRATION

A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain packaged engine generators. Refer to Division 01 Section "Demonstration and Training."

END OF SECTION 263213

MEP DESIGN NEW MEDICAL EXAMINER'S OFFICE FOR THE COUNTY OF ORANGE 09/05

SECTION 283111 - DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEM

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
 - 1. Fire-alarm control unit.
 - 2. Manual fire-alarm boxes.
 - 3. System smoke detectors.
 - 4. Notification appliances.
 - 5. Remote annunciator.
 - 6. Addressable interface device.
 - 7. Digital alarm communicator transmitter.
 - 8. Radio alarm transmitter.
 - 9. System printer.

1.3 DEFINITIONS

- A. LED: Light-emitting diode.
- B. NICET: National Institute for Certification in Engineering Technologies.

1.4 SYSTEM DESCRIPTION

- A. Noncoded, UL-certified addressable system, with multiplexed signal transmission, dedicated to fire-alarm service only.
- B. Noncoded addressable system, with automatic sensitivity control of certain smoke detectors and multiplexed signal transmission, dedicated to fire-alarm service only.

1.5 PERFORMANCE REQUIREMENTS

A. Seismic Performance: Fire-alarm control unit and raceways shall withstand the effects of earthquake motions determined according to SEI/ASCE 7.

1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event.

1.6 SUBMITTALS

- A. General Submittal Requirements:
 - 1. Submittals shall be approved by authorities having jurisdiction prior to submitting them to Architect.
 - 2. Shop Drawings shall be prepared by persons with the following qualifications:
 - a. Trained and certified by manufacturer in fire-alarm system design.
 - b. NICET-certified fire-alarm technician, Level III minimum.
 - c. Licensed or certified by authorities having jurisdiction.
- B. Product Data: For each type of product indicated.
- C. Shop Drawings: For fire-alarm system. Include plans, elevations, sections, details, and attachments to other work.
 - 1. Comply with recommendations in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter in NFPA 72.
 - 2. Include voltage drop calculations for notification appliance circuits.
 - 3. Include battery-size calculations.
 - 4. Include performance parameters and installation details for each detector, verifying that each detector is listed for complete range of air velocity, temperature, and humidity possible when air-handling system is operating.
 - 5. Include plans, sections, and elevations of heating, ventilating, and air-conditioning ducts, drawn to scale and coordinating installation of duct smoke detectors and access to them. Show critical dimensions that relate to placement and support of sampling tubes, detector housing, and remote status and alarm indicators. Locate detectors according to manufacturer's written recommendations.
 - 6. Include voice/alarm signaling-service equipment rack or console layout, grounding schematic, amplifier power calculation, and single-line connection diagram.
 - 7. Include floor plans to indicate final outlet locations showing address of each addressable device. Show size and route of cable and conduits.
- D. Qualification Data: For qualified Installer.
- E. Seismic Qualification Certificates: For fire-alarm control unit, accessories, and components, from manufacturer.
 - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
 - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.

- 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- F. Field quality-control reports.
- G. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
 - 1. Comply with the "Records" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
 - 2. Provide "Record of Completion Documents" according to NFPA 72 article "Permanent Records" in the "Records" Section of the "Inspection, Testing and Maintenance" Chapter.
 - 3. Record copy of site-specific software.
 - 4. Provide "Maintenance, Inspection and Testing Records" according to NFPA 72 article of the same name and include the following:
 - a. Frequency of testing of installed components.
 - b. Frequency of inspection of installed components.
 - c. Requirements and recommendations related to results of maintenance.
 - d. Manufacturer's user training manuals.
 - 5. Manufacturer's required maintenance related to system warranty requirements.
 - 6. Abbreviated operating instructions for mounting at fire-alarm control unit.
 - 7. Copy of NFPA 25.
- H. Software and Firmware Operational Documentation:
 - 1. Software operating and upgrade manuals.
 - 2. Program Software Backup: On compact disk, complete with data files.
 - 3. Device address list.
 - 4. Printout of software application and graphic screens.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: Personnel shall be trained and certified by manufacturer for installation of units required for this Project.
- B. Installer Qualifications: Installation shall be by personnel certified by NICET as fire-alarm Level III technician.
- C. Source Limitations for Fire-Alarm System and Components: Obtain fire-alarm system from single source from single manufacturer. Components shall be compatible with, and operate as, an extension of existing system.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

E. NFPA Certification: Obtain certification according to NFPA 72 by a UL-listed alarm company

1.8 SOFTWARE SERVICE AGREEMENT

- A. Comply with UL 864.
- B. Technical Support: Beginning with Substantial Completion, provide software support for twoyears.
- C. Upgrade Service: Update software to latest version at Project completion. Install and program software upgrades that become available within two years from date of Substantial Completion. Upgrading software shall include operating system. Upgrade shall include new or revised licenses for use of software.
 - 1. Provide 30 days' notice to Owner to allow scheduling and access to system and to allow Owner to upgrade computer equipment if necessary.

1.9 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
 - 1. Smoke Detectors, Fire Detectors: Quantity equal to 10 percent of amount of each type installed, but no fewer than 1 unit of each type.
 - 2. Detector Bases: Quantity equal to 2 percent of amount of each type installed, but no fewer than 1 unit of each type.
 - 3. Keys and Tools: One extra set for access to locked and tamper proof components.
 - 4. Audible and Visual Notification Appliances: One of each type installed.
 - 5. Fuses: Two of each type installed in the system.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- B. Basis-of-Design Product: Subject to compliance with requirements, provide Fire Lite MS 9600 series or comparable products by one of the following:
 - 1. Amseco a Potter brand; Potter Electric Signal Company.
 - 2. Bosch Security Systems.
 - 3. Commercial Products Group/CPG Life Safety Signals.
 - 4. Faraday; Siemens Building Technologies, Inc.
 - 5. Federal Signal Corporation.
 - 6. Fire Control Instruments, Inc.; a Honeywell company.

- 7. Fire Lite Alarms; a Honeywell company.
- 8. Gamewell; a Honeywell company.
- 9. GE Infrastructure; a unit of General Electric Company.
- 10. Gentex Corporation.
- 11. Harrington Signal, Inc.
- 12. NOTIFIER; a Honeywell company.
- 13. Siemens Building Technologies, Inc.; Fire Safety Division.
- 14. Silent Knight; a Honeywell company.
- 15. SimplexGrinnell LP; a Tyco International company.

2.2 SYSTEMS OPERATIONAL DESCRIPTION

- A. Fire-alarm signal initiation shall be by one or more of the following devices and systems:
 - 1. Manual stations.
 - 2. CO detector.
 - 3. Duct smoke detectors.
 - 4. Verified automatic alarm operation of smoke detectors.
 - 5. Automatic sprinkler system water flow.
 - 6. Heat detectors in elevator shaft and pit.
 - 7. Fire-extinguishing system operation.
 - 8. Fire standpipe system.
- B. Fire-alarm signal shall initiate the following actions:
 - 1. Continuously operate alarm notification appliances.
 - 2. Identify alarm at fire-alarm control unit.
 - 3. Transmit an alarm signal to the remote alarm receiving station.
 - 4. Unlock electric door locks in designated egress paths.
 - 5. Release fire and smoke doors held open by magnetic door holders.
 - 6. Activate voice/alarm communication system.
 - 7. Switch heating, ventilating, and air-conditioning equipment controls to fire-alarm mode.
 - 8. Activate smoke-control system (smoke management) at firefighter smoke-control system panel.
 - 9. Activate stairwell and elevator-shaft pressurization systems.
 - 10. Close smoke dampers in air ducts of designated air-conditioning duct systems.
 - 11. Recall elevators to primary or alternate recall floors.
 - 12. Activate emergency lighting control.
 - 13. Activate emergency shutoffs for gas and fuel supplies.
 - 14. Record events in the system memory.
 - 15. Record events by the system printer.
- C. Supervisory signal initiation shall be by one or more of the following devices and actions:
 - 1. Valve supervisory switch.
 - 2. Low-air-pressure switch of a dry-pipe sprinkler system.
- D. System trouble signal initiation shall be by one or more of the following devices and actions:

- 1. Open circuits, shorts, and grounds in designated circuits.
- 2. Opening, tampering with, or removing alarm-initiating and supervisory signal-initiating devices.
- 3. Loss of primary power at fire-alarm control unit.
- 4. Ground or a single break in fire-alarm control unit internal circuits.
- 5. Abnormal ac voltage at fire-alarm control unit.
- 6. Break in standby battery circuitry.
- 7. Failure of battery charging.
- 8. Abnormal position of any switch at fire-alarm control unit or annunciator.
- 9. Fire-pump power failure, including a dead-phase or phase-reversal condition.
- 10. Low-air-pressure switch operation on a dry-pipe or pre-action sprinkler system.
- E. System Trouble and Supervisory Signal Actions: Initiate notification appliance and annunciate at fire-alarm control unit and remote annunciators. Record the event on system printer.

2.3 FIRE-ALARM CONTROL UNIT

- A. General Requirements for Fire-Alarm Control Unit:
 - 1. Field-programmable, microprocessor-based, modular, power-limited design with electronic modules, complying with UL 864 and listed and labeled by an NRTL.
 - a. System software and programs shall be held in flash electrically erasable programmable read-only memory (EEPROM), retaining the information through failure of primary and secondary power supplies.
 - b. Include a real-time clock for time annotation of events on the event recorder and printer.
 - 2. Addressable initiation devices that communicate device identity and status.
 - a. Smoke sensors shall additionally communicate sensitivity setting.
 - b. Temperature sensors shall additionally test for and communicate the sensitivity range of the device.
 - 3. Addressable control circuits for operation of mechanical equipment.
- B. Alphanumeric Display and System Controls: Arranged for interface between human operator at fire-alarm control unit and addressable system components including annunciation and supervision. Display alarm, supervisory, and component status messages and the programming and control menu.
 - 1. Keypad: Arranged to permit entry and execution of programming, display, and control commands and to indicate control commands to be entered into the system for control of smoke-detector sensitivity and other parameters.
- C. Circuits:
 - 1. Initiating Device, Notification Appliance, and Signaling Line Circuits: NFPA 72, Class A

Install no more than 30 addressable devices on each signaling line circuitSerial Interface: Two RS-232 ports for printersRemote Smoke-Detector Sensitivity Adjustment: Controls shall select specific addressable smoke detectors for adjustment, display their current status and sensitivity settings, and change those settings. Allow controls to be used to program repetitive, time-scheduled, and automated changes in sensitivity of specific detector groups. Record sensitivity adjustments and sensitivity-adjustment schedule changes in system memory, and print out the final adjusted values on system printer.

- E. Printout of Events: On receipt of signal, print alarm, supervisory, and trouble events. Identify zone, device, and function. Include type of signal (alarm, supervisory, or trouble) and date and time of occurrence. Differentiate alarm signals from all other printed indications. Also print system reset event, including same information for device, location, date, and time. Commands initiate the printing of a list of existing alarm, supervisory, and trouble conditions in the system and a historical log of events.
- F. Primary Power: 24-V dc obtained from 120-V ac service and a power-supply module. Initiating devices, notification appliances, signaling lines, trouble signals, supervisory signals shall be powered by 24-V dc source.
 - 1. Alarm current draw of entire fire-alarm system shall not exceed 80 percent of the powersupply module rating.
- G. Secondary Power: 24-V dc supply system with batteries, automatic battery charger, and automatic transfer switch.
- H. Instructions: Computer printout or typewritten instruction card mounted behind a plastic or glass cover in a stainless-steel or aluminum frame. Include interpretation and describe appropriate response for displays and signals. Briefly describe the functional operation of the system under normal, alarm, and trouble conditions.

2.4 MANUAL FIRE-ALARM BOXES

- A. General Requirements for Manual Fire-Alarm Boxes: Comply with UL 38. Boxes shall be finished in red with molded, raised-letter operating instructions in contrasting color; shall show visible indication of operation; and shall be mounted on recessed outlet box. If indicated as surface mounted, provide manufacturer's surface back box.
 - 1. Single-action mechanism, pull-lever type; with integral addressable module arranged to communicate manual-station status (normal, alarm, or trouble) to fire-alarm control unit.
 - 2. Station Reset: Key- or wrench-operated switch.

2.5 SYSTEM SMOKE DETECTORS

- A. General Requirements for System Smoke Detectors:
 - 1. Comply with UL 268; operating at 24-V dc, nominal.
 - 2. Detectors shall be two-wire type.

- 3. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to fire-alarm control unit.
- 4. Base Mounting: Detector and associated electronic components shall be mounted in a twist-lock module that connects to a fixed base. Provide terminals in the fixed base for connection to building wiring.
- 5. Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
- 6. Integral Visual-Indicating Light: LED type indicating detector has operated.
- 7. Remote Control: Unless otherwise indicated, detectors shall be analog-addressable type, individually monitored at fire-alarm control unit for calibration, sensitivity, and alarm condition and individually adjustable for sensitivity by fire-alarm control unit.
 - a. Rate-of-rise temperature characteristic shall be selectable at fire-alarm control unit for 15 per minute.
 - b. Fixed-temperature sensing shall be independent of rate-of-rise sensing and shall be settable at fire-alarm control unit to operate at 135.
 - c. Provide multiple levels of detection sensitivity for each sensor.
- B. Photoelectric Smoke Detectors:
 - 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
 - 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).
- C. Ionization Smoke Detector:
 - 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
 - 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).
- D. Duct Smoke Detectors: Photoelectric type complying with UL 268A.
 - 1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.

- 2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
 - a. Primary status.
 - b. Device type.
 - c. Present average value.
 - d. Present sensitivity selected.
 - e. Sensor range (normal, dirty, etc.).
- 3. Weatherproof Duct Housing Enclosure: NEMA 250, Type 4X; NRTL listed for use with the supplied detector.
- 4. Each sensor shall have multiple levels of detection sensitivity.
- 5. Sampling Tubes: Design and dimensions as recommended by manufacturer for specific duct size, air velocity, and installation conditions where applied.
- 6. Relay Fan Shutdown: Rated to interrupt fan motor-control circuit.

2.6 HEAT DETECTORS

- A. General Requirements for Heat Detectors: Comply with UL 521.
- B. Heat Detector, Combination Type: Actuated by either a fixed temperature of 135 deg F at a rate of rise that exceeds 15 deg F per minute unless otherwise indicated.
 - 1. Mounting: Twist-lock base interchangeable with smoke-detector bases.
 - 2. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to fire-alarm control unit.

2.7 NOTIFICATION APPLIANCES

- A. General Requirements for Notification Appliances: Individually addressed, connected to a signaling line circuit, equipped for mounting as indicated and with screw terminals for system connections.
- B. General Requirements for Notification Appliances: Connected to notification appliance signal circuits, zoned as indicated, equipped for mounting as indicated and with screw terminals for system connections.
 - 1. Combination Devices: Factory-integrated audible and visible devices in a singlemounting assembly, equipped for mounting as indicated and with screw terminals for system connections.
- C. Chimes, Low-Level Output: Vibrating type, 75-dBA minimum rated output.
- D. Chimes, High-Level Output: Vibrating type, 81-dBA minimum rated output.
- E. Horns: Electric-vibrating-polarized type, 24-V dc; with provision for housing the operating mechanism behind a grille. Comply with UL 464. Horns shall produce a sound-pressure level

of 90 dBA, measured 10 feet (3 m) from the horn, using the coded signal prescribed in UL 464 test protocol.

- F. Visible Notification Appliances: Xenon strobe lights comply with UL 1971, with clear or nominal white polycarbonate lens mounted on an aluminum faceplate. The word "FIRE" is engraved in minimum 1-inch- (25-mm-) high letters on the lens.
 - 1. Rated Light Output:
 - a. 15/30/75/110 cd, selectable in the field.
 - 2. Mounting: Wall mounted unless otherwise indicated.
 - 3. For units with guards to prevent physical damage, light output ratings shall be determined with guards in place.
 - 4. Flashing shall be in a temporal pattern, synchronized with other units.
 - 5. Strobe Leads: Factory connected to screw terminals.
 - 6. Mounting Faceplate: Factory finished, white.
- G. Voice/Tone Notification Appliances:
 - 1. Appliances shall comply with UL 1480 and shall be listed and labeled by an NRTL.
 - 2. High-Range Units: Rated 2 to 15 W.
 - 3. Low-Range Units: Rated 1 to 2 W.
 - 4. Mounting: Flush
 - 5. Matching Transformers: Tap range matched to acoustical environment of speaker location.

2.8 MAGNETIC DOOR HOLDERS

- A. Description: Units are equipped for wall or floor mounting as indicated and are complete with matching doorplate.
 - 1. Electromagnet: Requires no more than 3 W to develop 25-lbf (111-N) holding force.
 - 2. Wall-Mounted Units: Flush mounted unless otherwise indicated.
 - 3. Rating: 24-V ac or dc.
- B. Material and Finish: Match door hardware.

2.9 REMOTE ANNUNCIATOR

- A. Description: Annunciator functions shall match those of fire-alarm control unit for alarm, supervisory, and trouble indications. Manual switching functions shall match those of fire-alarm control unit, including acknowledging, silencing, resetting, and testing.
 - 1. Mounting: Flush cabinet, NEMA 250, Type 1.
B. Display Type and Functional Performance: Alphanumeric display and LED indicating lights shall match those of fire-alarm control unit. Provide controls to acknowledge, silence, reset, and test functions for alarm, supervisory, and trouble signals.

2.10 ADDRESSABLE INTERFACE DEVICE

A. Description: Microelectronic monitor module, NRTL listed for use in providing a system address for alarm-initiating devices for wired applications with normally open contacts.

2.11 DIGITAL ALARM COMMUNICATOR TRANSMITTER

- A. Digital alarm communicator transmitter shall be acceptable to the remote central station and shall comply with UL 632 and be listed and labeled by an NRTL.
- B. Functional Performance: Unit shall receive an alarm, supervisory, or trouble signal from firealarm control unit and automatically capture two telephone line(s) and dial a preset number for a remote central station. When contact is made with central station(s), signals shall be transmitted. If either service line is interrupted for longer than 45 seconds, transmitter shall initiate a local trouble signal and transmit the signal indicating loss of telephone line to the remote alarm receiving station over the remaining line. Transmitter shall automatically report telephone service restoration to the central station. If service is lost on both telephone lines, transmitter shall initiate the local trouble signal.
- C. Local functions and display at the digital alarm communicator transmitter shall include the following:
 - 1. Verification that both telephone lines are available.
 - 2. Programming device.
 - 3. LED display.
 - 4. Manual test report function and manual transmission clear indication.
 - 5. Communications failure with the central station or fire-alarm control unit.
- D. Digital data transmission shall include the following:
 - 1. Address of the alarm-initiating device.
 - 2. Address of the supervisory signal.
 - 3. Address of the trouble-initiating device.
 - 4. Loss of ac supply or loss of power.
 - 5. Low battery.
 - 6. Abnormal test signal.
 - 7. Communication bus failure.
- E. Secondary Power: Integral rechargeable battery and automatic charger.
- F. Self-Test: Conducted automatically every 24 hours with report transmitted to central station.

2.12 SYSTEM PRINTER

A. Printer shall be listed and labeled by an NRTL as an integral part of fire-alarm system.

PART 3 - EXECUTION

3.1 EQUIPMENT INSTALLATION

- A. Comply with NFPA 72 for installation of fire-alarm equipment.
- B. Equipment Mounting: Install fire-alarm control unit on concrete base with tops of cabinets not more than 72 inches (1830 mm) above the finished floor. Comply with requirements for concrete base specified in Division 03 Section
 - 1. Install seismic bracing. Comply with requirements in Division 26 Section "Vibration and Seismic Controls for Electrical Systems."
 - 2. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch (450-mm) centers around the full perimeter of concrete base.
 - 3. For supported equipment, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete floor.
 - 4. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
 - 5. Install anchor bolts to elevations required for proper attachment to supported equipment.
- C. Equipment Mounting: Install fire-alarm control unit on finished floor with tops of cabinets not more than 72 inches (1830 mm) above the finished floor.
 - 1. Comply with requirements for seismic-restraint devices specified in Division 26 Section "Vibration and Seismic Controls for Electrical Systems."
 - 2. Comply with requirements for seismic-restraint devices specified in Division 26 Section "Vibration and Seismic Controls for Electrical Systems."
- D. Connecting to Existing Equipment: Verify that existing fire-alarm system is operational before making changes or connections.
 - 1. Connect new equipment to existing control panel in existing part of the building.
 - 2. Connect new equipment to existing monitoring equipment at the supervising station.
 - 3. Expand, modify, and supplement existing monitoring equipment as necessary to extend existing monitoring functions to the new points. New components shall be capable of merging with existing configuration without degrading the performance of either system.
- E. Smoke- or Heat-Detector Spacing:

- 1. Comply with NFPA 72, "Smoke-Sensing Fire Detectors" Section in the "Initiating Devices" Chapter, for smoke-detector spacing.
- 2. Comply with NFPA 72, "Heat-Sensing Fire Detectors" Section in the "Initiating Devices" Chapter, for heat-detector spacing.
- 3. Smooth ceiling spacing shall not exceed 30 feet.
- 4. Spacing of detectors for irregular areas, for irregular ceiling construction, and for high ceiling areas shall be determined according to Appendix A in NFPA 72.
- 5. HVAC: Locate detectors not closer than 3 feet from air-supply diffuser or return-air opening.
- 6. Lighting Fixtures: Locate detectors not closer than 12 inches (300 mm) from any part of a lighting fixture.
- F. Duct Smoke Detectors: Comply with NFPA 72 and NFPA 90A. Install sampling tubes so they extend the full width of duct.
- G. Heat Detectors in Elevator Shafts: Coordinate temperature rating and location with sprinkler rating and location.
- H. Single-Station Smoke Detectors: Where more than one smoke alarm is installed within a dwelling or suite, they shall be connected so that the operation of any smoke alarm causes the alarm in all smoke alarms to sound.
- I. Remote Status and Alarm Indicators: Install near each smoke detector and each sprinkler waterflow switch and valve-tamper switch that is not readily visible from normal viewing position.
- J. Audible Alarm-Indicating Devices: Install not less than 6 inches (150 mm) below the ceiling. Install bells and horns on flush-mounted back boxes with the device-operating mechanism concealed behind a grille.
- K. Visible Alarm-Indicating Devices: Install adjacent to each alarm bell or alarm horn and at least 6 inches (150 mm) below the ceiling.
- L. Device Location-Indicating Lights: Locate in public space near the device they monitor.
- M. Fire-Alarm Control Unit: Surface mounted, with tops of cabinets not more than 72 inches (1830 mm) above the finished floor.
- N. Annunciator: Install with top of panel not more than 72 inches (1830 mm) above the finished floor.

3.2 CONNECTIONS

- A. For fire-protection systems related to doors in fire-rated walls and partitions and to doors in smoke partitions, comply with requirements in Division 08 Section "Door Hardware." Connect hardware and devices to fire-alarm system.
 - 1. Verify that hardware and devices are NRTL listed for use with fire-alarm system in this Section before making connections.

3.3 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
- B. Install framed instructions in a location visible from fire-alarm control unit.

3.4 GROUNDING

A. Ground fire-alarm control unit and associated circuits; comply with IEEE 1100. Install a ground wire from main service ground to fire-alarm control unit.

3.5 FIELD QUALITY CONTROL

- A. Field tests shall be witnessed by authorities having jurisdiction.
- B. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.
- C. Perform tests and inspections.
 - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- D. Tests and Inspections:
 - 1. Visual Inspection: Conduct visual inspection prior to testing.
 - a. Inspection shall be based on completed Record Drawings and system documentation that is required by NFPA 72 in its "Completion Documents, Preparation" Table in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter.
 - b. Comply with "Visual Inspection Frequencies" Table in the "Inspection" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72; retain the "Initial/Reacceptance" column and list only the installed components.
 - 2. System Testing: Comply with "Test Methods" Table in the "Testing" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
 - 3. Test audible appliances for the public operating mode according to manufacturer's written instructions. Perform the test using a portable sound-level meter complying with Type 2 requirements in ANSI S1.4.
 - 4. Test audible appliances for the private operating mode according to manufacturer's written instructions.
 - 5. Test visible appliances for the public operating mode according to manufacturer's written instructions.

- 6. Factory-authorized service representative shall prepare the "Fire Alarm System Record of Completion" in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter in NFPA 72 and the "Inspection and Testing Form" in the "Records" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
- E. Reacceptance Testing: Perform reacceptance testing to verify the proper operation of added or replaced devices and appliances.
- F. Fire-alarm system will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.
- H. Maintenance Test and Inspection: Perform tests and inspections listed for weekly, monthly, quarterly, and semiannual periods. Use forms developed for initial tests and inspections.
- I. Annual Test and Inspection: One year after date of Substantial Completion, test fire-alarm system complying with visual and testing inspection requirements in NFPA 72. Use forms developed for initial tests and inspections.

3.6 DEMONSTRATION

A. Train Owner's maintenance personnel to adjust, operate, and maintain fire-alarm system.

END OF SECTION 283111



FORMATION THERMAL CONDUCTIVITY TEST & DATA ANALYSIS

TEST LOCATION

Goshen Emergency Services Center Goshen, NY

TEST DATE April 12-14, 2022

ANALYSIS FOR Connecticut Wells Inc. 49 Hard Hill Road North Bethlehem, CT 06751 Phone: (203) 266-5272

TEST PERFORMED BY Connecticut Wells Inc.

EXECUTIVE SUMMARY

A formation thermal conductivity test was performed on the geothermal test bore at the Goshen Emergency Services Center at 22 Wells Farm Road in Goshen, New York. The vertical bore was completed on April 5, 2022 by Connecticut Wells Inc. Geothermal Resource Technologies' (GRTI) test unit was attached to the vertical bore on the morning of April 12, 2022.

This report provides an overview of the test procedures and analysis process, along with plots of the loop temperature and input heat rate data. The collected data was analyzed using the "line source" method and the following average formation thermal conductivity was determined.

Formation Thermal Conductivity = 1.40 Btu/hr-ft-°F

Due to the necessity of a thermal diffusivity value in the design calculation process, an estimate of the average thermal diffusivity was made for the encountered formation.

Formation Thermal Diffusivity $\approx 0.92 \text{ ft}^2/\text{day}$

The undisturbed formation temperature for the tested bore was determined from the initial loop temperature data collected at startup.

Undisturbed Formation Temperature ≈ 52.4-54.0°F

The formation thermal properties determined by this test do not directly translate into a loop length requirement (i.e. feet of bore per ton). These parameters, along with many others, are inputs to commercially available loop-field design software to determine the required loop length. Additional questions concerning the use of these results are discussed in the frequently asked question (FAQ) section at <u>www.grti.com</u>.

TEST PROCEDURES

The American Society of Heating, Refrigeration, and Air-Conditioning Engineers (ASHRAE) has published recommended procedures for performing formation thermal conductivity tests in the ASHRAE HVAC Applications Handbook, Geothermal Energy Chapter. The International Ground Source Heat Pump Association (IGSHPA) also lists test procedures in their Design and Installation Standards. GRTI's test procedures meet or exceed those recommended by ASHRAE and IGSHPA, with the specific procedures described below:

Grouting Procedure for Test Loops – To ensure against bridging and voids, it is recommended that the bore annulus is uniformly grouted from the bottom to the top via tremie pipe.

Time Between Loop Installation and Testing – A minimum delay of five days between loop installation and test startup is recommended for bores that are air drilled, and a minimum waiting period of two days for mud rotary drilling.

Undisturbed Formation Temperature Measurement – The undisturbed formation temperature should be determined by recording the loop temperature as the water returns from the u-bend at test startup.

Required Test Duration – A minimum test duration of 36 hours is recommended, with a preference toward 48 hours.

Data Acquisition Frequency - Test data is recorded at five minute intervals.

Equipment Calibration/Accuracy – Transducers and datalogger are calibrated per manufacturer recommendations. Manufacturer stated accuracy of power transducers is less than $\pm 2\%$. Temperature sensor accuracy is periodically checked via ice water bath.

Power Quality – The standard deviation of the power should be less than or equal to 1.5% of the average power, with maximum power variation of less than or equal to 10% of the average power.

Input Heat Rate – The heat flux rate should be 51 Btu/hr (15 W) to 85 Btu/hr (25 W) per foot of installed bore depth to best simulate the expected peak loads on the u-bend.

Insulation – GRTI's equipment has 1 inch of foam insulation on the FTC unit and 1/2 inch of insulation on the hose kit connection. An additional 2 inches of insulation is provided for both the FTC unit and loop connections by insulating blankets.

Retesting in the Event of Failure – In the event that a test fails prematurely, a retest may not be performed until the bore temperature is within 0.5°F of the original undisturbed formation temperature or until a period of 14 days has elapsed.

DATA ANALYSIS

Geothermal Resource Technologies, Inc. (GRTI) uses the "line source" method of data analysis to determine the thermal conductivity of the formation. The line source method assumes an infinitely thin line source of heat in a continuous medium. A plot of the late-time temperature rise of the line source temperature versus the natural log of elapsed time will follow a linear trend. The linear slope is inversely proportional to the thermal conductivity of the medium. When a ubend grouted in a borehole is used to inject heat into the ground at a constant rate in order to determine the average formation thermal conductivity, the test must be run long enough to allow the finite dimensions of the u-bend pipes and the grout to become insignificant. Experience has shown that approximately ten hours is required to allow the error of early test times and the effects of finite borehole dimensions to become insignificant.

In order to analyze real data from a formation thermal conductivity test, the average temperature of the water entering and exiting the u-bend heat exchanger is plotted versus the natural log of elapsed testing time. Using the Method of Least Squares, linear coefficients are then calculated to produce a line that fits the data. This procedure is repeated for various time intervals to ensure that variations in the power or other effects are not producing inaccurate results.

The calculated results are based on test bore information submitted by the driller/testing agency. GRTI is not responsible for inaccuracies in the results due to erroneous bore information. All data analysis is performed by personnel that have an engineering degree from an accredited university with a background in heat transfer and experience with line source theory. The test results apply specifically to the tested bore. Additional bores at the site may have significantly different results depending upon variations in geology and hydrology.

Through the analysis process, the collected raw data is converted to spreadsheet format (Microsoft Excel®) for final analysis. If desired, please contact GRTI and a copy of the data will be made available in either a hard copy or electronic format.

CONTACT: Chad Martin Regional Managing Engineer Asheville, NC (828) 225-9166 cmartin@grti.com

TEST BORE DETAILS (As Provided By Connecticut Wells Inc.)

Site Name	Goshen Emergency Services Center
Location	Goshen, NY
Driller	Connecticut Wells Inc.
Installed Date	April 5, 2022
Borehole Diameter	8-3/4 inches, 0-140 ft 6 inches, 140-360 ft
Casing	Permanent 6 inch steel casing to 140 ft
U-Bend Size	1-1/4 inch DR9 HDPE
U-Bend Depth Below Grade	360 ft
Grout Type	GeoPro TG Lite/PowerTEC 1.0
Grout Mixture	100 lb TG Lite, 32 lb PowerTEC, 33 gal water
Grouted Portion	Entire bore

DRILL LOG

FORMATION DESCRIPTION	DEPTH (FT)
Top soil, brown clay	0'-10'
Clay hard pan-gray	10'-132'
Shale	132'-160'
Blue shale	160'-175'
Sandstone	175'-360'

Note: Bore produced 5 gpm water at 160 ft; 75 gpm at 258 ft; 100+ gpm at 360 ft.



THERMAL CONDUCTIVITY TEST DATA

FIG. 1: TEMPERATURE & HEAT RATE DATA VS TIME

Figure 1 above shows the loop temperature and heat input rate data versus the elapsed time of the test. The temperature of the fluid supplied to and returning from the U-bend are plotted on the left axis, while the amount of heat supplied to the fluid is plotted on the right axis on a per foot of bore basis. In the test statistics below, calculations on the power data were performed over the analysis time period listed in the Line Source Data Analysis section.

SUMMARY TEST STATISTICS

April 12-14, 2022
Approx. 52.4-54.0°F
47.1 hr
239.8 V
24,486 Btu/hr (7,174 W)
68.0 Btu/hr-ft (19.9 W/ft)
10.9 gpm
0.08%
0.17%



LINE SOURCE DATA ANALYSIS

FIG. 2: TEMPERATURE & HEAT RATE VS NATURAL LOG OF TIME

The loop temperature and input heat rate data versus the natural log of elapsed time are shown above in Figure 2. The temperature versus time data was analyzed using the line source method (see page 3) in conformity with ASHRAE and IGSHPA guidelines. A linear curve fit was applied to the average of the supply and return loop temperature data between 10 and 47.1 hr. The slope of the curve fit was found to be 3.87. The resulting thermal conductivity was found to be <u>1.40</u> **Btu/hr-ft-°F**.

THERMAL DIFFUSIVITY

The reported drilling log for this test borehole indicated that the formation consisted of top soil, clay, hardpan, shale, and sandstone. Average heat capacity values for shale and sandstone were calculated from specific heat and density values listed by Kavanaugh and Rafferty¹. A weighted average of heat capacity values based on the indicated formation was used to determine an average heat capacity of $36.6 \text{ Btu/ft}^3-\circ\text{F}$ for the formation. A diffusivity value was then found using the calculated formation thermal conductivity and the estimated heat capacity. The thermal diffusivity for this formation was estimated to be $0.92 \text{ ft}^2/\text{day}$.

¹Stephen P. Kavanaugh and Kevin Rafferty, Geothermal Heating and Cooling: Design of Ground-Source Heat Pump Systems (Atlanta: ASHRAE, 2014), 75.



CERTIFICATE OF CALIBRATION

GRTI maintains calibration of the datalogger, current transducer and voltage transducer on a regular schedule. The components are calibrated by the manufacturer using recognized national or international measurement standards such as those maintained by the National Institute of Standards and Technology (NIST).

FTC Unit 209

DA Unit 40

PRIMARY EQUIPMENT			
COMPONENT CALIBRATION DATE		CALIBRATION DUE DATE	
Datalogger	1/25/2021	1/25/2024	
Current Transducer	2/3/2021	2/3/2024	
Voltage Transducer	2/3/2021	2/3/2024	

GRTI periodically verifies the combined temperature sensor/datalogger accuracy via an ice water bath. Temperature readings are simultaneously taken with a digital thermometer that has been calibrated using instruments traceable to NIST.

DATE	2/18/2021		
THERMOCOUPLE 1 (°F)	32.1 32.1 32.1		
THERMOCOUPLE 2 (°F)	32.0 32.0 32.0		
THERMOCOUPLE 3 (°F)	31.9 31.9 31.9		
THERMOCOUPLE 4 (°F)	32.0 32.0 32.0		
DIGITAL THERMOMETER (°F)	32.1 32.0 32.0		



Orange County Medical Examiners Office

Goshen, New York

December 8, 2021 Terracon Project No. JB215178

Prepared for:

Hyman Hayes Associates, LLC Latham, NY

Prepared by:

Terracon Consultants-NY, Inc. Albany, New York



December 8, 2021

Hyman Hayes Associates, LLC 800 Troy Schenectady Road, Suite 103 Latham, NY 12110



Re: Geotechnical Engineering Report Orange County Medical Examiners Office Wells Farm Road Goshen, New York Terracon Project No. JB215178

Dear Mr. Hayes:

We have completed the Geotechnical Engineering services for the above-referenced project. This study was performed in general accordance with Terracon Proposal No. PJB215178, dated October 5, 2021. This report presents the findings of the subsurface exploration and provides geotechnical recommendations concerning earthwork and the design and construction of foundations, floor slabs retaining walls and pavements for the proposed project.

We appreciate the opportunity to be of service to you on this project. If you have any questions concerning this report or if we may be of further service, please contact us.

Sincerely, Terracon Consultants-NY, Inc.

Asa Barnhill, E.I.T. Staff Geotechnical Engineer

John T. Odorisio, P.E. Sr. Geotechnical Engineer

Joseph Robichaud, Jr., P.E. Sr. Associate/Office Manager

> Terracon Consultants-NY, Inc. 30 Corporate Circle, Suite 201 Albany, New York 12203 P (518) 266 0310 F (518) 266 9238 terracon.com



Environmental 🛑 Facilities 🛑 Geotechnical 🛑 Materials

REPORT TOPICS

INTRODUCTION	1
SITE CONDITIONS	1
PROJECT DESCRIPTION	2
GEOTECHNICAL CHARACTERIZATION	3
GEOTECHNICAL OVERVIEW	5
SEISMIC CONSIDERATIONS	6
LIQUEFACTION	6
EARTHWORK	6
SHALLOW FOUNDATIONS	9
FLOOR SLABS	1
LATERAL EARTH PRESSURES	2
PAVEMENTS1	4
GENERAL COMMENTS	6
FIGURES	7

Note: This report was originally delivered in a web-based format. **Orange Bold** text in the report indicates a referenced section heading. The PDF version also includes hyperlinks which direct the reader to that section and clicking on the *GeoReport* logo will bring you back to this page. For more interactive features, please view your project online at <u>client.terracon.com</u>.

ATTACHMENTS

EXPLORATION AND TESTING PROCEDURES SITE LOCATION AND EXPLORATION PLANS EXPLORATION RESULTS SUPPORTING INFORMATION

Note: Refer to each individual Attachment for a listing of contents.

Orange County Medical Examiners Office Wells Farm Road Goshen, New York Terracon Project No. JB215178 December 8, 2021

INTRODUCTION

This report presents the results of our subsurface exploration and geotechnical engineering services performed for the proposed Medical Examiner's Office to be located at Wells Farm Road in Goshen, New York. The purpose of these services is to provide information and geotechnical engineering recommendations relative to:

- Subsurface soil conditions
- Groundwater conditions
- Site preparation and earthwork
- Lateral earth pressures
- Pavement design and construction
- Frost considerations
- Foundation design and construction
- Floor slab design and construction
- Seismic site classification per NYSBC
- Excavation considerations

The geotechnical engineering Scope of Services for this project included the advancement of five test borings (B-1 through B-5) to depths ranging from about 22 to 52 feet below existing site grades, visual classification and limited laboratory testing of recovered soil samples, and preparation of this summary report.

Maps showing the site and boring locations are presented in the **Site Location** and **Exploration Plan** sections, respectively.

SITE CONDITIONS

ltem	Description		
	The project is located at the Orange County Emergency Services Campus on Wells Farm Road in Goshen, New York.		
	The approximate center of the proposed building is located at:		
Parcel Information	 Latitude: 41.4076° N Longitude: 74.3544° W 		
	See Site Location		

Orange County Medical Examiners Office
Goshen, New York
December 8, 2021
Terracon Project No. JB215178



Item	Description		
Existing Improvements	The area of the proposed building is partially occupied by an existing parking lot and gravel access road to a solar field and water tank.		
	We understand that there are a series of underground utilities which pass below the planned building footprint which are currently planned to be relocated such that they are outside of the new building's footprint.		
Current Ground Cover	r Mixture of asphalt, gravel and vegetation (brush and landscaping).		
Existing Topography (from drawings provided by Hyman Hayes) Grades within the proposed building footprint slope down to the sout the building footprint continue sloping down to the south east to We Road to about elevation 460 feet. Site grading plans indicate the slipinclined at about 1V:3H.			

PROJECT DESCRIPTION

Our understanding of the project is tabulated below.

Item	Description		
	Various correspondences with Hyman Hayes, along with the following schematic drawings and site plans:		
Information Provided	 "20071 – OCME Program_6-29-21" pdf "20071_OCME_Schematic Floor Plan_8-17-21" pdf "As Built Sewer OC Emergency Services Center_grading_utility_asbuilt" pdf "OCME Boring Stakeout" pdf "SITE PLAN 11-8-21 PROPOSED BLDG PARKING" pdf. 		
Project Description	Construction of a new medical examiner's office building located at the southeast corner of the existing parking lot.		
Proposed Structure	The project includes a single-story building with a footprint of about 13,000 square feet. The building will be slab-on-grade (non-basement). Due to the sloping site grades, portions of the building foundation walls will retain soil.		
Building Construction	We understand the building is planned to be structural steel-framed supported on cast-in-place concrete foundations with a concrete slab-on-grade floor.		
Finished Floor Elevation	511 feet.		

Orange County Medical Examiners Office
Goshen, New York
December 8, 2021
Terracon Project No. JB215178



Item	Description	
Maximum Loads (assumed)	 Columns: 100 kips Walls: 3 kips per linear foot (klf) Slabs: 150 pounds per square foot (psf) 	
Grading/Slopes	Cuts of up to about 2 feet and fills on the order of about 19 feet will be required to achieve the proposed fished floor elevation.	
Below-Grade Structures	Conceptual drawings indicate some type of wall structure at the body trailer/delivery truck area. Portions of the building foundation walls will retain earth due to the sloping site grade.	
Free-Standing Retaining Walls	Based on the plans provided there are retaining walls planned to the south west of the trailer loading dock supporting the adjacent water tower compound, one wall about the southern end of the building as well as one wall extending north from the building along the eastern edge of the parking lot. The retaining wall heights vary between about 2 feet and 8 feet in height.	
Pavements	New pavements are planned about the northern limits of the new building to connect the existing parking lot to the new building. We assume that these pavements may be a combination of flexible asphalt and rigid concrete, and that the design life of the pavements is 20 years.	
Estimated Start of Construction	Not provided.	

GEOTECHNICAL CHARACTERIZATION

We have developed a general characterization of the subsurface conditions based upon our review of the subsurface exploration, laboratory data, geologic setting, and our understanding of the project. This characterization, termed GeoModel, forms the basis of our geotechnical calculations and evaluation of site preparation and foundation options. Conditions encountered at each exploration point are indicated on the individual logs. The individual logs can be found in the **Exploration Results** section and the GeoModel can be found in the **Figures** section of this report.

Subsurface Profile

As part of our analyses, we identified the following model layers within the subsurface profile. For a more detailed view of the model layer depths at each boring location, refer to the GeoModel.

Model Layer	Layer Name	General Description
1	Fill	Silty Sand with varying amounts of gravel
2	Glacial Till	Silty Sand with varying amounts of gravel, occasional cobbles and boulders



Surficial materials consisted of about nil to 2 inches of topsoil or about 10 to 12 inches of pavement section at the locations investigated. The topsoil thicknesses indicated on the subsurface logs should be regarded as a rough approximation only; contractors are advised to make their own estimates or determination of topsoil thickness for bidding purposes.

Beneath the surficial materials, fill soils consisting of silty sand with varying amounts of gravel were encountered in borings B-3 through B-5 extending to depths of about 4 to 6 feet below the existing ground surface. The fill soils appear to consist of reworked native glacial till, likely as a result of the grading for construction of the adjacent parking lot and installation of the existing utility that runs through the site. The fill soils were noted to be loose to medium dense based on SPT 'N' values. Underlying the fill soils in borings B-3 through B-5 and directly beneath the surficial materials in borings B-1 and B-2, native glacial till soils consisting of silty sand with varying amounts of gravel with occasional cobbles and boulders noted. The soils were found to be medium dense to very dense based on SPT 'N' values. Each boring terminated without refusal in the native soils at depths varying from about 22 to 52 feet below existing grade.

It should be understood that test borings were not completed in the immediate vicinity of the existing buried utilities which traverse the planned building pad. The depth of uncontrolled fill above and adjacent to the utility lines may vary from those found in the test borings. Invert elevations of the utilities were not shown on the drawings provided.

Groundwater Conditions

Groundwater observations and measurements were made as the boreholes were completed or after being left to stabilize over a weekend as noted on the individual boring logs. It should be understood that, in some instances, these measurements may not reflect actual groundwater levels in the event adequate time did not pass upon completion of the drilling for groundwater to achieve a static level in the augers.

Groundwater was encountered in Boring B-1 at a depth of about 8 feet below existing grade after being left to stabilize over the weekend. Groundwater was not noted at the remaining explorations on site. Based on our observations of soil samples recovered and field measurements or groundwater, it is our opinion the groundwater table is likely present between about 15 to 20 feet below existing grades. As evidenced by Boring B-1, perched water is anticipated to be encountered at various depths at the site. Perched water levels develop when surface water (i.e. precipitation or runoff) enters the subsurface through loose surficial soils and becomes trapped, or perched, on top of less permeable soils such as glacial till.

Fluctuations in groundwater level may occur because of seasonal variations in the amount of rainfall, runoff, and other factors that may differ from those present at the time the explorations were performed. Additionally, grade adjustments on and around the site, as well as surrounding drainage improvements, may affect the water table. The possibility of groundwater level



fluctuations should be considered when developing the design and construction plans for the project.

GEOTECHNICAL OVERVIEW

In general, the subsurface conditions found by our investigation are judged typical of those expected within the general project vicinity, and the project site is considered suitable for support of the proposed building using conventional shallow spread foundations and slab-on-grade design. Based upon our evaluation of the subsurface conditions, we have developed the following guidelines to assist in planning for design and construction.

- New foundations may be supported on undisturbed native soils or on imported structural fill which is placed over the native soils after all existing utilities, fill, or otherwise unsuitable materials which may be found are removed. Existing fills should not be relied upon for new building foundation support.
- If existing fills throughout the site are similar in composition to those found in the test borings, consideration may be given to support the new pavements and floor slabs over the existing fills provided the subgrade surfaces are proof-rolled and stabilized as may be required. It should be understood the proof-rolling will lessen, but not eliminate, the possibility that settlement of pavements and slabs constructed over the existing fills may occur over time and require periodic maintenance.
- Based on the results of limited laboratory testing performed and our observation of the soil samples collected, it should be assumed that the native on-site soils are not suitable for reuse as Structural Fill due to their fines content. Additional laboratory testing of bulk samples should be performed prior to the start of construction to confirm the suitability of the on-site soils for use as Structural Fill.
- In general, groundwater is expected to be below foundation excavation depths and should not be a significant factor in planning for design and construction of the building. If perched water is encountered during construction, it is expected to be limited in volume and standard sump and pump methods should be sufficient for its removal. Dewatering is a means and methods consideration for the contractor.
- It is recommended that existing utilities be rerouted such that they are outside of the new building footprint. We understand that this is the current plan for the project.

We should be provided with the opportunity to review plans and specifications prior to their release for bidding to confirm that our recommendations were properly understood and implemented, and to allow us to refine our recommendations, if warranted, based upon the final design.



The General Comments section provides an understanding of the report limitations.

SEISMIC CONSIDERATIONS

The seismic design requirements for buildings and other structures are based on Seismic Design Category. Site Classification is required to determine the Seismic Design Category for a structure. The Site Classification is based on the upper 100 feet of the site profile defined by a weighted average value of either shear wave velocity, standard penetration resistance, or undrained shear strength in accordance with Section 20.4 of ASCE 7 and the International Building Code (IBC).

Seismic Site Classification

Based on the soil properties encountered at the site and as described on the exploration logs, and the results of shear wave velocity testing completed in similar subsurface profiles in the general project area, it is our professional opinion that the **Seismic Site Classification is D**. Subsurface explorations at this site were extended to a maximum depth of 52 feet. The site properties below the boring depth to 100 feet were estimated based on our experience and knowledge of geologic conditions of the general area. Additional deeper borings or geophysical testing may be performed to confirm the conditions below the current boring depth.

LIQUEFACTION

Based upon the composition, relative density and groundwater conditions encountered in the borings, it is our professional opinion that the site is not susceptible to liquefaction during the design seismic event.

EARTHWORK

Earthwork is anticipated to include stripping of topsoil and or pavements, excavation and backfill for removal of existing utilities, associated site fill and backfill, and foundation excavations. The following sections provide recommendations for use in the preparation of specifications for the work. Recommendations include critical quality criteria, as necessary, to render the site in the state considered in our geotechnical engineering evaluation for foundations, floor slabs, and pavements.

If the owner elects to leave the existing fills in place beneath the building floor slabs and pavements, the compaction and stabilization of the subgrades recommended above will reduce but cannot eliminate the risk of settlement as described in the **Geotechnical Overview** section of this report. If this risk cannot be accepted, the existing fills should be removed in their entirety as part of the site preparation.



Site Preparation

Site preparation should begin with stripping of existing pavements and topsoil from the building and pavement areas. Any existing utilities should be removed in their entirety from beneath the proposed building areas and rerouted outside of the new building footprint.

Prior to placing fills to raise site grades and/or after cuts are made to the plan subgrade elevations, the pavement and building subgrades should be proof-rolled using a steel drum roller with a static weight of at least ten tons. The roller should operate in its vibratory mode, unless requested otherwise by the Geotechnical Engineer observing the work, and travel at a speed not exceeding three feet per second (two miles per hour). The roller should complete at least five passes over all subgrade surfaces in opposing directions. The method of proof-rolling may be modified by the Geotechnical Engineer based upon the conditions revealed at the time of construction.

Soft areas identified by the proof rolling should be investigated to determine the cause and stabilized accordingly. These investigations may include the excavation of test pits. Where materials are found to be unsuitable by the Geotechnical Engineer, they should be removed and replaced as deemed necessary.

Fill Material Types

Based upon the limited soil laboratory testing performed, the on-site soils do not appear to be suitable for reuse as Structural Fill due to their high fines content and should be reserved for use in landscaped areas or wasted off site. Rather, Structural Fill should consist of imported sand and gravel which meets the limits of gradation given below. The imported materials should be free of recycled concrete, asphalt, brick, glass, and pyritic shale rock.

Sieve Size	Percent Finer	
3"	100	
1/4"	30 to 75	
No. 40	5 to 40	
No. 200	0 to 10	

IMPORTED STRUCTURAL FILL

Additional bulk sampling and laboratory testing of on-site materials may be considered to further define their composition and allow for verification of potential reuse as Structural Fill. Any reused material should be free of organics, oversized particles, and unsuitable foreign matter.

Fill Compaction Requirements

The Structural Fill should be placed in uniform loose layers no more than about one-foot thick where heavy vibratory compaction equipment is used. Smaller lifts should be used where hand



operated equipment is required for compaction. Each lift should be compacted to no less than 95 percent of the maximum dry density for the soil which is established by the Modified Proctor Compaction Test, ASTM D1557. In landscape areas, the compaction may be reduced to 90 percent of maximum dry density.

Grading and Drainage

All grades must provide effective drainage away from the building during and after construction and should be maintained throughout the life of the structure. Water retained next to the building can result in soil movements greater than those discussed in this report. Greater movements can result in unacceptable differential floor slab and/or foundation movements, cracked slabs and walls, and roof leaks.

Earthwork Construction Considerations

Shallow excavations for the construction of the proposed structure are anticipated to be accomplished with conventional construction equipment. Upon completion of filling and grading, care should be taken to maintain the subgrade water content prior to construction of floor slabs. Construction traffic over the completed subgrades should be avoided. The site should also be graded to prevent ponding of surface water on the prepared subgrades or in excavations. Water collecting over or adjacent to construction areas should be removed. If the subgrade freezes, desiccates, saturates, or is disturbed, the affected material should be removed, or the materials should be scarified, moisture conditioned, and recompacted prior to floor slab construction.

As a minimum, excavations should be performed in accordance with OSHA 29 CFR, Part 1926, Subpart P, "Excavations" and its appendices, and in accordance with any applicable local, and/or state regulations.

Construction site safety is the sole responsibility of the contractor who controls the means, methods, and sequencing of construction operations. Under no circumstances shall the information provided herein be interpreted to mean Terracon is assuming responsibility for construction site safety, or the contractor's activities; such responsibility shall neither be implied nor inferred.

Construction Observation and Testing

The earthwork efforts should be monitored under the direction of the Geotechnical Engineer. Monitoring should include documentation of adequate removal of surface materials and any unsuitable fills, proof-rolling, and mitigation of any areas identified as needing improvement through proof-rolling. Each lift of new compacted fill should be tested, evaluated, and reworked, as necessary, until approved by the Geotechnical Engineer prior to placement of additional lifts



Foundation bearing grades and subgrades for slabs should be evaluated under the direction of the Geotechnical Engineer. If unanticipated conditions are encountered, the Geotechnical Engineer should prescribe mitigation options.

It should be understood that subsurface conditions will be more fully known when the site is excavated. The continuation of the Geotechnical Engineer into the construction phase of the project will allow for validation of the subsurface conditions assumed to exist for this study and in the development of the design recommendations in this report, along with assessing any variations, providing interim recommendations as necessary and reviewing associated design changes.

SHALLOW FOUNDATIONS

If the site has been prepared in accordance with the requirements noted in **Earthwork** and **Foundation Construction Considerations** sections of this report, the following design parameters and construction procedures are applicable for shallow foundations.

Design Parameters – Compressive Loads

ltem	Description
Maximum Net Allowable Bearing Pressure ^{1, 2}	4,000 pounds per square foot (psf)
Required Bearing Stratum ³	Undisturbed native soils, or Structural Fill placed over the native soils after removal of any existing fill, utilities or otherwise unsuitable material that may be found
Minimum Foundation Dimensions	Columns: 24 inches Continuous: 18 inches
Ultimate Coefficient of Sliding Friction ⁴	.35 (concrete on native soils) .45 (concrete on Structural Fill)
Minimum Embedment below Finished Grade ⁵	Exterior footings in heated/unheated areas: 48 inches Interior footings in unheated areas: 48 inches Interior footings in heated areas: 24 inches
Estimated Total Settlement from Structural Loads ²	Less than about (1) inch
Estimated Differential Settlement ^{2, 6}	About ¾ of total settlement

Orange County Medical Examiners Office Goshen, New York December 8, 2021 Terracon Project No. JB215178



	ltem	Description	
1.	 The maximum net allowable bearing pressure is the pressure in excess of the minimum surrounding overburden pressure at the footing base elevation. An appropriate factor of safety has been applied. Values assume that exterior grades are no steeper than 20% within 10 feet of structure. 		
2.	Values provided are for maximum loads noted in Project Description .		
3.	The bearing grades should be prepared per the recommendations presented below in the Foundation Construction Considerations .		
4.	. Can be used to compute sliding resistance where foundations are placed on suitable soil/materials. Should be neglected for foundations subject to net uplift conditions.		
F	Embedment personant to minimize the offects of freet and/or according water content variations. For elemin		

- 5. Embedment necessary to minimize the effects of frost and/or seasonal water content variations. For sloping ground, maintain depth below the lowest adjacent exterior grade within 5 horizontal feet of the structure. Interior footings in heated area may be seated at the 24-inch depth if allowed by local building codes. In the case of haunched floor slab support for interior partition walls, the minimum depth requirement may be waived (again, if permitted by local building codes).
- 6. Differential settlements are as measured over a span of 50 feet.

A standard perimeter foundation drain should be provided to collect and relieve water which enters the backfill soils after construction is complete. The drain should consist of nominal fourinch diameter perforated PVC or corrugated HDPE pipe set within \pm 12 inches of clean crushed stone composed of ASTM C33 Blend 57 material. The stone should be enveloped with a nonwoven synthetic filter fabric meeting the requirements of NYSDOT standard specifications table 737-01C for drainage geotextile to inhibit siltation. All drains should be provided with clean outs for their maintenance.

Foundation Construction Considerations

The foundations may be seated directly upon undisturbed native soils, or on Structural Fill which is placed over the native soils after removal of existing utilities, fill or otherwise unsuitable materials that may be found. If over-excavation is required beneath the foundations to remove unsuitable material, the excavation should extend horizontally beyond each side of the foundation a distance equal to at least one-half depth of the undercut below the final bearing grade elevation. Replacement material should meet the specification and compaction guidelines for Structural Fill as outlined herein.

Foundation bearing grades should be proof-compacted using a mechanical or large reversible plate tamper to densify the soils loosened by the excavation process unless otherwise directed by the Geotechnical Engineer observing the grades. If groundwater seepage occurs or water collects within excavations from precipitation or runoff, proof compacting should be eliminated, and a minimum six-inch thick base of clean crushed stone should be provided to establish a more uniform and stable base for construction and to assist in dewatering. The stone should be an ASTM C33 Blend 57 aggregate which is enveloped in a non-woven synthetic filter fabric meeting the requirements of NYSDOT standard specifications table 737-01C for drainage geotextile.



All final bearing grades should be relatively firm, stable, and free of loose soil, mud, water and frost. The Geotechnical Engineer should approve the condition of the foundation bearing grades immediately prior to placement of reinforcing steel and concrete.

FLOOR SLABS

Design parameters for floor slabs assume the requirements in the **Earthwork** and **Floor Slab Construction Considerations** sections of this report have been followed. Specific attention should be given to positive drainage away from the structure and positive drainage of the aggregate base beneath the floor slab.

Floor Slab Design Parameters

The floor slabs should be constructed upon a minimum six-inch thick subbase course which conforms to the requirements for NYSDOT Type 2 Subbase or ASTM C33 Blend 57 aggregate. Consideration should be given to using a thicker subbase course in areas subject to heavier loads and/or use, or those exposed to freezing temperatures.

The use of a vapor retarder should be considered beneath concrete slabs on grade covered with wood, tile, carpet, or other moisture sensitive or impervious coverings, or when the slab will support equipment sensitive to moisture. When conditions warrant the use of a vapor retarder, the slab designer should refer to ACI 302 and/or ACI 360 for procedures and cautions regarding its use and placement.

Saw-cut control joints should be placed in the slab to help control the location and extent of cracking. For additional recommendations refer to the ACI Design Manual.

Floor slab subgrades should be prepared as outlined in the Earthwork section herein. Under these conditions, a modulus of subgrade reaction equal to 150 pounds per cubic inch (psi/in) may be assumed at the top of the stone base layer for slab design purposes.

Settlement of floor slabs supported on existing fill materials cannot be accurately predicted but could be larger than normal and result in some cracking. Mitigation measures, as noted in the **Earthwork** section of this report, are critical to the performance of floor slabs. If the risk of potential slab settlement is unacceptable to the owner, all fills must be removed from beneath the slab and replaced with Structural Fill.

Floor Slab Construction Considerations

Even with the base course recommended above, we caution that the subgrades may not support repeated heavy construction traffic or telehandlers without suffering rutting and weaving that may be especially severe during wet seasons. If the grades are to be repeatedly traversed by these types of equipment, they should be reinforced as necessary to support them. Areas which become



disturbed should be excavated and stabilized accordingly. Finished subgrade, within and for at least 10 feet beyond the floor slab, should be protected from traffic, rutting, or other disturbance and maintained in a relatively moist condition until floor slabs are constructed. If the subgrade should become damaged or desiccated prior to construction of floor slabs, the affected material should be removed and Structural Fill should be added to replace the resulting excavation. Final conditioning of the finished subgrade should be performed immediately prior to placement of the floor slab support course.

The Geotechnical Engineer should approve the condition of the floor slab subgrades immediately prior to placement of the floor slab support course, reinforcing steel, and concrete. Attention should be paid to high traffic areas that were rutted and disturbed earlier, and to areas where backfilled trenches are located.

LATERAL EARTH PRESSURES

Design Parameters

Building or site walls that retain earth should be designed to resist lateral pressures, with applicable surcharge loads, assuming the parameters listed below. Active earth pressures may be assumed for walls that are free to deflect as the backfill is placed. At-rest earth pressures should be assumed for all walls that are braced prior to backfilling or applying surcharge loads. The figure below can be referenced to determine the applicability of Active vs. At-Rest earth pressures.



The recommended design parameters, as applicable, are tabulated below;

Design Parameter	Value
Soil Angle of Internal Friction	30 degrees
Coefficient of At-Rest Earth Pressure (Ko)	0.50
Coefficient of Active Earth Pressure (Ka)	0.33
Coefficient of Passive Earth Pressure (Kp)	3.00

Orange County Medical Examiners Office
Goshen, New York
December 8, 2021
Terracon Project No. JB215178



Design Parameter	Value
Total Unit Weight of Compacted Soil	120 pcf
Coefficient of Sliding Friction	0.35 (concrete on native soils) 0.45 (concrete on Structural Fill)
 For the tabulated values to be valid, the wall must be backfilled with <u>imported</u> Structural Fill as specified in the <u>Earthwork</u> section of this report (onsite soils should not be reused for this purpose). The structural backfill must extend out and up from the base of the wall at an angle of at least 45 degrees from vertical for the active and at-rest cases. The tabulated values do not include a safety factor. 	

The recommended design parameters assume that backfill consists of imported Structural Fill as described in the Earthwork section herein, idealized non-sloping conditions on each side of the wall, and that the backfill remains permanently well-drained. Water must not be allowed to collect against the wall unless the wall is designed to accommodate the added hydrostatic pressure. Drainage system recommendations are provided below.

There are several options that may be considered if it is necessary to reduce the lateral loads acting against the building foundation walls. One method would be the use of mechanically (geogrid) stabilized earth with stone filled basket faces constructed several inches off the interior face of the foundation wall. We have used this method on several projects and can provide or assist in the design of this alternative if desired. Other methods to reduce or eliminate the lateral loading against the foundation walls involve the use of engineered materials, crushed aggregate, expanded lightweight shale and expanded polystyrene (geofoam) within the foundation wall's backfill zone.

Whichever material is selected, the engineered backfill material should entirely occupy the backfill zone wedge formed by a line extending up and away from a point two (2) feet beyond the interior edge of the wall at an angle of 45° off the vertical and the foundation wall itself. Where the wall extends beneath the exterior final grade and is backfilled on both its interior and exterior faces to that exterior grade with ordinary Structural Fill, the engineered fill materials to be placed within the backfill zone should be measured from a point two (2) feet beyond the interior edge of the wall at this grade and then up an angle of 45° off the vertical. The engineered material wall backfill evaluation may be performed using the following parameters which are unfactored, i.e. they do not contain a factor of safety and assume the backfills remain drained at all times.

Engineered Material	Total Unit Weight (pcf)	Coefficient of at Rest Earth Pressure (Ko)
50/50 Blend of NYSDOT #1&2 Crushed Aggregate	95	0.18
Nominal ¾" Norlite Expanded Shale Aggregate	65	0.33
Geofoam ASTM 578 Type II	2	N/A



Subsurface Drainage for Earth-Retaining Walls

Foundation drains should be installed as required to prevent surface infiltration and groundwater from becoming trapped in the wall backfill soils. It should extend around the entire building perimeter, not just along basement walls. The drain may consist of a nominal four (4) inch diameter perforated PVC or slotted HDPE pipe embedded at the base of a minimum twelve (12) inch wide column of clean crushed stone (ASTM C-33 Blend 57 crushed aggregate). The stone should be wrapped in a non-woven drainage geotextile meeting the requirements of NYSDOT Table 737-01C or approved equivalent. The drain should connect to a drainage structure or outlet to daylight.

PAVEMENTS

Flexible Pavement Design

The soils encountered in the test borings are considered generally suitable for the support of asphalt pavement, subject to the limitations outlined herein. A critical aspect of pavement performance is site preparation. The pavement sections recommended below assume the site has been prepared as described in the **Earthwork** section of this report.

The flexible pavements sections have been designed in general accord with AASHTO procedures using a reduced subgrade strength and local experience to account for frost and keep the anticipated pavement heave and cracking within generally tolerable limits. With the subgrades prepared as recommended below, a subgrade resilient modulus (M_r) equal to 4,000 psi has been assumed for design purposes.

Two flexible pavement sections may be considered for this site, a Light Duty Section for areas subject to automobile parking, and a Heavy-Duty Section for the entrance road and other areas which may be subject to truck traffic. For design purposes, it has been assumed that the pavement design life is 20-years, and that daily equivalent single axle loads (ESAL) are equal to 1 for Light Duty and 25 for Heavy Duty Sections. If the traffic loads vary from these, we should be provided with the opportunity to refine the pavement sections accordingly.

All materials should meet the requirements specified in the latest edition of the New York State Department of Transportation (NYSDOT) Standard Specifications for Construction Materials.

Flexible Pavement Design			
Layer	2019 NYSDOT Reference	Light Duty (inches)	Heavy Duty (inches)
Asphaltic Concrete Top	Item 402.127303	1.5	2.0

Orange County Medical Examiners Office Goshen, New York December 8, 2021 Terracon Project No. JB215178



Flexible Pavement Design			
Layer	2019 NYSDOT Reference	Light Duty (inches)	Heavy Duty (inches)
Asphaltic Concrete Binder	Item 402.257903	2.0	3.0
Crusher-Run Stone Base	Section 733.04, Type 2	8	12
Stabilization Geotextile	Section 737-01, Table E	Single Ply	Single Ply

Rigid Pavement Design

Rigid pavements should be provided with a minimum six-inch thick base of crusher-run stone (NYSDOT section 733-04, Type 2 material) placed over a stabilization geotextile. The pavements may be designed assuming a modulus of subgrade reaction equal to 150 pounds per cubic inch at the top of the base layer.

Pavement Drainage

Accumulation of water on pavement subgrades should be avoided by grading the subgrade to a slope of at least two percent, and/or by providing underdrains. Failure to provide adequate drainage will shorten pavement life.

Pavement Maintenance

All pavements require periodic care, and preventive maintenance should be planned and provided for through an on-going pavement management program. Maintenance activities are intended to slow the rate of pavement deterioration and to preserve the pavement investment. Maintenance consists of both localized maintenance (e.g., crack and joint sealing and patching) and global maintenance (e.g., surface sealing). Settlement of pavements due to consolidation of the existing fills may also occur and require periodic maintenance.

Frost Considerations

Frost may penetrate beneath sidewalks and pavements and cause them to heave, and resulting displacements may be differential, particularly where sidewalks and pavements meet building doorways and along curbs. If the potential heaving of these features is to be minimized, a 16-inch thick base of ASTM C33 Blend 57 crushed stone should be placed beneath the sidewalks or pavements, along with an underdrain to relieve any collected waters, to limit the potential heave to generally tolerable magnitudes for most winters.

Orange County Medical Examiners Office Goshen, New York December 8, 2021 Terracon Project No. JB215178



GENERAL COMMENTS

Our analysis and opinions are based upon our understanding of the project, the geotechnical conditions in the area, and the data obtained from our site exploration. Natural variations will occur between exploration point locations or due to the modifying effects of construction or weather. The nature and extent of such variations may not become evident until during or after construction. Terracon should be retained as the Geotechnical Engineer, where noted in this report, to provide observation and testing services during pertinent construction phases. If variations appear, we can provide further evaluation and supplemental recommendations. If variations are noted in the absence of our observation and testing services on-site, we should be immediately notified so that we can provide evaluation and supplemental recommendations.

Our Scope of Services does not include either specifically or by implication any environmental or biological (e.g., mold, fungi, bacteria) assessment of the site or identification or prevention of pollutants, hazardous materials or conditions. If the owner is concerned about the potential for such contamination or pollution, other studies should be undertaken.

Our services and any correspondence or collaboration through this system are intended for the sole benefit and exclusive use of our client for specific application to the project discussed and are accomplished in accordance with generally accepted geotechnical engineering practices with no third-party beneficiaries intended. Any third-party access to services or correspondence is solely for information purposes to support the services provided by Terracon to our client. Reliance upon the services and any work product is limited to our client and is not intended for third parties. Any use or reliance of the provided information by third parties is done solely at their own risk. No warranties, either express or implied, are intended or made.

Site characteristics as provided are for design purposes and not to estimate excavation cost. Any use of our report in that regard is done at the sole risk of the excavating cost estimator as there may be variations on the site that are not apparent in the data that could significantly impact excavation cost. Any parties charged with estimating excavation costs should seek their own site characterization for specific purposes to obtain the specific level of detail necessary for costing. Site safety, and cost estimating including, excavation support, and dewatering requirements/design are the responsibility of others. If changes in the nature, design, or location of the project are planned, our conclusions and recommendations shall not be considered valid unless we review the changes and either verify or modify our conclusions in writing.

FIGURES

Contents:

GeoModel

GEOMODEL

Orange County Medical Examiners Office Goshen, New York Terracon Project No. JB215178



This is not a cross section. This is intended to display the Geotechnical Model only. See individual logs for more detailed conditions.

Model Layer	Layer Name	General Description
1	Fill	Silty Sand with varying amounts of gravel
2	Glacial Till	Silty Sand with varying amounts of gravel, occasional cobbles and boulders



LEGEND

✓ Second Water Observation

NOTES:

Layering shown on this figure has been developed by the geotechnical engineer for purposes of modeling the subsurface conditions as required for the subsequent geotechnical engineering for this project. Numbers adjacent to soil column indicate depth below ground surface.

Terracon

GeoReport

Groundwater levels are temporal. The levels shown are representative of the date and time of our exploration. Significant changes are possible over time. Water levels shown are as measured during and/or after drilling. In some cases, boring advancement methods mask the presence/absence of groundwater. See individual logs for details. ATTACHMENTS


EXPLORATION AND TESTING PROCEDURES

Field Exploration

Number of Borings	Boring Depth (feet) ¹	Location
5	22 to 52	Planned building area
1. Below ground surface.		

Boring Layout and Elevations: The test locations were established in the field by Terracon using a hand-held GPS unit, taped measurements and/or visual reference from existing site features. Approximate ground surface elevations were obtained by interpolation from "OCME Boring Stakeout" pdf. If actual elevations in the field and more precise boring locations are desired, we recommend borings be surveyed following completion of fieldwork.

Subsurface Exploration Procedures: We advanced the borings with an ATV-mounted rotary drill rig using continuous flight augers. In the split-barrel sampling procedure, a standard 2-inch outer diameter split-barrel sampling spoon was driven into the ground by a 140-pound automatic hammer falling a distance of 30 inches. The number of blows required to advance the sampling spoon the middle 12 inches of a normal 24-inch penetration is recorded as the Standard Penetration Test (SPT) resistance value. When an 18-inch sample is taken, the N-value is recorded as the number of blows required to advance the sampling spoon the final 12 inches. The SPT resistance values, also referred to as N-values, are indicated on the boring logs at the test depths. We observed and recorded groundwater levels during drilling and sampling as well as over the weekend where noted. For safety purposes, all borings were backfilled with auger cuttings after their completion. Pavements were patched with cold-mix asphalt and/or pre-mixed concrete, as appropriate.

Our exploration team prepared field boring logs as part of the drilling operations. These field logs included visual classifications of the materials encountered during drilling and our interpretation of the subsurface conditions between samples. The sampling depths, penetration distances, and other sampling information were recorded on the field boring logs.

The samples were placed in appropriate containers and taken to our laboratory for visual classification by a Geologist or Geotechnical Engineer. The soils were described based on the material's color, texture, plasticity and moisture condition. Soil classifications are in general accordance with the Unified Soil Classification System (USCS) as summarized herein. Final boring logs were prepared, and they represent the Geotechnical Engineer's interpretation based on the field logs and visual classifications, along with any laboratory testing performed.

Geotechnical Engineering Report

Orange County Medical Examiners Office Goshen, New York December 8, 2021 Terracon Project No. JB215178



Laboratory Testing

The project engineer reviewed the field data and assigned laboratory tests to understand the engineering properties of the various soil strata, as necessary, for this project. Procedural standards noted below are for reference to methodology in general. In some cases, variations to methods were applied because of local practice or professional judgment. Standards noted below include reference to other, related standards. Such references are not necessarily applicable to describe the specific test performed.

- ASTM D2216 Standard Test Methods for Laboratory Determination of Water (Moisture) Content of Soil and Rock by Mass (6 samples tested)
- ASTM D6913 Standard Test Method for Particle-Size Analysis of Soils (6 samples tested)

SITE LOCATION AND EXPLORATION PLANS

Contents:

Site Location Plan Exploration Plan

Note: All attachments are one page unless noted above.

SITE LOCATION

Orange County Medical Examiners Office - Goshen, New York December 8, 2021 - Terracon Project No. JB215178





DIAGRAM IS FOR GENERAL LOCATION ONLY, AND IS NOT INTENDED FOR CONSTRUCTION PURPOSES

MAP PROVIDED BY MICROSOFT BING MAPS

EXPLORATION PLAN

Orange County Medical Examiners Office
Goshen, New York
December 8, 2021
Terracon Project No. JB215178





EXPLORATION RESULTS

Contents:

Boring Logs (B-1 through B-5) Grain Size Distribution (6 pages)

Note: All attachments are one page unless noted above.

_			BORING L	OG NO. B-1						Page 1 of	1
F	PROJ	EC1: Orange County Medical Examin 22 Wells Farm Road	ners Office	CLIENT: Hyman Latham	Hayes A , New Y	ork	ciates	s L	LC		
ER	g	Goshen, New York					NS	щ	ln.)		(9
MODEL LAYI	GRAPHIC LO	Latitude: 41.4076° Longitude: -74.3545°	٩	opproximate Surface Elev.: 50	9 (Ft.) +/-	DEPTH (Ft.)	WATER LEVE DBSERVATIO	SAMPLE TYF	RECOVERY (I	FIELD TESI RESULTS	WATER CONTENT (%
-	001	DEPTH 0.2.∧ ASPHALT		ELEVAT	<u>/\509+/</u> ∕						
		0.8 \ AGGREGATE BASE COURSE GLACIAL TILL: SILTY SAND (SM), occasi dense to very dense	ional cobbles and I	ooulders, brown,	508.5+/-	_		\langle	22	9-12-18-24 N=30	8.7
		Grades with gravel				_		\prec	4	28-50/4"	-
						5 — _		$\left \right $	24	16-24-23-25 N=47	_
		Grades grayish brown				_		$\left\langle \right\rangle$	22	21-23-28-34 N=51	
2		Same, trace clay				10— _		X	24	7-12-13-24 N=25	-
						-					
						15— _		X	1	16-19-24-26 N=43	-
						_					
		Grades gray			487+/-	20—		$\left\langle \right\rangle$	2	30-28-30-34 N=58	_
		Boring Terminated at 22 Feet				_					
	Sti	ratification lines are approximate. In-situ, the transition may	/ be gradual.		Hammer Ty	pe: Aut	omatic				
Adv	/ancem4	ent Method:	Soo Evolution and T		lotes:						
2	2 1/4" ID	HSA	See Exploration and Te description of field and used and additional da See Supporting Informe	ation for explanation of	ogged by A	EB					
Aba E	andonmo Borings I Sealed v	ent Method: backfilled with soil cuttings upon completion. vith bituminous cold patch at surface.	symbols and abbreviat Elevations were interposite plan	blated from a topographic							
		WATER LEVEL OBSERVATIONS		Bo	oring Started	: 10-25-	-2021		Borin	g Completed: 10-25	-2021
	No	o nee standing water observed	nerr		ill Rig: Died	rich D-5	60		Drille	er: S. Morey	
			30 Corpora Alba	te Cir Ste 201 ny, NY Pr	oject No.: JE	3215178	8				

PROJI									Ŭ	•	
	ECT: Orange County Medical Examine	ers Office	CLIENT: Hyman Lathan	n Hayes / n, New Y	Asso ′ork	ciate	s L	LC			
SITE:	22 Wells Farm Road Goshen, New York										
GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 41.4076° Longitude: -74.3542°	Aŗ	opproximate Surface Elev.: 5	i07 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (In.)	FIELD TEST RESULTS	WATER CONTENT (%)	
000	0.3 ^ ASPHALT		ELEVA	ATION (Ft.) 							
	AGGREGATE BASE COURSE GLACIAL TILL: SILTY SAND WITH GRAVEI boulders, brown, medium dense to very den	<u>L (SM)</u> , occasiona ise	al cobbles and		_	-	\setminus	22	3-12-15-10 N=27		
					-		X	20	12-16-19-34 N=35	8.5	
					5		X	24	16-21-29-35 N=50		
					-		X	_4	50/5"		
	Grades grayish brown				10- - -		X	18	15-19-28-33 N=47	-	
	Grades gray				- - 15		\setminus	24	15-19-15-16 N=34	_	
					- - 20		\bigvee	24	22-20-26-26		
	22.0 Boring Terminated at 22 Feet			485+/-	_		Δ		N=46		
Str	ratification lines are approximate. In-situ, the transition may be	e gradual.		Hammer Ty	rpe: Aut	omatic					
vanceme 2 1/4" ID	ent Method: Se HSA de: Use	ee Exploration and Test scription of field and land additional data	sting Procedures for a aboratory procedures a (If any).	Notes: Logged by A	ιЕВ						
andonme Borings b Sealed w	Se ent Method: syr packfilled with soil cuttings upon completion. vith bituminous cold patch at surface.	ee Supporting Informa mbols and abbreviatio evations were interpol e plan.	tion for explanation of ons. lated from a topographic								
N/-	WATER LEVEL OBSERVATIONS			Boring Started	d: 10-25	-2021		Borin	g Completed: 10-25	-2021	
IVC	The standing water UDSErved	30 Corporate Alban	CILUN e Cir Ste 201	Drill Rig: Diedrich D-50 Dr				Drille	Driller: S. Morey		
	Borings I Standonmed Scaled w	Image: Second state of the second s	Calculate. If JAURO Exclusional Computer State DEPTH Calculat Titl: SILTY SAND WITH GRAVEL (SM), occasional boulders, brown, medium dense to very dense Grades grayish brown Grades gray 22.0 Boring Terminated at 22 Feet Stratification lines are approximate. In-situ, the transition may be gradual. Areacement Method: 21/4 ID HSA Seade with bituminous cold patch at surface. Seade with bituminous cold patch at surface. Eventor Method: Sorgenet Method: Seade with bituminous cold patch at surface. No free standing water observed		Approximate Surface Elev: 507 (F.) +/- ElevAtion (F) Asserbat Sufface Elev: 507 (F) Sufface Suffa	Approximate Surface Elev: 507 (FL) +/- DEPTH ELEVATION (FL) Approximate Surface Elev: 507 (FL) +/- Second Surface Surface Test Second Surface Surface Test Second Surface S	Buildow - H.HOTO Exinglade H.HOT	Dependence Approximate Surface Elev:: 507 (R.) +/- DEPTH ELevatoria Cardes grayish Status Statistication lines are approximate. In-statu, the transition may be gradual. Image: Statistication lines are approximate. In-statu, the transition may be gradual. Statistication lines are approximate. In-statu, the transition may be gradual. Image: Statistication lines are approximate. In-statu, the transition may be gradual. Statistication lines are approximate. In-statu, the transition may be gradual. Image: Statistication lines are approximate. In-statu, the transition may be gradual. Asternet Method: Statistication lines are approximate. In-statu, the transition may be gradual. Image: Statistication lines are approximate. In-statu, the transition may be gradual. Asternet Method: Statistication lines are approximate. In-statu, the transition may be gradual. Image: Statistication lines are approximate. In-statu, the transition may be gradual. Asternet Method: Statistication lines are approximate. In-statu, the transition may be gradual. Image: Statistication lines are approximate. In-statu. Asternet Construction Statistication lines are approximate. In-statu. Statistication lines are approximate. In-statu. Asternet Construction Statistication lines are approximate. In-statu. Statistication lines are approximate. In-statu. Asternet Constructin Statistication lines are appr	Approximate Surface Elex: 507 (Pt) vi Fig. Fig. (Pt) DEPTH ELEXATION (FL) State DEPTH ELEXATION (FL) State Or addres Gravity Surface Elex: 507 (Pt) vi State 22 Grades grayish brown	Both Hard Hardon Approximate Burlace Elev: 507 (F) 1/4 End State End S	

					-					Fage 10	1
Ρ	ROJ	ECT: Orange County Medical Examiners Office	e	CLIENT: Hyma Latha	in Hayes . im, New \	Asso (ork	ciate	es L	LC		
S	ITE:	22 Wells Farm Road Goshen, New York									
MODEL LAYER	GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 41.4074° Longitude: -74.3542°	Ą	pproximate Surface Elev.:	: 500 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (In.)	FIELD TEST RESULTS	WATER CONTENT (%)
		0.2 \TOPSOIL FILL - SILTY SAND WITH GRAVEL (SM) rootlets note	ed fine	grained brown				\bigvee	19	3-4-3-3	
1		loose to medium dense		g, 2 ,		_	-	$\left\langle \right\rangle$	19	4-10-12-18	11.3
		4.0 GLACIAL TILL: SILTY SAND WITH GRAVEL (SM), oc	casiona	al cobbles and	496+/-	_	-	$\left(\right)$		N=22	
		boulders, brown, medium dense to dense				5		Д	24	N=23	
						_	-	X	24	14-16-14-14 N=30	
						_					
						10	-	X	24	12-15-18-22 N=33	
2						_	-				
		cobbles and boulders noted				15-				40.40.45.45	
						_		X	1	18-13-15-15 N=28	
						_	-				
		Grades gray				20	-	\mathbf{n}	7	15-18-20-24 N=38	
		22.0 Boring Terminated at 22 Feet			478+/-	-					
	Str	atification lines are approximate. In-situ, the transition may be gradual.			Hammer Ty	/pe: Aut	omatic	;			
Advancement Method: See Exploration and Testing Procedures for a description of field and laboratory procedures used and additional data (If any). Notes: Logged by AEB											
Aba B	ndonme oring ba	ent Method: ackfilled with soil cuttings upon completion. Elevations were	g Informa bbreviati e interpo	tion for explanation of ons. lated from a topographic							
		WATER LEVEL OBSERVATIONS			Boring Starte	d: 10-25	-2021		Borin	g Completed: 10-25-	-2021
	No	free standing water observed		acon	Drill Rig: Died	drich D-5	60		Drille	er: S. Morey	
		30	Corporat Albar	e Cir Ste 201	Project No	B21517	8		1	-	

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL JB215178 ORANGE COUNTY MED.GPJ TERRACON_DATATEMPLATE.GDT 11/29/21

Page 1 of 1

			BORING L	OG NO. B-4	4					Page 1 of	1
Ī	PROJ	ECT: Orange County Medical Exami	ners Office	CLIENT: Hyma	n Hayes	Asso	ciate	s L	LC		
	SITE:	22 Wells Farm Road Goshen, New York		Latia	iii, NCW I	UK					
MODEL LAYER	GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 41.4073° Longitude: -74.3545°	Ą	pproximate Surface Elev.:	496 (Ft.) +/- /ATION (Ft)	DEPTH (Ft.)	WATER LEVEL OBSERVATIONS	SAMPLE TYPE	RECOVERY (In.)	FIELD TEST RESULTS	WATER CONTENT (%)
1		FILL - SILTY SAND WITH GRAVEL (SM), loose	rootlets noted, fine	grained, brown,		_		$\left \right\rangle$	18	5-4-1-1 N=5	
29/21		4.0			492+/-	_		X	20	1-2-2-5 N=4	17.4
E.GDT 11/		GLACIAL TILL: SILTY SAND WITH GRAY boulders, brown, medium dense to dense	VEL (SM), occasiona e	al cobbles and		5 -		X	24	7-11-14-14 N=25	
ATATEMPLAT						-		X	24	14-18-19-21 N=37	_
D.GPJ TERRACON_D						- 10- -		$\left \right\rangle$	24	11-14-15-15 N=29	_
8 ORANGE COUNTY MEE						- - 15- -		$\left \right\rangle$	19	9-13-15-19 N=28	_
OG-NO WELL JB21517		Grades gray			474+/-	- 20 -		\setminus	22	22-18-19-17 N=37	_
D FROM ORIGINAL REPORT. GEU SMART I		Boring Terminated at 22 Feet									
PARATE	Str	atification lines are approximate. In-situ, the transition ma	ay be gradual.		Hammer Ty	/pe: Aut	omatic		I	1	
0G IS NOT VALID IF SE	vanceme 2 1/4" ID andonme Boring ba	ent Method: HSA ent Method: ackfilled with soil cuttings upon completion.	See Exploration and Te description of field and l used and additional dat See Supporting Informa symbols and abbreviation Elevations were interpo	sting Procedures for a laboratory procedures a (If any). ation for explanation of ons. lated from a topographic	Notes: Logged by A	AEB					
NG LC	N/-	WATER LEVEL OBSERVATIONS		Boring Started:			Started: 10-25-2021 Boring Complet			ng Completed: 10-25	-2021
BOR	INC	nice standing water observed			Drill Rig: Diec	Irich D-5	60		Drille	er: S. Morey	
THIS			30 Corporat Albar	e Cir Ste 201 ny, NY	Project No.: J	B21517	8		1		

		BORING L	_OG NO. B-	5				Page 1 of	2
PROJ	ECT: Orange County Medical Ex	aminers Office	CLIENT: Hyma Latha	n Hayes As m, New Yo	soci rk	iates	LLC		
SITE:	22 Wells Farm Road Goshen, New York								
10DEL LAYER SRAPHIC LOG	LOCATION See Exploration Plan Latitude: 41.4074° Longitude: -74.3547°		Approximate Surface Elev.	512 (Ft.) +/-	DEPTH (Ft.)	A LEVEL SERVATIONS AMPLE TYPE	ECOVERY (In.)	FIELD TEST RESULTS	WATER
2 0	DEPTH FILL - SILTY SAND (SM), rootlets no	oted, brown, loose to m	ELEV Edium dense	/ATION (Ft.)	\$	≤ <u>R</u> ⊗	8	3344	
							12	N=7	18
1					_		20	3-3-5-8 N=8	13
	Grades trace gravel			506+/-	5 —		22	7-10-18-18 N=28	
	GLACIAL TILL: SILTY SAND (SM), of gray, medium dense to very dense	occasional cobbles and	boulders, brown to			\mathbf{v}	1	16-22-22-22 N=44	
	Grades trace clay			1	- 10 -		24	5-10-10-13 N=20	_
				1	- 15 -		24	8-14-17-21 N=31	_
	Grades gray			2	 20 		24	14-16-19-20 N=35	_
				2	 		24	14-18-20-26 N=38	
				3	_ 30-				
St	ratification lines are approximate. In-situ, the transiti	ion may be gradual.		Hammer Type	: Autor	matic			
Advancem 2 1/4" ID	ent Method:) HSA	See Exploration and description of field an used and additional d	Testing Procedures for a diaboratory procedures lata (If any).	Notes: Logged by AEE	3				
Abandonm Boring b	ent Method: ackfilled with soil cuttings upon completion.	See Supporting Inforr symbols and abbrevia Elevations were interr	nation for explanation of ations.						
	WATER LEVEL OBSERVATIONS	site plan.		Boring Started: 1	0-22-20	021	Borir	ng Completed: 10-22	2-2021
<u> </u>	0' measured after weekend			Drill Rig: Diedric	h D-50		Drille	er: S. Morey	
			ale Or Ste 201 Dany, NY	Project No.: JB2	15178				

			BORING L	og no. B-	5					Page 2 of	2
Ρ	ROJ	ECT: Orange County Medical Exami	iners Office	CLIENT: Hyma	n Hayes A	Asso (ork	ciate	es L	LC	•	
S	ITE:	22 Wells Farm Road Goshen, New York				UII					
MODEL LAYER	GRAPHIC LOG	LOCATION See Exploration Plan Latitude: 41.4074° Longitude: -74.3547°	A¢	oproximate Surface Elev.:	: 512 (Ft.) +/-	DEPTH (Ft.)	WATER LEVEL BSERVATIONS	AMPLE TYPE	ECOVERY (In.)	FIELD TEST RESULTS	WATER CONTENT (%)
		DEPTH GLACIAL TILL: SILTY SAND (SM), occas gray, medium dense to very dense <i>(cont</i>	sional cobbles and b inued)	ELE oulders, brown to	VATION (Ft.)	_	-0		24	21-35-28-23 N=63	-
						- 35 -	-	X	22	14-15-18-19 N=33	-
2						- 40 -	-	X	24	10-11-15-20 N=26	-
						- 45- -	-	X	20	19-25-33-37 N=58	-
		52.0			460+/-	- 50- -	-	X	22	20-27-31-42 N=58	-
	Str	atification lines are approximate. In situ, the transition m	av be gradual		Hammer Ty	vpe: Aut	omatic				
	Gu	anisation mostare approximate, mosta, ute utansition me	-, yruddar.			, po. Au	Small				
Advancement Method: 2 1/4" ID HSA bandonment Method: See Exploration and Tes description of field and la used and additional data See Supporting Informat symbols and abbreviatio				sting Procedures for a aboratory procedures a (If any). tion for explanation of ons.	Notes: Logged by A	АЕВ					
	2	WATER LEVEL OBSERVATIONS	Elevations were interpol	lated from a topographic					L		
	7 g/)' measured after weekend	Terra	acon	Boring Started Drill Rig: Died	Boring Started: 10-22-2021 Boring Completed: 10-22-2 Drill Rig: Diedrich D-50 Driller: S. Morev					2021
	_ 0.(י וויבמטויבע מונכו שפפאפווע	30 Corporate Albar	e Cir Ste 201 ny, NY	Project No.: J	B21517	8				

THIS BORING LOG IS NOT VALID IF SEPARATED FROM ORIGINAL REPORT. GEO SMART LOG-NO WELL JB215178 ORANGE COUNTY MED.GPJ TERRACON_DATATEMPLATE.GDT 11/29/21

 ∇







GRAIN SIZE: USCS-2 JB215178 ORANGE COUNTY MED.GPJ TERRACON. DATATEMPLATE.GDT 11/16/21 LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT.





GRAIN SIZE: USCS-2 JB215178 ORANGE COUNTY MED.GPJ TERRACON. DATATEMPLATE.GDT 11/16/21 LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT.



GRAIN SIZE: USCS-2 JB215178 ORANGE COUNTY MED.GPJ TERRACON. DATATEMPLATE.GDT 11/16/21 LABORATORY TESTS ARE NOT VALID IF SEPARATED FROM ORIGINAL REPORT.

SUPPORTING INFORMATION

Contents:

General Notes Unified Soil Classification System Description of Rock Properties

Note: All attachments are one page unless noted above.

GENERAL NOTES DESCRIPTION OF SYMBOLS AND ABBREVIATIONS Orange County Medical Examiners Office Goshen, New York Terracon Project No. JB215178



SAMPLING	WATER LEVEL		FIELD TESTS
	_── Water Initially Encountered	N	Standard Penetration Test Resistance (Blows/Ft.)
Split Spoon	Water Level After a Specified Period of Time		Hand Penetrometer
	Water Level After (T) Torvane a Specified Period of Time		Torvane
	Cave In Encountered	(DCP)	Dynamic Cone Penetrometer
	Water levels indicated on the soil boring logs are the levels measured in the borehole at the times indicated. Croundwater level variations will accur	UC	Unconfined Compressive Strength
	over time. In low permeability soils, accurate determination of groundwater levels is not possible with short term water level	(PID)	Photo-Ionization Detector
	(OVA)	Organic Vapor Analyzer	

DESCRIPTIVE SOIL CLASSIFICATION

Soil classification as noted on the soil boring logs is based Unified Soil Classification System. Where sufficient laboratory data exist to classify the soils consistent with ASTM D2487 "Classification of Soils for Engineering Purposes" this procedure is used. ASTM D2488 "Description and Identification of Soils (Visual-Manual Procedure)" is also used to classify the soils, particularly where insufficient laboratory data exist to classify the soils in accordance with ASTM D2487. In addition to USCS classification, coarse grained soils are classified on the basis of their in-place relative density, and fine-grained soils are classified on the basis of their consistency. See "Strength Terms" table below for details. The ASTM standards noted above are for reference to methodology in general. In some cases, variations to methods are applied as a result of local practice or professional judgment.

LOCATION AND ELEVATION NOTES

Exploration point locations as shown on the Exploration Plan and as noted on the soil boring logs in the form of Latitude and Longitude are approximate. See Exploration and Testing Procedures in the report for the methods used to locate the exploration points for this project. Surface elevation data annotated with +/- indicates that no actual topographical survey was conducted to confirm the surface elevation. Instead, the surface elevation was approximately determined from topographic maps of the area.

	STRENGTH TERMS							
RELATIVE DENSITY (More than 50% Density determined by	OF COARSE-GRAINED SOILS retained on No. 200 sieve.) Standard Penetration Resistance	Consistency de	CONSISTENCY OF FINE-GRAINED (50% or more passing the No. 200 s termined by laboratory shear strength te procedures or standard penetration re	SOILS sieve.) esting, field visual-manual sistance				
Descriptive Term (Density)	Standard Penetration or N-Value Blows/Ft.	Descriptive Term (Consistency)	Unconfined Compressive Strength Qu, (tsf)	Standard Penetration or N-Value Blows/Ft.				
Very Loose	0 - 3	Very Soft	less than 0.25	0 - 1				
Loose	4 - 9	Soft	0.25 to 0.50	2 - 4				
Medium Dense	10 - 29	Medium Stiff	0.50 to 1.00	4 - 8				
Dense	30 - 50	Stiff	1.00 to 2.00	8 - 15				
Very Dense	> 50	Very Stiff	2.00 to 4.00	15 - 30				
		Hard	> 4.00	> 30				

RELEVANCE OF SOIL BORING LOG

The soil boring logs contained within this document are intended for application to the project as described in this document. Use of these soil boring logs for any other purpose may not be appropriate.

UNIFIED SOIL CLASSIFICATION SYSTEM

Terracon GeoReport

	Soil Classification Soil Classification										
Criteria for Assigni	ing Group Symbols	and Group Names	Using Laboratory	Tests A	Group Symbol	Group Name ^B					
		Clean Gravels:	$Cu \geq 4$ and $1 \leq Cc \leq 3$ $^{\textbf{E}}$		GW	Well-graded gravel F					
	Gravels: More than 50% of	Less than 5% fines ^C	Cu < 4 and/or [Cc<1 or 0	Cc>3.0] <mark>=</mark>	GP	Poorly graded gravel F					
	coarse fraction	Gravels with Fines:	Fines classify as ML or N	ИН	GM	Silty gravel F, G, H					
Coarse-Grained Soils:		More than 12% fines ^C	Fines classify as CL or C	ЭН	GC	Clayey gravel ^{F, G, H}					
on No. 200 sieve	Sands: 50% or more of coarse fraction passes No. 4 sieve	Clean Sands:	$Cu \ge 6$ and $1 \le Cc \le 3^{E}$		SW	Well-graded sand					
		Less than 5% fines P	Cu < 6 and/or [Cc<1 or 0	Cc>3.0] <mark>=</mark>	SP	Poorly graded sand					
		Sands with Fines:	Fines classify as ML or N	ИН	SM	Silty sand ^{G, H, I}					
		More than 12% fines ^D	Fines classify as CL or C	ж	SC	Clayey sand ^{G, H, I}					
		Incompation	PI > 7 and plots on or above "A"		CL	Lean clay ^{K, L, M}					
	Silts and Clays:	inorganic:	PI < 4 or plots below "A" line J		ML	Silt K, L, M					
	Liquid limit less than 50	Organic:	Liquid limit - oven dried	< 0.75		Organic clay ^{K, L, M, N}					
Fine-Grained Soils:		organic.	Liquid limit - not dried	< 0.75	OL	Organic silt ^K , L, M, O					
No. 200 sieve		Inorganic:	PI plots on or above "A"	line	СН	Fat clay ^{K, L, M}					
	Silts and Clays:	morganic.	PI plots below "A" line		MH	Elastic Silt K, L, M					
	Liquid limit 50 or more	Organic:	Liquid limit - oven dried	< 0.75	ОН	Organic clay K, L, M, P					
		Organic.	Liquid limit - not dried	< 0.75	On	Organic silt ^{K, L, M, Q}					
Highly organic soils: Primarily organic matter, dark in color, and organic odor					PT	Peat					
A Pased on the material passing the 2 inch (75 mm) signal HIIf fines are organic, add "with organic fines" to group name											

A Based on the material passing the 3-inch (75-mm) sieve.

^B If field sample contained cobbles or boulders, or both, add "with cobbles or boulders, or both" to group name.

- ^c Gravels with 5 to 12% fines require dual symbols: GW-GM well-graded gravel with silt, GW-GC well-graded gravel with clay, GP-GM poorly graded gravel with silt, GP-GC poorly graded gravel with clay.
- ^D Sands with 5 to 12% fines require dual symbols: SW-SM well-graded sand with silt, SW-SC well-graded sand with clay, SP-SM poorly graded sand with silt, SP-SC poorly graded sand with clay.

$$10 \quad Cc = \frac{(D_{30})^2}{D_{10} \times D_{60}}$$

 $E Cu = D_{60}/D_{10}$

F If soil contains \geq 15% sand, add "with sand" to group name.

^G If fines classify as CL-ML, use dual symbol GC-GM, or SC-SM.

- ^H If fines are organic, add "with organic fines" to group name.
- If soil contains \geq 15% gravel, add "with gravel" to group name.
- ^J If Atterberg limits plot in shaded area, soil is a CL-ML, silty clay.
- K If soil contains 15 to 29% plus No. 200, add "with sand" or "with gravel," whichever is predominant.
- L If soil contains ≥ 30% plus No. 200 predominantly sand, add "sandy" to group name.
- ^MIf soil contains ≥ 30% plus No. 200, predominantly gravel, add "gravelly" to group name.
- ^N PI \geq 4 and plots on or above "A" line.
- PI < 4 or plots below "A" line.
- P PI plots on or above "A" line.
- QPI plots below "A" line.



DESCRIPTION OF ROCK PROPERTIES



	WEATHERING
Term	Description
Unweathered	No visible sign of rock material weathering, perhaps slight discoloration on major discontinuity surfaces.
Slightly weathered	Discoloration indicates weathering of rock material and discontinuity surfaces. All the rock material may be discolored by weathering and may be somewhat weaker externally than in its fresh condition.
Moderately weathered	Less than half of the rock material is decomposed and/or disintegrated to a soil. Fresh or discolored rock is present either as a continuous framework or as corestones.
Highly weathered	More than half of the rock material is decomposed and/or disintegrated to a soil. Fresh or discolored rock is present either as a discontinuous framework or as corestones.
Completely weathered	All rock material is decomposed and/or disintegrated to soil. The original mass structure is still largely intact.
Residual soil	All rock material is converted to soil. The mass structure and material fabric are destroyed. There is a large change in volume, but the soil has not been significantly transported.

STRENGTH OK HARDNESS				
Description	Description Field Identification			
Extremely weak	Indented by thumbnail	40-150 (0.3-1)		
Very weak Crumbles under firm blows with point of geological hammer, can be peeled by a pocket knife		150-700 (1-5)		
Weak rockCan be peeled by a pocket knife with difficulty, shallow indentations made by firm blow with point of geological hammer		700-4,000 (5-30)		
Medium strongCannot be scraped or peeled with a pocket knife, specimen can be fractured with single firm blow of geological hammer		4,000-7,000 (30-50)		
Strong rock Specimen requires more than one blow of geological hammer to fracture it		7,000-15,000 (50-100)		
Very strong Specimen requires many blows of geological hammer to fracture it		15,000-36,000 (100-250)		
Extremely strong Specimen can only be chipped with geological hammer		>36,000 (>250)		
DISCONTINUITY DESCRIPTION				

Fracture Spacing (Joints, Faults, Other Fractures)		Bedding Spacing (May Include Foliation or Banding)		
Description	Spacing	Description	Spacing	
Extremely close	< ¾ in (<19 mm)	Laminated	< ½ in (<12 mm)	
Very close	¾ in – 2-1/2 in (19 - 60 mm)	Very thin	½ in – 2 in (12 – 50 mm)	
Close	2-1/2 in - 8 in (60 - 200 mm)	Thin	2 in – 1 ft. (50 – 300 mm)	
Moderate	8 in – 2 ft. (200 – 600 mm)	Medium	1 ft. – 3 ft. (300 – 900 mm)	
Wide	2 ft. – 6 ft. (600 mm – 2.0 m)	Thick	3 ft. – 10 ft. (900 mm – 3 m)	
Very Wide	6 ft. – 20 ft. (2.0 – 6 m)	Massive	> 10 ft. (3 m)	

Discontinuity Orientation (Angle): Measure the angle of discontinuity relative to a plane perpendicular to the longitudinal axis of the core. (For most cases, the core axis is vertical; therefore, the plane perpendicular to the core axis is horizontal.) For example, a horizontal bedding plane would have a 0-degree angle.

ROCK QUALITY DESIGNATION (RQD) ¹		
Description	RQD Value (%)	
Very Poor	0 - 25	
Poor	25 – 50	
Fair	50 – 75	
Good	75 – 90	
Excellent	90 - 100	
1 The combined length of all cound and intect are commente equal to or greater than 4 inches in length every action of a		

1. The combined length of all sound and intact core segments equal to or greater than 4 inches in length, expressed as a percentage of the total core run length.

Reference: U.S. Department of Transportation, Federal Highway Administration, Publication No FHWA-NHI-10-034, December 2009 <u>Technical Manual for Design and Construction of Road Tunnels – Civil Elements</u>

MS4 SWPPP Acceptance Form - continued

V. Certification Statement - MS4 Official (principal executive officer or ranking elected official) or Duly Authorized Representative

I hereby certify that the final Stormwater Pollution Prevention Plan (SWPPP) for the construction project identified in question 5 has been reviewed and meets the substantive requirements in the SPDES General Permit For Stormwater Discharges from Municipal Separate Storm Sewer Systems (MS4s). Note: The MS4, through the acceptance of the SWPPP, assumes no responsibility for the accuracy and adequacy of the design included in the SWPPP. In addition, review and acceptance of the SWPPP by the MS4 does not relieve the owner/operator or their SWPPP preparer of responsibility or liability for errors or omissions in the plan.

Printed Name: Alan J Sorensen, AICP

1//21

Title/Position: Orange County Planning Commissioner

2022

Signature:

Date:

VI. Additional Information

(NYS DEC - MS4 SWPPP Acceptance Form - January 2015)

OCME

TOWN OF GOSHEN ORANGE COUNTY, NEW YORK

STORMWATER POLLUTION PREVENTION PLAN NARRATIVE

PREPARED FOR:

- OCME
- TOWN OF GOSHEN
- NYS DEPT. OF ENVIRONMENTAL CONSERVATION

April 29, 2022 Revised August 29, 2022 Revised October 10, 2022

PREPARED BY:

Fusco Engineering & Surveying, D.P.C. 233 East Main St., Middletown, NY 10940 TEL: (845) 344-5863 EMAIL:<u>aafjr@fuscoengineering.com</u> **PROJECT: 21-034**

SWPPP Preparer Certification 10/10/22

revention Plan (SWPPP) for this project has been prepared in accordance with the terms and conditions of the GP-0-20-001. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of this permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

Al Fusco N.Y.S.P.E. License # 054404

TABLE OF CONTENTS

5

1.	PROJECT INFORMAITON
2.	INTRODUCTION
2.1	Project Description
2.2	Project Disturbance Area
2.3	Cultural Resources Investigation
2.4	Existing Drainage Patterns
2.5	Proposed Drainage Patterns
3.	STORMWATER MANAGEMENT
3.1	General
3.2	Stormwater Quantity
3.3	Increase in Stormwater Runoff Rates
4.	STORMWATER QUALITY
4.1	Impervious Surfaces
4.2	Sources of Pollutants

- 4.3 Use of Fertilizers Pesticides
- 5. EROSION & SEDIMENTATION CONTROL
- 5.1 General
- 6. MAINTENANCE OF STORMWATER AFTER MANAGEMENT FACILITIES
- 6.1 General
- 7. SUMMARY
- 7.1 General

APPENDICES

A- SOILS MAP

B- PRE & POST DEVELOPMENT MAPS, HYDROCAD RESULTS C- SWPPP CONSTRUCTION INSPECTION REPORTS

D- NOI, NOI ACCEPTANCE FORM & NOT

E- CONSTRUCTION WASTE MANAGEMENT PLAN

F- CONTRACTOR CERTIFICATION STATEMENT

G- STORMWATER MAINTENANCE AND MANAGEMENT INSPECTON CHECKLIST

1. PROJECT INFORMATION

1.1 Project Name and Location

Orange County Medical Examiner's Office 22 Wells Farm Road Goshen, New York 10924

1.2 Property Owner Name and Address

County of Orange 255-275 Main Street Goshen, New York 10924

1.3 Project Operator Name and Address

County of Orange 255-275 Main Street Goshen, New York 10924

1.4 SWPPP Municipality

Town of Goshen 41 Webster Avenue Goshen, New York 10924

1.5 SWPPP Reviewer

Orange County Department of Public Works 2455 NY Route 17M Goshen, New York 10924

2. INTRODUCTION

2.1. Project Description

The site is located at 22 Wells Farm Road, near the intersection of 6 ¹/₂ Station Road, in the Town of Goshen, New York. The tax map designation for the Parcels is10-1-60.21 (65 acres).

There is an existing government office located on the subject property. The current site is served by an existing water and sewer service that conveys flows to an existing main.

The portion of the site that is proposed for development is characterized by a southeasterly sloping topography that descends from the western portion of the site. Topography on the site reflects the local surrounding topography and the parcel is covered with open fields.

The soils on the property were identified using the soil classifications of the USDA Soil Conservation Service (SCS), Soil Survey of Orange County, New York and the USGS Soil Survey Database. The site soils consist primarily of Bath-Nassau channery silt loams (BnB), Mardin gravelly silt loam (MdC), and Mardin gravelly silt loam (MdD). The approximate soil boundaries and types are shown on the attached Pre & Post Development Drainage Analysis Maps.

The proposed project consists of a new medical examiners building. On-site parking is proposed with connection to municipal water & sewer. A stormwater drainage system will attenuate & treat post development stormwater flows. The proposed development is subject to a stormwater management plan that has been developed in accordance with the requirements of the current SPDES General Permit for Stormwater Discharges from Construction Activity NYS GP-0-20-001.

2.2. Project Disturbance Area

Total Project Property Area: 65 Acres Total Disturbed Area: 2.0 Acres Existing Impervious Area: 6.26 Acres Proposed Increase In Impervious Area: 0.65 Acres

2.3. Cultural Resources Investigation

The New York State Historic Preservation Office (SHPO) online CRIS tool indicates that the project site is not located in close proximity or adjacent to any sensitive archeological site(s).

2.4. Existing Drainage Patterns

Generally, the pre-development site conditions are best described as impervious surface. There is one watershed within the existing site that is shown on the shown on the attached Pre-Development Analysis Map.

2.5. Proposed Drainage Patterns

The pre-development watershed boundaries are very similar to the post development condition. The proposed building and parking is located within this watershed. The addition of the impervious surface increases post-developed runoff and pollutants in these watersheds.

3. STORMWATER MANAGEMENT

3.1. General

In general, increased imperviousness can change the volume and rate of runoff as well as the amount of suspended or dissolved substances entering local streams. In some cases, a change in the quantity of impervious surfaces can change the distribution of water in each area, affecting local water bodies, wetlands and associated fauna and flora. The project design includes measures to reduce the level of runoff and pollutants in post-development runoff in compliance with New York State DEC requirements.

3.2. Stormwater Quantity

There is an additional 28,749 SF of impervious surface associated with the project. This minor increase in impervious surface can be attenuated by the proposed Wet Pond stormwater management facility.

Information and data to prepare this report was obtained from the following sources:

- Topographic, Boundary and Planimetric information from a survey performed in the field by Fusco Engineering & Land Surveying, DPC as well as information provided by the owner
- Site Plan as prepared by Fusco Engineering & Land Surveying, DPC.
- The site soil information from USDA Web Soil Survey.

The TR-55 method was used to determine the pre-development and post-development runoff rates at the design points (DP) identified on the property, which is illustrated on the attached drawings entitled Pre Development Stormwater Analysis and Post Development Stormwater Analysis.

Drainage summaries have been shown on Table 1, which outline the runoff volume from the 1, 10 and 100 year storm events in the pre-development and post-development conditions, using a Type III storm distribution as evidenced by storm distribution boundaries found in the TR-55 publication. The 24-hour rainfall values used for each storm occurrence were taken from the NYSDEC Stormwater Design Manual as listed below:

1 year storm = 2.60 in. 10 year storm = 4.75 in 100 year storm = 8.5 in

Details of the proposed stormwater facilities have been included on Pre & Post Development

Drainage Analysis Maps and the project drawings. The Pre and Post Development Analysis Maps have been prepared to illustrate existing drainage areas and their configuration following construction on the site.

It is the overall goal of the SWPPP to provide for proper drainage control on a quality and quantity basis. The plan has been prepared so there will be no negative effect on downstream properties.

The hydrologic characteristics of the pre-development site conditions were modeled using HydroCAD computer software. The model analyzes watershed conditions and provides hydrograph generation and routing based on the Natural Resources Conservation Service (NRCS) Technical Release 55 (TR-55) procedures. These procedures consider the land cover and use on site, the underlying soils, the general topography and local rainfall distribution to model stormwater runoff volumes and flow rates resulting from the site.

3.3. Increase in Stormwater Runoff Rates

Table 1 Pre- vs. Post-Development Runoff to DP1 (cfs)				
Storm	Runoff (Pre)	Runoff (Post)		
Frequency				
1 year	0.70	0.10		
10 year	2.14	2.09		
100 year	5.14	2.53		

Table 1 below compares the pre- and post-development runoff calculations.

The post-development rates of runoff are slightly greater than the existing condition and can be attenuated and treated by the stormwater facility discussed above.

4. STORMWATER QUALITY

4.1. Impervious Surfaces

The impervious cover used in this analysis represents the land use as described and shown on the project plans. Water Quality Volume (WQv) is provided through the implementation of a Wet Pond. 100% of the WQv required is 3,181 CF while 3,253 CF of WQv has been provided within the Wet Pond. This treatment method does not require Runoff Reduction Volume (RRv) in accordance with Chapter 9 of the NYSDEC SWPPP Manual (January 2015) for re-development projects. The supporting calculations are presented in Appendix B located at the end of this report.

4.2. Sources of Pollutants

The New York State DEC lists several potential pollutants and their sources to be considered during site design. Nutrients, sediment, bacteria and various other components can potentially contribute to the reduction of water quality and impacts to downstream receiving waters and

habitat for water dependent species.

Many of these constituents, i.e., nitrogen, phosphorus, bacteria and others, are expected to be accounted for in the capture and treatment of the water quality volume. The DEC guidelines have established that if the water quality volume from impervious surfaces is treated, the water quality goals of the State are met. A primary source of nutrients, i.e., the use of fertilizers, is discussed below.

Sediments are typically associated with runoff from un-stabilized sites or are the result of erosion in watercourses that cannot handle the velocity of stormwater flows. They can also result from the sanding of impervious surfaces during winter storm events. Un-stabilized sediments can be transported via storm flows to receiving wetlands and watercourses, altering the soil-water-air interface in wetlands and burying established vegetation. The current proposal will include a sedimentation basin and a wet pond that will encourage removal of un-stabilized sediments.

1. Thermal impacts, i.e., the increase in water temperature caused by the process of water running off of parking lots, roofs and other impervious surfaces that are heated by the sun, are of greatest concern in areas where a site is directly tributary to a Class B creek. There are no such streams nearby. Furthermore, the site runoff will be treated by the existing stormwater facility located near Wells Farm Road. Based on this information, no special consideration was given to moderating the temperature of stormwater leaving the site.

4.3. Use of Fertilizers and Pesticides

The applicant proposes the use of a variety of construction and maintenance techniques reflecting best management practices in order to limit impacts of stormwater runoff. No fertilizers containing phosphorous will be utilized in order to limit pollutants from the project to the maximum extent possible.

Phosphorus from fertilizer runs off lawns via stormwater and can enter surface waters and ground water, both of which can reach other water bodies. Using phosphorus-free lawn fertilizers is one step that will be taken to protect water quality. The project sponsor therefore proposes that any fertilizers used during construction will be phosphorus-free.

These combined systems have been designed to treat the NYSDEC water quality volume, and control peak flow runoff rates from the 10- and 100-year storm events.

5. EROSION & SEDIMENT CONTROL

5.1. General

During construction of the Project, extensive erosion and sediment control consisting of vegetative and structural measures will be implemented. These practices will be included in the final plans and will show the location and details of these controls. Among the techniques to be utilized are:

- 1. Staked haybales and silt fences around the downhill perimeter of the construction.
- 2. A stabilized construction entrance installed at the access point to the site.
- 3. Temporary seeding of all disturbed areas if they will remain bare for more than three weeks.
- 4. Permanent seeding and mulching as soon as possible after final grading.
- 5. Water spray for dust control.
- 6. The plans will indicate the proposed controls to be implemented during construction. However, adjustment of these controls may be required to accommodate localized field conditions.
- 7. Disturbed areas will be permanently stabilized by establishing a permanent vegetative cover. The exposed area will receive a minimum of 4 inch topsoil prior to seeding.

6. MAINTENANCE OF STORMWATER MANAGEMENT FACILITIES

6.1. General

The storm water management facilities shall be maintained by the Owner of the Project during and after construction. All storm water management facilities shall be routinely inspected and any necessary repairs made immediately in order to maintain all practices as designed. The Contractor and Owner shall utilize good housekeeping methods for all litter and debris that is generated during construction. This shall include for example, placing all wastes in a dumpster on a daily basis and emptying dumpsters on a regular basis. It is also recommended to store any chemicals that are utilized during construction in a safe place according to manufacturer's safety data sheets (MSDS).

7. SUMMARY

7.1. General

Drainage from the proposed impervious surfaces will be collected by the proposed catch basins and routed to the existing stormwater management facility. The Soil Conservation Service TR-55 method has been utilized to evaluate the changes in stormwater runoff rates as a result of development of the site. The storm drainage system has been designed to collect and convey stormwater in a manner that would provide no increase in stormwater runoff rates downstream from the existing stormwater management facility.

The proposed project has also been designed to minimize the extent of proposed grading and disturbance. The construction activity on the site will therefore not result in additional pollutant loadings and post development runoff to downstream water bodies. The proposed erosion and sediment control practices will prevent the erosion and sediment deposits to downstream properties.

APPENDIX A

SOILS MAP



National Cooperative Soil Survey

Conservation Service

Page 1 of 4

Hydrologic Soil Group—Orange County, New York



4/26/2022 Page 2 of 4

Web Soil Survey National Cooperative Soil Survey

Conservation Service

Natural Resources

NSDA
Hydrologic Soil Group

Map unit symbol	Map unit name	Rating	Acres in AOI	Percent of AOI
BnB	Bath-Nassau channery silt loams, 3 to 8 percent slopes	С	0.5	25.3%
MdC	Mardin gravelly silt loam, 8 to 15 percent slopes	D	0.6	34.0%
IdD Mardin gravelly silt loam, 15 to 25 percent slopes		D	0.7	40.6%
Totals for Area of Interest			1.8	100.0%

Description

Hydrologic soil groups are based on estimates of runoff potential. Soils are assigned to one of four groups according to the rate of water infiltration when the soils are not protected by vegetation, are thoroughly wet, and receive precipitation from long-duration storms.

The soils in the United States are assigned to four groups (A, B, C, and D) and three dual classes (A/D, B/D, and C/D). The groups are defined as follows:

Group A. Soils having a high infiltration rate (low runoff potential) when thoroughly wet. These consist mainly of deep, well drained to excessively drained sands or gravelly sands. These soils have a high rate of water transmission.

Group B. Soils having a moderate infiltration rate when thoroughly wet. These consist chiefly of moderately deep or deep, moderately well drained or well drained soils that have moderately fine texture to moderately coarse texture. These soils have a moderate rate of water transmission.

Group C. Soils having a slow infiltration rate when thoroughly wet. These consist chiefly of soils having a layer that impedes the downward movement of water or soils of moderately fine texture or fine texture. These soils have a slow rate of water transmission.

Group D. Soils having a very slow infiltration rate (high runoff potential) when thoroughly wet. These consist chiefly of clays that have a high shrink-swell potential, soils that have a high water table, soils that have a claypan or clay layer at or near the surface, and soils that are shallow over nearly impervious material. These soils have a very slow rate of water transmission.

If a soil is assigned to a dual hydrologic group (A/D, B/D, or C/D), the first letter is for drained areas and the second is for undrained areas. Only the soils that in their natural condition are in group D are assigned to dual classes.

Rating Options

Aggregation Method: Dominant Condition Component Percent Cutoff: None Specified Tie-break Rule: Higher

APPENDIX B

PRE & POST DEVELOPMENT MAPS, HYDROCAD RESULTS





P

COUNT RM RD. 10924

LS FAI N, NY

222

ORANGE

CB RIM:484.70 INV:477.50 INV:477.20











Rainfall data sources

This section lists the most current 24-hour rainfall data published by the National Weather Service (NWS) for various parts of the country. Because NWS Technical Paper 40 (TP-40) is out of print, the 24-hour rainfall maps for areas east of the 105th meridian are included here as figures B-3 through B-8. For the area generally west of the 105th meridian, TP-40 has been superseded by NOAA Atlas 2, the Precipitation-Frequency Atlas of the Western United States, published by the National Ocean and Atmospheric Administration.

East of 105th meridian

Hershfield, D.M. 1961. Rainfall frequency atlas of the United States for durations from 30 minutes to 24 hours and return periods from 1 to 100 years. U.S. Dept. Commerce, Weather Bur. Tech. Pap. No. 40. Washington, DC. 155 p.

West of 105th meridian

Miller, J.F., R.H. Frederick, and R.J. Tracey. 1973. Precipitation-frequency atlas of the Western United States. Vol. I Montana; Vol. II, Wyoming; Vol III, Colorado; Vol. IV, New Mexico; Vol V, Idaho; Vol. VI, Utah; Vol. VII, Nevada; Vol. VIII, Arizona; Vol. IX, Washington; Vol. X, Oregon; Vol. XI, California. U.S. Dept. of Commerce, National Weather Service, NOAA Atlas 2. Silver Spring, MD.

Alaska

Miller, John F. 1963. Probable maximum precipitation and rainfall-frequency data for Alaska for areas to 400 square miles, durations to 24 hours and return periods from 1 to 100 years. U.S. Dept. of Commerce, Weather Bur. Tech. Pap. No. 47. Washington, DC. 69 p.

Hawaii

Weather Bureau. 1962. Rainfall-frequency atlas of the Hawaiian Islands for areas to 200 square miles, durations to 24 hours and return periods from 1 to 100 years. U.S. Dept. Commerce, Weather Bur. Tech. Pap. No. 43. Washington, DC. 60 p.

Puerto Rico and Virgin Islands

Weather Bureau. 1961. Generalized estimates of probable maximum precipitation and rainfall-frequency data for Puerto Rico and Virgin Islands for areas to 400 square miles, durations to 24 hours, and return periods from 1 to 100 years. U.S. Dept. Commerce, Weather Bur. Tech. Pap. No. 42. Washington, DC. 94 P.

New York State Stormwater Management Design Manual

Chapter 4: Unified Stormwater Sizing Criteria

Section 4.5 Overbank Flood Control Criteria (Qp)





Section 4.5 Overbank Flood Control Criteria (Q_p)

The primary purpose of the overbank flood control sizing criterion is to prevent an increase in the frequency and magnitude of out-of-bank flooding generated by urban development (i.e., flow events that exceed the bankfull capacity of the channel, and therefore must spill over into the floodplain).

Overbank control requires storage to attenuate the post development 10-year, 24-hour peak discharge rate (Q_p) to predevelopment rates.

The overbank flood control requirement (Q_p) does not apply in certain conditions, including:

- The site discharges directly tidal waters or fifth order (fifth downstream) or larger streams. Refer to Section 4.3 for instructions.
- A downstream analysis reveals that overbank control is not needed (see section 4.10).

Basis for Design of Overbank Flood Control

When addressing the overbank flooding design criteria, the following represent the minimum basis for design:

4-10

New York State Stormwater Management Design Manual

Chapter 4:Unified Stormwater Sizing CriteriaSection 4.5Overbank Flood Control Criteria (Qp)

- TR-55 and TR-20 (or approved equivalent) will be used to determine peak discharge rates.
- When the predevelopment land use is agriculture, the curve number for the pre-developed condition shall be "taken as meadow".
- Off-site areas should be modeled as "present condition" for the 10-year storm event.
- Figure 4.3 indicates the depth of rainfall (24 hour) associated with the 10-year storm event throughout the State of New York.
- The length of overland flow used in t_c calculations is limited to no more than 150 feet for predevelopment conditions and 100 feet for post development conditions. On areas of extremely flat terrain (<1% average slope), this maximum distance is extended to 250 feet for predevelopment conditions and 150 feet for post development conditions.



Figure 4.3: Ten-Year Design Storm in New York State (NYSDEC, 2013)

New York State Stormwater Management Design Manual

Chapter 4: Unified Stormwater Sizing Criteria

Section 4.7 Alternative Method

- When determining the storage required to reduce 100-year flood peaks, model off-site areas under current conditions.
- When determining storage required to safely pass the 100-year flood, model off-site areas under ultimate conditions.



Figure 4.4: One Hundred-Year Design Storm in New York State (NYSDEC, 2013)

Section 4.7 Alternative Method

New development causes changes to runoff volume, flow rates, timing of runoff and, most importantly, habitat destruction and degradation of the physical and chemical quality of the receiving waterbody. Traditionally, event based design storms are used for evaluation of hydrology and sizing of stormwater management practices. With an increasing need for assessment of the long term effects of development and maintenance of pre-development hydrology, the necessity of continuous simulation modeling as an effective tool for analysis and evaluation of flow-duration, downstream quality, quantity, biological, and hydro-habitat sustainability has been acknowledged.

Version 1.8 Last Updated: 11/09/2015

Is this project subject to Chapter 10 of the NYS Design Manual (i.e. WQv is equal to postdevelopment 1 year runoff volume)?..... No **Design Point:** 1 Manually enter P, Total Area and Impervious Cover. P= 1.40 inch **Breakdown of Subcatchments** Percent WQv Catchment **Total Area Impervious** Area Impervious Description Rv (ft³) Number (Acres) (Acres) % 0.82 0.65 79% 1 0.76 3,181 2 3 4 5 6 7

8						
9						
10						
Subtotal (1-30)	0.82	0.65	79%	0.76	3,181	Subtotal 1
Total	0.82	0.65	79%	0.76	3,181	Initial WQv
Identify Punoff Peduction Techniques By Area						

identify kunoff keduction Techniques By Area						
Technique	Total Contributing Area	Contributing Impervious Area	Notes			
	(Acre)	(Acre)				
Conservation of Natural Areas	0.00	0.00	minimum 10,000 sf			
Piparian Ruffers	0.00	0.00	maximum contributing length 75 feet to			
	0.00	0.00	150 feet			
Filter Strips	0.00	0.00				
Tree Planting	0.00	0.00	Up to 100 sf directly connected impervious			
Tree Planting	0.00	0.00	area may be subtracted per tree			
Total	0.00	0.00				
		•	•			

Recalculate WQv after application of Area Reduction Techniques						
	Total Area (Acres)	Impervious Area (Acres)	Percent Impervious %	Runoff Coefficient Rv	WQv (ft ³)	
"< <initial td="" wqv"<=""><td>0.82</td><td>0.65</td><td>79%</td><td>0.76</td><td>3,181</td></initial>	0.82	0.65	79%	0.76	3,181	
Subtract Area	0.00	0.00				
WQv adjusted after Area Reductions	0.82	0.65	79%	0.76	3,181	
Disconnection of Rooftops		0.00				
Adjusted WQv after Area Reduction and Rooftop Disconnect	0.82	0.65	79%	0.76	3,181	
WQv reduced by Area Reduction techniques					0	



E	Event#	Event	Storm Type	Curve	Mode	Duration	B/B	Depth	AMC
		Name				(hours)		(inches)	
	1	1-Year	Type III 24-hr		Default	24.00	1	2.70	2
	2	10-Year	Type III 24-hr		Default	24.00	1	4.75	2
	3	100-Year	Type III 24-hr		Default	24.00	1	8.50	2

Rainfall Events Listing (selected events)

Area Listing (all nodes)

Area	CN	Description
(acres)		(subcatchment-numbers)
0.893	74	>75% Grass cover, Good, HSG C (POST, PRE)
0.139	87	Dirt roads, HSG C (PRE)
0.626	98	Paved parking, HSG C (POST)
1.658	84	TOTAL AREA

Soil Listing (all nodes)

Area	Soil	Subcatchment
(acres)	Group	Numbers
0.000	HSG A	
0.000	HSG B	
1.658	HSG C	POST, PRE
0.000	HSG D	
0.000	Other	
1.658		TOTAL AREA

			ereana e		nouce,		
HSG-A	HSG-B	HSG-C	HSG-D	Other	Total	Ground	Subcatchment
 (acres)	(acres)	(acres)	(acres)	(acres)	(acres)	Cover	Numbers
 0.000	0.000	0.893	0.000	0.000	0.893	>75% Grass cover, Good	POST,
							PRE
0.000	0.000	0.139	0.000	0.000	0.139	Dirt roads	PRE
0.000	0.000	0.626	0.000	0.000	0.626	Paved parking	POST
0.000	0.000	1.658	0.000	0.000	1.658	TOTAL AREA	

Ground Covers (all nodes)

OCME Wet Pond 10-10-22

Prepared by Arden Cor	nsulting Engineers PLLC	
HydroCAD® 10.20-2f s/n 0	04164 © 2022 HydroCAD Softwa	re Solutions LLC

	Pipe Listing (all hodes)								
Line#	Node	In-Invert	Out-Invert	Length	Slope	n	Width	Diam/Height	Inside-Fill
	Number	(feet)	(feet)	(feet)	(ft/ft)		(inches)	(inches)	(inches)
1	WP	478.00	428.60	264.0	0.1871	0.013	0.0	8.0	0.0

Pipe Listing (all nodes)

OCME Wet Pond 10-10-22	Type III 24-hr	1-Year Ra	infall=2.70"
Prepared by Arden Consulting Engineers PLLC		Printed	10/10/2022
HydroCAD® 10.20-2f s/n 04164 © 2022 HydroCAD Software Solutions	s LLC		Page 7

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points Runoff by SCS TR-20 method, UH=SCS, Weighted-CN Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment POST:	: Basin 1 Post	Runoff Area=36,110 sf 75.52% Impervious Runoff Depth>1.88" Tc=6.0 min CN=92 Runoff=1.80 cfs 0.130 af
SubcatchmentPRE: I	Basin 1 Pre	Runoff Area=36,110 sf 0.00% Impervious Runoff Depth>0.82" Flow Length=184' Tc=7.5 min CN=76 Runoff=0.70 cfs 0.056 af
Pond SB: SEDIMENT	BASIN	Peak Elev=483.08' Storage=1,097 cf Inflow=1.80 cfs 0.130 af Outflow=1.78 cfs 0.107 af
Pond WP: WP	Primary=0.10 cfs	Peak Elev=479.67' Storage=3,163 cf Inflow=1.78 cfs 0.107 af 0.035 af Secondary=0.00 cfs 0.000 af Outflow=0.10 cfs 0.035 af
Total R	Runoff Area = 1.658	ac Runoff Volume = 0.186 af Average Runoff Depth = 1.35" 62.24% Pervious = 1.032 ac 37.76% Impervious = 0.626 ac

Summary for Subcatchment POST: Basin 1 Post

Runoff = 1.80 cfs @ 12.09 hrs, Volume= Routed to Pond SB : SEDIMENT BASIN

0.130 af, Depth> 1.88"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.70"

Ar	ea (sf)	CN	Description		
2	27,269	98	Paved park	ing, HSG C	
	8,841	74	>75% Gras	s cover, Go	ood, HSG C
	36,110	92	Weighted A	verage	
	8,841		24.48% Per	vious Area	
2	27,269		75.52% Imp	pervious Are	ea
Tc (min)	Length (feet)	Slope (ft/ft	e Velocity) (ft/sec)	Capacity (cfs)	Description
6.0					Direct Entry, Minimum

Subcatchment POST: Basin 1 Post



Summary for Subcatchment PRE: Basin 1 Pre

Runoff = 0.70 cfs @ 12.12 hrs, Volume= Routed to nonexistent node AP-PRE

0.056 af, Depth> 0.82"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type III 24-hr 1-Year Rainfall=2.70"

A	rea (sf)	CN	Description			
	6,073	87	Dirt roads, I	HSG C		
	30,037	74	>75% Gras	s cover, Go	bod, HSG C	
	36,110	76	Weighted A	verage		
	36,110		100.00% Pe	ervious Are	а	
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
7.0	100	0.0450	0.24		Sheet Flow, Sheet Flow, Woods: Light Underbrush	
0.5	84	0.1800	2.97		Grass: Short n= 0.150 P2= 3.25" Shallow Concentrated Flow, Shallow Concentrated Flow, Woo Short Grass Pasture Kv= 7.0 fps	od
7.5	184	Total				

Subcatchment PRE: Basin 1 Pre



Summary for Pond SB: SEDIMENT BASIN

Inflow Area Inflow Outflow Primary Routed	a = 0 = 1. = 1. = 1. to Pond W	.829 ac, 75 80 cfs @ .78 cfs @ .78 cfs @ /P : WP	5.52% Im 12.09 hrs 12.10 hrs 12.10 hrs	pervious, Inflow D s, Volume= s, Volume= s, Volume=	epth > 1.88" 0.130 af 0.107 af, Atte 0.107 af	for 1-Year event n= 1%, Lag= 0.7 i	min
Routing by Peak Elev Flood Elev	∕ Dyn-Stor- = 483.08' @ ⁄= 484.00'	Ind method ⊉ 12.10 hrs Surf.Area=	, Time Sp Surf.Ar 2,419 sf	oan= 0.00-24.00 hr ea= 1,455 sf Stor Storage= 2,865 c	s, dt= 0.01 hrs age= 1,097 cf f		
Plug-Flow Center-of-	detention t Mass det. t	ime= 107.6 ime= 37.8 ı	i min calc min (841	ulated for 0.107 af .2 - 803.4)	(82% of inflow)		
Volume	Invert	Avail.S	torage	Storage Descriptior	1		
#1	482.00'	2,	865 cf	Custom Stage Dat	a (Irregular) Lis	ted below (Recalc)
Elevation (feet)	Su	rf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
482.00 484.00		637 2,419	245.0 327.0	0 2,865	0 2,865	637 4,413	
Device F	Routing	Inver	t Outlet	Devices			
#1 F	Primary	483.00)' 35.0 ' I	long + 2.0 '/' Side	Z x 5.0' breadt	h Broad-Crested	Rectangular Weir

Primary OutFlow Max=1.78 cfs @ 12.10 hrs HW=483.08' TW=478.72' (Dynamic Tailwater) **1=Broad-Crested Rectangular Weir** (Weir Controls 1.78 cfs @ 0.65 fps)

OCME Wet Pond 10-10-22

Prepared by Arden Consulting Engineers PLLC HydroCAD® 10.20-2f s/n 04164 © 2022 HydroCAD Software Solutions LLC



Pond SB: SEDIMENT BASIN

Summary for Pond WP: WP

Inflow Area	a =	0.829 ac, 7	75.52% Imp	ervious, Inflo	w Depth >	1.55"	for 1-Ye	ar event	
Inflow	=	1.78 cfs @	12.10 hrs,	Volume=	0.107	af			
Outflow	=	0.10 cfs @	14.18 hrs,	Volume=	0.035	af, Att	en= 94%,	Lag= 124.9 r	nin
Primary	=	0.10 cfs @	14.18 hrs,	Volume=	0.035	af		•	
Routed	to none>	kistent node	DP N-1						
Secondary	' =	0.00 cfs @	0.00 hrs,	Volume=	0.000	af			

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Peak Elev= 479.67' @ 14.18 hrs Surf.Area= 2,920 sf Storage= 3,163 cf Flood Elev= 482.00' Surf.Area= 6,222 sf Storage= 13,703 cf

Plug-Flow detention time= 324.8 min calculated for 0.035 af (33% of inflow) Center-of-Mass det. time= 206.2 min (1,047.3 - 841.2)

Volume	Invert	Avail.Sto	orage	Storage Description	n		
#1	478.00'	13,7	03 cf	Custom Stage Da	ita (Irregular) Listed	d below (Recalc)	
Elevatio (fee	on Su et)	rf.Area F (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	
478.0 480.0 482.0)0)0)0	1,031 3,410 6,222	336.0 443.0 490.0	0 4,211 9,492	0 4,211 13,703	1,031 7,710 11,322	
Device	Routing	Invert	Outle	et Devices			
#1 #2	Primary Device 1	478.00' 479.65'	8.0" L= 2 Inlet n= 0 30.0 C= 0	Round Culvert 64.0' CPP, square / Outlet Invert= 478 .013, Flow Area= 0 " x 42.0" Horiz. Or 0.600 in 42.0" x 60.	edge headwall, K 8.00' / 428.60' S= 0.35 sf i fice/Grate 0" Grate (50% ope	e= 0.500 0.1871 '/' Cc= 0.900 n area)	
#3	Secondary	481.00'	Limit 20.0 Head 2.50 Coef 2.64	ted to weir flow at lo ' long x 8.0' bread d (feet) 0.20 0.40 3.00 3.50 4.00 4 f. (English) 2.43 2. 2.65 2.65 2.66 2	w heads th Broad-Crested 0.60 0.80 1.00 1. .50 5.00 5.50 54 2.70 2.69 2.68 .66 2.68 2.70 2.7	Rectangular Weir 20 1.40 1.60 1.80 2.00 3 2.68 2.66 2.64 2.64 4	0
Primary 1=Cu 1=2=	outFlow Ma Ilvert (Passe Orifice/Grate	ax=0.10 cfs (s 0.10 cfs of e (Weir Con	@ 14.1 1.94 c trols 0.	8 hrs HW=479.67' fs potential flow) 10 cfs @ 0.45 fps)	(Free Discharge)		

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=478.00' (Free Discharge) —3=Broad-Crested Rectangular Weir (Controls 0.00 cfs) Pond WP: WP



OCME Wet Pond 10-10-22	Type III 24-hr	10-Year Ra	infall=4.75"
Prepared by Arden Consulting Engineers PLLC		Printed	10/10/2022
HydroCAD® 10.20-2f s/n 04164 © 2022 HydroCAD Software Solution	is LLC		Page 14

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points Runoff by SCS TR-20 method, UH=SCS, Weighted-CN Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment	POST: Basin 1 Post	Runoff Area=36,110 sf 75.52% Impervious Runoff Depth>3.84" Tc=6.0 min CN=92 Runoff=3.56 cfs 0.265 af
Subcatchment	PRE: Basin 1 Pre	Runoff Area=36,110 sf 0.00% Impervious Runoff Depth>2.33" Flow Length=184' Tc=7.5 min CN=76 Runoff=2.14 cfs 0.161 af
Pond SB: SEDI	MENT BASIN	Peak Elev=483.12' Storage=1,163 cf Inflow=3.56 cfs 0.265 af Outflow=3.53 cfs 0.243 af
Pond WP: WP	Primary=2.09 cfs	Peak Elev=479.88' Storage=3,826 cf Inflow=3.53 cfs 0.243 af 0.171 af Secondary=0.00 cfs 0.000 af Outflow=2.09 cfs 0.171 af
т	otal Runoff Area = 1.658	ac Runoff Volume = 0.426 af Average Runoff Depth = 3.08

 $62.24\% \text{ Pervious} = 1.032 \text{ ac} \qquad 37.76\% \text{ Impervious} = 0.626 \text{ ac}$

Summary for Subcatchment POST: Basin 1 Post

Runoff = 3.56 cfs @ 12.08 hrs, Volume= Routed to Pond SB : SEDIMENT BASIN 0.265 af, Depth> 3.84"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.75"

Area (st	f) CN	Description		
27,26	9 98	Paved park	ing, HSG C)
8,84	1 74	>75% Gras	s cover, Go	bod, HSG C
36,11	0 92	Weighted A	verage	
8,84	1	24.48% Per	vious Area	l
27,26	9	75.52% Imp	pervious Are	ea
Tc Leng	th Slop	e Velocity	Capacity	Description
(min) (fee	et) (ft/	ft) (ft/sec)	(cfs)	
6.0				Direct Entry, Minimum

Subcatchment POST: Basin 1 Post



Summary for Subcatchment PRE: Basin 1 Pre

Runoff = 2.14 cfs @ 12.11 hrs, Volume= 0 Routed to nonexistent node AP-PRE

0.161 af, Depth> 2.33"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type III 24-hr 10-Year Rainfall=4.75"

A	rea (sf)	CN I	Description			
	6,073	87 I	Dirt roads, I	HSG C		
	30,037	74 >	>75% Gras	s cover, Go	bod, HSG C	
	36,110	76	Neighted A	verage		
	36,110		100.00% Pe	ervious Are	а	
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description	
7.0	100	0.0450	0.24		Sheet Flow, Sheet Flow, Woods: Light Underbrush Grass: Short n= 0.150 P2= 3.25"	
0.5	84	0.1800	2.97		Shallow Concentrated Flow, Shallow Concentrated Flow, We Short Grass Pasture Kv= 7.0 fps	ood
7.5	184	Total				

Subcatchment PRE: Basin 1 Pre



Summary for Pond SB: SEDIMENT BASIN

Inflow Area Inflow Outflow Primary Routed t	= 0 = 3. = 3. = 3. to Pond W	.829 ac, 7 56 cfs @ 53 cfs @ 53 cfs @ P : WP	75.52% In 12.08 hr 12.09 hr 12.09 hr	npervious, Inflow D s, Volume= s, Volume= s, Volume=	epth > 3.84" 0.265 af 0.243 af, Atte 0.243 af	for 10-Year even en= 1%, Lag= 0.6	nt min
Routing by Peak Elev= Flood Elev=	Dyn-Stor-I 483.12' @ = 484.00'	nd methoo) 12.09 hrs Surf.Area:	d, Time S s Surf.A = 2,419 s	pan= 0.00-24.00 hr rea= 1,496 sf Stor f Storage= 2,865 c	s, dt= 0.01 hrs age= 1,163 cf cf		
Plug-Flow c Center-of-M	letention ti 1ass det. ti	me= 70.6 me= 27.3	min calcu min (811	ulated for 0.243 af (I.0 - 783.7)	91% of inflow)		
Volume	Invert	Avail.S	Storage	Storage Descriptio	n		
#1	482.00'	2	,865 cf	Custom Stage Da	ta (Irregular)Lis	sted below (Recal	c)
Elevation (feet)	Su	rf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)	1 <u>)</u>
482.00 484.00		637 2,419	245.0 327.0	0 2,865	0 2,865	637 4,413	
D · D	outing	Inve	rt Outle	t Devices			
Device Ro	oaang						

Primary OutFlow Max=3.53 cfs @ 12.09 hrs HW=483.12' TW=479.78' (Dynamic Tailwater) **1=Broad-Crested Rectangular Weir** (Weir Controls 3.53 cfs @ 0.82 fps)

OCME Wet Pond 10-10-22

Prepared by Arden Consulting Engineers PLLC HydroCAD® 10.20-2f s/n 04164 © 2022 HydroCAD Software Solutions LLC



Pond SB: SEDIMENT BASIN

Summary for Pond WP: WP

Inflow Area = 0.829 ac, 75.52% Impervious, Inflow Depth > 3.51" for 10-Year event Inflow 3.53 cfs @ 12.09 hrs, Volume= 0.243 af = 2.09 cfs @ 12.20 hrs, Volume= Outflow = 0.171 af, Atten= 41%, Lag= 6.6 min 2.09 cfs @ 12.20 hrs, Volume= 0.171 af Primary = Routed to nonexistent node DP N-1 0.00 hrs, Volume= 0.000 af Secondary = 0.00 cfs @

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Peak Elev= 479.88' @ 12.20 hrs Surf.Area= 3,235 sf Storage= 3,826 cf Flood Elev= 482.00' Surf.Area= 6,222 sf Storage= 13,703 cf

Plug-Flow detention time= 141.9 min calculated for 0.171 af (70% of inflow) Center-of-Mass det. time= 54.0 min (865.1 - 811.0)

Volume	Invert	Avail.Sto	orage	Storage Descriptior	ו	
#1	478.00'	13,7	'03 cf	Custom Stage Dat	a (Irregular) Listed	below (Recalc)
Elevatio (fee	on Su et)	rf.Area F (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft <u>)</u>
478.0 480.0 482.0	00 00 00	1,031 3,410 6,222	336.0 443.0 490.0	0 4,211 9,492	0 4,211 13,703	1,031 7,710 11,322
Device	Routing	Invert	Outle	et Devices		
#1 #2	Primary Device 1	478.00' 479.65'	8.0" L= 2 Inlet n= 0 30.0 C= 0 Limit	Round Culvert 64.0' CPP, square / Outlet Invert= 478. .013, Flow Area= 0. " x 42.0" Horiz. Orif 0.600 in 42.0" x 60.0 ted to weir flow at low	edge headwall, Ke 00' / 428.60' S= 0 35 sf 'ice/Grate " Grate (50% open v heads	= 0.500 .1871 '/' Cc= 0.900 area)
#3	Secondary	481.00'	20.0 Head 2.50 Coef 2.64	' long x 8.0' breadt d (feet) 0.20 0.40 0 3.00 3.50 4.00 4.1 f. (English) 2.43 2.5 2.65 2.65 2.66 2.1	h Broad-Crested F 0.60 0.80 1.00 1.2 50 5.00 5.50 64 2.70 2.69 2.68 66 2.68 2.70 2.74	Rectangular Weir 20 1.40 1.60 1.80 2.00 2.68 2.66 2.64 2.64
Primary 1=Cι 1−2=	/ OutFlow Ma ulvert (Inlet C =Orifice/Grate	ax=2.09 cfs controls 2.09 e (Passes 2	@ 12.2 cfs @ .09 cfs	20 hrs HW=479.88' 6.00 fps) of 4.45 cfs potential	(Free Discharge) flow)	

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=478.00' (Free Discharge) —3=Broad-Crested Rectangular Weir (Controls 0.00 cfs) Pond WP: WP



OCME Wet Pond 10-10-22	Type III 24-hr	100-Year Ra	infall=8.50"
Prepared by Arden Consulting Engineers PLLC		Printed	10/10/2022
HydroCAD® 10.20-2f s/n 04164 © 2022 HydroCAD Software Solutic	ons LLC		Page 21
			-

Time span=0.00-24.00 hrs, dt=0.01 hrs, 2401 points Runoff by SCS TR-20 method, UH=SCS, Weighted-CN Reach routing by Dyn-Stor-Ind method - Pond routing by Dyn-Stor-Ind method

Subcatchment	POST: Basin 1 Post	Runoff Area=36,110 sf 75.52% Impervious Runoff Depth>7.53" Tc=6.0 min CN=92 Runoff=6.72 cfs 0.520 af
Subcatchment	PRE: Basin 1 Pre	Runoff Area=36,110 sf 0.00% Impervious Runoff Depth>5.61" Flow Length=184' Tc=7.5 min CN=76 Runoff=5.14 cfs 0.387 af
Pond SB: SEDI	MENT BASIN	Peak Elev=483.19' Storage=1,262 cf Inflow=6.72 cfs 0.520 af Outflow=6.68 cfs 0.497 af
Pond WP: WP	Primary=2.53 cfs	Peak Elev=480.60' Storage=6,491 cf Inflow=6.68 cfs 0.497 af 3 0.425 af Secondary=0.00 cfs 0.000 af Outflow=2.53 cfs 0.425 af
Т	otal Runoff Area = 1.658	ac Runoff Volume = 0.908 af Average Runoff Depth = 6.57

 $62.24\% \text{ Pervious} = 1.032 \text{ ac} \quad 37.76\% \text{ Impervious} = 0.626 \text{ ac}$

Summary for Subcatchment POST: Basin 1 Post

Runoff = 6.72 cfs @ 12.08 hrs, Volume= 0 Routed to Pond SB : SEDIMENT BASIN

0.520 af, Depth> 7.53"

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.50"

A	rea (sf)	CN	Description					
	27,269	98	Paved parking, HSG C					
	8,841	74	>75% Ġras	s cover, Go	bod, HSG C			
	36,110	92	Weighted A	verage				
	8,841		24.48% Pervious Area					
	27,269		75.52% Imp	pervious Are	ea			
Tc	Length	Slop	e Velocity	Capacity	Description			
(min)	(feet)	(ft/ft) (ft/sec)	(cfs)				
6.0					Direct Entry, Minimum			
					-			

Subcatchment POST: Basin 1 Post



Summary for Subcatchment PRE: Basin 1 Pre

Runoff = 5.14 cfs @ 12.11 hrs, Volume= 0.387 af, Depth> 5.61" Routed to nonexistent node AP-PRE

Runoff by SCS TR-20 method, UH=SCS, Weighted-CN, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Type III 24-hr 100-Year Rainfall=8.50"

A	rea (sf)	CN	Description					
	6,073	87	Dirt roads, HSG C					
	30,037	74	>75% Grass cover, Good, HSG C					
	36,110	76	Neighted Average					
	36,110		100.00% Pe	ervious Are	а			
Tc (min)	Length (feet)	Slope (ft/ft)	Velocity (ft/sec)	Capacity (cfs)	Description			
7.0	100	0.0450	0.24		Sheet Flow, Sheet Flow, Woods: Light Underbrush			
					Grass: Short n= 0.150 P2= 3.25"			
0.5	84	0.1800	2.97		Shallow Concentrated Flow, Shallow Concentrated Flow, V	Wood		
					Short Grass Pasture Kv= 7.0 fps			
7.5	184	Total						

Subcatchment PRE: Basin 1 Pre



Summary for Pond SB: SEDIMENT BASIN

Inflow An Inflow Outflow Primary Route	ea = (= 6 = 6 = 6 d to Pond V	0.829 ac, 7 6.72 cfs @ 6.68 cfs @ 6.68 cfs @ VP : WP	5.52% In 12.08 hr 12.09 hr 12.09 hr	npervious, Inflow De s, Volume= s, Volume= s, Volume=	pth > 7.53" 0.520 af 0.497 af, Atte 0.497 af	for 100-Year even n= 0%, Lag= 0.5 i	nt min		
Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Peak Elev= 483.19' @ 12.09 hrs Surf.Area= 1,556 sf Storage= 1,262 cf Flood Elev= 484.00' Surf.Area= 2,419 sf Storage= 2,865 cf									
Plug-Flow Center-of	v detention f-Mass det.	time= 45.1 i time= 19.6 i	min calcu min (786	ulated for 0.497 af (9 6.5 - 766.9)	6% of inflow)				
Volume	Invert	Avail.S	torage	Storage Description					
#1	482.00'	2,	865 cf	Custom Stage Dat	a (Irregular)Lis	ted below (Recalc)		
Elevation (feet	n Sı :)	urf.Area (sq-ft)	Perim. (feet)	Inc.Store (cubic-feet)	Cum.Store (cubic-feet)	Wet.Area (sq-ft)			
482.0 484.0	0 0	637 2,419	245.0 327.0	0 2,865	0 2,865	637 4,413			
Device	Routing	Inver	t Outle	t Devices					
	D :	100							

Primary OutFlow Max=6.68 cfs @ 12.09 hrs HW=483.19' TW=480.23' (Dynamic Tailwater) **1=Broad-Crested Rectangular Weir** (Weir Controls 6.68 cfs @ 1.01 fps)

Hydrograph Inflow Inflow Area=0.82 6.68 cfs Primary 7. Peak Elev=483.19' 6-Storage=1,262 cf 5-Flow (cfs) 4 3-2-1 0-2 3 9 10 12 13 14 15 16 17 18 19 20 21 22 23 24 1 4 5 6 Ż 8 11 Ó Time (hours)

Pond SB: SEDIMENT BASIN

Summary for Pond WP: WP

Inflow Area	a =	0.829 ac,	75.52% Imp	ervious,	Inflow	Depth >	7.20"	for	100-	Year e	event
Inflow	=	6.68 cfs @	2 12.09 hrs,	Volume	=	0.497	af				
Outflow	=	2.53 cfs @	2 12.33 hrs,	Volume	=	0.425	af, At	ten= 6	62%,	Lag=	14.3 min
Primary	=	2.53 cfs @	2 12.33 hrs,	Volume	=	0.425	af			•	
Routed	to none>	kistent node	DP N-1								
Secondary	=	0.00 cfs @) 0.00 hrs,	Volume	=	0.000	af				

Routing by Dyn-Stor-Ind method, Time Span= 0.00-24.00 hrs, dt= 0.01 hrs Peak Elev= 480.60' @ 12.33 hrs Surf.Area= 4,169 sf Storage= 6,491 cf Flood Elev= 482.00' Surf.Area= 6,222 sf Storage= 13,703 cf

Plug-Flow detention time= 103.0 min calculated for 0.425 af (85% of inflow) Center-of-Mass det. time= 42.4 min (828.9 - 786.5)

<u>Volume</u>	Invert	Avail.Sto	orage	Storage Description	on			
#1 478.00' 13,703 cf Custom Stage Dat		ata (Irregular)Liste	ed below (Recalc)					
Elevatio	on Su	rf.Area F	Perim.	Inc.Store	Cum.Store	Wet.Area		
(196	el)	(sq-it)	(leet)	(cubic-leet)	(cubic-leet)	(SQ-IL)		
478.0	00	1,031	336.0	0	0	1,031		
480.0	00	3,410	443.0	4,211	4,211	7,710		
482.0	00	6,222	490.0	9,492	13,703	11,322		
Device	Routing	Invert	Outle	et Devices				
#1	Primary	478.00'	8.0"	Round Culvert				
			L= 2	64.0' CPP, square	edge headwall, ł	Ke= 0.500		
			Iniet	/ Outlet Invert= 4/8	3.00°/428.60° S=	0.18717 Cc= 0.900		
	D · · · ·	470.051	n= 0	.013, Flow Area= (0.35 st			
#2	Device 1	479.65	30.0	" x 42.0" Horiz. Or	ifice/Grate			
			C= (0.600 in 42.0" x 60.	0" Grate (50% ope	en area)		
	- ·		Limit	ted to weir flow at lo	ow heads			
#3	Secondary	481.00'	20.0	long x 8.0' bread	Ith Broad-Crested	l Rectangular Weir		
			Head	d (feet) 0.20 0.40	0.60 0.80 1.00 1	1.20 1.40 1.60 1.80 2.00		
			2.50	3.00 3.50 4.00 4	.50 5.00 5.50			
			Coef	f. (English) 2.43 2.	.54 2.70 2.69 2.6	8 2.68 2.66 2.64 2.64		
			2.64	2.65 2.65 2.66 2	2.66 2.68 2.70 2.	74		
Primary 1=Cu 2=	Primary OutFlow Max=2.53 cfs @ 12.33 hrs HW=480.60' (Free Discharge) 1=Culvert (Inlet Controls 2.53 cfs @ 7.25 fps) 2=Orifice/Grate (Passes 2.53 cfs of 36.50 cfs potential flow)							

Secondary OutFlow Max=0.00 cfs @ 0.00 hrs HW=478.00' (Free Discharge) —3=Broad-Crested Rectangular Weir (Controls 0.00 cfs)
Pond WP: WP



TABLE OF CONTENTS

Project Reports

- 1 Routing Diagram
- 2 Rainfall Events Listing (selected events)
- 3 Area Listing (all nodes)
- 4 Soil Listing (all nodes)
- 5 Ground Covers (all nodes)
- 6 Pipe Listing (all nodes)

1-Year Event

- 7 Node Listing
- 8 Subcat POST: Basin 1 Post
- 9 Subcat PRE: Basin 1 Pre
- 10 Pond SB: SEDIMENT BASIN
- 12 Pond WP: WP

<u>10-Year Event</u>

- 14 Node Listing
- 15 Subcat POST: Basin 1 Post
- 16 Subcat PRE: Basin 1 Pre
- 17 Pond SB: SEDIMENT BASIN
- 19 Pond WP: WP

100-Year Event

- 21 Node Listing
- 22 Subcat POST: Basin 1 Post
- 23 Subcat PRE: Basin 1 Pre
- 24 Pond SB: SEDIMENT BASIN
- 26 Pond WP: WP

APPENDIX C

SWPPP CONSTRUCTION INSPECTION REPORTS

ATTACHMENT 1 Construction Stormwater Compliance Inspection Report

Project Name and Location:			Date:	Page 1 of 2
			Permit # (if any): 1	NYR
Municipality:	County:		Entry Time:	Exit Time:
On-site Representative(s)	and contact information:		Weather Condition	S:
Name and Address of SPD	ES Permittee/Title/Phone/Fax Numbers:	Contacted: Yes □ No		

SPDES Authority

INSPECTION CHECKLIST

Yes No N/A

	Yes	No	N/A		Law, rule or permit citation
1.				Is a copy of the NOI posted at the construction site for public viewing?	
2.				Is an up-to-date copy of the signed SWPPP retained at the construction site?	
3.				Is a copy of the SPDES General Permit retained at the construction site?	

SWPPP Content

	Yes	No	N/A		Law, rule or permit citation
4.				Does the SWPPP describe and identify the erosion & sediment control measures to be employed?	
5.				Does the SWPPP provide a maintenance schedule for the erosion & sediment control measures?	
6.				Does the SWPPP describe and identify the post-construction SW control measures to be employed?	
7.				Does the SWPPP identify the contractor(s) and subcontractor(s) responsible for each measure?	
8.				Does the SWPPP include all the necessary 'CONTRACTOR CERTIFICATION' statements?	
9.				Is the SWPPP signed/certified by the permittee?	

Recordkeeping

Ye	s No	N/A		Law, rule or permit citation
10. 🗖			Are inspections performed as required by the permit (every 7 days and after 1/2" rain event)?	
11. C			Are the site inspections performed by a qualified professional?	
12. 🗆			Are all required reports properly signed/certified?	
13. 🗆			Does the SWPPP include copies of the monthly/quarterly written summaries of compliance status?	

Visual Observations

Ye	s No	N/A		Law, rule or pe
14. 🗖			Are all erosion and sediment control measures installed/constructed?	
15. 🗆			Are all erosion and sediment control measures maintained properly?	
16. 🗆			Have all disturbances of 5 acres or more been approved prior to the disturbance?	
17. 🗆			Are stabilization measures initiated in inactive areas?	
18. 🗆			Are permanent stormwater control measures implemented?	
19. 🗖			Was there a discharge into the receiving water on the day of inspection?	
20. 🗆			Are receiving waters free of there evidence of turbidity, sedimentation, or oil ? (If no , complete Page 2	.)

Overall Inspection Rating: Satisfactory Marginal Unsatisfactory

Name/Agency of Lead Inspector:	Signature of Lead Inspector:
Names/Agencies of Other Inspectors:	

ermit citation

Water Quality Observations
Describe the discharge(s) [source(s), impact on receiving water(s), etc.]
Describe the quality of the receiving water(s) both upstream and downstream of the discharge
Describe any other water quality standards or permit violations
Additional Comments:
· · · · · · · · · · · · · · · · · · ·

Photographs attached

APPENDIX H

STATE POLLUTANT DISCHARGE ELIMINATION SYSTEM FOR CONSTRUCTION ACTIVITIES CONSTRUCTION SITE LOG BOOK

Table of Contents

- I. Pre-Construction Meeting Documents
 - a. Preamble to Site Assessment and Inspections
 - b. Operator's Certification
 - c. Qualified Professional's Credentials & Certification
 - d. Pre-Construction Site Assessment Checklist
- II. Construction Duration Inspections
 - a. Directions
 - b. Modification to the SWPPP
- III. Monthly Summary Reports
- IV. Monitoring, Reporting, and Three-Month Status Reportsa. Operator's Compliance Response Form

Properly completing forms such as those contained in Appendix H meet the inspection requirement of NYS-DEC SPDES GP for Construction Activities. Completed forms shall be kept on site at all times and made available to authorities upon request.

I. PRE-CONSTRUCTION MEETING DOCUMENTS				
Project Name				
Permit No. Date of Authorization				
Name of Operator				
Prime Contractor				

a. Preamble to Site Assessment and Inspections

The Following Information To Be Read By All Person's Involved in The Construction of Stormwater Related Activities:

The Operator agrees to have a qualified professional¹ conduct an assessment of the site prior to the commencement of construction² and certify in this inspection report that the appropriate erosion and sediment controls described in the SWPPP have been adequately installed or implemented to ensure overall preparedness of the site for the commencement of construction.

Prior to the commencement of construction, the Operator shall certify in this site logbook that the SWPPP has been prepared in accordance with the State's standards and meets all Federal, State and local erosion and sediment control requirements.

When construction starts, site inspections shall be conducted by the qualified professional at least every 7 calendar days and within 24 hours of the end of a storm event of 0.5 inches or greater (Construction Duration Inspections). The Operator shall maintain a record of all inspection reports in this site logbook. The site logbook shall be maintained on site and be made available to the permitting authorities upon request. The Operator shall post at the site, in a publicly accessible location, a summary of the site inspection activities on a monthly basis (Monthly Summary Report).

The operator shall also prepare a written summary of compliance with this general permit at a minimum frequency of every three months (Operator's Compliance Response Form), while coverage exists. The summary should address the status of achieving each component of the SWPPP.

Prior to filing the Notice of Termination or the end of permit term, the Operator shall have a qualified professional perform a final site inspection. The qualified professional shall certify that the site has undergone final stabilization³ using either vegetative or structural stabilization methods and that all temporary erosion and sediment controls (such as silt fencing) not needed for long-term erosion control have been removed. In addition, the Operator must identify and certify that all permanent structures described in the SWPPP have been constructed and provide the owner(s) with an operation and maintenance plan that ensures the structure(s) continuously functions as designed.

1 "Qualified Professional means a person knowledgeable in the principles and practice of erosion and sediment controls, such as a Certified Professional in Erosion and Sediment Control (CPESC), soil scientist, licensed engineer or someone working under the direction and supervision of a licensed engineer (person must have experience in the principles and practices of erosion and sediment control).

2 "Commencement of construction" means the initial removal of vegetation and disturbance of soils associated with clearing, grading or excavating activities or other construction activities.

3 "Final stabilization" means that all soil-disturbing activities at the site have been completed and a uniform, perennial vegetative cover with a density of eighty (80) percent has been established or equivalent stabilization measures (such as the use of mulches or geotextiles) have been employed on all unpaved areas and areas not covered by permanent structures.

b. Operators Certification

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. Further, I hereby certify that the SWPPP meets all Federal, State, and local erosion and sediment control requirements. I am aware that false statements made herein are punishable as a class A misdemeanor pursuant to Section 210.45 of the Penal Law.

Name (please print)	:	· · · · · · · · · · · · · · · · · · ·	
Title		Date:	
Address:			
Phone:	Email:	////	
Signature:			

c. Qualified Professional's Credentials & Certification

"I hereby certify that I meet the criteria set forth in the General Permit to conduct site inspections for this project and that the appropriate erosion and sediment controls described in the SWPPP and as described in the following Pre-construction Site Assessment Checklist have been adequately installed or implemented, ensuring the overall preparedness of this site for the commencement of construction."

Name (please print):		
Title	Date:	
Address:		
Phone: Email:		
Signature:		

d. Pre-construction Site Assessment Checklist (NOTE: Provide comments below as necessary)

1. Notice of Intent, SWPPP, and Contractors Certification:

Yes No NA

- [] [] Has a Notice of Intent been filed with the NYS Department of Conservation?
- [] [] [] Is the SWPPP on-site? Where?
- [] [] Is the Plan current? What is the latest revision date?
- [] [] [] Is a copy of the NOI (with brief description) onsite? Where?
- [] [] Have all contractors involved with stormwater related activities signed a contractor's certification?

2. Resource Protection

Yes No NA

- [] [] [] Are construction limits clearly flagged or fenced?
- [] [] Important trees and associated rooting zones, on-site septic system absorption fields, existing vegetated areas suitable for filter strips, especially in perimeter areas, have been flagged for protection.
- [] [] [] Creek crossings installed prior to land-disturbing activity, including clearing and blasting.

3. Surface Water Protection

Yes No NA

- [] [] Clean stormwater runoff has been diverted from areas to be disturbed.
- [] [] Bodies of water located either on site or in the vicinity of the site have been identified and protected.
- [] [] Appropriate practices to protect on-site or downstream surface water are installed.
- [] [] Are clearing and grading operations divided into areas <5 acres?

4. Stabilized Construction Entrance

Yes No NA

- [] [] A temporary construction entrance to capture mud and debris from construction vehicles before they enter the public highway has been installed.
- [] [] Other access areas (entrances, construction routes, equipment parking areas) are stabilized immediately as work takes place with gravel or other cover.
- [] [] [] Sediment tracked onto public streets is removed or cleaned on a regular basis.

5. Perimeter Sediment Controls

Yes No NA

- [] [] Silt fence material and installation comply with the standard drawing and specifications.
- [] [] Silt fences are installed at appropriate spacing intervals
- [] [] Sediment/detention basin was installed as first land disturbing activity.
- [] [] [] Sediment traps and barriers are installed.

6. Pollution Prevention for Waste and Hazardous Materials

Yes No NA

- [] [] The Operator or designated representative has been assigned to implement the spill prevention avoidance and response plan.
- [] [] The plan is contained in the SWPPP on page
- [] [] Appropriate materials to control spills are onsite. Where?

II. CONSTRUCTION DURATION INSPECTIONS

a. Directions:

Inspection Forms will be filled out during the entire construction phase of the project. Required Elements:

(1) On a site map, indicate the extent of all disturbed site areas and drainage pathways. Indicate site areas that are expected to undergo initial disturbance or significant site work within the next 14-day period;

(2) Indicate on a site map all areas of the site that have undergone temporary or permanent stabilization;

(3) Indicate all disturbed site areas that have not undergone active site work during the previous 14-day period;

(4) Inspect all sediment control practices and record the approximate degree of sediment accumulation as a percentage of sediment storage volume (for example, 10 percent, 20 percent, 50 percent);

(5) Inspect all erosion and sediment control practices and record all maintenance requirements such as verifying the integrity of barrier or diversion systems (earthen berms or silt fencing) and containment systems (sediment basins and sediment traps). Identify any evidence of rill or gully erosion occurring on slopes and any loss of stabilizing vegetation or seeding/mulching. Document any excessive deposition of sediment or ponding water along barrier or diversion systems. Record the depth of sediment within containment structures, any erosion near outlet and overflow structures, and verify the ability of rock filters around perforated riser pipes to pass water; and

(6) Immediately report to the Operator any deficiencies that are identified with the implementation of the SWPPP.

SITE PLAN/SKETCH

Inspector (print name)

Date of Inspection

Qualified Professional (print name)Qualified Professional SignatureThe above signed acknowledges that, to the best of his/her knowledge, all information provided on the forms is accurate and complete.

Maintaining Water Quality

Yes No NA

- [] [] [] Is there an increase in turbidity causing a substantial visible contrast to natural conditions?
- [] [] [] Is there residue from oil and floating substances, visible oil film, or globules or grease?
- [] [] All disturbance is within the limits of the approved plans.
- [] [] Have receiving lake/bay, stream, and/or wetland been impacted by silt from project?

Housekeeping

1. General Site Conditions

Yes No NA

- [] [] [] Is construction site litter and debris appropriately managed?
- [] [] Are facilities and equipment necessary for implementation of erosion and sediment control in working order and/or properly maintained?
- [] [] [] Is construction impacting the adjacent property?
- [] [] [] Is dust adequately controlled?

2. Temporary Stream Crossing

Yes No NA

- [] [] Maximum diameter pipes necessary to span creek without dredging are installed.
- [] [] [] Installed non-woven geotextile fabric beneath approaches.
- [] [] [] Is fill composed of aggregate (no earth or soil)?
- [] [] Rock on approaches is clean enough to remove mud from vehicles & prevent sediment from entering stream during high flow.

Runoff Control Practices

1. Excavation Dewatering

Yes No NA

- [] [] Upstream and downstream berms (sandbags, inflatable dams, etc.) are installed per plan.
- [] [] [] Clean water from upstream pool is being pumped to the downstream pool.
- [] [] [] Sediment laden water from work area is being discharged to a silt-trapping device.
- [] [] [] Constructed upstream berm with one-foot minimum freeboard.

2. Level Spreader

Yes No NA

- [] [] [] Installed per plan.
- [] [] [] Constructed on undisturbed soil, not on fill, receiving only clear, non-sediment laden flow.
- [] [] Flow sheets out of level spreader without erosion on downstream edge.

3. Interceptor Dikes and Swales

Yes No NA

- [] [] Installed per plan with minimum side slopes 2H:1V or flatter.
- [] [] Stabilized by geotextile fabric, seed, or mulch with no erosion occurring.
- [] [] [] Sediment-laden runoff directed to sediment trapping structure

CONSTRUCTION DURATION INSPECTIONS Runoff Control Practices (continued)

4. Stone Check Dam

Yes No NA

- [] [] Is channel stable? (flow is not eroding soil underneath or around the structure).
- [] [] Check is in good condition (rocks in place and no permanent pools behind the structure).

[] [] Has accumulated sediment been removed?.

5. Rock Outlet Protection

Yes No NA

[] [] [] Installed per plan.

[] [] Installed concurrently with pipe installation.

Soil Stabilization

1. Topsoil and Spoil Stockpiles

Yes No NA

- [] [] [] Stockpiles are stabilized with vegetation and/or mulch.
- [] [] Sediment control is installed at the toe of the slope.

2. Revegetation

Yes No NA

- [] [] Temporary seedings and mulch have been applied to idle areas.
- [] [] 4 inches minimum of topsoil has been applied under permanent seedings

Sediment Control Practices

1. Stabilized Construction Entrance

Yes No NA

- [] [] Stone is clean enough to effectively remove mud from vehicles.
- [] [] [] Installed per standards and specifications?
- [] [] Does all traffic use the stabilized entrance to enter and leave site?
- [] [] [] Is adequate drainage provided to prevent ponding at entrance?

2. Silt Fence

Yes No NA

- [] [] Installed on Contour, 10 feet from toe of slope (not across conveyance channels).
- [] [] Joints constructed by wrapping the two ends together for continuous support.
- [] [] Fabric buried 6 inches minimum.
- [] [] Posts are stable, fabric is tight and without rips or frayed areas.

Sediment accumulation is ___% of design capacity.

CONSTRUCTION DURATION INSPECTIONS

Sediment Control Practices (continued)

3. Storm Drain Inlet Protection (Use for Stone & Block; Filter Fabric; Curb; or, Excavated practices) Yes No NA

- [] [] Installed concrete blocks lengthwise so open ends face outward, not upward.
- [] [] Placed wire screen between No. 3 crushed stone and concrete blocks.
- [] [] [] Drainage area is 1 acre or 1ess.
- [] [] [] Excavated area is 900 cubic feet.
- [] [] [] Excavated side slopes should be 2:1.
- [] [] [] 2" x 4" frame is constructed and structurally sound.
- [] [] Posts 3-foot maximum spacing between posts.
- [] [] Fabric is embedded 1 to 1.5 feet below ground and secured to frame/posts with staples at max 8-inch spacing.
- [] [] Posts are stable, fabric is tight and without rips or frayed areas.
- Sediment accumulation ____% of design capacity.

4. Temporary Sediment Trap

Yes No NA

[] [] Outlet structure is constructed per the approved plan or drawing.

[] [] Geotextile fabric has been placed beneath rock fill.

Sediment accumulation is ___% of design capacity.

5. Temporary Sediment Basin

Yes No NA

[] [] Basin and outlet structure constructed per the approved plan.

[] [] Basin side slopes are stabilized with seed/mulch.

[] [] Drainage structure flushed and basin surface restored upon removal of sediment basin facility. Sediment accumulation is ____% of design capacity.

Note: Not all erosion and sediment control practices are included in this listing. Add additional pages to this list as required by site specific design.

Construction inspection checklists for post-development stormwater management practices can be found in Appendix F of the New York Stormwater Management Design Manual.

CONSTRUCTION DURATION INSPECTIONS

b. Modifications to the SWPPP (To be completed as described below)

The Operator shall amend the SWPPP whenever:

1. There is a significant change in design, construction, operation, or maintenance which may have a significant effect on the potential for the discharge of pollutants to the waters of the United States and which has not otherwise been addressed in the SWPPP; or

2. The SWPPP proves to be ineffective in:

- a. Eliminating or significantly minimizing pollutants from sources identified in the SWPPP and as required by this permit; or
- b. Achieving the general objectives of controlling pollutants in stormwater discharges from permitted construction activity; and

3. Additionally, the SWPPP shall be amended to identify any new contractor or subcontractor that will implement any measure of the SWPPP.

Modification & Reason:

III. Monthly Summary of Site Inspection Activities

Name of Permitted Facility:	Today's Date:	Reporting Month:
Location:	Permit Identificatio	n #:
Name and Telephone Number of Site Inspector:		

Date of Inspection	Regular / Rainfall based Inspection	Name of Inspector	Items of Concern
	······································		
· · · · · · · · · ·			

Owner/Operator Certification:

"I certify under penalty of law that this document and all attachments were prepared under my direction or supervision in accordance with a system designed to assure that qualified personnel properly gathered and evaluated the information submitted. Based on my inquiry of the person or persons who manage the system, or those persons directly responsible for gathering the information, the information submitted is, to the best of my knowledge and belief, true, accurate, and complete. I am aware that false statements made herein are punishable as a class A misdemeanor pursuant to Section 210.45 of the Penal Law."

Signature of Permittee or Duly Authorized Representative

Name of Permittee or Duly Authorized Representative Date

Duly authorized representatives <u>must have written authorization</u>, submitted to DEC, to sign any permit documents.

APPENDIX D

NOI, NOI ACCEPTANCE FORM & NOT



SWPPP Preparer Certification Form

SPDES General Permit for Stormwater Discharges From Construction Activity (GP-0-20-001)

Project Site Information

Project/Site Name

Orange County Medical Examiners Building

Owner/Operator Information Owner/Operator (Company Name/Private Owner/Municipality Name)

Orange County, New York

Certification Statement – SWPPP Preparer

I hereby certify that the Stormwater Pollution Prevention Plan (SWPPP) for this project has been prepared in accordance with the terms and conditions of the GP-0-20-001. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of this permit and the laws of the State of New York and could subject me to criminal, civil and/or administrative proceedings.

Alfred	A	Fusco, Jr.
First name	MI	Last Name
C/LA		
		10/10/22
Signature		

Revised: January 2020



Department of Environmental Conservation

Owner/Operator Certification Form

SPDES General Permit For Stormwater **Discharges From Construction** Activity (GP-0-20-001)

Project/Site Name:	Prange County Me	dical Examiners B	uilding
eNOI Submission Nun	nber: <u>HPJ-YT93-</u> ∖	/JJQJ	
eNOI Submitted by:	Owner/Operator	SWPPP Preparer	Other

Certification Statement - Owner/Operator

I have read or been advised of the permit conditions and believe that I understand them. I also understand that, under the terms of the permit, there may be reporting requirements. I hereby certify that this document and the corresponding documents were prepared under my direction or supervision. I am aware that there are significant penalties for submitting false information, including the possibility of fine and imprisonment for knowing violations. I further understand that coverage under the general permit will be identified in the acknowledgment that I will receive as a result of submitting this NOI and can be as long as sixty (60) business days as provided for in the general permit. I also understand that, by submitting this NOI. I am acknowledging that the SWPPP has been developed and will be implemented as the first element of construction, and agreeing to comply with all the terms and conditions of the general permit for which this NOI is being submitted.

Alfred

Owner/Operator First Name

Signature 10/10/22

Date

A. FUSCO, JV. P. E. M.I. Last Name

NYS	NEW YORK STATE OF OPPORTUNITYDepartment of Environmental ConservationDepartment of Environmental Conservation Division of Water 625 Broadway, 4th Floor Albany, New York 12233-3505
MS4 Stormwate	r Pollution Prevention Plan (SWPPP) Acceptance Form
Construction Act *(NOTE: Attach Co	for ivities Seeking Authorization Under SPDES General Permit mpleted Form to Notice Of Intent and Submit to Address Above)
I. Project Owner/Operato	or Information
1. Owner/Operator Name:	Orange County
2. Contact Person:	Erik Denega, PE
3. Street Address:	2455-2459 Route 17M
4. City/State/Zip:	Goshen, NY 10924
II. Project Site Information	on
5. Project/Site Name:	Orange County Medical Examiners Building
6. Street Address:	22 Wells Farm Road
7. City/State/Zip:	Goshen, NY 10924
III. Stormwater Pollution	Prevention Plan (SWPPP) Review and Acceptance Information
8. SWPPP Reviewed by:	Erik Denega, PE
9. Title/Position:	Commissioner Orange County DPW
10. Date Final SWPPP Rev	viewed and Accepted: 10/25/2022
IV. Regulated MS4 Inform	ation
11. Name of MS4:	Orange County
12. MS4 SPDES Permit Ide	entification Number: NYR20A
13. Contact Person:	Erik Denega, PE
14. Street Address:	2455-2459 Route 17M
15. City/State/Zip:	Goshen, NY 10924
16. Telephone Number:	845-291-2750

MS4 SWPPP Acceptance Form - continued

V. Certification Statement - MS4 Official (principal executive officer or ranking elected official) or Duly Authorized Representative

I hereby certify that the final Stormwater Pollution Prevention Plan (SWPPP) for the construction project identified in question 5 has been reviewed and meets the substantive requirements in the SPDES General Permit For Stormwater Discharges from Municipal Separate Storm Sewer Systems (MS4s). Note: The MS4, through the acceptance of the SWPPP, assumes no responsibility for the accuracy and adequacy of the design included in the SWPPP. In addition, review and acceptance of the SWPPP by the MS4 does not relieve the owner/operator or their SWPPP preparer of responsibility or liability for errors or omissions in the plan.

Printed Name: Alan J Sorensen, AICP

Title/Position: Orange County Planning Commissioner

Signature:

Date:

VI. Additional Information

(NYS DEC - MS4 SWPPP Acceptance Form - January 2015)

APPENDIX E

CONSTRUCTION WASTE MANAGEMENT PLAN

,

CONSTRUCTION WASTE MANAGEMENT & SPILL PREVENTION PLAN

At the commencement of construction, land clearing materials will be collected and stored on-site for reuse. Construction debris such as cardboard, concrete, metal, wood and similar garbage will be collected in dumpsters and disposed of properly. An open top container will be on site during construction. The contractor will be responsible for organizing and placing containers on site and timely removal/replacement when containers are filled to capacity.

On-site storage of fuel chemicals shall be equipped with a spill kit. The contractor must provide secondary containment for storing any hazardous chemicals on site.

All equipment stored on site shall be inspected daily by the contractor for any oil or lubricant spills or leaks. Any leaks shall be repaired immediately. In addition, all equipment must be closely inspected prior to working in any R.O.W.

The contractor shall clean all spills immediately and shall report all spills to the New York State Department of Environmental Conservation.

This plan will be displayed in the construction jobsite trailer at all times.

APPENDIX F

CONTRACTOR CERTIFICATION STATEMENT

Contractor Certification Statement

Name	of	Construction	Site
anne	0.	0011301 0001011	Site

NYR_____ DEC Permit ID

Municipality (MS4)

I hereby certify that I understand and agree to comply with the terms and conditions of the SWPPP and agree to implement any corrective actions identified by the *qualified inspector* during a site inspection. I also understand that the *owner or operator* must comply with the terms and conditions of the most current version New York State Pollution Discharge Elimination System ("SPDES") general permit for stormwater discharges from construction activities and that it is unlawful for any person to cause or contribute to a violation of water quality standards. Furthermore, I understand that certifying false, incorrect or inaccurate information is a violation of the referenced permit and the laws of State of New York and could subject me to criminal, civil and /or administrative proceedings.

Name		Title
Signature	· · · · · · · · · · · · · · · · · · ·	Date
Company Name & Address		Phone
Project Site Address		
Provisions Responsible for		· · · · · · · · · · · · · · · · · · ·
	2 - 2 ¹	
Information on the T	rained Certified Contrac	tor or Subcontractor
Name of Trained Employee	Title of Trained Employee	NYSDEC SWT#

A copy of this signed contractor certification statement must be maintained in the SWPPP on site.

APPENDIX G

STORMWATER MAINTENANCE AND MANAGEMENT INSPECTON CHECKLIST

STORMWATER OPERATION, MAINTENANCE AND MANAGEMENT INSPECTION CHECKLIST

Project: Location:	****
Site Status:	
Date:	
Time:	
Inspector:	

Maintenance Item	Satisfactory / Unsatisfactory	Comments
1.		
2.		
3.		

Comments:

Actions to be taken:

ORANGE COUNTY MEDICAL EXAMINER'S OFFICE





ORANGE COUNTY MEDICAL EXAMINER 22 WELLS FARM RD.

GOSHEN, NY 10924

BID SET

11/18/2022

HHA PROJ. NO.: 20071

CLIENT PROJ. NO.:

DRAWING LIST

CIVIL	
EX101	EXISTING CONDITIONS PLAN
DM101	DEMO PLAN
C101	UTILITY PLAN
C102	SITE PLAN
CE101	ELECTRICAL SITE PLAN (SHEET NUMBER REVISED - ADDENDUM D)
L101	LANDSCAPE PLAN
ESCP	EROSION & SEDIMENT CONTROL PLAN
D101	
D101	
D102	
D103	DETAILS
STRUCTUR	
STRUCTUR	
5001	
S002	DESIGN DATA AND GENERAL NOTES CONT
S003	SCHEDULE OF SPECIAL INSPECTIONS
S100	FOUNDATION PLAN
S200	MAIN ROOF FRAMING PLAN
S201	INTERMEDIATE ROOF FRAMING PLAN
S202	HIGH ROOF FRAMING PLAN
S300	FOUNDATION DETAILS
S301	FOUNDATION DETAILS CONT
S302	PIER, BASE PLATE AND ANCHOR ROD DETAILS
S400	MASONRY DETAILS
S500	STEEL FRAMING DETAILS
S501	STEEL FRAMING DETAILS CONT
S502	COLD FORMED METAL FRAMING DETAILS
S503	BRACED FRAME ELEVATIONS AND DETAILS
0000	
LIFE SAFET	Γγ
	Ι ΓΕΕ ΩΔΕΕΤΥ ΟΙ ΔΝΙ
LOCIUU	
	τισλι
ARCHITEC	TURAL
ARCHITEC	TURAL GENERAL NOTES, TYPICAL ELEVATIONS
ARCHITEC ⁻ A001 A002	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES
ARCHITEC ⁻ A001 A002 A100	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN
ARCHITEC A001 A002 A100 A101	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN
ARCHITEC A001 A002 A100 A101 A102	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN
ARCHITEC A001 A002 A100 A101 A102 A103	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN
ARCHITEC A001 A002 A100 A101 A102 A103 A104	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601 A602	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR PLAN DETAILS ENLARGED FLOOR PLANS INTERIOR ELEVATIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601 A602 A603	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR PLAN DETAILS INTERIOR ELEVATIONS INTERIOR ELEVATIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601 A602 A603 A604	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS INTERIOR ELEVATIONS INTERIOR ELEVATIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601 A602 A603 A604 A605	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601 A602 A603 A604 A605 A002	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIOR ELEVATIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601 A602 A603 A604 A605 A606 A606	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS INTERIOR ELEVATIONS INTERIOR ELEVATIONS INTERIONE ELEVATIONS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601 A602 A603 A604 A605 A606 A607 A002	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS INTERIOR ELEVATIONS INTERIOR DETAILS
ARCHITEC A001 A002 A100 A101 A102 A103 A104 A200 A201 A202 A400 A401 A500 A501 A502 A503 A504 A505 A506 A507 A600 A601 A602 A603 A604 A605 A606 A607 A608	TURAL GENERAL NOTES, TYPICAL ELEVATIONS WALL TYPES FURNITURE & EQUIPMENT PLAN FLOOR PLAN DIMENSION PLAN ROOF PLAN ROOF DETAILS EXTERIOR ELEVATIONS EXTERIOR ELEVATIONS BUILDING SECTIONS REFLECTED CEILING PLAN CEILING DETAILS WALL SECTIONS WALL SECTIONS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS EXTERIOR PLAN DETAILS INTERIOR ELEVATIONS INTERIOR DETAILS INTERIOR DETAILS INTERIOR DETAILS

MEP ENGINEER

CIVIL ENGINEER



Fusco Engineering & Land Surveying PC

A701	WINDOW/ BORROWED LITE SCHEDULE AND DETAILS
A800	ROOM FINISH SCHEDULE
A801	FINISH PLAN
A802	WALL PROTECTION PLAN AND SIGNAGE PLAN
A803	SIGNAGE
A900	MILLWORK SECTIONS AND DETAILS
FIRE PR	OTECTION
FP001	FIRE PROTECTION SYMBOLS, NOTES AND ABBREVIATIONS
FP100	FIRE PROTECTION SPRINKLER FLOOR PLAN
MECHAN	IICAL SYSTEMS
H001	HVAC SYMBOLS, NOTES & ABBREVIATIONS
H100	HVAC DUCTWORK FLOOR PLAN
H101	HVAC DUCTWORK FLOOR PLAN @ ROOMS 134 & 121
H102	HVAC SITE PLAN
H200	HVAC DUCTWORK ROOF PLAN
H700	HVAC DETAILS
H701	HVAC DETAILS
H702	HVAC DETAILS
H703	HVAC DETAILS
H704	HVAC DETAILS
H705	HVAC DETAILS
H801	HVAC SCHEDULES
H802	HVAC SCHEDULES
ELECTRI	CAL SYSTEMS
E001	ELECTRICAL SYMBOLS, NOTES & ABBREVIATIONS
ES101	ELECTRICAL SITE PLAN
E100	ELECTRICAL POWER FLOOR PLAN
E101	ELECTRICAL POWER FLOOR PLAN
E200	ELECTRICAL LIGHTING FLOOR PLAN
E300	ELECTRICAL POWER ROOF PLAN
E700	ELECTRICAL DETAILS
EOUI	ELECTRICAL SCHEDULES & DETAILS (SHEET ADDED - ADDENDUN D)
PLUMBIN	IG SYSTEMS
	FLUIVIDIING STIVIDULS, INUTES & ADDREVIATIUNS DI LIMBING SANITADY ELOOD DI ANI
P200	PLUMBING DAMITART FLOOR FLAM PLUMBING DAMESTIC WATER FLOOR PLAN
P300	
P701	PLUMBING DETAILS
P702	PLUMBING DETAILS
IT/SECU	RITY
TA001	LOW VOLTAGE SYSTEMS TITLESHEET
TA002	LV SITE PLAN ENABLING
TA003	
TA100	LOW VOLTAGE FLOOR PLAN
TA200	LV REFLECTED CEILING PLAN
TA300	ENLARGED LOW VOLTAGE DETAILS - I.T. ROOM 119
TA401	TYPICAL LOW VOLTAGE DEVICE DETAILS
TA411	TYPICAL LOW VOLTAGE INFRASTRUCTURE DETAILS
TA500	TYPICAL ELECTRONIC ACCESS CONTROL DOOR DETAILS
TA700	AV SIGNAL FLOW
FF&E	

FURNITURE PLAN F1.1



I.T./SECURITY













UNAUTHORIZED ALTERATION OR ADDITION TO THIS DOCUMENT IS A VIOLATION OF SECTION 7209 SUBDIVISION 2 OF THE NEW YORK STATE EDUCATION LAW.





UNAUTHORIZED ALTERATION OR ADDITION TO THIS DOCUMENT IS A VIOLATION OF SECTION 7209 SUBDIVISION 2 OF THE NEW YORK STATE EDUCATION LAW.







TYPICAL DROP CURB SIDEWALK ACCESS RAMP DETAIL



)1()1

N.T.S.

N.T.S.

CONCRETE CURB

CJ

5'-6

3

tov avay zone

BY PERMIT DNLY

N.T.S.

5' - 6'

GRADE

-12"ø CONCRETE

_ GRADE -12"ø CONCRETE

4" NYSDOT CLASS D — CONC. SIDEWALK W/ 6"x6"x10/10 WWM 2" FROM TOP.

- 6" COMPACTED SUBBASE








																									١	VATER TO WATER A	IR HANDI	ING SCH	IEDULE										
		Unit					Initial Filter		Hot Wa	ater Coil (1	l) (Prelin	ninary Ru	inaround	Loop Dat	a) - 30%	PG			Dual T	Гетрегаtu	re Coil - (Cooling Perfo	ormand	e (30%PG)		Dual Te	emperatu	e Coil - H	Heating Perfo	rmance (3	0%PG)		Hot	Water Rehe	at Coil -	for Dehun	nidificatio	n	
Тад	Model	Length (in)	Weight (lb)	Externa Height (in)	Dimensions* Supply Width (in)	– Туре	Filter Qty - Sizes Deptl	Mean l (inH20	PD Total EAT- Capacity DB (Btu/hr) °F	LAT- DB °F	F.V. ft/min) (A.P.D. I inH2O)	ewt lw ⁻ °F °F	Flow Rate (GPM)	W.P.D. (ftH2O)	Rows FI	Sensik Pl Capac (Btu/l	ble Total city Capacity hr) (Btu/hr)	EAT- y DB) °F	EAT- LA WB D °F °	.T- LAT- B WB F [°] F	A.P.D. EV (inH2O) °	VT LW F °F	/T Rate (GPM)	W.P.D. (ftH2O)	s FPI Capacity DB (Btu/hr) °F	- LAT- B DB °F (in	.P.D. E\ iH2O) °	WT LWT Flo °F °F (GP	w te (ftH20	D. O)	Total FPI Capaci (Btu/h	EAT- ty DB r) °F	LAT- DB °F (inH2	D. EWT D) °F	LWT °F (G	low tate iPM) (ftH	P.D. 20)	ws FP
AHU-1 SPEC Autopsy 2300	CAH009GDGM	1 174	2549.34	58	38	Pleated (MERV 8	2 - 24.00 x 24.00 2	0.56	-9		315	0.43		12.5	2.4	6 1	0 11567	71 191374	92	73 4	6 45.8	0.75 4	2 50.	.3 48	11.9 10	12 266831 2	108	0.51 1	.10 94.4 35	.9 5.7	10	12 56854	48	70.6 0.05	110	101.9	14 0.	.4 2	2 7
AHU-2 HP-5 Autopsy 3700	CAH010GDGM	1 178	2745.27	58	40	Pleated (MERV 8	1 2 - 24.00 x 12.00 3) 2 - 24.00 x 24.00	0.57	-9		470	0.85		19.5	5.4	6 1	0 17925	57 293219	92	73 47	7.7 47.5	1.41 4	2 49	.6 80	15.5 10	12 388092 2	106	0.86 1	10 94.6 53	.1 5.9	10	12 90600	48	70.4 0.11	110	100.9	20 0.	.8 2	2 9

				Supply	' Fan								Combin	ation F	ilter			
		Fan					Moto	or			Panel Filter				Ba	g Filter		
Туре	Airflow (CFM)	RPM	BHP	E.S.P. (inH2O)	T.S.P. (inH2O)	Voltage	Power (HP)	RPM	Control	Туре	Filter Qty - Sizes	Depth	Mean PD (inH2O)	Туре	Filter Qty - Sizes	Depth	Efficiency	Mean PD (inH2O)
DDPL15-12BL	2300	3286	3.6	1.5	5.64	200/60/3	5	3500	VFD	Pre Pleat (MERV 13)	2 - 24.00 x 24.00	2	0.58	HEPA	2 - 24.00 x 24.00	12	MERV 17	1.77
DDPL16-9BL	3700	3210	6.62	1.5	7.13	200/60/3	10	3500	VFD	Pre Pleat (MERV 13)	2 - 24.00 x 24.00	2	0.66	HEPA	2 - 24.00 x 24.00	12	MERV 17	2.04

NOTE: 1. ALL FANS TO HAVE VFD'S AND PIEZO RING AIRFLOW INDICATOR.

								ENERGY RECOVE	Y VENTILATOR	CHEDULE																						"TACO" AS	STANDARD OR
			Far	Data					Wheel Data						U	nit Inform ation										PUIV	IP 301	IEDUL				AP	PROVED EQUAL
Basis of Model	Location Tag	g #	Supply	Airflow		Outdoor		Supply	ummer/Cooling		Return	E	Exhaust	Bectrical	l (includes preh	eater load)	Electric Preheat (1) Minim um RER	UNIT NO	. LOCATION	SYSTEM	FLUID	CIRO SPEC.	TEMP.	D HEAD	-MOTOR H	P MOTOR RPM	MOTOR SPEED	IMPELLER DIAMETER	MIN. EFF. (%)	ELECTRICAL DATA WEIGHT	MODEL NO.	REMARKS
Design	Outdoor	Supply	CFM ESF	Motor HP 2.00	VFD D Yes	Ory BulbWet BulbGrains92.073.091.9	Dry Bulb Wet Bul 78.2 64.4	Grains Min Latent Eff % 68.7 0.76	Max PD (in/w g) Dry 0.54	Bulb RH We 2.0 50% 6	et Bulb Grains Ma	ax PD (in/w g) Dry Bu 0.47 87.3	ulb Grains 3 84.0	Voltage/Phase 208V/3Ph	23.5	MCA MOC 25.5 35.0	0.0 KW	Cooling 102.6	P-1	MER 121	LOAD IN CH-1	30% PG	1.026	42–110 4	2.6 60	2.0	1760	VFD	7.75	49	208/3 -	1919	SEE NOTES
SEMCO FV-2000	Unit	/-1 Return	Return	Airflow Motor HP	VFD C	Outdoor Dry Bulb Wet Bulb Grains	Dry Bulb Wet Bu	Supply	Max PD (in/w g) Dr	Bulb RH We	Return et Bulb Grains Ma	ax PD (in/w g) Dry Bu	Exhaust ulb Grains	Outdo	or Rating	Re1 Type Depti	urn Rating	Heating 200.0	P-2	MER 121	LOAD IN CH-2	30% PG	1.026	42-110 4	2.6 60	2.0	1760	VFD	7.75	49	208/3 -	1919	SEE NOTES
I	I I	1,59	0 1.00	2.00	Yes	2.0 1.2 4.6	49.0 39.2	20.0.5 0.76	0.48	0.0 25% 5	51.4 27.0	0.44 18.0	9.9	Pleated 2"	MERV 13	Pleated 2"	MERV 8		P-3	MER 121	LOAD IN CH-3	30% PG	1.026	42–110 4	2.6 60	2.0	1760	VFD	7.75	49	208/3 –	1919	SEE NOTES
	rr		Far	Data					Wheel Data						U	nit Inform ation			P-4	MER 121	LOAD IN CH-4	PLAIN WATER	1.0	32–110	4 40	1.0	1760	VFD	6.55	47	208/3 –	1919	SEE NOTES
Basis of Model	Location Tag	g#	Supply	Airflow	_	Outdoor		Supply	ummer/Cooling		Return	E	xhaust	- Bectrical	l (includes preh	eater load)	Electric Preheat (1	Minim um RER	P-5	MER 121	AHU-1 PHC/ERF-1	1 30% PG	1.026	25 1	2.5 35	0.75	1760	VFD	5.8	40	208/3 –	1915	SEE NOTES
Design		Supply	CFM ESF	Motor HP	VFD D	Ory Bulb Wet Bulb Grains	Dry Bulb Wet Bul	Grains Min Latent Eff 9	Max PD (in/w g) Dr	Bulb RH We	et Bulb Grains Ma	ax PD (in/w g) Dry Bu	ulb Grains	Voltage/Phase 208V/3Ph	FLA 20.0	MCA MOC	0.0 KW	Cooling 98.3	P-6	MER 121	AHU-2 PHC/ERF-2	2 30% PG	1.026	46 1	9.5 40	0.75	1750	VFD	6.2	41	208/3 –	1915	SEE NOTES
SEMCO FV-2000	Outdoor Unit ERV	/-3	Return	Airflow	-	Outdoor	11.0 01.2	Supply	Vinter/Heating	2.0 0070 0	Return	E	xhaust	Outdo	Fil	ters Ret	urn	Heating	P-A	MER 121	GEO SYSTEM SOURCE	M 30% PG	1.026	25 3	00 180	25	1760	VFD	7.15	77	208/3 –	F13013D	SEE NOTES
		Return 1,71	CFM ESF	Motor HP 1.50	VFD D	Dry BulbWet BulbGrains2.01.24.6	Dry Bulb Wet Bul 49.8 39.8	D Grains Min Latent Eff % 20.3.5 0.70	Max PD (in/w g) Dr 0.46	Bulb RH We	et Bulb Grains Ma	ax PD (in/w g) Dry Bu 0.48 22.2	ulb Grains 2 11.3	Type Depth Pleated 2"	n Rating MERV 13	Type Depti Pleated 2"	n Rating MERV 8	191.5	P-B	MER 121	GEO SYSTEM SOURCE	M 30% PG	1.026	25 3	00 180	25	1760	VFD	7.15	77	208/3 –	F13013D	SEE NOTES

																	E	NERGY REC	OVERY VE	NTILATOR	SCHEDULE										
						Fan Data															Energ	y Recovery	y Data								
														S	ummer/Coo	ling							N	/inter/Heat	ting						
			Supply Air Airflow Exhaust Air Airflow Ou									Outdoor A	Air		Fresh Air			Return Ai	r		Outdoor A	ir		Fresh Air			Return Air] I	Performance Effect	iver
Basis of Design Mode	el Location	Tag# Elevation (ft) Fresh Air CFM	ESP N	Motor HP	VFD FLA	Exhaust Air CFM	VI ESP	Motor HP	VFD FLA	Dry Bu	lb Wet Bulb	Grains/l	lb Dry Bulk	b Wet Bulb	Grains/II	b Dry Bulk	Wet Bulb	Grains/lb	Dry Bulb	Wet Bulb	Grains/lb	Dry Bulb	Wet Bulb	Grains/lb	Dry Bulb	Wet Bulb	Grains/lb	Sensible (%) Summer Total (%	,) [N
RenewAire HE2>	(Indoor Unit	ERV-2 364	1275	1	1.5	YES 4.6-4.	8 1175	1	1.5	YES 4.6-4	.8 92	73	93.1	78	66.7	81.4	72	60	59.1	2	1.2	4.8	49.5	39.2	19.4	70	51.4	27.4	75.9	55.9	

													W	ATER	SOUR	CE HEA		UNIT SCH	HEDULE												
					External										Cooling	g								Heati	ing					Elect	rical
TAC	Diakin	Airflow	Outdoor	OA From	Static	Fluid Flow		Antifreeze			E	AT	L	AT	T = 4 = 1	O a mailte la	Heat of					EAT	LAT	Tatal	Heat of	000	005		Compressor	Fan Motor	Tota
TAG	Model	(CFM)	(CFM)	ERV	Pressure (inH₂O)	(gpm)	Fiuld Type	(%)	(°F)	(°F)	EDB (°F)	EWB (°F)	LDB (°F)	LWB (°F)	(Btu/hr)	(Btu/hr)	Rejection (Btu/hr)	EER (Design)	(AHRI)	evvi (°F)	(°F)	EDB (°F)	LDB (°F)	(Btu/hr)	Absorption (Btu/hr)	(Design)	(AHRI)	Voltage	RLA	FLA	F
WSHP 001	WLVW1072	2200	220	ERV-1	1.28	15.00	Propylene Glycol	30.00	77.0	88.6	72.6	60.8	52.0	49.6	66235	49067	83580	12.6	14.6	32.0	26.6	67.0	90.1	55424	38595	3.2	3.4	208/60/3	13.2	5.0	3
WSHP 002	WLVW1096	3210	200	ERV-2	1.22	20.00	Propylene Glycol	30.00	77.0	87.5	72.4	60.6	55.2	51.8	77294	59560	100149	11.2	14.6	32.0	26.9	68.0	88.0	69869	48781	3.2	3.6	208/60/3	13.7	6.4	3
WSHP 003	WGTV0321	1000	195	ERV-1	0.7	6.50	Propylene Glycol	30.00	77.0	88.9	73.3	61.6	53.1	50.6	30030	21970	36597	15.6	18.9	32.0	26.5	65.0	86.3	23112	17029	3.8	4.1	208-	8.7	5.0	1
																												200/00/0		<u> </u>	
WSHP 004	WLVW1072	2310	255	ERV-1	1.24	18.00	Propylene Glycol	30.00	77.0	86.8	72.6	60.8	52.4	50.1	66857	50516	84381	12.63	14.6	32.0	27.2	67.0	90.1	58256	41118	3.27	3.4	208/60/3	13.2	5.0	3
WSHP 005	WGTV0381	1575	150	ERV-2	14	14.00	Propylene Glycol	30.00	77.0	88.7	76.1	64.7	53.1	50.2	61167	37505	72425	18.6	19.7	32.0	26.6	55.0	84.2	47496	35687	4	3.9	208-	16.5	9.4	2
																												200/00/0		<u> </u>	
WSHP 006	WGTV0721	1710	1710	ERV-3	0.7	18.00	Propylene Glycol	30.00	77.0	86.6	77.9	64.2	51.3	49.8	68353	49421	82299	16.7	18.1	32.0	27.0	50.0	79.7	55222	42701	4.4	3.7	208-	17.6	9.4	2
																												200/00/0		<u> </u>	
WSHP 007	WGTH0491	1600	150	N/A	0.7	12.00	Propylene Glycol	30.00	77.0	86.7	72.6	60.9	52.5	50.5	45353	34808	55063	15.9	19.2	32.0	27.4	62.0	82.4	35506	26418	3.9	4	208-	14.0	7.3	2
																														 '	\bot
WSHP 008	WGTV0381	1090	1090	ERV-1	0.7	9.00	Propylene Glycol	30.00	77.0	89.0	78.0	66.6	54.8	52.6	43049	26473	51415	17.5	19.8	32.0	26.4	50.0	77.0	30779	23784	4.4	4	208-	14.2	7.3	2
																														1'	

NOTE: 1. PROVIDE NEXUS COIL PACK FOR EACH WATER SOURCE HEAT PUMP BASED ON THEIR RESPECTIVE FLOW RATE OF EACH UNIT.

												WATER	TO WATEF	R HEAT	PUMP CH	HILLEF	RS/BOI	LERS																	
		General Unit Data				Co	oling			Heati	ing			Cool	ing Source	•			Co	oling Load					Heating So	ource				н	leating Load	d			
Tag	Quantity	Bosch Model Number	<u>Unit Size</u>	Description	<u>Total</u> Capacity	<u>Input</u> Watts	ER	<u>Heat of</u> Rejection	<u>Total</u> <u>Capacity</u>	Unput Watts		<u>Heat of</u> Absorbtion	Fluid Flow	EWT	PCT Glycol	LWT		Fluid Flo		PCT Glycol			<u>Fluid</u> Flow	EWT	PCT Glycol		<u>Freeze</u> <u>Point</u>	WPD	<u>Fluid</u> Flow	EWT	PCT Glyco		WPD	Unit Uni MCA MF	<u>Unit</u> Voltage
					BtuH	w	BtuH/W	BtuH	BtuH	w v	w/w	BtuH	GPM	F	%	F	ft H2O	GPM	F	%	F	ft H2O	GPM	F	%	F		ft H2O	GPM	F	%	F '	ft H2O	1	v
CH-1 2 3	3	WW210-3USC-RXXXCA-XDGDEHM	210	WW - Water2Water High Efficiency	158613	11205	14.2	196846	151873	14383 1	14.2	102798	40	77	30	87.4	15.8	40	50	30	41.7	19.8	40	32	30	26.6	8	22	40	101	30	109	14.1	69.7 125	3 - 208- 230/60/3
CH-4	1	WW180-3USC-RXXXCA-XDGDEHM	180	WW - Water2Water High Efficiency	126892	8295	15.3	155195	120639	10703 1	15.3	84121	This WM dehumidifica	/HP is de ation dur	edicated to t ing shoulde w armer	the reh r seas than th	neat coils sons and he desig	in the 2 A the geothe n conditior	utopsy A ermal (so i show n	.HUs. Those (urce) loop is here:	coils a expec	re for ted to be	34	32	30	26.8	8	16.4	34	101	0	108.1	8.5	60.1 100	3 - 208- 230/60/3

NOTE: 1. PROVIDE NEXUS COIL PACK FOR EACH WATER TO WATER HEAT PUMP CHILLERS BASED ON THEIR RESPECTIVE FLOW OF EACH UNIT. NOTES:

1. IMPELLER DIAMETER INDICATED IS APPROXIMATE. FINAL IMPELLER DIAMETER TO BE DETERMINED BY PUMP MFTR. CONTRACTOR SHALL TRIM IMPELLER AFTER INITIAL FLOW BALANCING TO ACHIEVE OPTIMAL PUMP PERFORMANCE.

2. M.C. TO FURNISH. E.C. TO INSTALL AND WIRE VFD'S.

REVISION SCHEDULE	DESCRIPTION DATE ADDENDUM D 1/6/23		
SEAL DANIEL STEINBERG, P.E.	#		NY PROFESSIONAL ENGINEER NO. 076975-1
	ŋ	COST CONSULTANT	STUART-LYNN COMPANY
	0 Troy-Schenectady Roa Suite 103 Latham, NY, 12110 (518) 452-3470 www.hymanhayes.com	FF&E CONSULTANT	CLASSIC CONTRACT INTERIORS, LLC
		I.T./SECURITY CONSULTANT	ONVERGENT ECHNOLOGIES BESIGN GROUP, INC.
		CIVIL CONSULTANT	Fusco Engineering & Land Surveying PC
UCTURAL ENGINEER	HYMAN HAYES ASSOCIATES -	M/E/P CONSULTANT	FELLENZER III ENGINEERING LLP FE PROJECT #: 20-335
ARCHITECT/STR		FORENSIC CONSULTANT	crime lab design
GECO	Shifty	The American	IGE COUNTY, NEW YORK

10

													HITEC
						Uni	t Informa	tion					ARCI
									Filte	ers			
				Electrical		1	0	utdoor	Air	R	eturn A	ir	
r Tc	otal (%)		Voltage/Pha	ase/HZ	MCA	MOPD	Туре	Depth	Rating	Туре	Depth	Rating	
74.7	7	208	-230V / 3 Ph	ase / 60 HZ	11.9	15	Pleated	2"	MERV-13	Pleated	2"	MERV-8	
t	MCA (/	A)	Max Fuse										
	34.7	,	45										
	37.2	2	50										
	15.9		20										
	34.7	,	45										
	30.0		45										
	31.4		45										
	24.8	;	35										
	25.0)	35										
		1		1									SHEET TITLE
													11/18/2022
													DATE:

H801

GENERAL NOTES:

- 1. ALL CONDUITS ARE SHOWN DIAGRAMMATICALLY, EXACT RUNS SHALL BE DETERMINED IN FIELD EXCEPT WHERE SPECIFICALLY DIMENSIONED ON CONDUIT LAYOUTS. CONTRACTOR SHALL FOLLOW MINIMUM SPACING REQUIREMENTS TO REDUCE ELECTROMAGNETIC INTERFERENCE. COORDINATE CONDUIT ROUTING WITH ALL OTHER TRADES.
- 2. ALL EXPOSED CONDUIT SHALL BE RUN PARALLEL TO BUILDING WALLS AND BEAMS EXCEPT WHERE OTHERWISE SHOWN. CONTRACTOR SHALL INSTALL CONDUIT IN SUCH A MANNER TO AVOID ALL INTERFERENCES.
- 3. DEFLECTION/EXPANSION FITTINGS SHALL BE PROVIDED WHERE RIGID METAL CONDUIT CROSSES STRUCTURAL EXPANSION JOINTS.
- 4. EXPOSED CONDUIT SHALL BE SUPPORTED ON WALLS OR CEILINGS BY APPROVED HANGERS OF ANGLE OR CHANNEL CONSTRUCTION. CONDUITS SHALL BE SUPPORTED AT LEAST EVERY EIGHT (8) FEET.
- 5. ALL SPARE CONDUITS SHALL BE TERMINATED AS SHOWN ON CONDUIT LAYOUTS AND SHALL BE CAPPED 3" ABOVE FINISHED FLOOR.
- 6. NO CONDUIT SHALL BE SMALLER THAN $\frac{3}{4}$ " UNLESS NOTED OTHERWISE ON PLANS.
- 7. EXACT CONDUIT STUB-UP LOCATIONS ARE TO BE DETERMINED BY THE ELECTRICAL CONTRACTOR BASED ON CERTIFIED MANUFACTURER'S DRAWINGS OF THE RESPECTIVE EQUIPMENT. CONDUIT SHALL BE INSTALLED TO AGREE WITH EQUIPMENT FURNISHED.
- 8. ALL LIGHTING WIRING SHALL BE #12AWG. UNLESS OTHERWISE NOTED. THE NUMBER OF WIRES SHOWN ON THE DRAWINGS IS NOT NECESSARILY THE CORRECT NUMBER REQUIRED. THE CONTRACTOR SHALL INSTALL AS MANY AS ARE NECESSARY FOR PROVIDING A COMPLETE ELECTRICAL SYSTEM IN EACH CASE.
- 9. CONDUITS PASSING THROUGH BUILDING FLOORS OR WALLS BELOW GRADE ARE TO BE INSTALLED WITH WATERTIGHT THRU WALL CONDUIT SEAL FITTINGS.
- 10. EQUIPMENT FURNISHED BY OTHERS SHALL BE INSTALLED & ENERGIZED BY THE ELECTRICAL CONTRACTOR.
- 11. THE ELECTRICAL CONTRACTOR SHALL NOT ENDANGER THE STABILITY OF THE STRUCTURE OR ANY PART THEREOF BY CUTTING, DRILLING OR OTHERWISE, AND SHALL NOT IN ANY WAY CUT OR ALTER THE WORK OF ANY OTHER CONTRACTOR, EXCEPT WITH THE WRITTEN CONSENT OF AND UNDER THE DIRECTION OF THE ARCHITECT AND/OR GENERAL CONTRACTOR.
- 12. THE ELECTRICAL CONTRACTOR SHALL SECURE ALL APPROVALS AND CERTIFICATES AND PAY ALL FEES FOR ALL THE WORK INSTALLED. CERTIFICATES SHALL BE DELIVERED TO THE GENERAL CONTRACTOR BEFORE FINAL PAYMENT WILL BE MADE.
- 13. ALL WORK SHALL BE DONE IN ACCORDANCE WITH THE LATEST APPLICABLE VERSION OF THE NEC AS WELL AS ALL STATE AND LOCAL CODES.
- 14. THE DRAWINGS INDICATE AND THE SPECIFICATIONS DESCRIBE THE GENERAL ARRANGEMENTS AND LOCATION OF OUTLET BOXES, ETC. THE CONTRACTOR SHALL, WITHOUT EXTRA COST TO THE OWNER, MAKE ALL REASONABLE MODIFICATIONS IN THE WORK AS MAY BE REQUIRED TO PREVENT CONFLICT WITH EXISTING CONDITIONS, THE WORK OF OTHER TRADES AND FOR THE PROPER INSTALLATION OF THE WORK.
- 16. ARRANGE FOR SITE VISIT WITH THE BLDG. OWNER REPRESENTATIVE AND GENERAL CONTRACTOR.
- 17. CLAIMS FOR ADDITIONAL COMPENSATION ARISING DUE TO THE FAILURE OF THE CONTRACTOR TO FULLY UNDERSTAND THE SITE CONDITIONS SHALL NOT BE PAID FOR BY ANY OTHER PARTY.
- 18. LEAVE WIRE SUFFICIENTLY LONG TO PERMIT MAKING FINAL CONNECTIONS. CONDUIT OVER 10 FEET IN WHICH WIRING IS NOT INSTALLED-FURNISH PULL STRING.
- 19. DO NOT PULL THERMOPLASTIC WIRES AT TEMPERATURES LOWER THAN 32 DEG F (0 DEG C). PROVIDE CABLE SUPPORTS FOR WIRE IN RISER CONDUITS AS REQUIRED BY CODE.
- 20. LOCATIONS INDICATED FOR LOCAL WALL SWITCHES ARE SUBJECT TO MODIFICATIONS AT OR NEAR DOORS. INSTALL SWITCH ON SIDE OPPOSITE HINGE; VERIFY FINAL DOOR HINGE LOCATION IN FIELD PRIOR TO SWITCH OUTLET INSTALLATION.

ACC COC	OF FIRE ALARM EQUIPMENT	CHEDULE	END AND S	LEG
43. UPS	DESCRIPTION	CATALOG #	MANUFACTURER	SYMBOL
DRO LE SYMBOI	FIRE ALARM CONTROL PANEL WITH ON-BOARD DIGITAL ALARM COMMUNICATOR TRANSMITTER, UP TO 318 ADDRESSABLE DEVICES PER LOOP AND FOUR ON-BOARD NOTIFICATION APPLIANCE CIRCUITS. PROVIDE ALL APPURTENANCES FOR A COMPETE SYSTEM.	MS-9600UDLS(E)	FIRE-LITE	FACP
*	ADDRESSABLE MANUAL DUAL—ACTION PULL STATION WITH HEX LOCK. RED	BG-12		Р
₩	CARBON MONOXIDE DETECTOR WITH DUAL	C01224TR	SYSTEM SENSOR	0
\$ _D	INDICATE NORMAL STANDBY, ALARM, OR END-OF-LIFE. WHEN THE SENSOR SUPERVISION IS IN A TROUBLE CONDITION, THE DETECTOR SHALL SEND A TROUBLE			
Ø	SIGNAL TO THE PANEL.			
	ADDRESSABLE NON-RELAY PHOTOELECTRIC DUCT SMOKE DETECTOR. PROVIDE WITH APPROPRIATELY SIZED METAL SAMPLING TUBE AND ALL OTHER APPURTENANCES NECESSARY FOR A COMPLETE SYSTEM. DUCT SMOKE DETECTOR, SUPPLIED AND WIRED BY E.C. INSTALLED BY M.C. COORDINATE INSTALLATION WITH M.C.	D335PL	FIRE-LITE	©
	STROBE WITH SELECTABLE 15,30,75,95,110, 135, AND 185 cd OUTPUT. RED INDOOR USE ONLY.	SRL	SYSTEM SENSOR	\$
RC2D	HORN–STROBE WITH SELECTABLE 15,30,75, 95,110,135, AND 185 cd STROBE OUTPUT AND SELECTABLE 83–90 db HORN OUTPUT. RED. INDOOR USE ONLY.	P2RL		KH∕S
ТС-#	REMOTE ANNUNCIATOR WITH 80-CHARACTER BACKLIT LCD DISPLAY.	ANN-80	FIRE-LITE	RA
TC-1, TC-				NOTES:

NOTES:

1. PROVIDE APPURTENANCES NECESSARY SUCH THAT IF MORE THEN TWO STROBES ARE VISIBLE THEY SHALL FLASH IN SYNCH.

2. STROBES MUST BE PLACED 15' FROM THE END OF ANY CORRIDOR.

LEGEND	& SCHED	ULE OF	GENERATOR EQUIPMENT		Р	FIRE ALA
SYMBOL	MANUFACTURER	MODEL#	DESCRIPTION	1	S S	SMOKE D
€ G−1	GENERAC	SG500	500KW 208/120V DIESEL GENERATOR. PROVIDE NEMA 2 SOUND ATTENUATED ENCLOSURE. PROVIDE WITH 1600A MAIN LINE CIRCUIT BREAKER AND 60A, SECONDARY MAIN LINE CIRCUIT BREAKER		2 2 2 2	FLOW SW
ATS-1	ASCO	H-03ATS- A-3-1600- C-G0-C	1600A, 120/208V, 3ø, 4W SERVICE ENTRANCE RATED AUTOMATIC TRANSFER SWITCH		(H/S) or (H/S) (H)	FIRE ALA HEAT DE
ATS-2	ASCO	D-03ATS- A-3-0070- C-G0-C	60A, 120/208V, 3ø, 4W AUTOMATIC TRANSFER SWITCH		©	DUCT SM TUBE WI CARBON

- 21. SUPPORT PANEL, JUNCTION & PULL BEARING ON CONDUIT.
- 22. ALL ACCESS DOOR LOCATIONS SHAL
- 23. FOR EACH LOCATION OF OTHER TRA
- 24. FOR RECEPTACLE & OUTLETS MOUN WITH ARCHITECT, OWNER, REPRESEN
- 25. CONTRACTOR SHALL PROVIDE AND SPECIFICATIONS AND ALL PERTINENT
- 26. ALL CONDUITS, TRANSFORMERS ETC. COORDINATE WITH GENERAL CONTRA
- 27. ALL FLOOR MOUNTED ELECTRICAL E BE INSTALLED ON 4" CONCRETE PA COORDINATE WITH GENERAL CONTRA
- 28. PROVIDE BARRIERS IN ALL PULL BO
- 29. PAINT AND RUST PROOF ALL HARDW BY GENERAL CONTRACTOR.
- 30. NUMBER SHOWN ADJACENT TO LIGHT INDICATES CIRCUIT NUMBER.
- 31. ALL GROUND CONNECTIONS TO THE
- 32. FLEXIBLE CONNECTIONS IN EXPOSED
- 33. ALL EQUIPMENT DEVICES, WIRING, I
- 34. ELECTRICAL CONTRACTOR SHALL PRO WALLS, ROOF & FLOOR SLABS. ALL WATERPROOF. METHOD OF PENETRA ARCHITECT AND STRUCTURAL ENGINE
- 35. ELECTRICAL CONTRACTOR SHALL BEC FOR CONSTRUCTION.
- 36. ALL FINAL CONNECTIONS TO VIBRAT LIQUID TIGHT FLEXIBLE METAL COND
- 37. CONTRACTOR SHALL WIRE NO MORE CIRCUIT. UTILIZE 2-#12&1 #12 GN EACH CIRCUIT. INSTALL ADDITIONAL
- 38. ALL PENETRATIONS THROUGH FIRE AN APPROPRIATE U.L. LISTED FIRES
- 39. THE TERMS "PROVIDE" OR "FURNISH IS TO FURNISH AND INSTALL THE REQUIRED FOR A COMPLETE AND O
- 40. CONTRACT CLOSE OUT: IN THE PRE OPERATION OF SYSTEMS AND THAT ALL PARTIES.
- 41. IT IS THE INTENT AND PURPOSE OF FOR ALL MATERIALS, APPLIANCES WORKING CONDITION THE ENTIRE SY APPLIANCE NOT SPECIFICALLY MENT BUT NECESSARY FOR A COMPLETE
- 42. JUNCTION & PULL BOXES: DO NOT WHERE NECESSARY, REROUTE COND PULL BOXES AS INDICATED AND WH COORDINATE LOCATIONS WITH OTHER ACCESSIBLE. FOR EMPTY CONDUITS, COORDINATE LOCATIONS WITH OTHER
- 43. UPSIZE WIRE WHERE NECESSARY PE DROP.

21. SUPPO	DRT PANEL, JUNCTION	I & PULL BOXE	S INDEPENDENTLY TO BUILDING STRUCTURE WITH NO WEIG	нт	PO	VER SYMBOLS	
22. ALL A	CCESS DOOR LOCATION	ONS SHALL BE	REVIEWED BY ARCHITECT PRIOR TO INSTALLATION.	₽	SPEC GRADE NE	IA 5–20R RECEPTACLE. GROUND FAULT INTERRUPTION	
23. FOR E 24. FOR F	ACH LOCATION OF O	THER TRADES E	QUIPMENT, SEE RESPECTIVE TRADE DRAWINGS. IEIGHTS AND POSITION (HORIZONTAL, VERTICAL), COORDINAT		-WP INDICATES N SPEC GRADE NE	VEATHER PROOF ENCLOSURE /A 5–20R RECEPTACLE. MOUNT AT	44" AFF OR
WITH . 25. CONTR	ARCHITECT, OWNER, F RACTOR SHALL PROVI	REPRESENTATIVE DE AND INSTALL	& DATA/ COMMUNICATION CONSULTANT. ALL COMPONENTS INDICATED ON DETAILS SHEETS, PLANS,	, *	6" ABOVE COUNT -GFI INDICATES (-WP INDICATES \	ER, UNO. GROUND FAULT INTERRUPTION VEATHER PROOF ENCLOSURE	
SPECII 26. ALL C	FICATIONS AND ALL F ONDUITS, TRANSFORM	PERTINENT EQUIF	PMENT REQUIRED FOR A COMPLETE WORKABLE SYSTEM. L BE SUPPORTED FROM STRUCTURAL STEEL ONLY.	φ-	2P, 3 WIRE, 250 -GFI INDICATES	V GROUNDING NEMA 6-30R RECEP GROUND FAULT INTERRUPTION	PTACLE.
27. ALL F BE IN COORI	LOOR MOUNTED ELEC STALLED ON 4" CONO DINATE WITH GENERAL	TRICAL EQUIPME CRETE PAD AS I CONTRACTOR.	ENT IN ELECTRICAL AND SERVICE SWITCHBOARD ROOM SHAI REQUIRED TO SUPPORT EACH SECTION OF EQUIPMENT.	╙ ♣	1P, 3 WIRE, 125 -GFI INDICATES (-WP INDICATES)	V QUAD RECEPTACLE. GROUND FAULT INTERRUPTION VEATHER PROOF ENCLOSURE	
28. PROVI	DE BARRIERS IN ALL	PULL BOXES F	OR CONDUIT SETS.	۲	SPECIAL PURPOS	E CONNECTION.	
29. PAINT BY GE	AND RUST PROOF A INERAL CONTRACTOR.	LL HARDWARE &	CONDUITS ON ROOF AND IN EXPOSED AREAS AS DIRECT	EDJ	JUNCTION BOX, S	SIZE PER N.E.C.	
30. NUMBI INDICA 31. ALL G	ER SHOWN ADJACENT TES CIRCUIT NUMBER ROUND CONNECTIONS	TO LIGHTING F R. 5 TO THE BUILD	IXTURES, RECEPTACLES, OUTLETS, JUNCTION BOXES ETC.	C C	3P, FUSED DISCO BY ELECTRICAL C POLES & AMPER	ONNECT SWITCH, FURNISHED AND IN ONTRACTOR. SHALL HAVE THE SA E RATING AS CONNECTING CIRCUIT	NSTALLED ME # OF UNLESS
32. FLEXIE	BLE CONNECTIONS IN	EXPOSED AREA	S SHALL NOT EXCEED 18" MAXIMUM.		OTHERWISE NOTE	D.	
33. ALL E	QUIPMENT DEVICES,	WIRING, ETC. SH	OWN ON THE DRAWINGS IS NEW UNLESS OTHERWISE NOTE	D.	SCHEDULE FOR (CONDUIT & CABLE QUANTITY AND S	IZE.
WALLS WATER ARCHI	RICAL CONTRACTOR S , ROOF & FLOOR SL RPROOF. METHOD OF TECT AND STRUCTUR/	ABS. ALL ROOF PENETRATIONS AL ENGINEER, C	SLEEVES/ OPENINGS FOR ALL CONDUIT RISERS PENETRATION AND MECH. ROOMS SLAB PENETRATIONS SHALL BE & FIRE/WATER WATER PROOFING SHALL BE APPROVED BY OORDINATE WITH GENERAL CONTRACTOR.		DOUBLE HOME R	UN N	
35. ELECT FOR (RICAL CONTRACTOR S	HALL BECOME	FAMILIAR AND COMPLY WITH OWNERS BUILDING STANDARDS	=	GROUND		
36. ALL F LIQUID	INAL CONNECTIONS T	O VIBRATING EQ TAL CONDUIT.	UIPMENT (MOTORS, GENERATORS ETC.) SHALL BE THROUGH		TRANSFORMER		
37. CONTR CIRCU EACH	RACTOR SHALL WIRE IT. UTILIZE 2-#12&1 CIRCUIT. INSTALL A	NO MORE THAN #12 GND IN ∛ DDITIONAL CIRCU	EIGHT CONVENIENCE RECEPTACLES TO A 20A SINGLE POLI 4" CONDUIT & 1–20A SINGLE POLE CIRCUIT BREAKER FOR IIT AS NECESSARY TO MEET THIS REQUIREMENT.	E \$m	120V, OR 208V, AS DISCONNECTIN	1P, MOTOR STARTER WITH OVERLO IG MEANS. COORDINATE WITH OTHE	ADS TO SERVE R TRADES.
38. ALL P AN AF	ENETRATIONS THROU PROPRIATE U.L. LIST	GH FIRE RATED ED FIRESTOPPIN	PARTITIONS SHALL BE SEALED FIRE AND SMOKE TIGHT WI IG MATERIAL AND OR SYSTEM.		CIRCUIT BREAKER	- 100A TRIP - SINGLE POLE	
39. THE T IS TO REQUI	ERMS "PROVIDE" OR FURNISH AND INSTA RED FOR A COMPLET	"FURNISH", AS LL THE REFEREI E AND OPERAB	USED ON THESE PLANS, INDICATE THAT THE CONTRACTOR NCED EQUIPMENT OR SYSTEMS IN THEIR ENTIRETY AS LE SYSTEM.	100A-3P	FUSE SWITCH -	100A FUSE – 3 POLE	
40. CONTR OPERA	RACT CLOSE OUT: IN ATION OF SYSTEMS A ARTIFS	THE PRESENCE ND THAT ALL S	OF THE OWNER, ENGINEER OR ARCHITECT; DEMONSTRATIN SPECIFICATIONS HAVE BEEN MET TO THE SATISFACTION OF	NG M	MUTUR ELECTRIC METER		
41. IT IS FOR A WORKI APPLI BUT N	THE INTENT AND PUP ALL MATERIALS, APPL NG CONDITION THE E ANCE NOT SPECIFICA IECESSARY FOR A CO	RPOSE OF THES IANCES AND LA INTIRE SYSTEM LLY MENTIONED DMPLETE INSTAL	E SPECIFICATIONS AND DRAWINGS TO INCLUDE AND PROVIE BOR TO PROPERLY COMPLETE AND LEAVE IN PERFECT HEREINAFTER SPECIFIED. ANY MATERIAL, LABOR OR IN THESE SPECIFICATIONS OR SHOWN ON THE DRAWINGS, LATION MUST BE FURNISHED BY THIS CONTRACTOR.	DE DO	AUTOMATIC DOOR HEIGHT. PROVIDE MANUFACTURER'S	OPENER PUSH BUTTON. MOUNTED WIRING TO DOOR OPERATOR PER WRITTEN INSTRUCTIONS.	AT ADA
42. JUNCI WHERI	TION & PULL BOXES: E NECESSARY, REROU	DO NOT LOCAT JTE CONDUIT OF	E EXPOSED IN FINISH SPACES UNLESS REQUIRED BY NEC. MAKE OTHER ARRANGEMENTS FOR CONCEALMENT. PROVID)E			
PULL COORI ACCES	BOXES AS INDICATED DINATE LOCATIONS WI SSIBLE, FOR EMPTY (AND WHEREVE TH OTHER TRAD ONDUITS, INSTA	R NECESSARY TO FACILITATE PULLING OF WIRE AND ES. COVERS OF JUNCTION AND PULL BOXES SHALL BE LL PULL BOXES EVERY 100 FEET AND AS INDICATED.		GENERA		
	DINATE LOCATIONS WI	TH OTHER TRAD	ES.	•	POINT OF CON EXISTING WORK	NECTION BETWEEN NEW AND	
DROP.	WHERE NECE		LEESTING & CODE TO COMILENDATE FOR VOLIAGE	X		TION LETTER	
LEG	END AND	SCHEDL	ILE OF LIGHTING EQUIPMENT		INDICATES DRA	WING NUMBER WHERE LOCATED	
SYMBOL		MODEL #					
\$			COLOR BY ARCHITECT.	_ Е	LECTRICA	L LINE TYPES	
*		DSW-301	LINE VOLTAGE PUSH-BUTTON WALL SWITCH WITH INTEGRAL DUAL-TECHNOLOGY VACANCY SENSOR. COLOR BY ARCHITECT.				
•			LOW VOLTAGE WALL MOUNTED DIMMING SWITCH.		NEW	WIRING	
ΨD			ARCHITECT.		NEW		
Ø		LMDC-100	DLM DUAL-TECHNOLOGY CEILING SENSOR, SET TO MANUAL-ON OPERATION.			ERGROUND FOWER	
Ø		LMLS-500	DAYLIGHT HARVESTING SENSOR, OPEN LOOP WITH ADJUSTABLE DIMMING, MULTIZONE PHOTOSENSOR AND OFF SETPOINTS. LIGHTING LOAD TO BE TURNED OFF AT 100% ABOVE SETPOINT.	WIF	RE & COND		
RC1		LMRC-101	DLM ON/OFF SINGLE RELAY ROOM CONTROLLER. MOUNT ABOVE FINISHED CEILING ABOVE LOCAL LIGH SWITCH. FOR ROOMS WITHOUT FINISHED CEILING,	HT TAG	FEEDER SIZE	WIRE AND CONDUIT	
			MOUNT INCONSPICUOUSLY AT/NEAR CEILING.		PRIMARY C COMPANY	ONDUCTORS PER UTILITY STANDARDS IN 5" CONDUIT	
KC2D		LMRC-212	CONTROLLER. MOUNT ABOVE FINISHED CEILING ABOVE LIGHT SWITCH. FOR ROOMS WITHOUT FINISHED CEILING, MOUNT INCONSPICUOUSLY	A	1600A	4 SETS OF: (4) #600 MCM CU, (1) 3/0 GND. (1) 3 1/2" CONDUIT	
TC-#	TORK	EWZ-201	INDOOR/OUTDOOR ASTRONOMIC TIMECLOCK WITH 2 SETS OF 40A SINGLE POLE SINGLE THROW	B	600A	2 SETS OF: (4) #350 MCM (1) #1 GND. (1) 2½" CONDUIT	
u-1, TC-2	l	I	CONTACTS. NEMA 3R RATED.		400A	(4) #500 KCMIL CU, (1) #3 GND. (1) 4" CONDUIT	
]		FIRE A		Ø	200A	(4) 3/0 CU, (1) #6 GND, (1) 2" CONDUIT	
	р S	FIRE ALARM P SMOKE DETEC	ULL STATION TOR. A=AUXILIARY CONTACTS.	Ē	60A	(4) #6, (1) #10 GND, (1) 1" CONDUIT	
A 2	(2) []]	STROBE ONLY	ADA COMPLIANT			(4) 4" CONDUIT WITH PULL	
DA MAIN		TAMPER SWITCH	н			STRING FOR COMMUNICATIONS	
D	(H/S) or (H/S)	FIRE ALARM H	ORN W/STROBE ADA COMPLIANT	69		(6) #14AWG CU, (1) 3/4" CONDUIT	
	E E E E E E E E E E E E E E E E E E E	HEAT DETECTO DUCT SMOKE TUBE WITH וח	R DETECTOR. COORDINATE SIZE OF SAMPLING ICTWORK, PROVIDE RELAYS AS REQUIRED	R)		REFER TO GENERAL MANUFACTURER'S WRITTEN INSTRUCTIONS.	
	0	CARBON MONC	DXIDE DETECTOR	* INDICATE	S SERVICE ENTRANO	E CONDUCTORS, GROUNDING	•
				CONDUC	TOR CAN BE OMITTE	ID.	

AMPERE ACOUSTIC CEIL AUTOMATIC DA AMPERE FRAM ABOVE FINISHE AMPERE INTER ALUMINUM AUTOMATIC TRA AUTOMATIC AMERICAN WIRE BARE COPPER CONDUIT CATALOG CIRCUIT BREAK CIRCUIT CEILING CURRENT TRAI COPPER DISTRIBUTION DRINKING FOU DIVISION DISCONNECT DRAWING EACH ELECTRICAL CO ELEVATOR QUIP. EQUIPMENT ELECTRICAL M FIRE ALARM FIRE ALARM C FLOOR FEET OR FOOT GROUND GND GENERAL CON GENERATOR GROUND FAUL GALVANIZED F HORSEPOWER HEATING, VEN HERTZ INTERRUPTING INTERMEDIATE KILO VOLT

ALARM NOTES:

REFER TO THE FLOOR PLA

- LL FIRE ALARM WIRING S VALLS.
- SYSTEM SCHEMATIC IS A E INSTALLED AND WIRED PERABLE SYSTEM.
- CONTRACTOR IS RESPONSI HAVING JURISDICTION.
- CONTRACTOR TO PROVIDE REQUIRED TO PROVIDE AN
- FIRE ALARM PANEL SHALL SHORTS AND GROUNDS.
- ACTIVATION OF THE SMOKE PERFORMS VERIFICATION.
- ACTIVATION OF ANY PULL ENTER THE ALARM MODE.
- JPON ENTERING THE PANE SUPPLY FANS SHALL SHU STATION. (LOCAL FIRE CO
- CONTRACTOR SHALL PROV PROPER OPERATION OF TH
- BATTERY BACKUP SHALL END OF 24 HRS.
- NEW FIRE ALARM SYSTEM -CNYS, LSC101 (2000)—CH CODE REQUIREMENTS.
- CONTRACTOR SHALL PROV OPERABLE SYSTEM. MODE COMPLETE INSTALLATION.
- PROVIDE APPURTENANCES FLASH IN SYNCH.
- PROVIDE FLOW SWITCH AND
- ENTIRE FIRE DETECTION AN LICENSED ALARM CONTRAC
- FIRE ALARM PANEL SHALL OCAL FIRE CONTROL CEN
- FIRE ALARM CONTRACTOR NEAREST THE FIRE ALARM COORDINATE ALL REQUIREN
- FIRE ALARM CONTRACTOR PRIMARY POWER AND BAT
- ALL AIR HANDLING SYSTEM FAN SHUTDOWNS CONNEC

RGY CODE STATEMEN

KNOWLEDGE, BELIEF AND PROFESSIONAL JUDGMENT, THESE PLANS AND/OR SPECIFICATIONS ARE IN COMPLIANCE WITH THE 2020 ENERGY CODE.

ABBREVIA	ATIONS		JLE 1/6/23
AMPERE			
ACOUSTIC CEILING TILE	LP	LIGHTING PANEL	SCH
	LTG		
ABOVE FINISHED FLOOR	MCM	THOUSAND CIRCULAR MILS	
AMPERE INTERRUPTING CAPACITY	MCB MECH	MAIN CIRCUIT BREAKER MECHANICAI	
AUTOMATIC TRANSFER SWITCH	MDP	MAIN DISTRIBUTION PANEL	
AUTOMATIC AMERICAN WIRE GAUGE	MLO MTD	MAIN LUGS ONLY MOUNTED	
BARE COPPER WIRE	MTG	MOUNTING	Ь. Б.
CONDUIT CATALOG	N NIC	NEUTRAL NOT IN CONTRACT	ERG,
CIRCUIT BREAKER	NEC	NATIONAL ELECTRIC CODE	EINBI S. SIF
CEILING	NM	NOT TO SCALE NON-METALLIC CONDUIT	L ST
CURRENT TRANSFORMER	P PR	POLE PULL BOX	JANIE JANIE
DISTRIBUTION PANEL	Ø	PHASE	SEAL
DRINKING FOUNTAIN DIVISION	PWR RECEPT	POWER RECEPTACLE	
DISCONNECT (LOCKOUT) SWITCH	REQ.	REQUIRED	
DRAWING EACH	RM SCHED.	ROOM SCHEDULE	
ELECTRICAL CONTRACTOR	SECT.	SECTION	Dad d
EQUIPMENT	SPEC. SPKR.	SPECIFICATION	tady Rc 3 12110 470
ELECTRICAL METALLIC TUBING	SW	SWITCH	Schenec Suite 10 m, NY, manha
FIRE ALARM FIRE ALARM CONTROL PANEL	SYS	SYSTEM) Troy-S E Lathau (518
FLOOR	TBD TEI		
GROUND	TC	TIME CLOCK	
GENERAL CONTRACTOR	ΤΥΡ ΠΝΟ	TYPICAL	
GROUND FAULT INTERRUPTER	UPS	UN-INTERRUPTABLE POWER SUPPLY	
GALVANIZED RIGID STEEL CONDUIT HORSEPOWER	VIF WP	VERIFY IN FIELD WEATHER PROOF	
HEATING, VENTILATING & AIR CONDITIONING	W	WATT	
HERIZ INTERRUPTING CAPACITY	XFMR/ TRANSF.	TRANSFORMER	
INTERMEDIATE METAL CONDUIT			
KILO VOLT AMP			
KILO WATT			
NOTES			AN FES
THE FLOOR PLANS FOR LOCATION & OLIANTITY	OF FIRE ALAR	MDEVICES	HAY MAY MAY
ADM WIDING CHARLE DE IN TEELON WIDE AND C			
LARM WIRING SHALL BE IN TEFLON WIRE AND S	HALL BE CON	CEALED IN CEILING SPACES &	/STRI
HEMATIC IS A DIAGRAMMATIC REPRESENTATION ED AND WIRED AS PER THE SYSTEM MANUFACT	OF THE FIRE 'URER'S REC(ALARM SYSTEM. THE SYSTEM SHALL OMMENDATION FOR A COMPLETE AND	RCHITEC
STSTEM.			
R IS RESPONSIBLE FOR ALL FILING AND FINAL RISDICTION.	INSPECTION A	S PER THE LOCAL AUTHORITY	
R TO PROVIDE AND INSTALL ALL NECESSARY M	ODULES, INTE	RFACE MODULES AND DEVICES	
O PROVIDE AN OPERABLE ALARM SYSTEM IN C	OMPLIANCE WI	ITH ALL CODES.	1 AL
I PANEL SHALL PROVIDE CONTINUOUSLY SUPER	VISED MONITOR	RING OF ALL SYSTEMS FOR OPENS,	
OF THE SMOKE DETECTORS SHALL CAUSE A C		M AFTER THE SMOKE DETECTOR	
VERIFICATION.	ENERAL ALAR	M AFTER THE SMOKE DETECTOR	(Carlor)
OF ANY PULL STATION OR HEAT DETECTOR SHALARM MODE.	IALL IMMEDIAT	ELY CAUSE THE ALARM PANEL TO	ORA
RING THE PANEL ALARM MODE, THE ALARM IND NS SHALL SHUT-DOWN AND THE DIGITAL COMM	ICATING DEVIO	CE SHALL BE ACTIVATED, AND THE ALL NOTIFY THE CENTRAL RECEIVING	
COME THE CONTROL CENTER).			
ERATION OF THE FAN SHUT-DOWN UNITS AND	OTHER RELAT	ES OR POWER TRANSFORMERS FOR ED DEVICES.	
ACKUP SHALL PROVIDE A MINIMUM OF 24 HRS. HRS.	OPERATION W	VITH A 15 MINUTE ALARM AT THE	ES
LARM SYSTEM SHALL BE TESTED IN ACCORDAN 101 (2000)—CH.32 NEW BOARD AND CARE OC	CE WITH NFPA CUPANCY AS	A CODES 70, 70E, 72, BCNYS, WELL AS ALL LOCAL AND STATE	
IREMENTS. R SHALL PROVIDE ALL ADDITIONAL APPURTENAI	NCES AS REQ	UIRED FOR A COMPLETE AND	S L S
SYSTEM. MODEL NUMBERS GIVEN MAY NOT INCL NSTALLATION.	UDE ALL SPE	CIFIC REQUIRED ACCESSORIES FOR	ABO ION(
PURTENANCES NECESSARY SUCH THAT IF MORE YNCH.	THEN TWO S	TROBES ARE VISIBLE THEY SHALL	SYN IATI
OW SWITCH AND TAMPER SWITCH AT SPRINKLER	RISER.		
DETECTION AND ALARM SYSTEM SHALL BE FUF LARM CONTRACTOR.	RNISHED AND	INSTALLED BY A N.Y. STATE	BRI
PANEL SHALL BE PROVIDED WITH A REMOTE D CONTROL CENTER.	IALER WITH (2	2) DIRECT CONNECTIONS TO THE	o ABI
CONTRACTOR SHALL PROVIDE AND INSTALL A F IE FIRE ALARM PANEL WITH SIGNAGE ON THE D	(NOX BOX AT OOR TO THE	THE ENTRANCE TO THE BUILDING FIRE ALARM CONTROL PANEL ROOM.	
CONTRACTOR SHALL INTERCONNECT CO DETECT	ORS WITH THI	E NEW FIRE ALARM SYSTEM FOR	022 NWC
NULL AND DATIENT BAUKUP. UU ALAKM SHALL		NUDED WITH DUAT SHOKE DETERTORS	11/18/2 AS SHC
OWNS CONNECTED TO THE FIRE ALARM SYSTEM.	DALL BE PRO	WIT DUCT SMUKE DETECTORS	
			и на
			DATE SCAL DRAM
			SHEET NUMBER
<u>= STATEMENT:</u>	UNIFOR	VI CODE STATEMENT:	



BEST OF THE REGISTERED DESIGN PROFESSIONAL'S

TO THE BEST OF THE REGISTERED DESIGN PROFESSIONAL'S KNOWLEDGE, BELIEF AND PROFESSIONAL JUDGMENT, THESE PLANS AND/OR SPECIFICATIONS ARE IN COMPLIANCE WITH THE 2020 UNIFORM CODE.









					CONDUCTORS			CONDUCTORS			CONDUCTORS		7
	CONDO				CONDUCTORS	LUAD	XRAY GENERATOR	(4)#8, (1)#10 GND, 1"C	<u>し.</u> 50 上个 前	<u>(C.D.</u>)의		SPACE	-
PP-1-1	(4)#500 KCMIL C IN 4" CO	U, (1)#3 GND NDUIT	^{9,} 400	400	(4)#500 KCMIL CU, (1)#3 (IN 4" CONDUIT	GND, PP-CT							
							CUUNT	• • •					-
PP-1-2	2 SETS (4)350 MC	M, (1)#1 GND,	600	60	(4)#6, (1)#10 GND, 1"0	C LP-EM	SHUNI			 \10			
	2 1/2 00									12			
COLD ROOM	(4)#6 (1)#10	GND 1"C	60	400	(4)#500 KCMIL CU, (1)#3	GND,				<u>14</u> 16			-
CONTROL PANEL	$(+)_{\pi}^{+}, (+)_{\pi}^{+}, (+)_{\pi}^{+}$	GND, TC		400	IN 4" CONDUIT					18			
									NOTES:	• •			-
SPACE		-				SPACE	POWERPA	ANEL - PP-CI	1. ALL WIRE	SHALL E	BE DUAL RATED 4. PROVID	E 50 AMP 3 POLE ODYNAMIC CIRCUIT BREAKER	BAR JO
							TYPE: RATING:	EATON PRL-2a 200A, 277/480V, 3ø, 4W	UNLESS C	THERWIS	SE NOTED. WITH S	HUNT TRIP DEVICE.	HANGE
							MAINS:	MLO 14 KAIC	2. ALL CIRCU SIZE INSU	JITS SHA ILATED G	ALL HAVE FULL 5. LOCATE GREEN GROUND A.F.F.	: TOP OF ENCLOSURE 6'—0' EC SHALL ENSURE THAT	"
	<u>↓</u>						ENCLOSUR	E: NEMA1, RECESSED	UNLESS C	THERWIS	SE NOTED. LUGS A	ARE LARGE ENOUGH TO ATE OVERSIZED INCOMING	
RATING: 1600	N POW-R-LINE C)A, 120/208V, 3ø, 4	W,			1. ALL WIRE SHALL BE DU	AL RATED THHN/THWN	FOLES.	10	E-801 FC	DR MORE	E INFO. CABLES	S REQUIRED BY X-RAY IENT.	
MAINS: MLO BRACING: 42 K	AIC				COPPER CONDUCTOR UN	ILESS OTHERWISE NOTED.		CONDUCTORS	C.B.	C.B.]
ENCLOSURE: NEMA AVAILABLE	1, SURFACE		סופדסום				CH-1	(4)#3, (1)#8 GND, 1 1/4"C	90 7 <u>3</u> 1 1	174 90	(4)#3, (1)#8 GND, 1 1/4"C	CH-3	
SPACE: 38X										<u>76</u> 78			-
LOAD	COND	UCTORS	C.B.	C.B.	CONDUCTORS	LOAD	CH-2	(4)#3, (1)#8 GND, 1 1/4"C		1 <u>80</u> 80	(4)#4, (1)#8 GND, 1 1/4"C	CH-4	
ELECTRICAL ROOM RI	ECEPT (2)#12, (1)#	12 GND, 3/4"	"C 20 1		(2)#12, (1)#12 GND, 3/4"C	GEAR ROOM RECEPT				82			- -
MOTHER'S RM/RECORD STOR.	RECEPT		5			CONFERENCE ROOM RECEPT	▲HU_1	(4)#10 (1)#10 GND 3/4"C		<u>86</u> 25	(4)#10 (1)#10 GND 3/4"C	▲HU−2	-
ADMIN RECEPT						ROOM 122/123 RECEPT				<u>88</u>			-
ROOM 124/125 RE	CEPT		9			ROOM 126 RECEPT	•			90			-
OFFICE 128 RECE	CEPT					CONTRACT DOC. RECEPT	ERF-1	(4)#10, (1)#10 GND, 3/4 C		<u>)94</u> 25	(4)#10, (1)#10 GND, 3/4°C	ERF-2	-
EVIDENCE STOR. RE	CEPT		15			SPECIAL AUTOPSY RECEPT				\ <u>96</u>	•		
SPECIAL AUTOPSY RE	ECEPT					AUTOPSY CLG RECEPT	BONE KETTLE	(4)#3, (1)#8 GND, 1 1/4"C	90 97 99	100 100		SPARE	HANGE
AUTOPSY RECEP						AUTOPSY RECEPT DRINKING FOUNTAIN RECEPT				102 20	(2)#12, (1)#12 GND. 3/4"C	COPIER RECEPT	
SECURITY RECEP	PT		23			AUTOPSY ASSIST RECEPT	EVIDENCE REFRIG. RECEPT	(2)#12, (1)#12 GND, 3/4"C	20 103	<u>104</u>		TISSUE REFRIG. RECEPT	
CONTROL ROOM REG	CEPT					SALLY PORT RECEPT	BATHROOM RECEPT			106		BATHROOM RECEPT	
ROOF RECEPT			29			SPARE	AUTOPSY CLG RECEPT			1 <u>10</u> 15	(2)#12, (1)#12 GND, 3/4"C	EF-1	$(1)_{N}$
ROOF RECEPT			31			V	EF-2	(2)#12, (1)#12 GND, 3/4"C	15 111 +	112		EF-3	
ROOF RECEPT	(2) # 12 (1) #	12 CND 3/4"	33		(2)#12, (1)#12 GND, 3/4"C	ROOM 131 RECEPT	EV CHARGER	(3)#8, (1)#10 GND, 1"C	$40 \qquad 113 \qquad 116 \qquad 115 \qquad 116 \qquad 117 \qquad$	<u>114</u> 40	(3)#8, (1)#10 GND, 1"C	EV CHARGER	-
MENS/WOMENS L/S/T R	ECEPT $(2)#12, (1)#$	12 GND, $3/4$ 12 GND, $3/4$ "	°C 20 °C 37	→ → → → → → → → → → → → → →	(4)#4, (1)#8 GND, 1 1/4"C	WH-1	EV CHARGER	(3)#8, (1)#10 GND, 1"C		1 <u>118</u> 15	(2)#12, (1)#12 GND, 3/4"C	FORKLIFT CHARGER	-
CT/XRAY ROOM REC	CEPT						•			120		DISPOSAL	-
MUD ROOM RECE	PT FCFPT				(2)#12 (1)#12 GND 3/4"C		GEN. ACCESSORY	(3)#6, (1)#10 GND, 1"C		124 15	(2)#8, (1)#10 GND, 3/4"C (3)#12 (1)#12 GND 3/4"C	SCISSOR LIFT	
STORAGE RECEP	T		45		(3)#10, (1) #10 GND, $3/4$ °C	DRYER RECEPT	ERV-1	(3)#8, (1)#8 GND, 3/4"C	35 125	126			-
TISSUE STORAGE RE													-
WSHP-1	(4)#8, (1)#1	0 GND, 3/4"(C 45 - 7		(4)#12, (1)#12 GND, 3/4°C	WSHP-3	SPARF	I I		<u>132</u> 20	 (3)#12, (1)#12_GND, 3/4"C	SPARE XRAY STANDBY POWFR	-
		V	53				ERC-1	(3)#8, (1)#10 GND, 3/4"C	30 133	134			_
WSHP-2	(4)#8, (1)#1	0 GND, 3/4"	$\begin{array}{c c} C & 50 \\ \hline 57 \\ \hline 57 \\ \hline 57 \\ \hline \end{array}$	◆ 58 45 58	(4)#8, (1)#10 GND, 3/4"C	WSHP-4				1 <u>36</u> 30	(3)#8, (1)#10 GND, 3/4"C	ERV-3	_
		•					ERC-2	$(3)_{\#12}, (1)_{\#12}$		1 <u>40</u>			-
WSHP-5	(4)#8, (1)#1	0 GND, 3/4"	C 45 $\frac{61}{10}$		(4)#8, (1)#10 GND, 3/4"C	WSHP-7	P-5	(4)#12, (1)#12 GND, 3/4"C		142 15	(4)#12, (1)#12 GND, 3/4"C	P-6	-
										146			-
WSHP-6	(4)#8, (1)#1	0 GND, 3/4"(<u> て 45 ⁶⁷ 介 </u>		(4)#8, (1)#10 GND, 3/4"C	WSHP-8	P-A	(4)#1, (1)#8 GND, 1 1/4"C	125 147	1 <u>48</u> 125	(4)#1, (1)#8 GND, 1 1/4"C	Р-В	-
										1 <u>50</u>			ABOVE COUNTER
	R (2)#12 (1)#	<u>↓</u> 12 GND 3/4"	20 $\overline{73}$	$ \begin{array}{c c} & & & \\ \hline \\ \hline$	(2)#12 (1)#12 GND 3/4"C			(3)#12 (1)#12 GND 3/4"C		1 <u>154</u> 20	<u> </u>		RECEPTACLE
										1 <u>156</u>	•		_
OVERHEAD DOOF	R (2)#12, (1)#	12 GND, 3/4"	"C 20 77 1	⁷⁸ 20	(2)#12, (1)#12 GND, 3/4"C	OVERHEAD DOOR		POW	ER PANE	EL - P	P-1-2 <u>NOTES:</u>		
SPARE		<u> </u>		<u>82</u> 20	(2)#12, (1)#12 GND, 3/4"C	BIOSAFETY CABINET					THHN/T	THE SHALL BE DUAL RATED	
V			83	84 20		SPARE			TYPE: E RATING: 6	ATON PF	RL—1A UNLESS 0.208V.30.4W 2 ALL CIE	OTHERWISE NOTED.	
					NOTES:				MAINS: M BRACING: 4	LO 2 KAIC	SIZE IN	SULATED GREEN GROUND	15" MIN.
		<u>P0\</u>	WER PA	NEL - P	P-1-1 1. ALL '	NIRE SHALL BE DUAL RATED /THWN COPPER CONDUCTOF			ENCLOSURE: N	EMA1, S	URFACE	OTHERWISE NOTED.	
			ΤΥΡΓ·		UNLE	SS OTHERWISE NOTED.							¬ <u>* *</u>
			RATING:	400A, 120	2. ALL V 208V, 3ø, 4W SIZE	INSULATED GREEN GROUND	LUAD AUTOPSY HEADWALL POWF	R (2)#12, (1)#12 GND. 3/4"C	<u>∪.D.</u> 20 1	<u> </u> 0.8. ∖² 20	(2)#12, (1)#12 GND. 3/4"C	LUAU AUTOPSY HEADWALL POWFR	- ₹
			BRACING:	MLU 42 KAIC	UNLE	SS UTERWISE NUILD.	AUTOPSY HEADWALL POWER	R				AUTOPSY HEADWALL POWER	2
			ENCLOSURE POLES:	.: NEMA1, SU 84	JRFACE		ROLLING LADDER	(2)#10 (1)#10 CND 3/4"C				GROSSING STATION	-
					00000107050		CDU-1	(3)#8, (1)#10 GND, 3/4°C	<u>45</u> ₽₩ 45	1 <u>0</u> 45	(3)#8, (1)#10 GND, 3/4"C	CDU-2	
NORTH LIGHTS	(2)#12 (1)#	UCTURS 12 GND 3/4"	<u> C.B.</u> "C _20 ⊥へ	<u> C.B.</u> •ा∩्री 20	CUNDUCIORS (2)#12. (1)#12 GND 3/4"C	LUAD EAST LIGHTS			<u>╷</u> , Ţ				N.T.S.
SOUTH LIGHTS			3			WEST LIGHTS	P-1	(4)#12. (1)#12 GND 3/4"C		<u>16</u> 15	(4)#12. (1)#12 GND 3/4"C	P-3	-
LOBBY LIGHTS (VIA 1	TC-1)				(2) # 12 (1) # 12 (ND 3 / 4" C)	OUTDOOR LIGHTS (VIA TC-2)				18			- END OF LINE F QUAINTLY
* FIRE ALARM CONTROL PANEL	(FACP) (2)#12, (1)#1	 2 GND, 3/4"GR			(2) π (2)	AUTOMATIC DOUR OPENER AUTOPSY EAST SIDE LTG				20			
AUTOPSY WEST SIDE	LTG (2)#12, (1)#	12 GND, 3/4"	"C 11		· · · · · · · · · · · · · · · · · · ·	SPARE		$ (+)_{\#+Z}, (+)_{\#+Z} \text{ GND, } 3/4^{\circ}\text{C} $		15 <u>24</u>	$ (+)_{\#+Z}, (+)_{\#+Z} \text{ GND, } 3/4^{\circ}\text{C}$	P-4	+
SPECIAL AUTOPSY L	LTG	<u>+</u>				SPACE							
						V	EXERO-DR SCANNER	(3)#10, (1)#10 GND, 3/4"C	25 29	<u>×°</u> 20 ∖ <u>30</u>		SPARE	- I
.1.					P.FM <u>NOTES:</u>		SPACE			<u>32</u>			j (#/\$)
│ * PROVIDE RED LC	OCK ON HANDLE				• • • • • • • • • • • • • • • • • • •	RE SHALL BE DUAL RATED				<u>34</u>	 	SPACE	-
			I YPE: RATING:	EATON PR 60A, 1207	L-1a UNLESS (208V, 3ø, 4W	OTHERWISE NOTED.				\ <u>38</u>			-
			MAINS: BRACING:	MLO 42 KAIC	Z. ALL CIP SIZE IN	SULATED GREEN GROUND				\ <u>40</u>			
			ENCLOSURE POLES:	: NEMA1, SU 18	JRFACE UNLESS	UTHERWISE NUIED.	V			1 <u>42</u>			
				-				POV	VER PAN	EL -	PP-2 NOTES:	RE SHALL RE DUNI DATED	
												HWN COPPER CONDUCTOR	
									I YPE: E RATING: 4	ATON PF 00A, 120	<pre>KL-1a UNLESS 0/208V, 3Ø, 4W 2. ALL CIF</pre>	RCUITS SHALL HAVE FULL	
									MAINS: M BRANCHES: 4	LU 2 KAIC	SIZE IN UNLESS	SULAILD GREEN GROUND OTHERWISE NOTED.	(3) N.T.S.
									ENCLOSURE: N	EMA1, S	URFACE		\mathbf{i}

1. 480 VAC, 3-PHASE, POWER FOR THE X-RAY GENERATOR.

1

N.T.S.

2. 208-240 VAC, SINGLE PHASE, 25 AMP, FOR THE EXERO-DR SCANNER. (CLEAN POWER).

ELECTRIC BLOCK DIAGRAM

3. 120 VAC, 20 AMP FOR THE CONTROL WORKSTATION DEVICES. (CLEAN POWER).

RACEWAY & WIRING SCHEDULE (CONTRACTOR FURNISHED - CONTRACTOR INSTALLED)									
RUN #	FROM	то	SIZE	REMARKS					
	MDP-1	PP-CT	2" CONDUIT	(4) 3/0 CU, (1)#6 GND, 2"C. EC TO CONNECT AT BOTH ENDS.					
2	PP-CT	E	1" CONDUIT	(4)#8, (1)#10 GND, 1"C. EC TO CONNECT AT <a> AND TERMINATE CABLES AT <e> WITH ILSCO CLEAR SPLICE CONNECTORS.</e>					
$\langle \! \! \circ \! \rangle$	PP-2	F	3/4" CONDUIT	2-#10AWG PLUS 1-#10AWG NEUTRAL AND GROUND. EC SHALL CONNECT TO 25AMP, 2P, CB IN (PP-2) "EXERO-DR SCANNER" AND LEAVE 15'-0" TAILS AT (F). EC SHALL IDENTIFY WIRES AS "EXERO-DR SCANNER" POWER.					
5	PP-CT	В	3/4" CONDUIT	2-#12 AWG PLUS GROUND. EC SHALL CONNECT TO SHUNT TRIP DEVICE IN (A) AND CONNECT "EMERGENCY OFF" SWITCH IN BOX (B). 24VAC PREFERRED.					
6	JB	F	3/4" CONDUIT	2-#12 AWG PLUS GROUND. EC SHALL CONNECT TO "X-RAY IN USE" WARNING SIGN AT BOX (W) AND LEAVE TAILS AT (F). EC SHALL ENSURE NO LIVE WIRES IN (F).					
$\langle 7 \rangle$	F	С	2 1/2" CONDUIT	EMPTY CONDUIT. LEAVE PULL STRINGS. FOR LODOX SUPPLIED CONTROL CABLES.					
THI	E ELECTR TWEEN AI		NTRACTOR	SHALL FURNISH AND INSTALL ONE #8AWG GREEN EQUIPMENT GROUND WIRE T. CONSULT WITH THE LOCAL X-RAY EQUIPMENT REPRESENTATIVE REGARDING					

NEW ACCESSIBLE CEILING -

(1) 3/4" EMT CONDUIT FOR DATA WITH (2) CAT 6 CABLES.

FIN. FLOOR 4

6" ABOVE FINISH FLOOR

DOWEL INSTALLATION DETAIL

3" MIN.

EMBEDMENT

D AND SCHE	DULE OF LIGHTING EQUIPMENT					
MODEL #	DESCRIPTION					
-4000- 35K-1%-UN	2'X4' LED TROFFER, 4000 LUMENS, 3500K CCT, 80+ CRI, 120–277V WITH 1% 0–10V DIMMING DRIVER					
2W-24G-4000- <-1%-UNI-EM10	SAME AS TYPE "A" ABOVE WITH INTEGRAL 10W BATTERY PACK					
(4 6000LM 80CRI 35K IN10 ZT MVOLT	2'X4' EDGE LIT FLAT PANEL 6000 LUMENS, 3500K CCT, 80+ CRI, 120–277V WITH 10% 0–10V DIMMING DRIVER					
(4 6000LM 80CRI 35K ZT MVOLT EM10WCP	SAME AS TYPE "A1" ABOVE WITH INTEGRAL 10W BATTERY PACK					
G L48 24000LM OAW OLT GZ1 35K 90CRI DWAM	2'X4' LED CLEANROOM TROFFER, 24,000 LUMENS, 3500K CCT, 90+ CRI, 120-277V WITH 1% 0-10V DIMMING DRIVER. IP66 RATED, NSF RATED FOR SPLASH ZONE 2					
L48 24000LM OAW AFL GZ1 35K 90CRI DWAM E10WLCP	SAME AS TYPE "A2" ABOVE WITH INTEGRAL 10W BATTERY PACK					
RW 22G 4000 35K 1% UNI	2'X2' LED TROFFER, 4000 LUMENS, 3500K CCT, 80+ CRI, 120–277V WITH 1% 0–10V DIMMING DRIVER					
03 SWW1 AR LSS MWD OLT UGZ 90CRI	6" LED DOWNLIGHT WITH 2000/2500/3000 SELECTABLE LUMENS, 3500K CCT, 90+ CRI, 120–277V WITH 0% 0–10V DIMMING DRIVER					
02 SWW1 AR LSS MWD /OLT UGZ 90CRI	6" LED DOWNLIGHT WITH 1000/1500/2000 SELECTABLE LUMENS, 3500K CCT, 90+ CRI, 120-277V WITH 0% 0-10V DIMMING DRIVER					
H 35/30 DFF SMO /OLT EZ1 90CRI	6" LED DOWNLIGHT, IP66 RATED, NSF RATED FOR SPLASH ZONE 2, FLUSH LENS, 90+ CRI. 1% 0–10V DIMMING DRIVER.					
4 4500 35K HTA 1% UNI	4' SUSPENDED FIXTURE, 4500 LUMENS, 3500K CCT, 120–277V WITH 0–10V DIMMING DRIVER, SUSPENDED MOUNT					
4500 35K HTA 1% UNI	SAME AS TYPE "E" ABOVE BUT 6' LENGTH					
4500 35K HTA 1% UNI	SAME AS TYPE "E" ABOVE BUT 8' LENGTH					
3R LP TD TFWP H DML MEODF 835 VU D	3.5" APERTURE RECESSED LINEAR, EXTRUDED ALUMINUM, EDGE LIT OPTICS, DIFFUSED LENS. TOOLESS MAINTENANCE. 1% 0-10V DIMMING DRIVER. 522 LUMENS PER FOOT. CONFIRM MOUNTING					
DWIT-4-R-LED930	WIT PENDANT SERIES, 4 GLASS, 120V, 62.2 WATTS 2672 DELIVERED LUMENS, 3000K, LED LINEAR MODULE, COORDINATE MOUNTING HEIGHT WITH ARCHITECT.					
OMDP3-C-R-R	MODERNRAIL PENDANT SERIES CYLINDRICAL DESIGNED FIXTURE, INTEGRATED LED MODULES, 3000K CCT, COORDINATE MOUNTING LENGTH WITH ARCHITECT.					
2 LED-P2-30K- MVOLT-E8WC	EXTERIOR WALL PACK LED, 2000 LUMENS, 4000K CCT 120/277V WITH 8 WATT INTEGRAL EMERGENCY BATTERY PACK.					
LM 35K MVOLT G4 CRI ZT HM CS	4" DOWNLIGHT WITH HYPERBOLIC TRIM, 4000 LUMENS, 3500K CCT, 80+ CRI , 120–277V WITH 10% 0–10V DIMMING DRIVER, CLEAR SPECULAR FINISH REFLECTOR					
1R LP TD TF(XX) GTH SLO-19(748) CODF 835 VU D	1.5" APERTURE RECESSED LINEAR, EXTRUDED ALUMINUM, EDGE LIT OPTICS, DIFFUSED LENS. TOOLESS MAINTENANCE. 1% 0–10V DIMMING DRIVER. 748 LUMENS PER FOOT. CONFIRM MOUNTING.					
d dt length dml meodf Nish Sdl Rod Mount - By others Mh C5 RNS	3.5" APERTURE LINEAR ROD MOUNTED (BY EC), EXTRUDED ALUMINUM EDGE LIT OPTICS, DIFFUSED LENS. TOOLESS MAINTENANCE. 1% 0–10V DIMMING DRIVER. 522 LUMENS PER FOOT. CONFIRM MOUNTING.					
5L-4-L38-8- 40-DMA	6"x48" LED STRIP LIGHT, 4000 LUMENS, 4000K CCT, SUITABLE FOR DAMP LOCATIONS. 120/277V.					
–0–L6–80–35– TG–BLK–120V	OUTDOOR WALL LIGHT. 6000 LUMENS, 3500 CCT, 80 CRI, 120V					
I-PYC-HLO-SW-90- 00-35-4-UNV-D1- 1-BF-EMB	4' LED FIXTURE PROVIDING DIRECT AND INDIRECT LIGHTING DISTRIBUTION. 4000 LUMENS, 90 CRI, 3500K CCT, SUITABLE FOR WET LOCATIONS.					
T-R-AC-WHT-D	WHITE EXIT FIXTURE WITH RED LETTERING. AC, 120/277V.					

