

FIRE ALARM
SYSTEM
(EXISTING
SYSTEM)

**SECTION 28 4601
FIRE ALARM SYSTEM (EXISTING SYSTEM)**

PART 1 - GENERAL

1.01 SCOPE & RELATED DOCUMENTS

- A. The work covered by this section of the specifications includes the furnishing of all labor, equipment, materials, and performance of all operations in connection with the modifications and additions to the existing Fire Alarm System(s) as shown on the drawings and as herein specified.
- B. The requirements of the conditions of the Contract, Supplementary Conditions and General Requirements, apply to the work specified in this section.
- C. The complete installation is to conform to the applicable sections of NFPA-72, NFPA-71, Local Code Requirements and National Electrical Code with particular attention to Article 760.
- D. Additionally, the entire installed system and all integrated system operations shall be within the guidelines of the SBCCI Standard Building Code.
- E. The work covered by this section of the specifications is to be coordinated with the related work as specified elsewhere under the project specifications.
- F. The contractor shall provide all required modifications and additions to the existing Fire Alarm System for the removal, relocation of existing devices and addition of new devices. This shall include all additional wiring, devices, modifications to the existing control panel, additional components and modules, addressable cards, testing, troubleshooting and instructions to the owner.

1.02 QUALITY ASSURANCE

- A. Each and all items of the Fire Alarm System shall be listed compatible with the existing system under the appropriate category by Underwriters' Laboratories, Inc. (UL), and shall bear the "U.L." label. All control equipment is to be listed under UL category UOJZ as a single control unit. Partial listing shall NOT be acceptable.
- B. All items shall match and be of the same manufacturer as the existing system.
- C. The equipment and installation supervision furnished under this specification is to be provided by a manufacturer who has been engaged in production of this type (software driven) of equipment for at least ten (10) years, and has a fully-equipped service organization within thirty-five (35) miles of the installation.
- D. All control equipment must have transient protection devices to comply with UL864 requirements.
- E. In addition to the UL-UOJZ requirement mentioned above, the system controls shall be UL listed for Power Limited Applications per NEC 760. All circuits must be marked in accordance with NEC article 760-23.

1.03 SUBMITTALS

- A. Submit shop drawings for each piece of equipment specified including complete wiring and connection diagrams.
 - B. All submittals shall be submitted in a single complete brochure, which shall be in the form of a soft cover binder with each group separated by an identified index tab.
 - C. Submittals that fail to comply with the above requirements will automatically be rejected.
 - D. It is the Contractor's responsibility to provide submittals in an organized and timely manner in order so as not to delay the project schedule and hamper the work of other trades.
-

FIRE ALARM
SYSTEM
(EXISTING
SYSTEM)

- E. Submit certificate of Fire Alarm System operating tests.

PART 2 PRODUCTS**2.01 PERIPHERAL DEVICES**

- A. The Contractor shall furnish and install addressable devices that are compatible with the existing Simplex 4100es fire alarm System.

PART 3 EXECUTION**3.01 INSTALLATION**

- A. Provide and install all devices in accordance with the plans and specifications, all applicable codes and the manufacturer's recommendations. All wiring shall be installed in strict compliance with all the provisions of NEC - Article 760 A and C, Power-Limited Fire Protective Signaling Circuits or if required may be reclassified as non-power limited and wired in accordance with NEC-Article 760 A and B. Upon completion, the contractor shall so certify in writing to the owner and general contractor.
- B. Installation of equipment and devices that pertain to other work in the contract shall be closely coordinated with the appropriate subcontractors.
- C. The contractor shall clean all dirt and debris from the inside and the outside of the fire alarm equipment after completion of the installation.
- D. The manufacturer's authorized representative shall provide on-site supervision of installation.

3.02 TESTING

- A. The completed fire alarm system shall be fully tested in accordance with NFPA-72H by the contractor in the presence of the owner's representative and the Local Fire Marshal. Upon completion of a successful test, the contractor shall so certify in writing to the owner and general contractor.

3.03 WARRANTY

- A. The contractor shall warrant the completed fire alarm system wiring and equipment to be free from inherent mechanical and electrical defects for a period of one (1) year from the date of the completed and certified test or from the date of first beneficial use.
- B. The equipment manufacturer shall make available to the owner a maintenance contract proposal to provide a minimum of two (2) inspections and tests per year in compliance with NFPA-72H guidelines.

END OF SECTION 28 4601