

JAMES J. DEAN
Superintendent of Highways
Roadmaster IV

Orangetown Representative:
R.C. Soil and Water Conservation Dist.-Chairman
Stormwater Consortium of Rockland County
Rockland County Water Quality Committee



HIGHWAY DEPARTMENT
TOWN OF ORANGETOWN
119 Route 303 · Orangeburg, NY 10962
(845) 359-6500 · Fax (845) 359-6062
E-Mail - highwaydept@orangetown.com

Affiliations:
American Public Works Association NY Metro Chapter
NYS Association of Town Superintendents of Highways
Hwy. Superintendents' Association of Rockland County

August 18, 2023

Dear Potential Bidder:

Enclosed please find an addendum to the Contract Document for Installation of New 4" Ductile Iron Sprinkler Main. This is a two (2) page addendum.

Please acknowledge receipt of this addendum by attaching it to the last page of the Contract Document. If you have any questions regarding this addendum, please contact me as soon as possible.

Very truly yours,

Stephen F. Munno
Senior Administrative Assistant

Kf
Enclosure



Notice of Revisions in Contract Documents

Installation of New 4" Ductile Iron Sprinkler Main

Addendum #1

Dated: August 18, 2023

The information in this addendum supersedes any contradictory information set forth in the Contract Documents. Acknowledge receipt of this addendum by attaching this addendum to the last page of the Contract Document. Failure to attach this addendum to the last page of the Contract Document may subject the bidder to disqualification. This addendum forms a part of the Contract Documents.

Page 1 – Remove:

**Request for Proposal
For Installation of New 4" Ductile Iron Sprinkler Main**

The Town of Orangetown Highway Department is hereby requesting proposals to furnish and install approximately 70' of New 4" Ductile Iron Sprinkler Main from the watermain shed to existing "Dry Fire Suppression System" located in the South Storage Building at 119 Route 303, Orangeburg, NY 10962. **Please see attached site location map.**

Replace with:

**Request for Proposal
For Installation of New 4" Ductile Iron Sprinkler Main**

The Town of Orangetown Highway Department is hereby requesting proposals to furnish and install approximately 70' of New 4" Ductile Iron Sprinkler Main from the watermain to existing "Dry Fire Suppression System" located in the South Storage Building at 119 Route 303, Orangeburg, NY 10962. **Please see attached site location map.**

Page 2 – Remove:

- ALL SAW CUTTING OF ASPHALT, ASPHALT EXCAVATION AND SOIL EXCAVATION BETWEEN THE WATERMAIN SHED AND SOUTH STORAGE BUILDING TO BE CONDUCTED BY OTHERS.
- CONTRACTOR TO PROVIDE PIPE SAND AND ITEM 4.
- CONTRACTOR INSTALL THRUST BLOCKS ON ALL MJ90 AND MJ45.
- PAVING TO BE DONE BY OTHERS.
- ALL SAW CUT AND JACK HAMMERED CONCRETE MATERIALS ARE TO BE LEFT ON SITE.

Replace with:

- ALL SAW CUTTING OF ASPHALT, ASPHALT EXCAVATION AND SOIL EXCAVATION BETWEEN THE WATERMAIN AND SOUTH STORAGE BUILDING TO BE CONDUCTED BY OTHERS.
- CONTRACTOR TO PROVIDE PIPE SAND AND ITEM 4.
- CONTRACTOR TO PREPARE EXCAVATED TRENCH FOR PAVING RESTORATION AND BACKFILL.
- CONTRACTOR TO BACKFILL USING ONLY CLEAN, DRY, APPROVED MATERIALS (NYS DOT "ITEM 4"). ALL MATERIALS MUST BE COMPACTED IN 8" LIFTS AND ALLOW FOR 5" OF ASPHALT TO BE INSTALLED BY OTHERS.
- CONTRACTOR INSTALL THRUST BLOCKS ON ALL MJ90 AND MJ45.
- PAVING TO BE DONE BY OTHERS.
- ALL SAW CUT AND JACK HAMMERED CONCRETE MATERIALS ARE TO BE LEFT ON SITE.