



**VILLAGE OF HASTINGS-ON-HUDSON**

Municipal Building  
7 Maple Avenue  
Hastings-on-Hudson, New York 10706  
Mary Beth Murphy, Village Manager  
[villagemanager@Hastingsgov.org](mailto:villagemanager@Hastingsgov.org)  
914 478 3420

**Request for Proposals Roof Replacement (Phase 3) for Village Hall in the Village of  
Hastings-on-Hudson**

**Addendum No. 5  
January 9, 2023**

**RESPONSE TO RFI NO. 1**

Please see the attached response to RFI No. 1 regarding roof drains.

EASTON ARCHITECTS LLP  
20 WEST 44<sup>TH</sup> STREET, SUITE 604  
NEW YORK, NEW YORK, 10036

212 779 9570 TELEPHONE  
INFO@EASTONARCH.COM

## Request for Information

R.F.I. No.: 01

---

To: All Bidders  
From: Easton Architects  
Project: Hastings-on-Hudson Village Hall  
Phase 3: Roof Replacement and Repairs Project  
Project No.: 2118  
Date: January 6, 2023

---

### Question:

Are combination drains to be installed as a replacement for both drains.  
Are there "Plumbing drawings" as mentioned on drawing 404.00 available?  
If combination drains are required what is the route for the overflow piping?  
Please provide make & model number for roof drains.

---

### Reply:

Specification Section 07560, Part 1.13, Section G, Item 1 notes the drain body as:

Drains: Provide full size #1010 cast iron replacement roof drains by Smith Inc. at all drain locations. Drains are to be provided with inside caulk connections, cast iron domes and sump receivers.

Also note that all drains shall be replaced at current locations. Connections shall be made to existing plumbing drainage. No plumbing drawings are provided for the bid documents.

---

By EA: T. Talbert

Date: January 6, 2023